DESIGN AND CONSTRUCTION GUIDELINES AND STANDARDS

DIVISION 14 • CONVEYING EQUIPMENT

14 20 00 • ELEVATORS

SECTION INCLUDES

Electric Traction Elevators Hydraulic Elevators Lifts

RELATED SECTIONS

03 30 00	Concrete
04 20 00	Masonry
09 25 00	Gypsum Drywall
24 00 00	HVAC
23 00 00	Plumbing
26 00 00	Electrical
28 00 00	Electronic Safety and Security
31 00 00	Earthwork



Elevators is a stipulated filed sub-bid category under M.G.L. Chapter 149, §44F. If the cumulative estimated value of the work in this section exceeds \$20,000 and the project's total cost is over \$100,000, it triggers the filed sub-bid requirement. In general most elevator upgrades exceed \$100,000 therefore Electrical, HVAC, etc work that exceeds \$20,000 needs to be defined as a filed sub-bid.

Projects mostly include upgrades of existing elevators or in some cases providing a second elevator in buildings with only one elevator.

Upgrades of existing elevators without any architectural changes generally do not need the services of an architect, however if a new elevator is being provided an architect should be the lead consultant with a vertical transportation specialist needed for the elevator (this section) specification and other engineering sub-consultants.

Elevators are primarily traction type for buildings 75 'or higher and hydraulic for less than 75'. Traction type elevators are also appropriate in high use situations or where there is ledge or a high water table.

ELEVATOR UPGRADES

Prior to design of elevator upgrades:

- ☐ Evaluate all existing equipment. Identify equipment having useful life remaining. If equipment is being reused specify cleaning, painting, refurbishing, grease and/oil, etc
- ☐ Evaluate and specify all of the fire alarm improvements required for elevators, e.g. firefighter recall.
- ☐ Upgrades to existing elevators in buildings having only one elevator may require a relocation plan for residents being in place prior to elevator work being started. This is a major effort and requires a great deal of coordination with the LHA.



14 20 00 • ELEVATORS

February 2007

1 of 3

DESIGN AND CONSTRUCTION GUIDELINES AND STANDARDS

DIVISION 14 • CONVEYING EQUIPMENT

14 20 00 • ELEVATORS

Evaluate existing machine rooms lighting, electrical, ventilation, heat, etc. and upgrade with improved systems in accordance with current code.
Determine if the existing emergency generator is sized appropriately for the full load operating or if it is controlled by a selector switch. If the generator was sized originally to have capacity for both elevators operating, provide a selector switch control to allow for operating one elevator at a time (if permitted by code). This additional emergency generator capacity could be used for other loads, or a future replacement generator could be smaller and less costly.
Test, to the extent possible, for disruptive harmonics to existing sensitive electrical systems such as fire alarm panels and systems.
Provide emergency generator interface and test the generator for satisfactory operation of this interface.
Check the elevator pit for water infiltration and accumulation. If it occurs determine cause and correct if possible. Possible solutions include adding a crystalline coating on the walls of the pit or adding sump pumps. If pumps are the solution, a dual pump system is preferred.
Investigate the shaft and design giving consideration to existing building fireproofing and shaft wall construction. Debris from fire proofing can become problematic with new solid state controls and microprocessors.
Holeless and roped hydraulic elevators are preferred for new installations.
In single elevator buildings that are being provided with a new (second) elevator, specify that the existing elevator should not be used for construction purposes.
Design new elevators to fit the character of the existing building.
CMU for shaft walls is preferred.

NEW ELEVATORS INCLUDING ADDITIONAL ELEVATORS

DESIGN CONSIDERATIONS – ALL ELEVATORS

Research & reference all applicable codes, laws, regulations and standards that apply: e.g. NFPA 70, 72, etc.

Fit standard "off the shelf" elevator equipment (i.e. Pre-engineered and premanufactured) into existing buildings footprints if possible. Do not specify custom equipment unless absolutely necessary. Use current technology in elevator equipment.

Provide all of the required ADA upgrades to elevators and call stations for the requirements for handicap and special needs residents.

Interior of elevator cabs should also be upgraded to improve aesthetics. Do not use carpet in elevator cars.

Always specify new elevator pads with the appropriate hanging pins.



dhed Massachusetts

14 20 00 • ELEVATORS

February 2007 2 of 3

DESIGN AND CONSTRUCTION GUIDELINES AND STANDARDS

DIVISION 14 • CONVEYING EQUIPMENT

14 20 00 • ELEVATORS

Specify patching and painting of hallway where elevator work occurs.

Call button replacements shall be specified, and always provide lobby lights for car direction on each floor

On new hydraulic elevators or when doing an upgrade of an existing older type hydraulic elevator which has been determined not to have cylinder protection always specify; new PVC lined cylinders, environmentally safe replacement hydraulic oils and provide additional corrosion protection such as cathodic protection.

Provide heat and air conditioning in the hydraulic room to keep oil at a reasonable operating temperature.

Provide a scavenger pump to return the oil to the reservoir...

Provide state of the art solid state non-proprietary microprocessor controller provided with an integral air conditioning system for controller cabinet. This is usually more costly initially but is more efficient and will provide for savings in power consumption that will usually justify the additional cost.

Design documents should be clear that the successful bidder for the upgrade/new installation is responsible for emergency repairs and routine maintenance and inspections of all elevators covered under the contract during the entire the duration of the construction contract and warranty period (usually one year after substantial completion).

WHEEL CHAIR LIFTS

Evaluate the alternatives and options (LULA) thoroughly; our experience with lifts is typically that they don't get used much and that other solutions are more effective.

Exterior stair lifts should be avoided.

