

## **APPENDIX C**

### **Gypsum Removal Best Management Practices Protocol**

New Ventures LLC (“New Ventures”) shall require and document that all facilities that send C & D Fines and Residuals to the Crow Lane Landfill (the “Facility” or the “Site”) implement the procedures described herein to minimize to the greatest extent practicable the amount of gypsum contained in the C & D Fines and Residuals.

1. Notifies all of its customers in writing that they are to segregate gypsum wallboard from other C & D Waste prior to the shipment of C & D Waste to the Facility for processing.
2. Visually inspects all loads for gypsum wallboard immediately upon the tipping of each load.
3. Segregates and transports off-Site for proper disposal any and all loads/containers that, based on visible inspection, contain greater than 50% gypsum wallboard.
4. For loads that, upon visible inspection, contain greater than 10% but less than 50% visible gypsum wallboard, the Facility shall either transfer for disposal off-Site the gypsum contaminated C & D Waste, or move the gypsum contaminated C & D Waste to a tipping area designated solely for the management of loads containing gypsum wallboard for processing as follows:
  - a. the C&D Waste is spread;
  - b. visible pieces of gypsum free C&D Waste are then removed for further processing and sorting in accordance with paragraph 5 below; and
  - c. the remaining mixed gypsum wallboard and C&D Waste are segregated and transported off-Site for proper disposal.
5. Processes loads/containers containing less than 10% by volume visible gypsum wallboard as follows:
  - a. the C & D Waste is spread upon tipping;
  - b. visible pieces of gypsum wallboard are then removed and segregated for disposal prior to the inclusion of the C & D Waste into the processing stream (that is, prior to any screening, mechanical crushing, shredding, or compacting of the C & D Waste); and
  - c. the remaining C & D Waste are then run through the processing stream and any visible gypsum wallboard is removed from the C & D Waste during processing including wood, metal, and other material contaminated with visible gypsum wallboard.
6. Maintains records that include:
  - a. the daily tonnage of the gypsum waste removed and disposed of by the Facility; and
  - b. the daily number and tonnage of loads rejected by the Facility.
7. Provides the truck operator of any load containing gypsum wallboard with a written notice of the Facility’s gypsum removal protocol.