Webinar
May 29, 2015
12:30 PM

Helping Massachusetts Municipalities Create a Cleaner Energy Future

#### COMMONWEALTH OF MASSACHUSETTS


Charles D. Baker, Governor Matthew Beaton, Secretary Judith Judson, Commissioner

### **LED Street Lighting Webinar**

Kevin F. Galligan, Galligan Energy Consulting Inc.

### **Green Communities Division**

The energy hub for **all** Massachusetts cities and towns, not just designated "Green Communities."



### **Outreach - Regional Coordinators**

- Regional Coordinators act as direct liaisons with cities and towns on energy efficiency and renewable energy activities
- Located at each of the DEP Regional Offices:



WERO – SPRINGFIELD: Jim Barry Jim.Barry@state.ma.us



NERO - WILMINGTON: Joanne Bissetta Joanne.Bissetta@state.ma.us



CERO - WORCESTER: Kelly Brown Kelly.Brown@state.ma.us



SERO - LAKEVILLE: Seth Pickering Seth.Pickering@state.ma.us



Helping Massachusetts Municipalities Create A Cleaner Energy Future



# **Green Communities Division - Programs & Resources for Municipalities**

- ${}^{\bullet}\:$  Green Communities Designation and Grant Program
- MassEnergyInsight energy tracking and analysis tool
- Municipal Energy Efficiency Program
- Energy Management Services Technical Assistance
- Clean Energy Results Program (CERP)
- Mass Municipal Energy Group (MMEG)
- Website filled with tools & resources: www.mass.gov/energy/greencommunities

Email updates via e-blasts – Sign up by sending an email to: join-ene-greencommunities@listserv.state.ma.us



Helping Massachusetts Municipalities Create A Cleaner Energy Futur



### **Recording & Presentation**

- The webinar is being recorded and will be available on our website in approximately 48 hours at: <a href="http://www.mass.gov/eea/energy-utilities-clean-tech/webinars.html">http://www.mass.gov/eea/energy-utilities-clean-tech/webinars.html</a>
- Click on the camera icon top right of your screen to save any slides for future reference
- Use the Q & A icon on your screen to type in questions
- The slide presentation will also be posted at: <a href="http://www.mass.gov/eea/energy-utilities-clean-tech/webinars.html">http://www.mass.gov/eea/energy-utilities-clean-tech/webinars.html</a>
  <a href="http://www.mass.gov/eea/energy-utilities-clean-tech/webinars.html">http://www.mass.gov/eea/energy-utilities-clean-tech/webinars.html</a>
- Websites are also listed at end of presentation



Helping Massachusetts Municipalities Create A Cleaner Energy Futur



### Agenda

- Background and assumptions
- Technology, Specs, & Standards
- Cape Light Retrofit Project
  - Working with 23 municipal program participants
- Demonstration/pilot phase
- Procurement
- Product selection
- Costs, benefits, and results
- Some lessons learned & ideas for the future
- Appendix: Helpful references



Helping Massachusetts Municipalities Create A Cleaner Energy Future



### **Background and Assumptions**

- This retrofit project converted all eligible municipalowned streetlights to LEDS among 23 participating municipalities on Cape Cod & Martha's Vineyard
- Cost-effective measure fully funded as part of a multiyear energy efficiency project administered by Cape **Light Compact**
- One Energy Management Services (EMS) agreement
- Individual participation agreements with each
- Inventory & street light utility billing process described here is specific to Eversource (formerly NSTAR





### **Technology, Specs & Standards**

- · Trend continues to lower cost of LED roadway luminaires
- . Efficacy (efficiency) continues to improve (Im/w)
- Educate, learn & share (see appendix for helpful references)
  - Roadway Lighting specifications are well established and continue to evolve based on improvement in technology
  - Not all roadway lighting was designed/installed with any specs
    - . Some older mercury vapor and sodium fixtures may go
    - Some more oriented to pedestrian vs. roadway application







### **Cape Light Compact Retrofit Project OVERALL TOTALS**

- 23 participating municipalities
- 15.700\* eligible lights converted (projected 12/31/2014)
- 17,000 points GIS GPS-mapped
- Annual energy savings > 3,310,000 kWh (approx. 70%
  - Annual utility bill savings > \$657,000
  - Annual maintenance savings> \$212.000
- Combined annual billing and maintenance savings > \$869,000

Energy Efficiency Program Funding by Cape Light Compact

- Approx. \$5.9 million (incl. GIS GPS-audit), part of 2013-2015 Three Year DPU Approved Energy Efficiency Plan
- 10-year energy savings performance contract (Ch. 25A)



eatte Municipalities Create A Cleaner Energ



### **Cape Light Compact Project Highlights**

- Multi-vear, multi-phase, effort from early 2012-2014
  - Demonstration project led to 6-phase full conversion project
  - Mostly non-summer work, 60-day adjustment period
  - Special terms & conditions unique to many communities
- Provided for purchase from NSTAR for Phase II participation
- Special recognition
  - Falmouth greatest # of streetlights (2,573, not incl. admiral
  - West Tisbury greatest % energy savings (87%)
  - Provincetown most engaged community in demonstration
- · Thanks and appreciation
  - CLC board members and staff, DOER, DPU, NSTAR, Town Administrators, DPW/HWY staff, selectman, and all involved





## **Cape Light Compact Project Benefits**

#### Project Benefits

- Significant increase over planned estimates
- Combined total savings

	Annual Estimated kWh Savings	Annual Estimated Utility Bill Savings	Annual Estimated Maintenance Savings
January, 2014	3,170,904	\$652,441	\$210,398
September, 2014	3,309,419	\$656,912	\$211,561
(Peak Demand	Reduction = 0.827 MW)		

\*\*Savings estimate revised based on "as installed" actuals and the addition of additional Phase II participants including: C-O-MM. Tisbury and West Tisbury who completed their purchase of street lights from NSTAR Electric





### Poll Question #1

- What is the stage of LED street lights in your community?
  - A. Already installed
  - B. Procurement or installation in process
  - c. Pilot, inventory or research
  - D. Don't own, not started, don't know





### **Special Considerations**

- · Admiral Hats (324 fixtures) retained (1960's vintage)
  - Incandescents/CFLs replaced with screw-in LEDs (including feeder wire replacements to extend life of fixtures)
- Floods & decoratives included in final Phase 6
  - Subject to cost-effectiveness screening
  - Only for outdoor roadway/parking area-type fixtures





### **Cape Light Compact Project Schedule**

- · Demonstration/pilot project (8 LED fixtures/community)
- · Gathered DPW Directors & community feedback (survey)
- · Set Schedule in early 2013 for Full Conversion Project:
  - June 14: Participation Agreements Executed
  - Including Special terms and Conditions beyond standard specs July 12: REP Issued

  - July 26: Bidder Questions/Pre-Bid Meeting/Field Site Visits
  - August 9: Proposals Due
  - Aug 16: Bidder Presentations
  - Sept 6: Award (Contracts executed by Oct 4)
  - Oct 4: Project Kick-off
  - Nov 1: Pre-install field assessments (investment grad GIS GPS-based audits)
- Nov 15: Fixture orders placed
- Jan, 2014: Installations begin (batching billing updates town-by-town)
- June, 2014: Installations complete
- November, 2014: Fixture revisions (if needed)

December, 2014; Final invoices and wrap-up





### **Full Project Scope Fixture Selection**

- Competitive Procurement (RFQ per M.G.L. Ch. 25A, Sec. 11I)
  - A Guaranteed Energy Savings Contract (IGA (Audit) &EMS)
- Cape Light Compact contract on behalf of participants:
  - New LED fixtures replace existing operating fixtures
  - New LED fixtures replace comparable, or lower, lumen size
  - Retrofit all municipal-owned streetlights to LED
- Pre-installation energy assessment/audit
- Fixture selection/procurement
- Fixture installation
- 100% Cape Light Compact energy efficiency program incentive for Project (except any police detail) subject to cost-effectiveness screening





### Full Project Scope Cnt'd **Operations and Maintenance**

- · Participating Municipality will have separate contract for O&M services:
  - General Maintenance Fixed Price per lamp/mo
  - · Contractor does visual inspections "spotting" OR
  - Community (Town/FD) does "spotting"
    - Considering request for web-based app to submit outage reports
- For additional fixture changes to LED (after Retrofit Project)
- Call Center
- Emergency response
- Extra work
- Response times
  - Repairs done not more than five business days from outage





## Fixture Selection and GIS Mapping

Primary Fixture Selected



GIS Mapping (example section of Yarmouth)



Cree Beta LED XSP Series hEp://www.cree.com/lighBng/products/outdoor/streetlig



### Fixture Choice

· Evaluated performance, features and costs of multiple manufacturers

**Fixture Selection Cnt'd** 

- · Selected Cree Beta XSP 1 series fixture
  - Similar cobra head design to old HPS figures
  - Warmer color temperature CCT: 4000 K (+/- 300K)
  - Highest energy efficiency (70% savings over HPS)
  - Optical and lumen controls
    - Field installed shields
    - Field adjustable (lumen) output



Cree Beta LED XSP Series

hEp://www.cree.com/lighBng/products/outdoor/streetlig hts/xsp---series---streetlight





### Poll Question #2

- What is the primary barrier to your community's LED street light retrofit?
  - A. Don't own the street lights
  - B. Financial
  - c. Technical assistance and/or project management
  - D. Community support
  - E. Other (please enter in comments)





### Ultimate Schedule used a Phased **Approach** Phase Locations 1 Hyannis, Yarmouth Dennis, Harwich, Martha's Vineyard Chatham, Brewster, Orleans, Wellfleet, Truro, Provincetown Barnstable, W. Barnstable, Cotuit, Mashpee, Bourne, Sandwich 5 Falmouth \*Status within phase tracked: Field audit, eng/design, report, fixtures ordered, installation, billing revisions, EM&V, close-out

### Web-based app - Track Feedback







### **Provincetown Aerial Views**

Before (high pressure sodium)



After (LED)





### **Billing Revisions & Annual M&V**

Billing Revisions

- Submitted to NSTAR by Contractor on Town-wide basis
- NSTAR typically implemented revised billing codes within 1 to 2 billing cycles following batches submittal by

Annual Measurement & Verification (per Chap. 25A, Sec11I)

- Contractor will request by October each year a copy of billing detail from each Participant and submit energy savings performance report to Cape Light Compact
- The Compact then submits Annual Report to DOER (for 10-years)





### Some Ideas for the Future

- · Looking ahead to grid modernization and timevarying rates
- Consider fixture specs that include capacity for adaptive control and remote monitoring
- With verifiable EMS additional energy savings and life extension of fixtures may be possible

K Option Occupancy Control





### Poll Question #3

- How controls-ready are your LED street lights?
  - A. Have or installing controls
  - B. Have or installing 7 pin lights
  - c. Not started
  - D. Don't know





### **Lessons Learned**

- 1. Publish the call center number and website for the project, communicate and respond promptly to all
  - See Project Task matrix in Appendix
- 2. Use, share and post on website updated FAQs
- 3. Hold periodic (during high production, weekly) check-in calls with contractor
- 4. Frequent site visits, night time QA/QC confirms compliance with Ts and Cs and contractor can quickly respond to concerns
- 5. Look for more energy efficiency opportunities that may be within scope or outside of scope (and have script to get those additional customer measures served)





### Links

- . U.S. DOE Municipal Solid-State Street Lighting Consortium http://energy.gov/eere/ssl/doe-municipal-solid-state-street-lightingconsortium
- MA DOER Energy Management Services http://www.mass.gov/eea/energy-utilities-clean-tech/greencommunities/ems.htm
- Metropolitan Area Planning Council http://www.mapc.org/led-street-lighting
- Cape Light Compact Energy Efficiency for Municipalities http://www.capelightcompact.org/energy-efficiency/municipal/
- · Statewide Contract for LED Roadway/Streetlight Purchases: FAC76, Category 6







Helping Massachusetts Municipalities Create a Cleaner Energy Future

### **Thank You**

Kevin F. Galligan Galligan Energy Consulting, Inc. 508 - 255 - 2036 kgalligan@galliganenergy.com

Lisa Capone Acting Division Director, Green Communities

lisa.capone@state.ma.us

Helping Massachusetts Municipalities Create a Cleaner Energy Future

**Appendix: Helpful References** 

#### **Luminaire Performance Metrics**

- Light output measured as lumens (lm)
- The higher the number, the more light is emitted Measured input power (watts (W))
- The higher the number, the less energy used
- Luminaire efficacy (lumens per watt (lpw))
- The higher the number, the more efficient the product Correlated color temperature (CCT) sometimes simply referred to as color temperature is measures in degrees
- "Cool" colors have higher color temperatures (3600-
- 5500K) "Warm" colors have lower color temperatures (2700-
- A full moon has a color temperature of about 4150 K
- A high pressure sodium street light has a color temperature of about 2000 K
- Color rendering index (CRI)
- The higher the CRI, the more accurate the color of illuminated objects appear under the luminaire
  - Natural sunlight = 100 CRI
- LED light source = 70 75 CRI



7000

6500

6000

5500

5000

4500

2500





## **Project Task Matrix**

Project Task	Funded by	Contract
Audit of existing fixtures	Cape Light Compact	Investment Grade Audit (IGA)
Design of new LED system	Cape Light Compact	Energy Management Services (EMS)
Supply & install new LED fixtures	Cape Light Compact	Energy Management Services (EMS)
Make adjustments as requested within 60 days post completion	Cape Light Compact	Energy Management Services (EMS)
Repair outages, day burners	Member communities	Operations & Maintenance (O&M)
Emergency repairs due to vehicle or weather damage	Member communities	Operations & Maintenance (O&M)
Pole transfers	Member communities	Operations & Maintenance (O&M)
Police details	Member communities	Operations & Maintenance (O&M)
Electrical troubleshooting, misc. work as requested, addition, removal, or modification of LED fixtures	Member communities	Operations & Maintenance (O&M)







# Example Retrofit Comparison 100 W HPS to 26 W LED

	Watts	Lumens*		Est'd Annual Energy Savings (kWh)	Est'd Annual Energy Savings (\$)**
100 W HPS	121	9,500	56		
LED XSP1 (G)	26	2,543	95	377	\$75

\*Lumen differences between HPS and LED exist for multiple reasons, including the directional illumination pattern of LED vs.

\*\*Est'd Annual Energy Savings assumes \$0.20/kWh



Helping Massachusetts Municipalities Create A Cleaner Energy Future



## **Operations & Maintenance**

- O&M contract in place with each Town or Fire District & Siemens
- Contract term: 3 years
  - Option to extend for 2 years
- Outage reporting call Siemens at 800-544-4876 (800-LIGHTS-ON)
   O&M Contract Comparison
- 5 business day response

	non-LED fixture	LED fixture
Old O&M contract	\$1.22	n/a
New O&M contract	\$1.27	\$0.33



Halping Massachusetts Municipalities Create & Cleaner Energy Enture

