

COMMONWEALTH OF MASSACHUSETTS

OFFICE OF CONSUMER AFFAIRS AND BUSINESS REGULATION

**DEPARTMENT OF
TELECOMMUNICATIONS & ENERGY**

PIPELINE ENGINEERING AND SAFETY DIVISION

INCIDENT REPORT

82 Marsh View Road, Chatham, Massachusetts
October 30, 2002

INCIDENT REPORT:

82 Marsh View Road, Chatham, Massachusetts

October 30, 2002

TABLE OF CONTENTS

I. INTRODUCTION Page 1

A. Scope of this Investigation Page 1

B. Overview of the Incident Page 2

II. THE DEPARTMENT’S INVESTIGATION Page 3

A. Description of the Site Page 3

B. Description of the Scene Page 4

C. KeySpan Energy Delivery Company Page 5

D. The Contractor Page 5

E. The Maintenance Man Page 6

F. Examination of the Pipe Page 7

III. FINDINGS AND CONCLUSIONS Page 7

A. Findings Page 7

B. Conclusions Page 8

IV. LIST OF EXHIBITS Page 9

I. INTRODUCTION

A. Scope of this Investigation

The Pipeline Engineering and Safety Division of the Massachusetts Department of Telecommunications and Energy (“Department”), pursuant to G. L. c. 164, § 105A and G. L. c. 82, § 40 (“Dig Safe”) has investigated a natural gas (“gas”) explosion (“incident”) at 82 Marsh View Road, Chatham, that occurred on October 30, 2002. The incident resulted in a flash fire, damaging the house at that address. One person, a maintenance man working for the homeowner, was hospitalized with smoke inhalation. KeySpan Energy Delivery Company (“KeySpan” or “Operator”), the operator of the pipeline reported the incident to the U.S. Department of Transportation/Office of Pipeline Safety (Exh. 1).

The Department’s investigation included a review of compliance with the Dig Safe law. The procedures to determine the nature and extent of Dig Safe violations are contained in 220 C.M.R. §§ 99.00 et seq. In addition, these regulations set forth the standards used to determine the amount of civil penalties to be imposed. On December 30, 2002, the Department issued a Notice of Probable Violation (“NOPV”) to Solid Earth Technologies (“SET” or “Contractor”) (Exh. 2). In the NOPV, the Department alleged that a violation of the Dig Safe law occurred on October 30, 2002 on Marsh View Road, Chatham. SET signed a Consent Order (Exh. 3) on January 7, 2003.

As part of the Department’s annual certification process by the United States Department of Transportation (“DOT”), the Department must report to the DOT

“[e]ach accident or incident . . . involving a fatality, personal injury requiring

hospitalization, of property damage of loss of more than an amount the Secretary establishes, any other accident the [Department] considers significant, and a summary of the investigation by the authority of the cause and circumstances surrounding the accident or incident.”

See 49 U.S.C. § 60105(c)(1)(B).

The purpose of the report is to inform the DOT as to the circumstances surrounding and the cause of the incident.

The Department has established procedures for determining the nature and extent of the violations of codes and regulations pertaining to the safety of pipeline facilities and the transportation of gas, including, but not limited to, 220 C.M.R. §§ 101.00 through 113.00.

See 220 C.M.R. §§ 69.00 et seq. The Department also enforces the DOT safety standards for gas pipeline systems and the drug and alcohol testing regulation as set forth in 49 C. F. R. §§192.00 et seq. and §§ 199.00 et seq. and 220 C.M.R. § 69.12.

B. Overview of the Incident

At approximately 8:30 p.m. on October 30, 2002, KeySpan attempted to notify the Department of a fire at 82 Marsh View Drive, Chatham. On October 31, 2002, KeySpan reported that a Contractor, SET, had punctured the one-inch diameter plastic service line¹ while constructing a walkway to the house. The resulting failure allowed gas to leak into the house causing a fire where one person was hospitalized. The Department sent an investigator to the scene.

On October 28, 29 and 30, 2002, SET was constructing the plank walkway or

1 A service line is a distribution line that transports gas from a common source of supply to a customer meter . . . 49 C.F.R. §192.3: Definitions.

footbridge over marshy terrain to the house at 28 Marsh View Road. The walkway was anchored by metal stakes or piers. While drilling a pier into the marshy ground, SET contacted the high pressure² plastic service line, owned and operated by KeySpan. The service line was encased in a plastic conduit. The pier penetrated the conduit and the plastic service line. The small service line puncture allowed gas to enter the basement. The ignition source may have been a light switch operated by a maintenance man as he was leaving the half-basement (Exh. 4). Some of the insulation and the electrical wiring in the house was damaged by the resulting fire.

The Department's investigation finds that the contractor, SET, failed to notify Dig Safe prior to excavating in the vicinity of KeySpan's underground facilities. The Dig Safe law requires that notification be tendered at least 72 hours before excavating.

II. THE DEPARTMENT'S INVESTIGATION

A. Description of the Site

Marsh View Road is located in a residential area of Chatham adjacent to a salt water marsh. The houses are single family and are supplied with gas by means of a two-inch diameter plastic gas main (Exh 5). On the day of the incident, the main was operating at approximately 52 pounds per square inch gauge ("psig") (Exh. 6).

The house at 82 Marsh View is located on an island in the marsh (Exh. 7). A wooden walkway connects the island to Marsh View Road. The house is a one-story wood-frame

2 A high pressure system is a system in which the pressure in the main is higher than the pressure provided to the customer. 49 C.F.R. §192.3: Definitions.

construction, with a half-basement (Exh. 8).³

KeySpan tied the 608-foot plastic service line to the two-inch diameter plastic main in March 2002 (Exh. 9). The section of the service line that traversed the marsh was encased in a black plastic conduit. The conduit had been placed in the marsh by means of directional drilling. Similar conduits were installed nearby to carry telephone and electric cables (Exhs. 10a, b). The gas service line exited the conduit about 20 feet from the house (Exh. 11) and entered the half-basement through the northwest foundation wall. The customer meter and regulator were located outside of the building (Exh. 12).

B. Description of the Scene

On October 31, 2002 at about 12:30 p.m., an investigator from the Department's Pipeline Engineering and Safety Division ("Division") arrived at 82 Marsh View Road. He met with representatives from KeySpan and the Contractor.

The Division investigator observed that there was some fire and smoke damage in the half-basement. There was fire damage to the wood structure, electrical wiring and insulation in the half-basement (Exhs. 13a, b). The upper level of the house displayed no visible damage (Exh. 14).

The Department inspector observed that the curb valve⁴ was closed and the service line had been cut and capped near the house (Exh. 15). On October 31, 2002, KeySpan excavated

3 A half basement is a basement with a height of approximately 4 feet.

4 A curb valve is a manually operated valve on a service line located at or near the property line. Department regulations require that all high pressure service lines have a curb shutoff. 220 C.M.R. 101.06(14).

and disconnected the service line downstream of the curb valve, capping the live end. Then the service line was pulled out of the conduit (Exh. 16). The service line pipe had a puncture in it. There were some scuff marks on the pipe near the puncture (Exh. 17). Both the marks and the hole were located about 83 feet from the street end of the conduit.

C. KeySpan Gas Company

KeySpan was notified by the Chatham Fire Department (CFD) at 4:52 p.m. on October 30, 2002, of a fire and gas odor at 82 Marsh View Road. The service person that arrived found a gas reading of 30 percent gas in air at the foundation wall. In the lawn and garden in front of the house, the crew found 97 percent gas in air (Exh. 18). The gas concentration in the half-basement was 25 percent of the lower flammable limit (LFL).⁵ The crew shut the gas off at the curb valve after locating the probable area of the leak (Exh. 19). The service was also cut and capped near the house. After making the area safe, the crew left for the day.

D. The Contractor

The homeowner hired SET to reconstruct the walkway connecting the island to mainland. The walkway paralleled and was close to the gas service line (Exh. 9). The piers were drilled into the marsh (Exh. 20). Most of the piers were installed about six months prior to the incident (Exh. 4).

On Monday October 28, 2002, SET began installing additional new piers. SET told the

5 The LFL of natural gas is five percent gas in air; the upper flammable limit is 15 percent gas in air.

Department investigator that the pier at the location of the service line damage was drilled on Monday, October 28, 2002 (Exh. 21). SET continued working at the site the following two days. SET admitted that it had failed to tender notification to Dig Safe prior to installing the piers (Exh. 4).⁶ Instead, SET called the homeowner's maintenance man on Wednesday afternoon. The maintenance man said that the Contractor asked him where the gas line was located. SET told the maintenance man that they had to do some additional work on the piers (Exh. 4).

E. The Maintenance Man

After visiting the house on October 30, the homeowner called the maintenance man and asked him "... to check an unknown odor at the house." (Exh. 4). The maintenance man arrived at the house at about 3:15 p.m. The maintenance man smelled no gas outside or in the first floor of the house. After opening a hatch from the bedroom to the half-basement, he turned on the light switch and went down stairs. He stated that he smelled something, but he did not think it was natural gas. While going upstairs, he turned off the light switch (Exh. 22), and he saw a flash and some burning paper. He went upstairs and called the Chatham Fire Department. Upon seeing flames and smoke coming from the half-basement hatch, he

6 The Dig Safe Law, G. L. C. 82, § 40, requires an excavator to use care when excavating near underground utilities. G. L. c. 82, § 40C states, in the relevant part:

When excavating in close proximity to the underground facilities of any company when such facilities are to be exposed, non-mechanical means shall be employed, as necessary to avoid damage in locating such facility and any further excavating shall be performed employing reasonable precaution to avoid damage to the underground facilities, including but not limited to, . . . penetrating or destruction of any pipe . . . protective coating thereof, or damage to any pipe. . . .

unsuccessfully employed a small fire extinguisher and a garden hose. The dark smoke then forced him from the house. Shortly after, the Chatham Fire Department extinguished the fire. The maintenance man was admitted to Cape Cod Hospital overnight for treatment of smoke inhalation.

F. Examination of the Pipe

The service pipe was examined on the day after the incident by the Department investigator, representatives of KeySpan, and representatives of the Contractor. The service pipe had been cut and capped near the house on the previous day by KeySpan to make the area safe. The street end of the service pipe and the conduit had not been exposed (Exh. 21).

Once the street end of the service pipe and the conduit were exposed, the service pipe was extracted. There were scuff marks on the service pipe surface and there was also a hole in the service pipe (Exh. 17). The scuff marks and the hole were located 83 feet from service line cut made on the island (Exh. 21). On October 30, 2003, KeySpan excavated a small hole near the pier in question and a pool of water formed. KeySpan observed bubbles in the water. These were located in the marsh and were 83 feet from where the service line had been cut. (Exhs. 23a, b).

III. FINDINGS AND CONCLUSIONS

A. Findings

- (1) KeySpan Energy Delivery installed a two-inch diameter plastic main under Marsh View Road, Chatham in 2000.
- (2) KeySpan Energy Delivery installed the plastic service line to #82 Marsh View Road, Chatham, on May 12, 2002.
- (3) A one-inch diameter plastic service line connected the house at #82 Marsh View Road to the two-inch diameter plastic main on Marsh View Road.

82 Marsh View Road, Chatham, Massachusetts (October 30, 2002)

- (4) The service line was inserted in a plastic conduit in the marsh area.
- (5) Dig Safe was not notified by the Contractor of the work that began on October 28, 2002.
- (6) The Contractor was drilling piers for a new walkway.
- (9) The Homeowner first noticed an odor of gas in the house two days after the pier was installed.
- (10) The Maintenance man was in the house when the flash fire occurred.
- (11) The Maintenance man attempted, unsuccessfully, to put out the fire.
- (12) The Maintenance man suffered smoke inhalation, requiring hospitalization.
- (13) The flash fire damaged the wood structure, electrical wiring and insulation in the half-basement of the house.
- (14) The odorant level in the gas meet regulatory requirements.

B. Conclusions

- (1) The contractor, Solid Earth Technology is found to be in violation of the notification provisions of G. L. c. 82, § 40.
- (2) A pier, drilled by the Contractor on October 28, 2002, punctured the service line and the conduit in which it was located..
- (3) The puncture allowed gas to escape into the conduit.
- (4) Some of the gas flowed through the conduit to the island and into the ground.
- (5) The gas flowed into the half-basement of the house through penetrations in the foundation wall.
- (5) The gas was ignited by the maintenance man turning off the light switch.
- (6) The flash fire was attributable to hazardous gas concentrations in the house.

IV. LIST OF EXHIBITS

- Exhibit 1:** U. S. Department of Transportation Incident Reporting Form. (3 pages)
- Exhibit 2:** NOPV sent to Solid Earth Technologies. (3 pages)
- Exhibit 3:** Consent Order signed by Solid Earth Technologies. (2 pages)
- Exhibit 4:** Investigative Report by the Chatham Fire Department. (3 pages)
- Exhibit 5:** Map of Marsh View Road, Chatham, showing the location of the two-inch diameter main and the conduit through the marsh.
- Exhibit 6:** Telemetry reports of pressure readings at locations near Marsh View Road at the time of the incident.
- Exhibit 7:** View of the marsh, the island and the walkway to the island.
- Exhibit 8:** View of the half-basement.
- Exhibit 9:** Installation records of the service line to #82 Marsh View Road.
- Exhibit 10a:** View of electric conduit in the half-basement.
- Exhibit 10b:** View of the telephone conduit in the half-basement.
- Exhibit 11:** KeySpan Underground Damage Report. (2 pages)
- Exhibit 12:** View of gas meter and regulator located outside of the house.
- Exhibit 13a:** View of some of the fire damage to the electrical wiring.
- Exhibit 13b:** View of fire damage to wood structure, insulation and electrical wiring.
- Exhibit 14:** Close up view of the house. Orange cones show the location near the end of the conduit where the service was cut and capped.
- Exhibit 15:** View of the service where it was cut and capped on the island.
- Exhibit 16:** Service line being pulled out of the conduit
- Exhibit 17:** View of the service pipe showing the puncture and the scratches.

Exhibit 18: KeySpan Leak Investigation Report. (3 pages)

Exhibit 19: KeySpan Leak Repair Work Orders. (4 pages)

Exhibit 20: SET Brochure describing the piers and the installation process. (3 pages)

Exhibit 21: Memo from Paul Grieco, DTE, to Robert Smallcomb, DTE, November 1, 2002. (2 pages)

Exhibit 22: View of the light switch.

Exhibit 23a: View of pier at the location where the pipe was damaged.

Exhibit 23b: Close-up view of pier at the location where the pipe was damaged. Note the gas bubbles in the water.

Fax

To: Information Resources Manager Office of Pipeline Safety Research and Special Projects Administration U.S. Department of Transportation 400 Seventh Street, S.W. Washington, DC 20590	From: Stanley T. Kastanas Manager of Regulatory Compliance KeySpan Energy Delivery 201 Rivermoor Str. W. Roxbury, MA 02132
Fax: (202) 366-4566	Fax: (978) 459-0773
Phone: (800) 424-8802	Phone: (978) 815-8909
Date: 11/26/02	Pages: 3, including cover page
Re: Telephonic Incident Report #627826	CC: File

Urgent For Review Please Comment Please Reply Please Recycle

● **Comments:** Attached is Form RSPA F 7100.1 (3-84) regarding telephonic incident # 627826 reported on 10/31/02 by the above named fax sender. The sender is providing this follow-up written report (via this facsimile), on behalf of KeySpan, based on inpatient hospitalization reporting. However, the sender does not believe this event rises to the RSPA incident reporting criteria. To the best of KeySpan's knowledge, the contractor's person receiving inpatient hospitalization was for observation due to smoke inhalation. This happened when the contractor's person returned, presumably after an initial gas ignition in the home's crawl space, to fight a fire sustained by the secondary ignition of electrical wires or other materials. At your convenience, please advise KeySpan on such reporting criteria for future reference, or if you need any further information, by contacting the above named sender.

Thank you for your attention to this matter.

Stanley T. Kastanas

Exhibit 1: U. S. Department of Transportation Incident Reporting Form (1 of 3)

NOTICE: This report is required by 49 CFR Part 191. Failure to report can result in a civil penalty not to exceed \$1,000 for each violation for each day that such violation persists except that the maximum civil penalty shall not exceed \$200,000 as provided in 49 USC 1678. Form Approved OMB No. 2137-0522

INCIDENT REPORT - GAS DISTRIBUTION SYSTEM		Report Date
U.S. Department of Transportation Research and Special Programs Administration		11/26/02
PART 1: GENERAL REPORT INFORMATION		*SEE INSTRUCTIONS*
1. a. Operator's 5 digit Identification Number 11111	4. Reason for reporting <input type="checkbox"/> Fatality Number 1111 persons <input checked="" type="checkbox"/> Injury requiring inpatient hospitalization Number 10,011 persons <input type="checkbox"/> Property damage/loss Estimate \$. <input type="checkbox"/> Operator judgment/emergency action <input type="checkbox"/> Supplemental Report	No. (RSPA)
b. Name of Operator <u>KeySpan Energy Delivery</u>	5. Elapsed time until area was made safe <u>10.2</u> hr. <u>00</u> min.	
c. <u>201 Rivermoor Street</u> Number and Street	6. Telephone Report <u>1101</u> mo. <u>1311</u> day <u>1021</u> yr.	
d. <u>West Roxbury, MA 02132</u> City, County, State and Zip Code	7. a. Estimated pressure at point and time of incident (PSIG) <u>52</u>	
2. Location of Incident	b. Maximum allowable operating pressure (MAOP)(PSIG) <u>60</u>	
a. <u>82 Marshview Road</u> Number and Street	c. MAOP established by: (1) Test pressure <u>70</u> (PSIG) (2) 49 CFR § 192.619 (e)(3) <input type="checkbox"/>	
b. <u>Chatham</u> City and County		
c. <u>MA</u> State and Zip Code		
d. Class location <input type="checkbox"/> 1 <input type="checkbox"/> 2 <input checked="" type="checkbox"/> 3 <input type="checkbox"/> 4		
e. Incident on Federal land <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		
3. Time and date of Incident <u>11/16/02</u> hr. <u>1101</u> mo. <u>1310</u> day <u>1021</u> yr.		
PART 2: APPARENT CAUSE		
<input type="checkbox"/> Corrosion (Continue in Part A)	<input checked="" type="checkbox"/> Damage by Outside Forces (Continue in Part B)	<input type="checkbox"/> Construction/Operating error (Continue in Part C)
<input type="checkbox"/> Accidentally caused by operator (Continue in Parts B and/or C)	<input type="checkbox"/> Other _____	
PART 3: NARRATIVE DESCRIPTION OF FACTORS CONTRIBUTING TO THE INCIDENT (Attach additional sheet(s) as necessary)		
<u>Third party damage during construction of stake supported footbridge for a home. The stake pierced through the 2" CTS service line allowing escape of natural gas.</u>		
PART 4: ORIGIN OF THE INCIDENT		
1. Part of system where incident occurred <input type="checkbox"/> Main <input type="checkbox"/> Meter Set Assembly <input checked="" type="checkbox"/> Service Line <input type="checkbox"/> Other _____	2. Component which failed a. Part <input checked="" type="checkbox"/> Body of pipe <input type="checkbox"/> Valve <input type="checkbox"/> Joint type <input type="checkbox"/> Regulator/meter <input type="checkbox"/> Fitting <input type="checkbox"/> Weld (Specify: _____ (girth, longitudinal, fillet)) <input type="checkbox"/> Drip/Riser <input type="checkbox"/> Other _____	
3. Material involved: <input type="checkbox"/> Steel <input type="checkbox"/> Cast Iron <input checked="" type="checkbox"/> Polyethylene plastic <input type="checkbox"/> Other plastic: _____ <input type="checkbox"/> Other _____	Nominal pipe size (NPS) <u>CTS 1.1001</u> in. Wall thickness <u>1.0901</u> in.	
4. Specification <u>TE 2106</u> Manufacturer <u>Discoplex</u> Yr Manufactured <u>210121</u> Yr Installed <u>210121</u>		
PART 5: ENVIRONMENT		
Area of incident <input type="checkbox"/> Within Under bldg <input type="checkbox"/> Under pavement <input type="checkbox"/> Above ground <input checked="" type="checkbox"/> Under ground or Under water <input type="checkbox"/> Other _____		
PART 6: PREPARER AND AUTHORIZED SIGNATURE		
<u>Stanley T. Kastanas, Manager Regulatory Compliance 617 723-5572</u> (Type or print) Preparer's Name and Title Area Code and Telephone Number		
<u>Stanley T. Kastanas</u> Authorized Signature	<u>11/26/02</u> Date	<u>978-815-8909</u> Area Code and Telephone Number

Form RSPA F 7100.1 (3-84)

Reproduction of this form is permitted.

Exhibit 1: U. S. Department of Transportation Incident Reporting Form (2 of 3)

PART A: CORROSION *N/A*

1. Where did the corrosion occur?
 Internally
 Externally

2. Visual Description
 Localized pitting
 General corrosion
 Other _____

3. Cause
 Galvanic
 Other _____

4. Pipe coating information
 Bare Coated

5. Was corroded part of pipeline considered to be under cathodic protection prior to discovering incident?
 Yes Year protection started
 No

6. Additional information:

PART B: DAMAGE BY OUTSIDE FORCES

1. Primary cause of incident
 Damage resulted from action of operator or his agent.
 Damage resulted from action by outside party/third party.
 Damage by earth movement
 Subsidence
 Landslide/washout
 Frost
 Other _____
 Damage by lightning or fire

2. Locating information (for damage resulting from action of outside party/third party)
a. Did operator get prior notification that equipment would be used in the area?
 Yes Date received mo. day yr.
 No
b. Was pipeline location marked either as a result of notification or by markers already in place? *N/A*
 Yes Permanent markers Temporary stakes Other _____
 No
c. Does statute or ordinance require the outside party to determine whether underground facility (ies) exist?
 Yes
 No

3. Additional Information:
No record of Dig-safe (one-call-system) exists to verify any notification to KeySpan. (This was confirmed with Dig safe)

PART C: CONSTRUCTION DEFECTS *N/A*

1. Cause
 Poor workmanship during construction
 Physical damage during construction
 Operating procedure inappropriate
 Error in operating procedure application
 Other _____

2. Additional information:

PART D: OTHER

Brief Description:
Contractor or contractor's representative or subcontractor, drove a stake through 1" CTS service line. The escaping natural gas apparently traveled through a conduit that terminated in the home's crawlspace. There was an initial ignition, but it appears that any fire was sustained by electrical wiring, or other materials and was subdued by contractor. Contractor was not injured by initial ignition, but inhaled smoke when he returned to fight fire.

Form RSPA F 7100.1 (3-84)

Exhibit 1: U. S. Department of Transportation Incident Reporting Form (3 of 3)



THE COMMONWEALTH OF MASSACHUSETTS
OFFICE OF CONSUMER AFFAIRS AND BUSINESS REGULATION

DEPARTMENT OF
TELECOMMUNICATIONS & ENERGY

ONE SOUTH STATION

BOSTON, MA 02110
(617) 305-3500

JANE SWIFT
GOVERNOR

JENNIFER DAVIS CAREY
DIRECTOR OF CONSUMER
AFFAIRS
AND BUSINESS REGULATION

FILE

PAUL B. VASINGTON
CHAIRMAN

JAMES CONNELLY, ESQ.
COMMISSIONER

W. ROBERT KEATING
COMMISSIONER

EUGENE J. SULLIVAN, JR.
COMMISSIONER

DEIRDRE K. MANNING
COMMISSIONER

CERTIFIED MAIL - RETURN RECEIPT REQUESTED

December 30, 2002

Solid Earth Technologies
3 Howe Drive, Unit 3
Amherst, NH 03031

SUBJECT: NOTICE OF PROBABLE VIOLATION

To Whom It May Concern:

Based on information submitted to the Department of Telecommunications and Energy ("Department"), the Department has reason to believe that you performed excavations on or about October 30, 2002, on Marshview Road, West Chatham, without complying with the provisions of Chapter 82, Section 40 of the General Laws ("Dig Safe Law").

In a report submitted by KeySpan Energy Delivery, it is alleged that you failed to tender proper notification to the underground utility operators and failed to exercise reasonable precaution which resulted in damage to an underground utility operated by that company at the location and on the date indicated in the preceding paragraph.

If you are found to have violated the "notification provision" of the statute and/or the "reasonable precaution" provision, you will be required to pay a civil penalty of \$500.00, being a first offense within the past 12-month period.

You have a right to appear before a Department Investigator in an informal conference on January 28, 2003 at 9:15 A.M., at the Department's offices at One South Station, 2nd floor, Boston. You have a right to be represented at the informal conference by an attorney or other

FAX: (617) 345-9101 TTY: (800) 323-3298
www.mass.gov/dps

Exhibit 2: NOPV sent to Solid Earth Technologies (1 of 3)

FILE

-2-

person, and you have the right to present relevant documents to the Investigator at the conference. At the informal conference, the Investigator will make available to you any evidence which indicates that you may have violated the law, and you will have the opportunity to rebut this evidence.

If you wish to dispute the allegations in this notice but do not want to come to the informal conference, you may respond to the Department at the above address a written reply to this notice. This written reply must be filed with the Department on or before January 28, 2003, and must be signed by you. The reply must include a complete statement of all relevant facts to include:

(1) Proof that proper notification was tendered to the operator(s) prior to excavating. This proof may be in the form of a proper Dig Safe number or a copy of a certified letter to each operator with facilities in that area.


(2) In the cases where an underground operator's facilities sustained damage, a complete description of the precautions you took to protect the underlying facilities and why those precautions failed.

If you do not choose to dispute the violations alleged in this notice, you should sign and return the enclosed consent order. The consent order must be accompanied by the check or money order for \$500.00, being a first offense within the past 12-month period, made payable to the Commonwealth of Massachusetts, and mailed to the Department of Telecommunications and Energy, Pipeline Engineering and Safety Division, One South Station, Boston, MA 02110.

If you do not respond to this notice as specified above by January 28, 2003, you will be deemed to have admitted the allegations and will be subject to statutory civil penalties.

If you have any questions concerning this notice, please direct your inquiries to Virgil Glenn at (617) 305-3537. Also direct all written responses to Mr. Glenn at the above address or you may fax your response to (617) 478-2589.

Very truly yours,


Robert F. Smallcomb
Director

RFS/dh
Enclosure

Exhibit 2: NOPV sent to Solid Earth Technologies (2 of 3)

MASSACHUSETTS DEPARTMENT OF TELECOMMUNICATIONS AND ENERGY
PIPELINE ENGINEERING AND SAFETY DIVISION
REPORT OF DIG-SAFE VIOLATION AND/OR
DAMAGE TO UNDERGROUND FACILITIES

NO #
NO PER

FILE

Date: 11-18-02

Reporting Party/Telephone No.: KeySpan Energy Delivery (617) 723-5512

Mailing Address: One Beacon Street, Boston, MA 02108

Person Reporting: Deane M Moore (Tel: (617) 723-5512 X4521)

Location, Date and Time of Incident: 82 Mansfield Rd, West Chatham
10-30-02

Operator of Underground Facility: KeySpan Energy Delivery - Cape Division

Facility Sitting: In a public way On private property

Injury Occurred: Yes No If yes, describe: _____

Damage Occurred: Yes No If yes, provide a technical description of the damaged facility to include: Type of facility (service, main, other), material, pressure/voltage, depth of cover, repair costs and other pertinent data:

1" plastic service Pressure H.P. Depth: _____
Estimated cost of repairs: \$ 773.41 Surface Removed: Yes No

Year of installation (if less than 12 months, provide month and year.) _____

Description of activity causing damage, citing any lack of precautions:
Contractor damaged service installing support post

Were marks within 18" of facility?: Yes No
Were photographs taken?: Yes No
Is the excavator being held liable for damages?: Yes No

When was the incident reported and by whom?: 10-30-02 Contractor

Excavation Company: Solid Earth Technologies Tel. No.: 603-882-5319
Address: 3 Howe St Unit 3, Amherst, N.H. Zip: 03031
Equipment/Registration No.: prot digger Operator: _____

Dig-Safe Number: None found Attach Dig-Safe message, if applicable.

If additional remarks are necessary to fully describe the disposition of the above, please attach a separate sheet. ✓

Exhibit 2: NOPV sent to Solid Earth Technologies (3 of 3)



The Commonwealth of Massachusetts
DEPARTMENT OF
TELECOMMUNICATIONS AND ENERGY

FILE

CONSENT ORDER

1. This document is a consent order entered into between the Department of Telecommunications and Energy of the Commonwealth of Massachusetts ("Department") and Solid Earth Technologies ("Respondent").

2. The Department finds that a violation occurred on October 30, 2002, on Marshview Road, West Chatham.

3. Pursuant to 220 C.M.R. § 99.11(1), this Consent Order need not constitute an admission by the Respondent that a violation occurred.

4. The Department, pursuant to the terms of this Consent Order, hereby imposes upon the Respondent a civil penalty of \$500.00, being a first offense, pursuant to G.L. c. 82 § 40A, § 40E, and 220 C.M.R. § 99.12. The Respondent hereby agrees, upon signing and returning this Consent Order to the Department, to attach payment of the penalty by check or money order payable to the Commonwealth of Massachusetts.

5. The Department and the Respondent also agree that this Consent Order shall constitute a final Order of the Department. The Respondent hereby expressly waives any and all right of appeal or right of judicial review that might otherwise attach to a final Order of the Department.

1-7-03

Date


PRESIDENT
Solid Earth Technologies

1-14-03

Date


Robert F. Smallcomb
Director
Pipeline Engineering & Safety Division
Department of Telecommunications and Energy

3

Exhibit 3: Consent Order signed by Solid Earth Technologies
(1 of 2)

CHATHAM FIRE-RESCUE & EMERGENCY SERVICE DEPARTMENT

William Schwerdtfeger
Chief of Department

FAX COVER SHEET

DATE: 11/1/02
TO: PAUL
FAX: 617-478-2589
COMPANY: _____
FROM: R. HUNTER, DEPUTY
Number of Pages (including cover sheet) 3
Comments:

STATEMENT OF CONFIDENTIALITY: The pages accompanying this facsimile cover sheet contain information from the CHATHAM FIRE-RESCUE which may be CONFIDENTIAL and intended only for the use of the addressee listed on this cover sheet. If the reader of this message is not the intended recipient, you are hereby notified that any dissemination, distribution or copying of this information is strictly prohibited.

135 DEPOT ROAD - CHATHAM, MA 02633
(508) 945-2324 - FAX (508) 945-5120

new FAX cover sheet

Exhibit 4: Investigative Report by the Chatham Fire Department
(1 of 3)

INVESTIGATIVE REPORT

Incident #021905
31 October 2002
82 Marshview Rd
West Chatham
Structure Fire

The following narrative is based upon an interview conducted with Mr. Leonard Savery at the Intensive Care Unit of Cape Cod Hospital, on this date.

Mr. Jeffrey Taylor, owner of the property visited the dwelling during the morning of Wednesday, 30 October. Sometime between 1200 & 1300 hours, Mr. Taylor called Mr. Savery and asked his to check an unknown odor in the house.

At approximately 1515 hours, Mr. Savery visited the dwelling. He states he did not notice an odor of natural gas as he crossed the marsh or approached the dwelling. He entered the dwelling and stated he did not notice an odor of gas. He then went to the bed room, opened the access hatch to the basement crawl space and proceeded down the steps, turning on the light switch as he did so. He looked around, saw nothing, and smelled an unusual odor, which he did not attribute to gas. He then climbed the steps, turning off the light switch as he did so. There was an immediate flash fire which he described as being very small. He looked down into the basement and saw what he thought to be paper burning on a shelf area. He reached down and brushed the burning material onto the floor with his hand. He then proceeded to the kitchen and began to place a call the Chatham Fire & Rescue Department. As he did so the other telephone line rang and he hung up and answered. The call was from the alarm company inquiring if help was needed as they were receiving an alarm from the dwelling. Before he could answer, he looked back in the direction of the bedroom and observed flames and heavy black smoke emitting from the open hatch. He hung up, located a small (dry chemical) fire extinguisher and attempted to contain the fire, without success. He then went outside and located a garden hose which he connected to and outside faucet. He returned to the bedroom door, observed an even greater volume of fire and smoke emitting from the opening, took a deep breath and entered the bedroom. He then sprayed water on the fire for as long as he could stand the smoke. He did this several time until he no longer saw any fire. Shortly thereafter he met Captain Roy Eldredge in front of the dwelling.

When questioned about the installation of the gas line to the island, he stated Bay State Gas Company did the installation in February of 2002. When questioned about the installation of the "screw piers" the new supports for the 400 +/- long footbridge, connecting the island to the main land, he stated Solid Earth Technologies of Amhurst, N.H., had installed most of the piers some six months ago. He went on to state the company had been working the site on Monday, Tuesday and Wednesday of this week, and that on Wednesday afternoon, he received a call from Mike Parkhurst, superintendent of the Solid Earth Technologies company, inquiring where the gas line was, since some work was required on the piers.

Exhibit 4: Investigative Report by the Chatham Fire Department
(2 of 3)

Incident #021905, page two.

NSTAR Gas Company conducted an investigation which included the removal of the underground gas service from the sleeve under the marsh. They determined the gas line had been damaged by the pier, causing a leak approximately twenty feet from the island out in the marsh.

It is believed the gas emitting from the damaged pipe migrated to the island and found its way into the basement by one of two avenues. One was via the sleeve in which the gas line was contained. In this scenario, the gas exited the end of the sleeve some ten feet from the dwelling, underground, then migrated into the basement. In the other, the sleeve containing the electric service was also damaged, and the gas entered the basement directly through the electric service panel. No effort has been made to determine if the electric sleeve has been damaged.

It is reported Dig Safe was not initiated prior to the installation of the screw piers.

Well after Mr. Savery was transported to the hospital, this department checked the basement with a combustible gas meter and found the LEL to be 89%. Natural gas has an ignition parameter of 5 to 15%, and it is believed the initial high concentration of natural gas in the basement prevented an ignition as Mr. Savery entered. The "venting" of the basement by opening the hatch, at least in the area of the switch, which is located just inside the hatch way, reduced the concentration of gas to a level conducive to ignition.



William Schwerdtfeger
Chief of Department

Exhibit 4: Investigative Report by the Chatham Fire Department
(3 of 3)

Example 2D - OPERATING PRESSURES

<u>Telemetry Location</u>	<u>Press (PSI)</u>	<u>DATE</u>	<u>TIME</u>			
CMSC_CHATHAM_PRESS	54.18	10/30/02	11:00	AVERAGE	Data is valid	No Alarm - OK
CMSC_CHATHAM_PRESS	53.65	10/30/02	12:00	AVERAGE	Data is valid	No Alarm - OK
CMSC_CHATHAM_PRESS	53.73	10/30/02	13:00	AVERAGE	Data is valid	No Alarm - OK
CMSC_CHATHAM_PRESS	53.24	10/30/02	14:00	AVERAGE	Data is valid	No Alarm - OK
CMSC_CHATHAM_PRESS	52.88	10/30/02	15:00	AVERAGE	Data is valid	No Alarm - OK
<i>Incident</i> → CMSC_CHATHAM_PRESS	52.37	10/30/02	16:00	AVERAGE	Data is valid	No Alarm - OK ← <i>Incident</i>
CMSC_CHATHAM_PRESS	52.30	10/30/02	17:00	AVERAGE	Data is valid	No Alarm - OK
CMSC_CHATHAM_PRESS	52.50	10/30/02	18:00	AVERAGE	Data is valid	No Alarm - OK
CMSC_CHATHAM_PRESS	52.33	10/30/02	19:00	AVERAGE	Data is valid	No Alarm - OK
CMSC_CHATHAM_PRESS	52.68	10/30/02	20:00	AVERAGE	Data is valid	No Alarm - OK
CMSC_CHATHAM_PRESS	52.95	10/30/02	21:00	AVERAGE	Data is valid	No Alarm - OK
CMSC_CHATHAM_PRESS	53.49	10/30/02	22:00	AVERAGE	Data is valid	No Alarm - OK
CMSC_CHATHAM_PRESS	54.00	10/30/02	23:00	AVERAGE	Data is valid	No Alarm - OK
CMSC_CHATHAM_PRESS	54.00	10/31/02	0:00	AVERAGE	Data is valid	No Alarm - OK
CMSC_CHATHAM_PRESS	54.00	10/31/02	1:00	AVERAGE	Data is valid	No Alarm - OK
CMSC_CHATHAM_PRESS	53.98	10/31/02	2:00	AVERAGE	Data is valid	No Alarm - OK
CMSC_CHATHAM_PRESS	53.57	10/31/02	3:00	AVERAGE	Data is valid	No Alarm - OK
CMSC_CHATHAM_PRESS	53.20	10/31/02	4:00	AVERAGE	Data is valid	No Alarm - OK
CMSC_CHATHAM_PRESS	52.56	10/31/02	5:00	AVERAGE	Data is valid	No Alarm - OK
CMSC_CHATHAM_PRESS	51.24	10/31/02	6:00	AVERAGE	Data is valid	No Alarm - OK
CMSC_CHATHAM_PRESS	51.41	10/31/02	7:00	AVERAGE	Data is valid	No Alarm - OK
CMSC_CHATHAM_PRESS	52.44	10/31/02	8:00	AVERAGE	Data is valid	No Alarm - OK
CMSC_CHATHAM_PRESS	53.91	10/31/02	9:00	AVERAGE	Data is valid	No Alarm - OK
CMSC_CHATHAM_PRESS	54.78	10/31/02	10:00	AVERAGE	Data is valid	No Alarm - OK
CMSC_CHATHAM_PRESS	55.11	10/31/02	11:00	AVERAGE	Data is valid	No Alarm - OK
CMSC_CHATHAM_PRESS	55.70	10/31/02	12:00	AVERAGE	Data is valid	No Alarm - OK

Exhibit 6: Telemetry reports of pressure readings at locations near Marsh View Road at the time of the incident.



Exhibit 7: View of the marsh, the walkway to the island and the island.




Exhibit 8: View of the half-basement.




Exhibit 10a: View of electric conduit in the half-basement.




Exhibit 10b: View of the telephone conduit in the half-basement.

EXAMPLE 4

UNDERGROUND DAMAGE REPORT

Mon	Day	Yr	Project#	Task	Work Order#
10	3	02	CPE1424285	2285	2285

LOCATION STREET ADDRESS W. Chatham CITY/TOWN

FACILITIES DAMAGED MAIN SERVICE OTHER _____

SIZE 1" PRESSURE LOW I.P./M.P. H.P.

STEEL PLASTIC C.I. COPPER

DEPTH FROM ORIGINAL GRADE 2'-8"

CONTRACTOR/EXCAVATOR'S NAME Solid Earth Tech.

CONTRACTOR'S ADDRESS 3 Howe Dr. Unit 3A, H03

EQUIPMENT CAUSING DAMAGE Part for new walkway

REGISTRATION OF EQUIPMENT _____

MARKINGS ON EQUIPMENT phone # 877-389-782

OF OPERATOR _____

CONTRACTOR DIG SAFE # _____

FACILITY LOCATION PUBLIC PROPERTY PRIVATE PROPERTY

GAS MARKINGS VISIBLE YES NO

METHOD OF MARKOUT OFFSET CENTER LINE

STAKES FLAGS

IF MARKINGS ARE VISIBLE ARE MARKINGS CORRECT YES NO

DISTANCE MARKINGS OFF _____

SURFACE TYPE ASPHALT GRAVEL GRASS Marsh CONCRETE/BRICK

SURFACE REMOVED YES NO

PICTURES TAKEN YES NO

THIS REPORT BY Coulter Gilbert TITLE MIF-Superv

PLEASE PRINT

Exhibit 11: KeySpan Underground Damage Report (1 of 2)

NATURE OF WORK
 SEWER WATER ROAD CONSTRUCTION
 CONDUIT INSTALLATION LANDSCAPING OTHER walkway

NATURE OF ACTIVITY
 EMERGENCY NON-EMERGENCY

WAS GAS SHUT OFF BY FLOW LIMITER YES NO

SIZE OF HOLE IN PIPE (FOR VOLUME LOSS CALCULATION) 1/4" slice
TIME MADE SAFE (NEED FOR LOSS OF GAS CALCULATION) 19:15

DESCRIPTION OF INCIDENT
Called to location for part explosion, upon arrival found clear leak, 20% at foundation 1" plastic service had been damaged by contractor installing support post for new walkway over mach area. Turned off at gate box to make safe. Flt at river area dug hole at 100' reading 20' from house, found end of 2" sleeve, left hole open to vent gas away from house.

CONTRACTOR DIG SAFE INFORMATION
FOR OFFICE USE ONLY
Compliance with M.G.L., C. 82, S. 40 as Amended:
Dig Safe No. _____ Date Reported _____
72 Hour Did Safe Notice Yes No
Dis Safe Violation Yes No

CLAIM TO BE MADE Yes No

PICTURES TAKEN BY FIELD SUPERVISOR Yes No

GROUP LEADER Coulter DATE 10/30/02

FORM NO. 1174A REV. 8/99

Exhibit 11: KeySpan Underground Damage Report (2 of 2)




Exhibit 12: View of the gas meter and regulator located outside of the house.



Exhibit 13a: View of some of the fire damage to the electrical wiring.



Exhibit 13b: View of fire damage to the wood structure, insulation and electrical wiring.



Exhibit 14: Close up view of the house. Orange cones show the location near the end of the sleeve where the service was cut and capped.



Exhibit 15: View of the service where it was cut and capped on the island.



Exhibit 16: Service line being pulled out of the sleeve.



Exhibit 17: View of the service pipe showing the puncture and scratches.

EXAMPLE 2




LEAK INVESTIGATION REPORT

PREMARKED DATE: _____ PROJECT # _____
 DATE: 10/30/02 REPORTED BY: CONTRACTOR/FIRE TIME TAKEN: 5:30 PM LEAK # _____
 ADDRESS: 84 MARSH BLVD AVE CITY/TOWN: CHATHAM JOB # _____

LEAK CLASSIFICATION		LEAK STAND-BY		PREMISE CONDITION REPORT	
Grade I	<input checked="" type="checkbox"/>	Yes	<input checked="" type="checkbox"/>	Yes	<input checked="" type="checkbox"/>
Grade II	<input type="checkbox"/>	No	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
Grade III	<input type="checkbox"/>				
TYPE OF AREA		PRESSURE		ODOR PRESENT	
Rural	<input type="checkbox"/>	High	<input checked="" type="checkbox"/>	Yes	<input checked="" type="checkbox"/>
Residential	<input checked="" type="checkbox"/>	Intermediate	<input type="checkbox"/>	No	<input type="checkbox"/>
Urban	<input type="checkbox"/>	Low	<input type="checkbox"/>		

SURVEY TYPE / PROJECT #	PROJECT #
Public	136
Employee	136
Winter Patrol	148
Summer F.I.	140
Walking	144
Re-Check	132
C.I. Encroachment	128
Prepave	134
Special	138
Contractor	142
Building	130
Business District	130



CGI TEST	
Positive	<u>97</u> % <input checked="" type="checkbox"/>
Negative	<input type="checkbox"/>

LEAK APPEARS TO BE ON	
Main	<input type="checkbox"/>
Service	<input checked="" type="checkbox"/>
Drp	<input type="checkbox"/>
Curb Valve	<input type="checkbox"/>
Main Valve	<input type="checkbox"/>
Other	<input type="checkbox"/>

METHOD OF TEST	
Portable F.I.	<input type="checkbox"/>
Mobile F.I.	<input type="checkbox"/>
CGI	<input checked="" type="checkbox"/>
Selected Test	<input type="checkbox"/>
Other	<input type="checkbox"/>

COVER	
Asphalt	<input type="checkbox"/>
Concrete	<input type="checkbox"/>
Brick	<input type="checkbox"/>
Gravel	<input type="checkbox"/>
Soil	<input checked="" type="checkbox"/>
Other	<input checked="" type="checkbox"/>

COMMENTS:
 READINGS IN CRAWL SPACE 0.25 ON ARRIVAL / 30% AT FOUNDATION
 CALLED SUPERVISOR + STREET CREW
 SHUT GAS OFF AFTER LEAK WAS LOCATED
 GAS LEAK WAS MIGRATING THROUGH SLEEVE TO HOUSE FROM MARSH

CONTACTED: CREW LEADER Y N
 SUPERVISOR Y N KEITH COLTER
STEVE CALLAGHAN COMPANY REPRESENTATIVE 25350 EMPLOYEE #
 _____ CONSULTANT REPRESENTATIVE _____ COMPANY _____

GAS DETECTED IN	
Atmosphere	<input checked="" type="checkbox"/>
Bar Hole	<input checked="" type="checkbox"/>
Manhole	<input type="checkbox"/>
Valve Box	<input type="checkbox"/>
Main Valve	<input type="checkbox"/>
Curb Valve	<input type="checkbox"/>
Thru Foundation	<input checked="" type="checkbox"/>

Exhibit 18: KeySpan Leak Investigation Report (1 of 3)

**PREMISE INVESTIGATION SUMMARY
(FOR E.R.U. USE ONLY)**

LIST ALL ADDRESSES IN THE ORDER THAT THEY WERE CHECKED

LEAK MONITORING RESULTS

ADDRESS	READ	COMMENTS	DATE	READ	COMMENTS
1 84 MESH VIEW	47%	30' AT CALIBRATION			
2					
3					
4					
5					
6					
7					
8					
9					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					

LEAK INVESTIGATION COMPLETED

YES
NO

START TIME
END TIME
TOTAL TIME

5:30
11:00
5:30

COMMENTS:

**Exhibit 18: KeySpan Leak Investigation Report
(2 of 3)**

INCIDENT / LEAK FORM CPE 136

Date	Time	Reported By	Token By	Area	Job #	Leak #	Grade
10-30-02	1652	Chm Fire Dept	24608		283856		L
Customer Name		Street #	Pre	Street Name	Suf	Suite	Town
		82		Manstevier	RD		Chm
@ INTERSECTION OF:				Pre	Intersecting Street		Suf
Remarks:							
inside 125 is a fl/wall Men cont. Turned on							
lights + gas ignited in basement 30% AT DISTANCE							
TERRIBLE FIRE							
Strong odor outside. Call in street @ 1912							
S-rep	25350 / per to Capa Cont Hattip. (Sam Savery) Contractor						
Crew Name/Number	Time	Ref By	Dig Safe #	Time	Ref By		
Adamo / Helbert	1849	24608	20024402286	1911	24608		
Supervisor	Time	Ref By	Legal Dept	Time	Ref By		
Jacobsen, S	1900	R. LEAN	T. VIGENT	1912	R. LEAN		
Supervisor	Time	Ref By	Public Relations	Time	Ref By		
Coalter K	1836	1837	J. CANNELL	1950	R. LEAN		
Dispatch Manager	Time	Ref By	Gas Supply	Time	Ref By		
J. Mac. A. GIBSE	1947	R. LEAN					
Director	Time	Ref By	Fire Dept	Time	Ref By		
Ed. LEE	1850	D. HENNING					
V.P.	Time	Ref By	Police Dept	Time	Ref By		
Damage Prevention	Time	Ref By	Other/Follow-up	Time	Ref By		
ME	Repair Information						
AT	Called DTE 1900 + 2030						

KEYSPAN
Energy Delivery

FAX

(EXAMPLE 1)

Exhibit 18: KeySpan Leak Investigation Report
(3 of 3)

FWMS - WORK ORDER COMPLETION FORM

Street Address: St. Mary's Organization: St. Mary's Finish Date (if Diff): 1st 2nd 3rd
 Town: St. Mary's Start Date (immediately): 1/23/06 Crew Shift: 1st 2nd 3rd
 Day of Week: Sun Mon Tues Wed Thur Fri Sat

Cost Center #: CA 442 Activity #: A 4185 Activity #: B Activity #: C
 Work Order #: 183856

New Valve Repair St. Light New Valve Repair St. Light
 Leak Survey Meter Relocate Leak Survey Meter Relocate
 Misc. Other Stop/Blockage Misc. Other Stop/Blockage
 New Regulator New Regulator
 New St. Light New St. Light

Abandon Main Abandon Regulator Abandon Service Abandon St. Light
 Callback to Worksite Corrosion Request Emergency Repair
 Inspect Pipe Marker Inspect Pipe

Overtime Code: Extended Call-In Scheduled

Job Complete: YES NO

Police Hours: _____ Police Minimum? Yes No

Crew ID: 77-57106 Field Supervisor: _____ Approved By: _____

Activity (Circle)	Yard Work	Travel	Site	Other	Start Time	Finish Time	Crew ST Hours	Crew OT Hours
A/B/C	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	1:00	4:00	1.0	1.0
A/B/C	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	10:00	1:30	3.0	3.0
A/B/C	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	2:30	4:00	1.0	1.0

OPERATIONS STANDARD UNITS ACTIVITIES:

Activity	A	B	C
General			
Install 2 Wire Test Station			
Install 4 Wire Test Station			
Locate/Adjust Box			
Main Anode & Insulator			
Main Anode & Test Sta			
Main Anode & Test Sta			
Main Clear Underground			
Main Insulate			
Main Repair Coating			
Repair 4 Wire Test Sta			
Buried Pipelines Inspection			
Service Anode			
Svc Anode, Insul. & Test Sta			
Service Anode & Test Sta			
Leak Repair			
Investigate			
Pinpoint			
Aerator/Purge			

SERVICE WORK:

Activity	A	B	C
Abandon			
Adjust Box			
Replace Box			
Drip Repair			
Joint Repair			
Minor Relay			
Capital Main Relay			
Broken Pipe Repair			
Rusted Pipe Repair			
Stoppage Repair			
Valve Repair			
Relocate Meter In-Out			
Meter Protection			
Restoration			
Pickup(PUB/PUD/PUC)			
Digout Depression			
Patch Depression			
Other Surface Restore			
Other (AO, Mig, Trng)			

MISC. WORK ORDER COMPLETION:

Repair Activity	A	B	C
High			
Medium			
Intermediate			
Low			
Clamped			
Sealed			
Cut-Off			
Grease Valve			
Plastic Relay/Anson			
Inside Leak			
Regulator			
Repair Filling			
Steel Filling			
Steel Relay			
Tap Connection			
Other Location			
Other Repair			

RGD/RECONNECT/STANDBY: A B C
 RGD's Performed: Y / N / House Heater Water Heater Range Other Standby Performed: Yes No Reconnect Performed: Yes No

PRESSURE TEST RESULTS: A B C
 Pressure: _____ PSIG Duration: _____ Hrs:Min: _____

Chart Recorder Used: Yes No

Leak Cause: Corrosion Damage Mal/Direct Constr/Direct Natural Causes Other Causes

Exhibit 19: KeySpan Leak Repair Work Orders (1 of 4)

Street Address: _____ Town: _____
 Cross Street: _____

Construction Activity:
 Main Conn.
 Main Relay
 New Services
 Insert

RESTORATIONS (OPENINGS)

FIELD SKETCH

Opening Site

<input type="checkbox"/>	Street
<input type="checkbox"/>	Sidewalk
<input type="checkbox"/>	Lawn (Pri Prop)

Original Surface

<input type="checkbox"/>	Asphalt
<input type="checkbox"/>	Concrete
<input type="checkbox"/>	Gravel
<input type="checkbox"/>	Cobblestone
<input type="checkbox"/>	Grass
<input type="checkbox"/>	Brick
<input type="checkbox"/>	Conc&Asph
<input type="checkbox"/>	Brick&Cobble

Paving Method

<input type="checkbox"/>	Hot Patch
<input type="checkbox"/>	Loam&Seed
<input type="checkbox"/>	Cust. Reimb.
<input type="checkbox"/>	None
<input type="checkbox"/>	Cold Patch

Paving Contr. Notified Yes No


Length: _____ ft
Width: _____ ft
DCP Drops: _____ in.
Lifts: _____
Lift Thickness: _____ in.

Pick Ups

<input type="checkbox"/>	Done
<input type="checkbox"/>	Req'd
<input type="checkbox"/>	Not Req'd

Dirt
 Plate(s)
 Barricade/Cone
 Spoil Bag

Opening Sketch



EXPOSED PIPE (UNDERGROUND BURIED PIPE)

Activity A B C

Opened By	Material	Service	Pipe Condition	Main	Service	Fitting Type	Main	Service	Fitting Condition	Main	Service
<input checked="" type="checkbox"/> Company	<input type="checkbox"/> Plastic	<input checked="" type="checkbox"/> Service	<input type="checkbox"/> No Corrosion	<input type="checkbox"/> Main	<input checked="" type="checkbox"/> Service	<input type="checkbox"/> Joint	<input type="checkbox"/> Main	<input checked="" type="checkbox"/> Service	<input type="checkbox"/> No Corrosion	<input type="checkbox"/> Main	<input checked="" type="checkbox"/> Service
<input type="checkbox"/> Contractor	<input type="checkbox"/> Cast Iron	<input type="checkbox"/> Main	<input type="checkbox"/> Surface Rust	<input type="checkbox"/> Service	<input type="checkbox"/> Saddle	<input type="checkbox"/> Tee	<input type="checkbox"/> Main	<input type="checkbox"/> Service	<input type="checkbox"/> Surface Rust	<input type="checkbox"/> Main	<input type="checkbox"/> Service
	<input type="checkbox"/> Steel	<input type="checkbox"/> Main	<input type="checkbox"/> Minor Pitting	<input type="checkbox"/> Service	<input type="checkbox"/> Coupling	<input type="checkbox"/> Valve	<input type="checkbox"/> Main	<input type="checkbox"/> Service	<input type="checkbox"/> Minor Pitting	<input type="checkbox"/> Main	<input type="checkbox"/> Service
	<input type="checkbox"/> W Iron	<input type="checkbox"/> Main	<input type="checkbox"/> Deep Pitting	<input type="checkbox"/> Service	<input type="checkbox"/> Other	<input type="checkbox"/> Leaking	<input type="checkbox"/> Main	<input type="checkbox"/> Service	<input type="checkbox"/> Deep Pitting	<input type="checkbox"/> Main	<input type="checkbox"/> Service
	<input type="checkbox"/> Copper	<input type="checkbox"/> Main	<input type="checkbox"/> Leaking	<input type="checkbox"/> Service	<input type="checkbox"/> Other	<input type="checkbox"/> Leaking	<input type="checkbox"/> Main	<input type="checkbox"/> Service	<input type="checkbox"/> Leaking	<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Main		<input type="checkbox"/> Service			<input type="checkbox"/> Main	<input type="checkbox"/> Service		<input type="checkbox"/> Main	<input type="checkbox"/> Service
		<input type="checkbox"/> Service		<input type="checkbox"/> Main			<input type="checkbox"/> Main	<input type="checkbox"/> Service			

Street Address: _____

Town: _____

Construction Activity:

Cross Street: _____

- Main Conn.
- Main Relay
- New Services
- Insert

RESTORATIONS (OPENINGS)

Opening Site

A	B	C
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Street
Sidewalk
Lawn (Pri Prop)

Original Surface

<input type="checkbox"/>	Asphalt
<input type="checkbox"/>	Concrete
<input type="checkbox"/>	Gravel
<input type="checkbox"/>	Cobblestone
<input type="checkbox"/>	Grass
<input type="checkbox"/>	Brick
<input type="checkbox"/>	Conc&Asph
<input type="checkbox"/>	Brick&Cobble

Length: _____ ft.
Width: _____ ft.
DCP Drops: _____ in.
Lifts: _____
Lift Thickness: _____ in.

Paving Method

<input type="checkbox"/>	Hot Patch
<input type="checkbox"/>	Loam&Seed
<input type="checkbox"/>	Cust. Reimb.
<input type="checkbox"/>	None
<input type="checkbox"/>	Cold Patch


Paving Contr. Notified Yes No

Pick Ups

<input type="checkbox"/>	Dirt	Done
<input type="checkbox"/>	Plate(s)	Req'd
<input type="checkbox"/>	Barricade/Cone	Not Req'd
<input type="checkbox"/>	Spoil Bag	

Opening Sketch

FIELD SKETCH



EXPOSED PIPE (UNDERGROUND BURIED PIPE):

Company Contractor

<input type="checkbox"/>	Plastic
<input type="checkbox"/>	Cast Iron
<input type="checkbox"/>	Steel
<input type="checkbox"/>	W Iron
<input type="checkbox"/>	Copper

Soil Condition

<input type="checkbox"/>	Gravel
<input type="checkbox"/>	Sand
<input type="checkbox"/>	Clay
<input type="checkbox"/>	Rocky
<input type="checkbox"/>	Ledge

Size (in.) _____
Depth (ft.) _____

Activity

<input type="checkbox"/>	Main	<input type="checkbox"/>	Service
<input type="checkbox"/>	No Corrosion	<input type="checkbox"/>	Joint
<input type="checkbox"/>	Surface Rust	<input type="checkbox"/>	Tee
<input type="checkbox"/>	Minor Pitting	<input type="checkbox"/>	Saddle
<input type="checkbox"/>	Deep Pitting	<input type="checkbox"/>	Coupling
<input type="checkbox"/>	Leaking	<input type="checkbox"/>	Valve
<input type="checkbox"/>		<input type="checkbox"/>	Other

Location

<input type="checkbox"/>	External
<input type="checkbox"/>	Internal
<input type="checkbox"/>	Both (E&I)

Coating Type

<input type="checkbox"/>	None (bare)
<input type="checkbox"/>	Coal Tar (blk)
<input type="checkbox"/>	X-Tru (yellow)
<input type="checkbox"/>	Pri-tec
<input type="checkbox"/>	TF Epoxy - Red
<input type="checkbox"/>	TF Epoxy-Gm
<input type="checkbox"/>	TF Epoxy-Yel

Coating Damage

<input type="checkbox"/>	None
<input type="checkbox"/>	Minor
<input type="checkbox"/>	Extensive

Repair Action

<input type="checkbox"/>	Coating Repair
<input type="checkbox"/>	Anode Installed
<input type="checkbox"/>	Test Sta. Inst/Rep

Anode Qty: _____ Corr. Rdg. _____

Comments

Damage Repair
 PULLED 1" PL PIPE OUT OF SLEWING
 FOUND DAMAGED AREA, CUT OUT AND
 INSTALLED COP. CAPPED END AND
 TESTED AT 100 LBS FOR 25 MIN. *PIPE*
 TEST AT 2:20 PM - ALL OK - *ESTABLISH*
 CAP ON 1" FORMERLY ~~EXPOSED~~ *TOOK MEAS.*
 CAP ON BLUE TRUCK - ALSO CAPPED END
 HOUSE. GAS IS ON AT G.B. SOAP TESTED

Exhibit 19: KeySpan Leak Repair Work Orders
(4 of 4)

Home | [about us](#) | [services](#) | [projects](#) | [products](#) | [contact us](#)

about us

Solid Earth Technologies, formerly Jager Construction, has completed hundreds of projects throughout New England. We have specialized in foundation stabilization and repair for over ten years.

From stabilizing and raising sinking foundations for existing homes to new construction piles, Solid Earth Technologies has the experience and resources needed to complete your project.

Solid Earth Technologies uses only the best products available and are trained in the newest technologies that guarantee lasting solutions. An extensive list of very pleased customers will gladly be furnished upon request.

Sinking Foundations, cracked and buckled walls and uneven floors are problems commonly faced annually by some quarter-million homeowners. Homes and other structures may settle when situated on unstable soils. A shifting foundation may result in structural damage to your home and a loss of your investment.

1 HOWE DEL
UNIT 3
AMSTERDAM, NH
03031
TEL: 603-741-2122
FAX: 603-742-2222

Exhibit 20: SET Brochure describing the piers and the installation process. (1 of 3)

Home | About Us | Services | Products | Projects | Contact Us

products

Solid Earth TECHNOLOGIES

1 HOWELL STREET
ANN ARBOR, MI 48106
D-371

PH: 734.769.1100
FAX: 734.769.7422

We use THE CHANCE® HELICAL PIER® SYSTEM:

The Industry Leader in Foundation Underpinning Solutions

Applied in a wide variety of projects, the reliability of CHANCE® HELICAL PIERS has been thoroughly proven over decades in all types of soil conditions. Based on this cumulative experience Solid Earth Technologies has acquired a unique resource to support our services.

For a complete listing of available products and specifications, we invite you to visit the [CHANCE®](http://www.chance.com) web site.

products most often used



<p>New Construction HELICAL PIER®</p>  <p>Used for deep foundations, supports 10 to 100 kip ultimate capacities with field verified results.</p>	<p>Underpinning System</p>  <p>Used to remediate building settlement or to apply additional loads to an existing foundation. Patented, and BOCA approved Report 94-27.</p>	<p>HELICAL PIER® Screw Earth Anchor</p>  <p>Used to develop high tensile and/or compression forces. Available in a variety of shaft sizes and helical plate configurations to match site specific soil conditions.</p> <p>Tie-backs</p> <p>Screwed in for remediation of failing walls or construction of new walls and shoring.</p>
--	--	--

Exhibit 20: SET Brochure describing the piers and the installation process. (2 of 3)

home | about us | services | projects | products | contact us

projects

Environmental Walkways | Residential | Commercial

about us
services
projects
products
contact us

Andover Walkway

Soil Foundation Problem:
A stretch of wetlands between nature walkways not suitable to support a connecting bridge.

Solid Earth's Solution:
The landscape architect representing the office complex who wanted to build the connecting bridge selected CHANGE® HELICAL PIERS as the foundations for the elevated walkway. Solid Earth Technologies installed 14 HELICAL PIERS and 6 Diagonal Brace Anchors through 3 to 4 feet of peat to depths between 6 and 11 feet. Our team of carpenters then constructed the 6 foot wide wooden walkway with rails on both sides.



Audubon Society's Broadmoor Sanctuary

Soil Foundation Problem:
The wildlife sanctuary wanted a new walkway system out into the swamp.

Solid Earth's Solution:
108 HELICAL PIER Foundations were installed through up to 10' of peat to support over 500' of walkways. 32 Diagonal Brace Anchors were used in areas of deeper water and mud.




Exhibit 20: SET Brochure describing the piers and the installation process. (3 of 3)

Department of Telecommunications and Energy
Pipeline Safety Division
MEMO

Date: November 1, 2002

To: Robert Smallcomb, Director
From: Paul Grieco, Engineer
Subject: 82 Marsh View Rd, Chatham

I arrived at 82 Marsh View Road, Chatham at about 12:30 PM on October 31, 2002 with John Higgins, Manager Field Operations from Keyspan.

At this location was a 550 foot 1" plastic service, tied to the main on the long side of the street. The service was installed in a 350 foot black plastic sleeve (material unknown). The sleeve was installed by a contractor working for the general contractor by directional drilling through a marsh, to a small piece of high ground out in the marsh. The only access to this house is by an elevated walk way over the marsh. The service was installed without an EFV (excess flow valve) due to the distance from the main to the house. The main was not exposed. The service was shut off at the curb cock.

Linda Dole of Polhemus Savery DaSilva, Architects-Builders, (the general contractor) 101 Depot Rd Chatham 02633, phone 508-945-4500 stated that a company was hired to install a new walk way to the island. That company is;
Solid Earth Technologies Inc.
Matt Stacey, President
3 Howe Drive, unit 3
Amherst N.H. 03031
877-389-7822

www.solidearthtech.com (see attached)

Mr. Stacey admitted to John Higgins that dig safe was not notified. The person who was installing the piers stated to the general contractor that the location where the damage occurred was drilled on Monday October 28, 2002, the fire occurred on Wednesday October 30, 2002.

In approximately the same location as the gas sleeve and gas service line were the other conduits, two electric, one being used and a spare, telephone and cable, the location of the water service was unknown. The electric conduits and the others did not appear to be sealed on the inside of the house. There was also a 4" sleeve that penetrated the foundation of the house, it was not being used, Linda Dole had no information about this sleeve.

The injured party was Len Savery. The Fire Chief interviewed Len Savery and told John Higgins that Savery stated that an odor was noticed by the owner. Savery opened the hatch to the crawl space, turned on the light and noticed some paper on fire. He then went to get a fire extinguisher. In the meantime the fire alarm went off and the alarm company called the house. Savery fought the fire with the extinguisher and told the alarm company to send the Fire Department. Savery suffered smoke inhalation, he was released from the hospital on October 31, 2002.

An excavation had been made near the house at the end of the sleeve and the service was cut and capped prior to my arriving, there was also an excavation near the street side of the service, no cuts were observed. The gas company made another excavation near the end of the gas service line sleeve so that the service line could be pulled out. The live end was sealed. When the service was pulled out a hole and scuff marks were discovered. The company measured the line so that it could be determined where the damage was in relation to the end of the sleeve. The damage occurred approximately 83 feet from the end of the gas sleeve (house side). The crew used a tape measure to measure above ground 83 feet from the sleeve and found this to be approximately where bubbles were observed.

Exhibit 21: Memo from Paul Grieco, DTE, to Robert Smallcomb, DTE, November 1, 2002 (1 of 2)

The crew cut out the damaged section and put the pipe back together with a compression fitting. A pressure test was then applied to determine if there were any other leaks. The pressure test was at 100 PSIG for 25 minutes (removed at 2:20 PM). No other leaks were discovered. The company will in the near future test the section from the sleeve to the meter at the rear of the house.

John Higgins is in control of the section of 1" plastic service that was cut out.

Exhibit 21: Memo from Paul Grieco, DTE, to Robert Smallcomb,
DTE, November 1, 2002 (2 of 2)



Exhibit 22: View of the light switch.



Exhibit 23a: View of the pier at the location where the pipe was damaged.



Exhibit 23b: Close-up view of the pier at the location where the pipe was damaged. Note the gas bubbles in the water.