



### NOTES:

1. THE CONTRACTOR SHALL MAKE SURE THAT THE STRIATION FINS ARE PLUMB AND LINED UP VERTICALLY FROM PANEL TO PANEL FOR THE FULL HEIGHT OF THE WALL.
2. THE HORIZONTAL JOINT MAY BE OMITTED IF THE CONTRACTOR CAN DEMONSTRATE THAT THE FORM LINER PANELS CAN BE INSTALLED END TO END WITHOUT CREATING A VISIBLE SEAM IN THE FINAL CAST CONCRETE.

## TYPICAL STRIATION DETAIL

SCALE: 3" = 1'-0"



LRFD BRIDGE  
MANUAL, PART II

## TYPICAL STRIATION DETAIL

STRIATION DETAILS

DATE OF ISSUE  
JUNE 2013

DRAWING NUMBER

**3.4.4**