

CONSTRUCTION SEQUENCE NOTES:

1. AFTER ALL BEAMS HAVE BEEN ERECTED, TENSION EACH TRANSVERSE TIE TO 5 KIPS.
2. FILL ALL KEYWAYS WITH MORTAR (M4.04.0). IF THE KEYWAYS ARE NOT FILLED WITHIN FIVE (5) DAYS AFTER THE BEAMS ARE ERECTED, THE CONTRACTOR SHALL COVER AND PROTECT THE KEYWAYS FROM WEATHER AND DEBRIS UNTIL THEY ARE FILLED.
3. AFTER THE MORTAR HAS CURED (24 HOURS MINIMUM), TENSION EACH TRANSVERSE TIE TO 44 KIPS.
4. CONCRETE FOR DECK SLAB SHALL BE 4000 PSI, $\frac{3}{4}$ IN, 585 HP CEMENT CONCRETE AND SHALL BE PLACED AFTER THE TRANSVERSE TIES HAVE BEEN FULLY TENSIONED.
5. NO TRAFFIC OR HEAVY EQUIPMENT WILL BE PERMITTED ON THE BRIDGE UNTIL ALL TRANSVERSE TIES HAVE BEEN PROPERLY TENSIONED AND THE DECK HAS BEEN CAST AND CURED PER THE STANDARD SPECIFICATIONS.

NOTE:

Include the Notes from Dwg. No. 4.1.21 on projects with Stage Construction.



LRFD BRIDGE
MANUAL, PART II

CONSTRUCTION SEQUENCE NOTES

PRECAST CONCRETE DECK BEAMS

DATE OF ISSUE
JUNE 2013

DRAWING NUMBER
4.1.16