



### NOTE:

#6 HEADED DOWEL BAR SPLICERS SHALL BE CAST INTO THE PRECAST BEAMS BY THE FABRICATOR. THEY SHALL BE EMBEDDED AS REQUIRED TO PROVIDE A MINIMUM NOMINAL TENSILE RESISTANCE OF 39.0 KIPS AS SPECIFIED BY THE MANUFACTURER.

## INTERMEDIATE DIAPHRAGM

SCALE: 1" = 1'-0"



LRFD BRIDGE  
MANUAL, PART II

## INTERMEDIATE DIAPHRAGM

PRECAST CONCRETE BOX BEAMS

DATE OF ISSUE  
JUNE 2013

DRAWING NUMBER

**6.2.13**