


BID PACKAGE COVER PAGE

**DEPARTMENT OF MENTAL HEALTH
OFFICE OF ENGINEERING AND FACILITIES MANAGEMENT
167 LYMAN ST.
WESTBOROUGH, MA 01581**

BID DOCUMENTS FOR:

**2023-068B FLOORING ABATEMENT & REPLACEMENT
HASKELL BUILDING
ONE PRINCE STREET
NORTHAMPTON, MA 01060**

OUT TO BID: WEDNESDAY, MARCH 15, 2023



BID PACKAGE

TABLE OF CONTENTS

**DMH PROJECT# 2023-068B
FLOORING ABATEMENT & REPLACEMENT
HASKELL BUILDING
ONE PRINCE STREET
NORTHAMPTON, MA 01060**

**NOTICE TO CONTRACTORS
WALK-THRU NOTICE**

PART 1 – INSTRUCTIONS TO BIDDERS

PART 2 – FORMS FOR CONTRACT EXECUTION

PART 3 – GENERAL CONDITIONS

PART 4 – SPECS AND DRAWINGS

**NOTICE TO CONTRACTORS
CLASSIFIED LEGAL ADVERTISEMENT**

**COMMONWEALTH OF MASSACHUSETTS
EXECUTIVE OFFICE FOR HEALTH AND HUMAN SERVICES
DEPARTMENT OF MENTAL HEALTH – FACILITIES MANAGEMENT**

General Bids Submission Deadline: 2:00 P.M. Friday, March 31, 2023

The Category of Work is: FLOORING

Project Name: 2023-068B Flooring Abatement & Replacement

Project Location: Haskell Building, One Prince Street, Northampton, MA 01060

Estimated Construction Cost: \$145,000

Project will require the furnishing and installation of carpet square flooring and removal, disposal, and abatement of existing floor tiles.

Minimum rates of wages to be paid on the project have been determined by the Commissioner of the Division of Occupational Safety under the provisions of Sections 26 and 27, Chapter 149 of the General Laws and will be included in the bid package.

Proposals will ONLY be submitted online via COMMBUYS website by the General Bids & Sub-bids Submission Deadline date on forms furnished by the Department of Mental Health (DMH) and clearly identified as a bid, endorsed with the name and address of the bidder, and the project name.

Each general bid and sub-bid proposal must be secured by an uploaded photocopy of an accompanying **deposit of 5%** of the total bid amount, including all alternates, in the form of a bid bond, a certified treasurer's or cashier's check issued by a responsible bank or trust company made payable to the Commonwealth of Massachusetts. Awarded vendor will then mail the original 5% deposit bond or check to the Department of Mental Health, Office of Engineering and Facilities Management, 167 Lyman Street, Room 158, Westborough, MA 01581. The Department reserves the right to waive any informality in or reject any or all Bids if it is in the public interest to do so.

Plans and Specifications will **ONLY** be available at COMMBUYS from **3/15/2023** thru general bid opening. Bid must be submitted electronically on COMMBUYS by the Submission Deadlines dated above. If you have any questions or concerns with using COMMBUYS, please contact the COMMBUYS help desk at 617-720-3197 (8am - 5pm EST Monday thru Friday).

Pre-Bid Conference: MANDATORY Pre Bid Conference will be held **10:00AM on Thursday 3/23/2023**. **Contractors shall meet the Project Engineer at the main lobby located at Haskell Building at One Prince Street, Northampton** to review project details. Please contact DMH Project Engineer, Fred Bergstrom, at (508) 616-2245. **After attending the Mandatory Pre Bid Conference, all bidder questions must be uploaded to COMMBUYS by 12:00 P.M. Friday 3/24/2023.**

Covid-19 Precaution Notice: Anyone attending site viewing(s) will be required to follow state and city precaution guidelines by wearing the necessary face mask and practicing safe distancing.

Project duration is forty-five (45) calendar days.

MBW/WBE Contractors are encouraged to inquire about this project.

**DEPARTMENT OF MENTAL HEALTH
BROOKE DOYLE, COMMISSIONER**

DEPARTMENT OF MENTAL HEALTH
OFFICE OF FACILITIES MANAGEMENT
HADLEY BUILDING
167 LYMAN STREET
WESTBOROUGH, MASSACHUSETTS 01581

***FLOORING ABATEMENT & REPLACEMENT
AT
HASKELL BUILDING
ONE PRINCE STREET
NORTHAMPTON, MA
(DMH Project #2023-068B)***

NOTICE OF MANDATORY PRE-BID CONFERENCE

ALL CONTRACTORS INTERESTED IN BIDDING ON THIS PROJECT ARE
HEREBY NOTIFIED OF A MANDATORY PRE-BID CONFERENCE AND
WALK-THROUGH

ON

THURSDAY MARCH 23, 2023

AT

10:00 A.M.

CONTRACTORS ARE TO MEET IN THE MAIN LOBBY OF
HASKELL BUILDING LOCATED AT
ONE PRINCE STREET
NORTHAMPTON, MASSACHUSETTS 01060



BID PACKAGE

PART I

INSTRUCTIONS TO BIDDERS

For Projects with no Filed Sub Bidders

**2023- 068B Flooring Abatement & Replacement
Haskell Building
1 Prince Street
Northampton, Massachusetts 01060**

Instructions to Bidders

Attachment A:

Minimum Wage Rates

Prevailing Wage Schedule – Bidder Acknowledgement

Attachment B: Forms Used During Bidding

Form for General Bid



**COMMONWEALTH OF MASSACHUSETTS
INSTRUCTIONS TO BIDDERS**

Awarding Authority:

Department of Mental Health
Office of Engineering and Facilities Management
Hadley Building
167 Lyman Street
Westborough, MA 01581
Fred Bergstrom, DMH Project Engineer
Office Tel: (508) 616 – 2245

**Project Title: 2023- 068B Flooring Abatement & Replacement
Haskell Building
1 Prince Street
Northampton, Massachusetts 01060**

Category of Work: FLOORING

Project Description and Scope:

Project will require the furnishing and installation of carpet square flooring and removal, disposal, and abatement of existing floor tiles.

Deadline for filing General bids is at: 2:00 PM Friday March 31, 2023

The minimum wage rate requirements for this Contract are located in Attachment A to these Instructions to Bidders.

Pursuant to M.G.L. c. 30, §39S(a) (2) all employees to be employed on the project must have successfully completed a course in construction safety and health approved by OSHA and of at least 10 hours in duration.

The Contractor must provide written verification as detailed in the General Conditions of compliance with Federal Department of Homeland Security

Requirements, including but not limited to the Employment Eligibility Verification (Form I-9) Process.

Bid forms for this Contract are located in Attachment B to these Instructions to Bidders.

COVID-19 Precaution Notice: Anyone attending site viewing(s) will be required to follow state and city precaution guidelines by wearing the necessary face mask and practicing safe distancing.

The estimated time for completion of the Work is forty-five calendar days (45), and will be specified in Article 2 of the Owner - Contractor Agreement for the successful bidder. Liquidated damages for failure to complete work on time is \$500 per day, and will be stated in Article 7 of the Owner - Contractor Agreement.

Bidding Documents must be obtained via COMMBUYS website. If you need assistance with COMMBUYS, please call the COMMBUYS help desk at (617) 720-3197. COMMBUYS Job Aids for Vendors on how to use COMMBUYS are available by clicking the link below.

<https://www.mass.gov/lists/job-aids-for-vendors-using-commbuys>

The filed subtrades for this project are as follows: **(not applicable)**

As used herein, capitalized terms shall have the meaning assigned to them in the General Conditions of the Contract and the Owner - Contractor Agreement unless the context clearly indicates otherwise.

SECTION I - BIDDER'S REPRESENTATION

1.1 Each general bidder or sub-bidder (hereinafter sometimes referred to as "Bidder") by making a bid or sub-bid (hereinafter sometimes referred to as "Bid") represents and warrants that Bidder has visited and examined the Site and the Contract Documents, that Bidder is familiar with the local conditions under which the Work is to be performed, that Bidder has correlated personal observations with the requirements of the Contract Documents, and that where the Contract Documents require, in any part of the Work, a given result to be produced, the Contract Documents are adequate and that Bidder will produce the required result within the Bid price and that the Bid is made in accordance therewith.

1.2 Failure to so examine the Contract Documents and the Site will not relieve any Bidder from any obligation under the Bid as submitted. Neither the Commonwealth nor the Designer will be responsible for errors, omissions and/or charges for extra work arising from Bidder's failure to familiarize itself with the Contract Documents or existing conditions.

SECTION 2 -- GENERAL BIDDERS - CERTIFICATE OF ELIGIBILITY AND UPDATE STATEMENT (NOT APPLICABLE)

2.1 (not applicable) Every general bidder must submit the following with its general bid:

--A Prime/General Contractor Certificate of Eligibility issued by the Division of Capital Asset Management and Maintenance (DCAMM), showing that the Bidder has been approved to bid on projects for the category of work required and that the Bidder has a single project limit in an amount no lower than the amount of its Bid including all "add" alternates.

--A fully completed Prime/General Contractor Update Statement.

2.2 (not applicable) It is the Bidder's responsibility to obtain the necessary forms from DCAMM and to submit its Application for Certificate of Eligibility so as to allow sufficient time for DCAMM's evaluation of the application and issuance of a Certificate of Eligibility prior to the deadline for bidding.

2.3 (not applicable) The Prime/General Contractor Update Statement is not a public record as defined in M.G.L. c. 4, § 7 and will not be open to public inspection.

SECTION 3 -- FILED SUB-BIDDERS - CERTIFICATE OF ELIGIBILITY AND UPDATE STATEMENT (NOT APPLICABLE)

3.1 (not applicable) Every filed sub-bidder must submit the following with each filed sub-bid:

--A Sub-Bidder Certificate of Eligibility issued by the Division of Capital Asset Management and Maintenance (DCAMM) for that sub-bid trade, showing that the sub-bidder has been approved to bid on projects of the category of work required.

--A fully completed Sub-Bidder Update Statement.

3.2 (not applicable) It is the sub-bidder's responsibility to obtain the necessary forms from DCAMM and to submit its Application for Sub-bidder Certificate of Eligibility so as to allow sufficient time for DCAMM's evaluation of the application and issuance of a Sub-Bidder Certificate of Eligibility prior to the deadline for bidding.

3.3 (not applicable) The Sub-Bidder Update Statement is not a public record as defined in M.G.L. c. 4, §7 and will not be open to public inspection.

SECTION 4 -- REQUESTS FOR INTERPRETATION

4.1 Any questions by prospective Bidders concerning interpretation of the Contract Documents must be uploaded to COMMBUYS by **Friday March 24, 2023 by 12:00PM.** The Awarding Authority will post any addenda or written interpretations on

COMMBUYS that it deems necessary to Bidders at least 48 hours before the General Bids Submission Deadline Date. Bidders may NOT rely upon oral communications or interpretations from the Awarding Authority or the Designer and the Awarding Authority shall not be bound by them.

4.2 It is the sole responsibility of the Bidder to ascertain the existence of any addenda issued by the Awarding Authority on COMMBUYS, by Bidder.

4.3 Wherever in the Contract Documents reference is made to Massachusetts General Laws, it shall be construed to include all amendments thereto effective as of the date of the issuance of the invitation to bid on the proposed work.

SECTION 5 -- PREPARATION OF BIDS; ALTERNATES

5.1 General Bids shall be submitted on the Form for General Bid included in Attachment B to these Instructions to Bidders.

5.2 All entries on the Bid form shall be typewritten or in ink.

5.3 Where so indicated on the Bid form, sums shall be expressed in both words and numerals. Where there is a discrepancy between the Bid sum expressed in words and the Bid sum expressed in figures, the Bid sum expressed in words shall control unless the intention of the Bidder clearly is otherwise as determined by the Awarding Authority in its sole discretion.

5.4 Each general Bidder shall acknowledge all required alternates in Section C on the Form for General Bid by entering the dollar amount of addition or subtraction necessitated by the alternate. General Bidders shall enter on the Form for General Bid a single amount for each alternate that shall consist of the sub-Bidders' amounts and the amount for work performed by the general Bidder.

5.5 If an alternate includes work within the Bidder's scope of work and does not involve a change in the cost of the Bid, the Bidder shall so indicate by writing "No Change" or "N/C" or "0" in the space provided for that alternate.

5.6 The lowest Bidder will be determined on the basis of the sum of the base Bid and the accepted alternates.

5.7 (not applicable) If the space for indicating a requirement for payment and performance bonds for filed subcontractors is left blank by the general Bidder on the Form for General Bid, the Awarding Authority shall interpret this as a "No."

5.8 (not applicable) Costs for subcontractors' bond premiums shall be paid for by the general Contractor in accordance with M.G.L. c. 149, § 44F unless the project is a project in which contractor and subcontractor prequalification are required pursuant to M.G.L. 149, §§ 44D1/2 or 44D3/4.

5.9 (not applicable) If the general Bidders are instructed to carry an amount for a given subtrade listed under Item 2, general Bidders shall list the subtrade and the amount provided by the Awarding Authority. The line under "bonds required" on the Form for General Bid should be left blank or marked "N/A" in order for subsection 5.10 to apply.

5.10 (not applicable) Upon solicitation of a subcontractor to perform the work required with respect to a subtrade referenced in subsection 5.9, the general Bidder's Contract Price shall be adjusted by the following: a) the difference between the subcontract amount and the amount carried in the general Bid; b) the total cost of the subcontractor's bonds, if the general Bidder requires such bonds after the solicitation is completed and if the general Bidder complied with 5.9 above; c) the documented increased costs for the general Bidder's bonds, if any, attributable to the incremental difference between the amount carried for the given subtrade and the actual subcontract amount.

5.11 (not applicable) Overhead and profit for supervision of the subtrade mentioned in subsections 5.9 and 5.10 above shall be included by all general Bidders in Item 1 of the subdivision of the Contract Price. No additional overhead or profit will be paid on the incremental difference between the amount carried for the subtrade and the subcontract amount as stated in M.G.L. c. 149, § 44F(4)(a)(2).

5.12 (not applicable) Sub-Bidders should not list Paragraph E sub-subcontractors unless requested to do so by the Awarding Authority.

5.13 Each general Bid ~~and each Bid of a filed subcontractor~~ must be accompanied by a bid deposit in the form of a bid bond; cash; or a check certified by, or a treasurer's or cashier's check issued by, a responsible bank or trust company, payable to the Commonwealth of Massachusetts. Any bid bond shall be (a) in a form satisfactory to the Awarding Authority, (b) with a surety company qualified to do business in the Commonwealth and (c) conditioned upon the faithful performance by the principal of the agreements contained in the Bid.

5.14 The amount of such bid deposit shall be **5% five per cent** of the value of the Bid including alternates.

SECTION 6 - SUBMISSION OF BIDS

6.1 Each general Bid, **including a photo copy of the bid deposit** shall be uploaded into COMMBUYS.

General Bid for:

**Project Title: 2023- 068B Flooring Abatement & Replacement
Haskell Building
1 Prince Street
Northampton, Massachusetts 01060**

General Bidders name, business address, and telephone number.

6.2 All Bids must be received by the Awarding Authority via the COMMBUYS Website no later than the **Deadline for Filing General Bid date** specified on page two of these Instructions to Bidders. Any Bid received after this deadline date and time will not be accepted.

SECTION 7 - WITHDRAWAL OF BIDS; REJECTION OF BIDS

7.1 Any Bid may be withdrawn prior by emailing Fred Bergstrom at **fred.e.bergstrom@mass.gov** prior to the **Deadline for filing General Bid date on page two.**

7.2 A Bidder may withdraw its Bid without penalty by emailing Fred Bergstrom at **fred.e.bergstrom@mass.gov** at any time up to the time of Award as defined below in subsection 9.1 only upon demonstrating to the satisfaction of the Awarding Authority that a death or disability has occurred or a bona fide clerical or mechanical error of a substantial nature was made during the preparation of the bid. Failure to demonstrate conclusively that a bona fide clerical or mechanical error of a substantial nature was made may result in forfeiture of the Bid deposit.

7.3 The Awarding Authority reserves the right to waive any informality in or to reject any and all Bids if it is in the public interest to do so. Without limiting the foregoing, the Awarding Authority reserves the right to reject unit prices which it deems unduly high or unduly low as unbalanced.

SECTION 8 - MBE AND WBE PARTICIPATION (not applicable)

SECTION 9 -- CONTRACT AWARD

9.1 "Award" means the determination, selection, and notification of the lowest, responsible and eligible Bidder by the Awarding Authority.

9.2 The Awarding Authority will award the Contract within thirty (30) days, Saturdays, Sundays, and legal holidays excluded after the opening of Bids in accordance with M.G.L. c.149 §44A.

9.3 The Contract will be awarded to the lowest responsible and eligible Bidder as determined by the Awarding Authority, except in the event of substitution as provided under M.G.L. c.149, §§44E and 44F, in which cases the procedure as required by said sections shall govern the award of the Contract.

9.4 As used herein, the term "lowest responsible and eligible Bidder" shall mean the general Bidder whose Bid is the lowest of those Bidders who, in the Awarding Authority's opinion, are ready, willing and able to comply with all requirements of the Contract Documents and demonstrably possess the skill, ability, and integrity necessary for the faithful performance of the Work, based on the determination of past performance and financial soundness under (i) M.G.L. c.149 §44A and following sections, (ii) the rules, regulations, orders, guidelines and policies promulgated from time to time by the Commissioner of the Division of Capital Asset Management and Maintenance ("DCAMM") and (iii) any other relevant criteria that the Commissioner may prescribe. If the Awarding Authority determines that any non-filed subcontractor chosen by a Bidder is not qualified or responsible, then the Bidder shall obtain another subcontractor satisfactory to Awarding Authority and the contract price shall not be adjusted.

9.5 The general Bid price shall be the price set forth in paragraph C of the Form for General Bid. No general Bid shall be rejected (i) because the sum of the prices set forth in Item 1 and 2 does not equal the general Bid price set forth in said paragraph C or (ii) because of one or more errors in setting forth the name, the sub-Bid price of a sub-Bidder, or the total of Item 2, provided that the sub-Bidder or sub-Bidders designated are clearly identifiable, or (iii) because the plans and specifications do not accompany the Bid or are not submitted with the Bid.

9.6 Should the Contract Documents require submission of special data to accompany the Bid, the Awarding Authority reserves the right to rule the Bidder's failure to submit such data an informality and to receive said data subsequently within a reasonable time as set by the Awarding Authority, provided that no such ruling shall result in an unfair advantage to the Bidder.

9.7 The Awarding Authority also reserves the right to reject any sub-Bid if it determines that such sub-Bid does not represent the Bid of a person competent to perform the work as specified, or if fewer than three sub-Bids are received for a sub-trade, and the Bid prices are not reasonable for acceptance without further competition.

9.8 If the Awarding Authority decides to reject all general Bids or if the Awarding Authority does not receive any general Bids, the Awarding Authority may retain and use the sub-Bids received for a second opening of general Bids; provided, however, that there are no changes in the work involved for the subtrades for which the sub-Bids are so retained and used; and provided, further, that the Awarding Authority shall obtain the consent of each sub-Bidder included in any award of a general Contract made pursuant to

the second opening of general Bids if such award is not made within ninety days, Saturdays, Sundays and legal holidays excluded, after the opening of such sub-Bids.

SECTION 10 - EXECUTION OF CONTRACTS

10.1 If a selected filed sub-Bidder fails, within five days, Saturdays, Sundays and legal holidays excluded, after presentation of a Subcontract by the general Bidder to which the Contract was awarded, to perform its agreement to execute a Subcontract in the form provided by the Awarding Authority with such general Bidder contingent upon the execution of the general Contract, and, if requested to do so by such general Bidder in the general Bid, to furnish a 100% payment bond and a 100% Performance Bond as stated in its filed sub-Bid, such general Bidder and the Awarding Authority shall select from the other filed sub-Bids duly filed with the Awarding Authority for such sub trade and not rejected the lowest responsible and eligible filed sub-Bidder at the amount named in its filed sub-Bid as so filed against whose standing and ability the general Contractor makes no objection, and the Contract price shall be adjusted by the difference between the amount of such filed sub-bid and the amount of the sub-bid of the delinquent filed sub-Bidder.

10.2 Upon receipt of the Award, the general Bidder awarded the Contract shall submit a properly executed original of each of the following documents prior to execution of the Contract by the Awarding Authority. All such documents shall be in the form prescribed by the Awarding Authority.

- Owner-Contractor Agreement
- 50% Payment Bond with power of attorney attached
- Certificates of Insurance evidencing coverages in amounts required by the Contract Documents
- Any other documents that the Awarding Authority may reasonably require in connection with the Contractor's execution of the Contract.

-Written representation by the General Contractor to the effect that it has presented subcontracts to all selected filed sub-Bidders and a statement as to whether or not each such selected filed sub-Bidder has executed its subcontract such that the Awarding Authority may release the Bid deposit with respect to the same. **Misrepresentation of the foregoing shall render the general Contractor liable to the Awarding Authority for the sum of any Bid deposit released by the Awarding Authority with respect to a filed sub-Bidder that fails to execute its subcontract.**

10.3 Please note that **no part of the General Contractor's work may be subcontracted without the prior written approval of the Awarding Authority.** If the General Contractor desires to subcontract any part of the Work, other than work covered by Item 2, filed sub-Bidders, the General Contractor must promptly forward to the Awarding Authority a list in triplicate designating the work to be performed and the name of each proposed subcontractor for approval by the Awarding Authority. Approved subcontractors

are eligible for direct payments under M.G.L. 30, § 39F, as amended. Material suppliers not involving site labor need not be submitted for approval.

SECTION 11 - RETURN OF BID DEPOSITS

11.1 If no award is made, upon the expiration of the time prescribed in M.G.L. c. 149, § 44A for making an award; except that, if any general Bidder fails to perform its agreement to execute the Contract and furnish a 50% Payment Bond as stated in its Bid, then said general Bidder's Bid deposit shall become the property of the Commonwealth as liquidated damages; provided that the amount of the Bid deposit that becomes the property of the Commonwealth shall not exceed the difference between the Contractor's Bid price and the Bid price of the next lowest responsible and eligible Bidder; and provided further that, in the case of death, disability, bona fide clerical or mechanical error of a substantial nature, or other similar unforeseen circumstances affecting the general Bidder, such general Bidder's Bid deposit shall be returned.

11.2 If a selected sub-Bidder fails to perform its agreement to execute a sub-contract with the general Bidder selected as the general Contractor, contingent upon the execution of the General Contract, and, if requested to do so in the general Bid by such general Bidder, to furnish a Performance and Payment Bonds as stated in its sub-Bid in accordance with M.G.L. c. 149, § 44F(2), the Bid deposit of such sub-Bidder shall become the property of the Commonwealth as liquidated damages, provided that the amount of the Bid deposit that shall become the property of the Commonwealth shall not exceed the difference between its sub-Bid price and the sub-Bid price of the next lowest responsible and eligible sub-Bidder.

11.3 In addition to the provisions for the return of Bid deposits as provided above, upon receipt of a Bid Bond in an amount not less than the amount of the required Bid deposit, the Awarding Authority shall return any Bid deposit of a Bidder forthwith after the public opening of Bids.

ATTACHMENT A

PREVAILING WAGE SCHEDULE/OSHA 10 HRS ACKNOWLEDGEMENT

The minimum wage rates provided in the following pages have been provided by the Division of Occupational Safety of the Massachusetts Department of Labor and Workforce Development. The Awarding Authority is not responsible for errors or omissions in such wage rates.

M.G.L. c. 149, §§ 26 and 27 provide as follows:

... Payments by employers to health and welfare plans, pension plans and supplementary unemployment benefit plans under collective bargaining agreements or understandings between organized labor and employers shall be included for the purpose of establishing minimum wage rates as herein provided.

... The aforesaid rates of wages in the schedule of wage rates shall include payments by employers to health and welfare plans, pension plans and supplementary unemployment benefit plans as provided in said section twenty-six, and such payments shall be considered as payments to persons under this section performing work as herein provided. Any employer engaged in the construction of such works who does not make payments to a health and welfare plan, a pension plan and a supplementary unemployment benefit plan, where such payments are included in said rates of wages, shall pay the amount of said payments directly to each employee engaged in said construction"

Wage Request Number: 20230217-045

The undersigned hereby certifies that it is able to furnish labor that can work in harmony with all other elements of labor employed or to be employed on the work; that all employees to be employed at the worksite will have successfully completed a course in construction safety and health approved by the United States Occupational Safety and Health Administration that is at least 10 hours in duration at the time the employee begins work and who shall furnish documentation of successful completion of said course with the first certified payroll report for each employee; and that it will comply fully with all laws and regulations applicable to awards made subject to section 39M of Chapter 30 of the General Laws.

Bidder acknowledges receipt of the most recent prevailing wage rates and has incorporated said rates into their proposed bid(s).

Signature: _____

Name and Title: _____



MAURA HEALEY
Governor

KIM DRISCOLL
Lt. Governor

THE COMMONWEALTH OF MASSACHUSETTS
EXECUTIVE OFFICE OF LABOR AND WORKFORCE DEVELOPMENT
DEPARTMENT OF LABOR STANDARDS

Prevailing Wage Rates

As determined by the Director under the provisions of the
Massachusetts General Laws, Chapter 149, Sections 26 to 27H

LAUREN JONES
Secretary

MICHAEL FLANAGAN
Director

Awarding Authority: Department of Mental Health
Contract Number: 2023-068B **City/Town:** NORTHAMPTON
Description of Work: Abate the existing 9X9 asbestos flooring, existing carpet, and prep for installation of new carpet.
Job Location: 1 Prince Street Northampton, MA

Information about Prevailing Wage Schedules for Awarding Authorities and Contractors

- The wage rates will remain in effect for the duration of the project, except in the case of multi-year public construction projects. For construction projects lasting longer than one year, awarding authorities must request an updated wage schedule no later than two weeks before the anniversary of the date the contract was executed by the awarding authority and the general contractor. For multi-year CM AT RISK projects, the awarding authority must request an annual update no later than two weeks before the anniversary date, determined as the earlier of: (a) the execution date of the GMP Amendment, or (b) the execution date of the first amendment to permit procurement of construction services. The annual update requirement is not applicable to 27F "rental of equipment" contracts. **The updated wage schedule must be provided to all contractors, including general and sub-contractors, working on the construction project.**
- This wage schedule applies only to the specific project referenced at the top of this page and uniquely identified by the "Wage Request Number" on all pages of this schedule.
- An Awarding Authority must request an updated wage schedule if it has not opened bids or selected a contractor within 90 days of the date of issuance of the wage schedule. For CM AT RISK projects (bid pursuant to G.L. c.149A), the earlier of: (a) the execution date of the GMP Amendment, or (b) the bid for the first construction scope of work must be within 90-days of the wage schedule issuance date.
- The wage schedule shall be incorporated in any advertisement or call for bids for the project as required by M.G.L. c. 149, § 27. The wage schedule shall be made a part of the contract awarded for the project. The wage schedule must be posted in a conspicuous place at the work site for the life of the project in accordance with M.G.L. c. 149 § 27. The wages listed on the wage schedule must be paid to employees performing construction work on the project whether they are employed by the prime contractor, a filed sub-bidder, or a sub-contractor.
- Apprentices working on the project are required to be registered with the Massachusetts Division of Apprentice Standards (DAS). Apprentices must keep their apprentice identification card on their persons during all work hours on the project. An apprentice registered with DAS may be paid the lower apprentice wage rate at the applicable step as provided on the prevailing wage schedule. **Any apprentice not registered with DAS regardless of whether they are registered with another federal, state, local, or private agency must be paid the journeyworker's rate.**
- Every contractor or subcontractor working on the construction project must submit weekly payroll reports and a Statement of Compliance directly to the awarding authority by mail or email and keep them on file for three years. Each weekly payroll report must contain: the employee's name, address, occupational classification, hours worked, and wages paid. Do not submit weekly payroll reports to DLS. For a sample payroll reporting form go to <http://www.mass.gov/dols/pw>.
- Contractors with questions about the wage rates or classifications included on the wage schedule have an affirmative obligation to inquire with DLS at (617) 626-6953.
- Contractors must obtain the wage schedules from awarding authorities. Failure of a contractor or subcontractor to pay the prevailing wage rates listed on the wage schedule to all employees who perform construction work on the project is a violation of the law and subjects the contractor or subcontractor to civil and criminal penalties.
- Employees not receiving the prevailing wage rate set forth on the wage schedule may file a complaint with the Fair Labor Division of the office of the Attorney General at (617) 727-3465.

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
Construction						
(2 AXLE) DRIVER - EQUIPMENT <i>TEAMSTERS JOINT COUNCIL NO. 10 ZONE B</i>	12/01/2021	\$35.95	\$13.41	\$16.01	\$0.00	\$65.37
(3 AXLE) DRIVER - EQUIPMENT <i>TEAMSTERS JOINT COUNCIL NO. 10 ZONE B</i>	12/01/2021	\$36.02	\$13.41	\$16.01	\$0.00	\$65.44
(4 & 5 AXLE) DRIVER - EQUIPMENT <i>TEAMSTERS JOINT COUNCIL NO. 10 ZONE B</i>	12/01/2021	\$36.14	\$13.41	\$16.01	\$0.00	\$65.56
ADS/SUBMERSIBLE PILOT <i>PILE DRIVER LOCAL 56 (ZONE 3)</i>	08/01/2020	\$103.05	\$9.40	\$23.12	\$0.00	\$135.57
For apprentice rates see "Apprentice- PILE DRIVER"						
AIR TRACK OPERATOR <i>LABORERS - ZONE 3 (BUILDING & SITE)</i>	12/01/2022	\$34.38	\$9.10	\$16.19	\$0.00	\$59.67
	06/01/2023	\$35.00	\$9.10	\$16.19	\$0.00	\$60.29
	12/01/2023	\$35.63	\$9.10	\$16.19	\$0.00	\$60.92
For apprentice rates see "Apprentice- LABORER"						
AIR TRACK OPERATOR (HEAVY & HIGHWAY) <i>LABORERS - ZONE 3 (HEAVY & HIGHWAY)</i>	12/01/2022	\$33.75	\$9.35	\$14.41	\$0.00	\$57.51
	06/01/2023	\$34.37	\$9.35	\$14.41	\$0.00	\$58.13
	12/01/2023	\$35.00	\$9.35	\$14.41	\$0.00	\$58.76
	06/01/2024	\$36.20	\$9.35	\$14.41	\$0.00	\$59.96
	12/01/2024	\$37.40	\$9.35	\$14.41	\$0.00	\$61.16
	06/01/2025	\$38.65	\$9.35	\$14.41	\$0.00	\$62.41
	12/01/2025	\$39.89	\$9.35	\$14.41	\$0.00	\$63.65
	06/01/2026	\$41.19	\$9.35	\$14.41	\$0.00	\$64.95
	12/01/2026	\$42.48	\$9.35	\$14.41	\$0.00	\$66.24
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)"						
ASBESTOS WORKER (PIPES & TANKS) <i>HEAT & FROST INSULATORS LOCAL 6 (SPRINGFIELD)</i>	12/01/2020	\$34.29	\$12.80	\$8.95	\$0.00	\$56.04
ASPHALT RAKER <i>LABORERS - ZONE 3 (BUILDING & SITE)</i>	12/01/2022	\$33.88	\$9.10	\$16.19	\$0.00	\$59.17
	06/01/2023	\$34.50	\$9.10	\$16.19	\$0.00	\$59.79
	12/01/2023	\$35.13	\$9.10	\$16.19	\$0.00	\$60.42
For apprentice rates see "Apprentice- LABORER"						
ASPHALT RAKER (HEAVY & HIGHWAY) <i>LABORERS - ZONE 3 (HEAVY & HIGHWAY)</i>	12/01/2022	\$33.25	\$9.35	\$14.41	\$0.00	\$57.01
	06/01/2023	\$33.87	\$9.35	\$14.41	\$0.00	\$57.63
	12/01/2023	\$34.50	\$9.35	\$14.41	\$0.00	\$58.26
	06/01/2024	\$35.70	\$9.35	\$14.41	\$0.00	\$59.46
	12/01/2024	\$36.90	\$9.35	\$14.41	\$0.00	\$60.66
	06/01/2025	\$38.15	\$9.35	\$14.41	\$0.00	\$61.91
	12/01/2025	\$39.39	\$9.35	\$14.41	\$0.00	\$63.15
	06/01/2026	\$40.69	\$9.35	\$14.41	\$0.00	\$64.45
	12/01/2026	\$41.98	\$9.35	\$14.41	\$0.00	\$65.74
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)"						
AUTOMATIC GRADER-EXCAVATOR (RECLAIMER) <i>OPERATING ENGINEERS LOCAL 98</i>	12/01/2022	\$38.21	\$13.38	\$15.00	\$0.00	\$66.59
	06/01/2023	\$39.16	\$13.38	\$15.00	\$0.00	\$67.54
	12/01/2023	\$40.11	\$13.38	\$15.00	\$0.00	\$68.49
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
BACKHOE/FRONT-END LOADER OPERATOR <i>OPERATING ENGINEERS LOCAL 98</i>	12/01/2022	\$38.21	\$13.38	\$15.00	\$0.00	\$66.59
	06/01/2023	\$39.16	\$13.38	\$15.00	\$0.00	\$67.54
	12/01/2023	\$40.11	\$13.38	\$15.00	\$0.00	\$68.49
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
BARCO-TYPE JUMPING TAMPER <i>LABORERS - ZONE 3 (BUILDING & SITE)</i>	12/01/2022	\$33.88	\$9.10	\$16.19	\$0.00	\$59.17
	06/01/2023	\$34.50	\$9.10	\$16.19	\$0.00	\$59.79
	12/01/2023	\$35.13	\$9.10	\$16.19	\$0.00	\$60.42
For apprentice rates see "Apprentice- LABORER"						
BATCH/CEMENT PLANT - ON SITE <i>OPERATING ENGINEERS LOCAL 98</i>	12/01/2022	\$37.68	\$13.38	\$15.00	\$0.00	\$66.06
	06/01/2023	\$38.63	\$13.38	\$15.00	\$0.00	\$67.01
	12/01/2023	\$39.58	\$13.38	\$15.00	\$0.00	\$67.96
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
BLOCK PAVER, RAMMER / CURB SETTER <i>LABORERS - ZONE 3 (BUILDING & SITE)</i>	12/01/2022	\$34.38	\$9.10	\$16.19	\$0.00	\$59.67
	06/01/2023	\$35.00	\$9.10	\$16.19	\$0.00	\$60.29
	12/01/2023	\$35.63	\$9.10	\$16.19	\$0.00	\$60.92
For apprentice rates see "Apprentice- LABORER"						
BLOCK PAVER, RAMMER / CURB SETTER (HEAVY & HIGHWAY) <i>LABORERS - ZONE 3 (HEAVY & HIGHWAY)</i>	12/01/2022	\$33.75	\$9.35	\$14.41	\$0.00	\$57.51
	06/01/2023	\$34.37	\$9.35	\$14.41	\$0.00	\$58.13
	12/01/2023	\$35.00	\$9.35	\$14.41	\$0.00	\$58.76
	06/01/2024	\$36.20	\$9.35	\$14.41	\$0.00	\$59.96
	12/01/2024	\$37.40	\$9.35	\$14.41	\$0.00	\$61.16
	06/01/2025	\$38.65	\$9.35	\$14.41	\$0.00	\$62.41
	12/01/2025	\$39.89	\$9.35	\$14.41	\$0.00	\$63.65
	06/01/2026	\$41.19	\$9.35	\$14.41	\$0.00	\$64.95
12/01/2026	\$42.48	\$9.35	\$14.41	\$0.00	\$66.24	
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)"						
BOILER MAKER <i>BOILERMAKERS LOCAL 29</i>	01/01/2023	\$47.37	\$7.07	\$20.31	\$0.00	\$74.75
	01/01/2024	\$48.12	\$7.07	\$20.60	\$0.00	\$75.79

Classification

Effective Date Base Wage Health Pension Supplemental Unemployment Total Rate

Apprentice - BOILERMAKER - Local 29

Effective Date - 01/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	65	\$30.79	\$7.07	\$13.22	\$0.00	\$51.08
2	65	\$30.79	\$7.07	\$13.22	\$0.00	\$51.08
3	70	\$33.16	\$7.07	\$14.23	\$0.00	\$54.46
4	75	\$35.53	\$7.07	\$15.24	\$0.00	\$57.84
5	80	\$37.90	\$7.07	\$16.25	\$0.00	\$61.22
6	85	\$40.26	\$7.07	\$17.28	\$0.00	\$64.61
7	90	\$42.63	\$7.07	\$18.28	\$0.00	\$67.98
8	95	\$45.00	\$7.07	\$19.32	\$0.00	\$71.39

Effective Date - 01/01/2024

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	65	\$31.28	\$7.07	\$13.22	\$0.00	\$51.57
2	65	\$31.28	\$7.07	\$13.22	\$0.00	\$51.57
3	70	\$33.68	\$7.07	\$14.23	\$0.00	\$54.98
4	75	\$36.09	\$7.07	\$15.24	\$0.00	\$58.40
5	80	\$38.50	\$7.07	\$16.25	\$0.00	\$61.82
6	85	\$40.90	\$7.07	\$17.28	\$0.00	\$65.25
7	90	\$43.31	\$7.07	\$18.28	\$0.00	\$68.66
8	95	\$45.71	\$7.07	\$19.32	\$0.00	\$72.10

Notes:

Apprentice to Journeyworker Ratio:1:4

BRICK/STONE/ARTIFICIAL MASONRY (INCL. MASONRY WATERPROOFING)	02/01/2023	\$48.76	\$11.49	\$20.37	\$0.00	\$80.62
BRICKLAYERS LOCAL 3 (SPRINGFIELD/PITTSFIELD)	08/01/2023	\$50.81	\$11.49	\$20.37	\$0.00	\$82.67
	02/01/2024	\$52.06	\$11.49	\$20.37	\$0.00	\$83.92
	08/01/2024	\$53.31	\$11.49	\$20.37	\$0.00	\$85.17
	02/01/2025	\$54.61	\$11.49	\$20.37	\$0.00	\$86.47
	08/01/2025	\$56.76	\$11.49	\$20.37	\$0.00	\$88.62
	02/01/2026	\$58.11	\$11.49	\$20.37	\$0.00	\$89.97
	08/01/2026	\$60.31	\$11.49	\$20.37	\$0.00	\$92.17
	02/01/2027	\$61.71	\$11.49	\$20.37	\$0.00	\$93.57

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
CAISSON & UNDERPINNING TOP MAN <i>LABORERS - FOUNDATION AND MARINE</i>	12/01/2022	\$42.58	\$9.35	\$17.97	\$0.00	\$69.90
	06/01/2023	\$43.58	\$9.35	\$17.97	\$0.00	\$70.90
	12/01/2023	\$44.83	\$9.35	\$17.97	\$0.00	\$72.15
	06/01/2024	\$46.31	\$9.35	\$17.97	\$0.00	\$73.63
	12/01/2024	\$47.78	\$9.35	\$17.97	\$0.00	\$75.10
	06/01/2025	\$49.28	\$9.35	\$17.97	\$0.00	\$76.60
	12/01/2025	\$50.78	\$9.35	\$17.97	\$0.00	\$78.10
	06/01/2026	\$52.33	\$9.35	\$17.97	\$0.00	\$79.65
	12/01/2026	\$53.83	\$9.35	\$17.97	\$0.00	\$81.15
For apprentice rates see "Apprentice- LABORER"						
CARBIDE CORE DRILL OPERATOR <i>LABORERS - ZONE 3 (BUILDING & SITE)</i>	12/01/2022	\$33.88	\$9.10	\$16.19	\$0.00	\$59.17
	06/01/2023	\$34.50	\$9.10	\$16.19	\$0.00	\$59.79
	12/01/2023	\$35.13	\$9.10	\$16.19	\$0.00	\$60.42
For apprentice rates see "Apprentice- LABORER"						
CARPENTER <i>CARPENTERS LOCAL 336 - HAMPDEN HAMPSHIRE FRANKLIN</i>	09/01/2022	\$39.82	\$7.16	\$18.15	\$0.00	\$65.13
	03/01/2023	\$40.32	\$7.16	\$18.15	\$0.00	\$65.63

Apprentice - CARPENTER - Local 336 Hampden Hampshire Franklin

Effective Date - 09/01/2022

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$19.91	\$7.16	\$1.38	\$0.00	\$28.45
2	60	\$23.89	\$7.16	\$1.38	\$0.00	\$32.43
3	70	\$27.87	\$7.16	\$13.95	\$0.00	\$48.98
4	75	\$29.87	\$7.16	\$13.95	\$0.00	\$50.98
5	80	\$31.86	\$7.16	\$15.35	\$0.00	\$54.37
6	80	\$31.86	\$7.16	\$15.35	\$0.00	\$54.37
7	90	\$35.84	\$7.16	\$16.75	\$0.00	\$59.75
8	90	\$35.84	\$7.16	\$16.75	\$0.00	\$59.75

Effective Date - 03/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$20.16	\$7.16	\$1.38	\$0.00	\$28.70
2	60	\$24.19	\$7.16	\$1.38	\$0.00	\$32.73
3	70	\$28.22	\$7.16	\$13.95	\$0.00	\$49.33
4	75	\$30.24	\$7.16	\$13.95	\$0.00	\$51.35
5	80	\$32.26	\$7.16	\$15.35	\$0.00	\$54.77
6	80	\$32.26	\$7.16	\$15.35	\$0.00	\$54.77
7	90	\$36.29	\$7.16	\$16.75	\$0.00	\$60.20
8	90	\$36.29	\$7.16	\$16.75	\$0.00	\$60.20

Notes:

% Indentured After 10/1/17; 45/45/55/55/70/70/80/80
Step 1&2 \$26.46/ 3&4 \$31.82/ 5&6 \$50.38/ 7&8 \$55.77

Apprentice to Journeyworker Ratio:1:5

CARPENTER WOOD FRAME <i>CARPENTERS-ZONE 3 (Wood Frame)</i>	04/01/2022	\$23.66	\$7.21	\$4.80	\$0.00	\$35.67
	04/01/2023	\$24.16	\$7.21	\$4.80	\$0.00	\$36.17

Classification

All Aspects of New Wood Frame Work

Effective Date Base Wage Health Pension Supplemental Unemployment Total Rate

Apprentice - CARPENTER (Wood Frame) - Zone 3

Effective Date - 04/01/2022

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	60	\$14.20	\$7.21	\$0.00	\$0.00	\$21.41
2	60	\$14.20	\$7.21	\$0.00	\$0.00	\$21.41
3	65	\$15.38	\$7.21	\$0.00	\$0.00	\$22.59
4	70	\$16.56	\$7.21	\$0.00	\$0.00	\$23.77
5	75	\$17.75	\$7.21	\$3.80	\$0.00	\$28.76
6	80	\$18.93	\$7.21	\$3.80	\$0.00	\$29.94
7	85	\$20.11	\$7.21	\$3.80	\$0.00	\$31.12
8	90	\$21.29	\$7.21	\$3.80	\$0.00	\$32.30

Effective Date - 04/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	60	\$14.50	\$7.21	\$0.00	\$0.00	\$21.71
2	60	\$14.50	\$7.21	\$0.00	\$0.00	\$21.71
3	65	\$15.70	\$7.21	\$0.00	\$0.00	\$22.91
4	70	\$16.91	\$7.21	\$0.00	\$0.00	\$24.12
5	75	\$18.12	\$7.21	\$3.80	\$0.00	\$29.13
6	80	\$19.33	\$7.21	\$3.80	\$0.00	\$30.34
7	85	\$20.54	\$7.21	\$3.80	\$0.00	\$31.55
8	90	\$21.74	\$7.21	\$3.80	\$0.00	\$32.75

Notes:

% Indentured After 10/1/17; 45/45/55/55/70/70/80/80
 Step 1&2 \$17.86/ 3&4 \$20.22/ 5&6 \$27.57/ 7&8 \$29.94

Apprentice to Journeyworker Ratio:1:5

CEMENT MASONRY/PLASTERING	01/01/2023	\$44.81	\$12.70	\$17.97	\$0.87	\$76.35
BRICKLAYERS LOCAL 3 (SPRINGFIELD/PITTSFIELD)	07/01/2023	\$45.82	\$12.70	\$17.97	\$0.87	\$77.36
	01/01/2024	\$46.83	\$12.70	\$17.97	\$0.87	\$78.37

Classification

Effective Date Base Wage Health Pension Supplemental Unemployment Total Rate

Apprentice - CEMENT MASONRY/PLASTERING - Springfield/Pittsfield

Effective Date - 01/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$22.41	\$12.70	\$15.49	\$0.00	\$50.60
2	60	\$26.89	\$12.70	\$17.97	\$0.87	\$58.43
3	65	\$29.13	\$12.70	\$17.97	\$0.87	\$60.67
4	70	\$31.37	\$12.70	\$17.97	\$0.87	\$62.91
5	75	\$33.61	\$12.70	\$17.97	\$0.87	\$65.15
6	80	\$35.85	\$12.70	\$17.97	\$0.87	\$67.39
7	90	\$40.33	\$12.70	\$17.97	\$0.87	\$71.87

Effective Date - 07/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$22.91	\$12.70	\$15.49	\$0.00	\$51.10
2	60	\$27.49	\$12.70	\$17.97	\$0.87	\$59.03
3	65	\$29.78	\$12.70	\$17.97	\$0.87	\$61.32
4	70	\$32.07	\$12.70	\$17.97	\$0.87	\$63.61
5	75	\$34.37	\$12.70	\$17.97	\$0.87	\$65.91
6	80	\$36.66	\$12.70	\$17.97	\$0.87	\$68.20
7	90	\$41.24	\$12.70	\$17.97	\$0.87	\$72.78

Notes:
Steps 3,4 are 500 hrs. All other steps are 1,000 hrs.

Apprentice to Journeyworker Ratio:1:3

CHAIN SAW OPERATOR <i>LABORERS - ZONE 3 (BUILDING & SITE)</i>	12/01/2022	\$33.88	\$9.10	\$16.19	\$0.00	\$59.17
	06/01/2023	\$34.50	\$9.10	\$16.19	\$0.00	\$59.79
	12/01/2023	\$35.13	\$9.10	\$16.19	\$0.00	\$60.42
For apprentice rates see "Apprentice- LABORER"						
COMPRESSOR OPERATOR <i>OPERATING ENGINEERS LOCAL 98</i>	12/01/2022	\$37.68	\$13.38	\$15.00	\$0.00	\$66.06
	06/01/2023	\$38.63	\$13.38	\$15.00	\$0.00	\$67.01
	12/01/2023	\$39.58	\$13.38	\$15.00	\$0.00	\$67.96
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
CRANE OPERATOR <i>OPERATING ENGINEERS LOCAL 98</i>	12/01/2022	\$41.71	\$13.38	\$15.00	\$0.00	\$70.09
	06/01/2023	\$42.66	\$13.38	\$15.00	\$0.00	\$71.04
	12/01/2023	\$43.61	\$13.38	\$15.00	\$0.00	\$71.99
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
DELEADER (BRIDGE) <i>PAINTERS LOCAL 35 - ZONE 3</i>	01/01/2023	\$56.06	\$8.65	\$23.05	\$0.00	\$87.76
	07/01/2023	\$57.26	\$8.65	\$23.05	\$0.00	\$88.96
	01/01/2024	\$58.46	\$8.65	\$23.05	\$0.00	\$90.16
	07/01/2024	\$59.66	\$8.65	\$23.05	\$0.00	\$91.36
	01/01/2025	\$60.86	\$8.65	\$23.05	\$0.00	\$92.56

Classification

Effective Date Base Wage Health Pension Supplemental Unemployment Total Rate

Apprentice - PAINTER Local 35 - BRIDGES/TANKS

Effective Date - 01/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$28.03	\$8.65	\$0.00	\$0.00	\$36.68
2	55	\$30.83	\$8.65	\$6.27	\$0.00	\$45.75
3	60	\$33.64	\$8.65	\$6.84	\$0.00	\$49.13
4	65	\$36.44	\$8.65	\$7.41	\$0.00	\$52.50
5	70	\$39.24	\$8.65	\$19.63	\$0.00	\$67.52
6	75	\$42.05	\$8.65	\$20.20	\$0.00	\$70.90
7	80	\$44.85	\$8.65	\$20.77	\$0.00	\$74.27
8	90	\$50.45	\$8.65	\$21.91	\$0.00	\$81.01

Effective Date - 07/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$28.63	\$8.65	\$0.00	\$0.00	\$37.28
2	55	\$31.49	\$8.65	\$6.27	\$0.00	\$46.41
3	60	\$34.36	\$8.65	\$6.84	\$0.00	\$49.85
4	65	\$37.22	\$8.65	\$7.41	\$0.00	\$53.28
5	70	\$40.08	\$8.65	\$19.63	\$0.00	\$68.36
6	75	\$42.95	\$8.65	\$20.20	\$0.00	\$71.80
7	80	\$45.81	\$8.65	\$20.77	\$0.00	\$75.23
8	90	\$51.53	\$8.65	\$21.91	\$0.00	\$82.09

Notes:

Steps are 750 hrs.

Apprentice to Journeyworker Ratio:1:1

DEMO: ADZEMAN LABORERS - ZONE 3 (BUILDING & SITE)	12/01/2022	\$43.33	\$9.10	\$17.57	\$0.00	\$70.00
	06/01/2023	\$44.33	\$9.10	\$17.57	\$0.00	\$71.00
	12/01/2023	\$45.58	\$9.10	\$17.57	\$0.00	\$72.25

For apprentice rates see "Apprentice- LABORER"

DEMO: BACKHOE/LOADER/HAMMER OPERATOR LABORERS - ZONE 3 (BUILDING & SITE)	12/01/2022	\$44.33	\$9.10	\$17.57	\$0.00	\$71.00
	06/01/2023	\$45.33	\$9.10	\$17.57	\$0.00	\$72.00
	12/01/2023	\$46.58	\$9.10	\$17.57	\$0.00	\$73.25

For apprentice rates see "Apprentice- LABORER"

DEMO: BURNERS LABORERS - ZONE 3 (BUILDING & SITE)	12/01/2022	\$44.08	\$9.10	\$17.57	\$0.00	\$70.75
	06/01/2023	\$45.08	\$9.10	\$17.57	\$0.00	\$71.75
	12/01/2023	\$46.33	\$9.10	\$17.57	\$0.00	\$73.00

For apprentice rates see "Apprentice- LABORER"

DEMO: CONCRETE CUTTER/SAWYER LABORERS - ZONE 3 (BUILDING & SITE)	12/01/2022	\$44.33	\$9.10	\$17.57	\$0.00	\$71.00
	06/01/2023	\$45.33	\$9.10	\$17.57	\$0.00	\$72.00
	12/01/2023	\$46.58	\$9.10	\$17.57	\$0.00	\$73.25

For apprentice rates see "Apprentice- LABORER"

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
DEMO: JACKHAMMER OPERATOR <i>LABORERS - ZONE 3 (BUILDING & SITE)</i>	12/01/2022	\$44.08	\$9.10	\$17.57	\$0.00	\$70.75
	06/01/2023	\$45.08	\$9.10	\$17.57	\$0.00	\$71.75
	12/01/2023	\$46.33	\$9.10	\$17.57	\$0.00	\$73.00
For apprentice rates see "Apprentice- LABORER"						
DEMO: WRECKING LABORER <i>LABORERS - ZONE 3 (BUILDING & SITE)</i>	12/01/2022	\$43.33	\$9.10	\$17.57	\$0.00	\$70.00
	06/01/2023	\$44.33	\$9.10	\$17.57	\$0.00	\$71.00
	12/01/2023	\$45.58	\$9.10	\$17.57	\$0.00	\$72.25
For apprentice rates see "Apprentice- LABORER"						
DIVER <i>PILE DRIVER LOCAL 56 (ZONE 3)</i>	08/01/2020	\$68.70	\$9.40	\$23.12	\$0.00	\$101.22
For apprentice rates see "Apprentice- PILE DRIVER"						
DIVER TENDER <i>PILE DRIVER LOCAL 56 (ZONE 3)</i>	08/01/2020	\$49.07	\$9.40	\$23.12	\$0.00	\$81.59
For apprentice rates see "Apprentice- PILE DRIVER"						
DIVER TENDER (EFFLUENT) <i>PILE DRIVER LOCAL 56 (ZONE 3)</i>	08/01/2020	\$73.60	\$9.40	\$23.12	\$0.00	\$106.12
For apprentice rates see "Apprentice- PILE DRIVER"						
DIVER/SLURRY (EFFLUENT) <i>PILE DRIVER LOCAL 56 (ZONE 3)</i>	08/01/2020	\$103.05	\$9.40	\$23.12	\$0.00	\$135.57
For apprentice rates see "Apprentice- PILE DRIVER"						
DRAWBRIDGE OPERATOR (Construction) <i>DRAWBRIDGE - SEIU LOCAL 888</i>	07/01/2020	\$26.77	\$6.67	\$3.93	\$0.16	\$37.53
ELECTRICIAN (Including Core Drilling) <i>ELECTRICIANS LOCAL 7</i>	01/01/2023	\$47.01	\$12.50	\$13.96	\$0.00	\$73.47

Apprentice - ELECTRICIAN - Local 7

Effective Date - 01/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	40	\$18.80	\$7.50	\$0.56	\$0.00	\$26.86
2	45	\$21.15	\$7.50	\$0.63	\$0.00	\$29.28
3	50	\$23.51	\$12.50	\$7.26	\$0.00	\$43.27
4	55	\$25.86	\$12.50	\$7.33	\$0.00	\$45.69
5	65	\$30.56	\$12.50	\$9.27	\$0.00	\$52.33
6	70	\$32.91	\$12.50	\$10.54	\$0.00	\$55.95

Notes:

Steps 1-2 are 1000 hrs; Steps 3-6 are 1500 hrs.

Apprentice to Journeyworker Ratio:2:3****

ELEVATOR CONSTRUCTOR <i>ELEVATOR CONSTRUCTORS LOCAL 41</i>	01/01/2022	\$58.62	\$16.03	\$20.21	\$0.00	\$94.86
---	------------	---------	---------	---------	--------	---------

Apprentice - ELEVATOR CONSTRUCTOR - Local 41

Effective Date - 01/01/2022

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$29.31	\$16.03	\$0.00	\$0.00	\$45.34
2	55	\$32.24	\$16.03	\$20.21	\$0.00	\$68.48
3	65	\$38.10	\$16.03	\$20.21	\$0.00	\$74.34
4	70	\$41.03	\$16.03	\$20.21	\$0.00	\$77.27
5	80	\$46.90	\$16.03	\$20.21	\$0.00	\$83.14

Notes:

Steps 1-2 are 6 mos.; Steps 3-5 are 1 year

Apprentice to Journeyworker Ratio:1:1

ELEVATOR CONSTRUCTOR HELPER <i>ELEVATOR CONSTRUCTORS LOCAL 41</i>	01/01/2022	\$41.03	\$16.03	\$20.21	\$0.00	\$77.27
--	------------	---------	---------	---------	--------	---------

For apprentice rates see "Apprentice - ELEVATOR CONSTRUCTOR"

FENCE & GUARD RAIL ERECTOR (HEAVY & HIGHWAY) <i>LABORERS - ZONE 3 (HEAVY & HIGHWAY)</i>	12/01/2022	\$33.25	\$9.35	\$14.41	\$0.00	\$57.01
	06/01/2023	\$33.87	\$9.35	\$14.41	\$0.00	\$57.63
	12/01/2023	\$34.50	\$9.35	\$14.41	\$0.00	\$58.26
	06/01/2024	\$35.70	\$9.35	\$14.41	\$0.00	\$59.46
	12/01/2024	\$36.90	\$9.35	\$14.41	\$0.00	\$60.66
	06/01/2025	\$38.15	\$9.35	\$14.41	\$0.00	\$61.91
	12/01/2025	\$39.39	\$9.35	\$14.41	\$0.00	\$63.15
	06/01/2026	\$40.69	\$9.35	\$14.41	\$0.00	\$64.45
	12/01/2026	\$41.98	\$9.35	\$14.41	\$0.00	\$65.74

For apprentice rates see "Apprentice- LABORER (Heavy and Highway)"

FIELD ENG.INST/ROD-BLDG,SITE,HVY/HWY <i>OPERATING ENGINEERS LOCAL 98</i>	06/01/1999	\$18.84	\$4.80	\$4.10	\$0.00	\$27.74
---	------------	---------	--------	--------	--------	---------

FIELD ENG.PARTY CHIEF:BLDG,SITE,HVY/HWY <i>OPERATING ENGINEERS LOCAL 98</i>	06/01/1999	\$21.33	\$4.80	\$4.10	\$0.00	\$30.23
--	------------	---------	--------	--------	--------	---------

FIELD ENG.SURVEY CHIEF-BLDG,SITE,HVY/HWY <i>OPERATING ENGINEERS LOCAL 98</i>	06/01/1999	\$22.33	\$4.80	\$4.10	\$0.00	\$31.23
---	------------	---------	--------	--------	--------	---------

FIRE ALARM INSTALLER <i>ELECTRICIANS LOCAL 7</i>	01/01/2023	\$47.01	\$12.50	\$13.96	\$0.00	\$73.47
---	------------	---------	---------	---------	--------	---------

For apprentice rates see "Apprentice- ELECTRICIAN"

FIRE ALARM REPAIR / MAINTENANCE <i>/ COMMISSIONING ELECTRICIANS</i> <i>LOCAL 7</i>	01/01/2023	\$47.01	\$12.50	\$13.96	\$0.00	\$73.47
--	------------	---------	---------	---------	--------	---------

For apprentice rates see "Apprentice- TELECOMMUNICATIONS TECHNICIAN"

FIREMAN <i>OPERATING ENGINEERS LOCAL 98</i>	12/01/2022	\$37.68	\$13.38	\$15.00	\$0.00	\$66.06
	06/01/2023	\$38.63	\$13.38	\$15.00	\$0.00	\$67.01
	12/01/2023	\$39.58	\$13.38	\$15.00	\$0.00	\$67.96

Classification

Effective Date Base Wage Health Pension Supplemental Unemployment Total Rate

Apprentice - OPERATING ENGINEERS - Local 98 Class 3

Effective Date - 12/01/2022

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	60	\$22.61	\$12.47	\$14.50	\$0.00	\$49.58
2	70	\$26.38	\$12.47	\$14.50	\$0.00	\$53.35
3	80	\$30.14	\$12.47	\$14.50	\$0.00	\$57.11
4	90	\$33.91	\$12.47	\$14.50	\$0.00	\$60.88

Effective Date - 06/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	60	\$23.18	\$12.47	\$14.50	\$0.00	\$50.15
2	70	\$27.04	\$12.47	\$14.50	\$0.00	\$54.01
3	80	\$30.90	\$12.47	\$14.50	\$0.00	\$57.87
4	90	\$34.77	\$12.47	\$14.50	\$0.00	\$61.74

Notes:

Steps 1-2 are 1000 hrs.; Steps 3-4 are 2000 hrs.

Apprentice to Journeyworker Ratio:1:6

FLAGGER & SIGNALER (HEAVY & HIGHWAY)	12/01/2022	\$25.23	\$9.35	\$14.41	\$0.00	\$48.99
LABORERS - ZONE 3 (HEAVY & HIGHWAY)	06/01/2023	\$25.98	\$9.35	\$14.41	\$0.00	\$49.74
	12/01/2023	\$25.98	\$9.35	\$14.41	\$0.00	\$49.74
	06/01/2024	\$27.01	\$9.35	\$14.41	\$0.00	\$50.77
	12/01/2024	\$27.01	\$9.35	\$14.41	\$0.00	\$50.77
	06/01/2025	\$28.09	\$9.35	\$14.41	\$0.00	\$51.85
	12/01/2025	\$28.09	\$9.35	\$14.41	\$0.00	\$51.85
	06/01/2026	\$29.21	\$9.35	\$14.41	\$0.00	\$52.97
	12/01/2026	\$29.21	\$9.35	\$14.41	\$0.00	\$52.97

For apprentice rates see "Apprentice- LABORER (Heavy and Highway)

FLOORCOVERER	03/01/2022	\$39.22	\$7.16	\$18.15	\$0.00	\$64.53
FLOORCOVERERS LOCAL 2168 ZONE III						

Classification

Effective Date Base Wage Health Pension Supplemental Unemployment Total Rate

Apprentice - FLOORCOVERER - Local 2168 Zone III

Effective Date - 03/01/2022

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$19.61	\$7.16	\$1.40	\$0.00	\$28.17
2	55	\$21.57	\$7.16	\$1.40	\$0.00	\$30.13
3	60	\$23.53	\$7.16	\$13.95	\$0.00	\$44.64
4	65	\$25.49	\$7.16	\$13.95	\$0.00	\$46.60
5	70	\$27.45	\$7.16	\$15.35	\$0.00	\$49.96
6	75	\$29.42	\$7.16	\$15.35	\$0.00	\$51.93
7	80	\$31.38	\$7.16	\$16.75	\$0.00	\$55.29
8	85	\$33.34	\$7.16	\$16.75	\$0.00	\$57.25

Notes: Steps are 750 hrs.
 % After 10/1/17; 45/45/55/55/70/70/80/80 (1500hr Steps)
 Step 1&2 \$26.21/ 3&4 \$31.49/ 5&6 \$49.96/ 7&8 \$55.29

Apprentice to Journeyworker Ratio:1:1

FORK LIFT	12/01/2022	\$37.90	\$13.38	\$15.00	\$0.00	\$66.28
<i>OPERATING ENGINEERS LOCAL 98</i>	06/01/2023	\$38.85	\$13.38	\$15.00	\$0.00	\$67.23
	12/01/2023	\$39.80	\$13.38	\$15.00	\$0.00	\$68.18

For apprentice rates see "Apprentice- OPERATING ENGINEERS"

GENERATORS/LIGHTING PLANTS	12/01/2022	\$34.45	\$13.38	\$15.00	\$0.00	\$62.83
<i>OPERATING ENGINEERS LOCAL 98</i>	06/01/2023	\$35.40	\$13.38	\$15.00	\$0.00	\$63.78
	12/01/2023	\$36.35	\$13.38	\$15.00	\$0.00	\$64.73

For apprentice rates see "Apprentice- OPERATING ENGINEERS"

GLAZIER (GLASS PLANK/AIR BARRIER/INTERIOR SYSTEMS)	06/01/2020	\$39.18	\$10.80	\$10.45	\$0.00	\$60.43
<i>GLAZIERS LOCAL 1333</i>						

Apprentice - GLAZIER - Local 1333

Effective Date - 06/01/2020

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$19.59	\$10.80	\$1.80	\$0.00	\$32.19
2	56	\$22.04	\$10.80	\$1.80	\$0.00	\$34.64
3	63	\$24.49	\$10.80	\$2.45	\$0.00	\$37.74
4	69	\$26.94	\$10.80	\$2.45	\$0.00	\$40.19
5	75	\$29.39	\$10.80	\$3.15	\$0.00	\$43.34
6	81	\$31.83	\$10.80	\$3.15	\$0.00	\$45.78
7	88	\$34.28	\$10.80	\$10.45	\$0.00	\$55.53
8	94	\$36.73	\$10.80	\$10.45	\$0.00	\$57.98

Notes:

Apprentice to Journeyworker Ratio:1:3

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
GRADER/TRENCHING MACHINE/DERRICK <i>OPERATING ENGINEERS LOCAL 98</i>	12/01/2022	\$38.21	\$13.38	\$15.00	\$0.00	\$66.59
	06/01/2023	\$39.16	\$13.38	\$15.00	\$0.00	\$67.54
	12/01/2023	\$40.11	\$13.38	\$15.00	\$0.00	\$68.49
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
HVAC (DUCTWORK) <i>SHEETMETAL WORKERS LOCAL 63</i>	01/01/2023	\$41.30	\$10.64	\$17.54	\$2.05	\$71.53
	07/01/2023	\$42.55	\$10.64	\$17.54	\$2.05	\$72.78
	01/01/2024	\$43.80	\$10.64	\$17.54	\$2.05	\$74.03
	07/01/2024	\$45.05	\$10.64	\$17.54	\$2.05	\$75.28
	01/01/2025	\$46.30	\$10.64	\$17.54	\$2.05	\$76.53
For apprentice rates see "Apprentice- SHEET METAL WORKER"						
HVAC (ELECTRICAL CONTROLS) <i>ELECTRICIANS LOCAL 7</i>	01/01/2023	\$47.01	\$12.50	\$13.96	\$0.00	\$73.47
For apprentice rates see "Apprentice- ELECTRICIAN"						
HVAC (TESTING AND BALANCING - AIR) <i>SHEETMETAL WORKERS LOCAL 63</i>	01/01/2023	\$41.30	\$10.64	\$17.54	\$2.05	\$71.53
	07/01/2023	\$42.55	\$10.64	\$17.54	\$2.05	\$72.78
	01/01/2024	\$43.80	\$10.64	\$17.54	\$2.05	\$74.03
	07/01/2024	\$45.05	\$10.64	\$17.54	\$2.05	\$75.28
	01/01/2025	\$46.30	\$10.64	\$17.54	\$2.05	\$76.53
For apprentice rates see "Apprentice- SHEET METAL WORKER"						
HVAC (TESTING AND BALANCING -WATER) <i>PLUMBERS & PIPEFITTERS LOCAL 104</i>	09/17/2022	\$45.71	\$9.55	\$17.10	\$0.00	\$72.36
	03/17/2023	\$46.96	\$9.55	\$17.10	\$0.00	\$73.61
	09/17/2023	\$47.96	\$9.55	\$17.10	\$0.00	\$74.61
	03/17/2024	\$49.21	\$9.55	\$17.10	\$0.00	\$75.86
For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"						
HVAC MECHANIC <i>PLUMBERS & PIPEFITTERS LOCAL 104</i>	09/17/2022	\$45.71	\$9.55	\$17.10	\$0.00	\$72.36
	03/17/2023	\$46.96	\$9.55	\$17.10	\$0.00	\$73.61
	09/17/2023	\$47.96	\$9.55	\$17.10	\$0.00	\$74.61
	03/17/2024	\$49.21	\$9.55	\$17.10	\$0.00	\$75.86
For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"						
HYDRAULIC DRILLS (HEAVY & HIGHWAY) <i>LABORERS - ZONE 3 (HEAVY & HIGHWAY)</i>	12/01/2022	\$33.75	\$9.35	\$14.41	\$0.00	\$57.51
	06/01/2023	\$34.37	\$9.35	\$14.41	\$0.00	\$58.13
	12/01/2023	\$35.00	\$9.35	\$14.41	\$0.00	\$58.76
	06/01/2024	\$36.20	\$9.35	\$14.41	\$0.00	\$59.96
	12/01/2024	\$37.40	\$9.35	\$14.41	\$0.00	\$61.16
	06/01/2025	\$38.65	\$9.35	\$14.41	\$0.00	\$62.41
	12/01/2025	\$39.89	\$9.35	\$14.41	\$0.00	\$63.65
	06/01/2026	\$41.19	\$9.35	\$14.41	\$0.00	\$64.95
12/01/2026	\$42.48	\$9.35	\$14.41	\$0.00	\$66.24	
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)"						
INSULATOR (PIPES & TANKS) <i>HEAT & FROST INSULATORS LOCAL 6 (SPRINGFIELD)</i>	09/01/2022	\$44.05	\$13.80	\$17.14	\$0.00	\$74.99

Apprentice - ASBESTOS INSULATOR (Pipes & Tanks) - Local 6 Springfield

Effective Date - 09/01/2022

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$22.03	\$13.80	\$12.42	\$0.00	\$48.25
2	60	\$26.43	\$13.80	\$13.36	\$0.00	\$53.59
3	70	\$30.84	\$13.80	\$14.31	\$0.00	\$58.95
4	80	\$35.24	\$13.80	\$15.25	\$0.00	\$64.29

Notes:
Steps are 1 year

Apprentice to Journeyworker Ratio:1:4

IRONWORKER/WELDER <i>IRONWORKERS LOCAL 7 (SPRINGFIELD AREA)</i>	09/16/2022	\$38.06	\$8.25	\$22.70	\$0.00	\$69.01
	03/16/2023	\$38.91	\$8.25	\$22.70	\$0.00	\$69.86
	09/16/2023	\$39.81	\$8.25	\$22.70	\$0.00	\$70.76
	03/16/2024	\$40.66	\$8.25	\$22.70	\$0.00	\$71.61

Apprentice - IRONWORKER - Local 7 Springfield

Effective Date - 09/16/2022

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	60	\$22.84	\$8.25	\$22.70	\$0.00	\$53.79
2	70	\$26.64	\$8.25	\$22.70	\$0.00	\$57.59
3	75	\$28.55	\$8.25	\$22.70	\$0.00	\$59.50
4	80	\$30.45	\$8.25	\$22.70	\$0.00	\$61.40
5	85	\$32.35	\$8.25	\$22.70	\$0.00	\$63.30
6	90	\$34.25	\$8.25	\$22.70	\$0.00	\$65.20

Notes:

Apprentice to Journeyworker Ratio:1:4

JACKHAMMER & PAVING BREAKER OPERATOR <i>LABORERS - ZONE 3 (BUILDING & SITE)</i>	12/01/2022	\$33.88	\$9.10	\$16.19	\$0.00	\$59.17
	06/01/2023	\$34.50	\$9.10	\$16.19	\$0.00	\$59.79
	12/01/2023	\$35.13	\$9.10	\$16.19	\$0.00	\$60.42

For apprentice rates see "Apprentice- LABORER"

LABORER <i>LABORERS - ZONE 3 (BUILDING & SITE)</i>	12/01/2022	\$33.63	\$9.10	\$16.19	\$0.00	\$58.92
	06/01/2023	\$34.25	\$9.10	\$16.19	\$0.00	\$59.54
	12/01/2023	\$34.88	\$9.10	\$16.19	\$0.00	\$60.17

Classification

Effective Date Base Wage Health Pension Supplemental Unemployment Total Rate

Apprentice - LABORER - Zone 3 Building & Site

Effective Date - 12/01/2022

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	60	\$20.18	\$9.10	\$16.19	\$0.00	\$45.47
2	70	\$23.54	\$9.10	\$16.19	\$0.00	\$48.83
3	80	\$26.90	\$9.10	\$16.19	\$0.00	\$52.19
4	90	\$30.27	\$9.10	\$16.19	\$0.00	\$55.56

Effective Date - 06/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	60	\$20.55	\$9.10	\$16.19	\$0.00	\$45.84
2	70	\$23.98	\$9.10	\$16.19	\$0.00	\$49.27
3	80	\$27.40	\$9.10	\$16.19	\$0.00	\$52.69
4	90	\$30.83	\$9.10	\$16.19	\$0.00	\$56.12

Notes:

Apprentice to Journeyworker Ratio:1:5

LABORER (HEAVY & HIGHWAY)	12/01/2022	\$33.00	\$9.35	\$14.41	\$0.00	\$56.76
LABORERS - ZONE 3 (HEAVY & HIGHWAY)	06/01/2023	\$33.62	\$9.35	\$14.41	\$0.00	\$57.38
	12/01/2023	\$34.25	\$9.35	\$14.41	\$0.00	\$58.01
	06/01/2024	\$35.45	\$9.35	\$14.41	\$0.00	\$59.21
	12/01/2024	\$36.65	\$9.35	\$14.41	\$0.00	\$60.41
	06/01/2025	\$37.90	\$9.35	\$14.41	\$0.00	\$61.66
	12/01/2025	\$39.14	\$9.35	\$14.41	\$0.00	\$62.90
	06/01/2026	\$40.44	\$9.35	\$14.41	\$0.00	\$64.20
	12/01/2026	\$41.73	\$9.35	\$14.41	\$0.00	\$65.49

Classification

Effective Date Base Wage Health Pension Supplemental Unemployment Total Rate

Apprentice - LABORER (Heavy & Highway) - Zone 3

Effective Date - 12/01/2022

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	60	\$19.80	\$9.35	\$14.41	\$0.00	\$43.56
2	70	\$23.10	\$9.35	\$14.41	\$0.00	\$46.86
3	80	\$26.40	\$9.35	\$14.41	\$0.00	\$50.16
4	90	\$29.70	\$9.35	\$14.41	\$0.00	\$53.46

Effective Date - 06/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	60	\$20.17	\$9.35	\$14.41	\$0.00	\$43.93
2	70	\$23.53	\$9.35	\$14.41	\$0.00	\$47.29
3	80	\$26.90	\$9.35	\$14.41	\$0.00	\$50.66
4	90	\$30.26	\$9.35	\$14.41	\$0.00	\$54.02

Notes:

Apprentice to Journeyworker Ratio:1:5

LABORER: CARPENTER TENDER
LABORERS - ZONE 3 (BUILDING & SITE) 12/01/2022 \$33.63 \$9.10 \$16.19 \$0.00 \$58.92

06/01/2023 \$34.25 \$9.10 \$16.19 \$0.00 \$59.54

12/01/2023 \$34.88 \$9.10 \$16.19 \$0.00 \$60.17

For apprentice rates see "Apprentice- LABORER"

LABORER: CEMENT FINISHER TENDER
LABORERS - ZONE 3 (BUILDING & SITE) 12/01/2022 \$33.63 \$9.10 \$16.19 \$0.00 \$58.92

06/01/2023 \$34.25 \$9.10 \$16.19 \$0.00 \$59.54

12/01/2023 \$34.88 \$9.10 \$16.19 \$0.00 \$60.17

For apprentice rates see "Apprentice- LABORER"

LABORER: HAZARDOUS WASTE/ASBESTOS REMOVER
LABORERS - ZONE 3 (BUILDING & SITE) 12/01/2022 \$33.48 \$9.10 \$16.44 \$0.00 \$59.02

06/01/2023 \$34.10 \$9.10 \$16.44 \$0.00 \$59.64

12/01/2023 \$34.73 \$9.10 \$16.44 \$0.00 \$60.27

For apprentice rates see "Apprentice- LABORER"

LABORER: MASON TENDER
LABORERS - ZONE 3 (BUILDING & SITE) 12/01/2022 \$34.63 \$9.10 \$16.19 \$0.00 \$59.92

06/01/2023 \$35.25 \$9.10 \$16.19 \$0.00 \$60.54

12/01/2023 \$35.88 \$9.10 \$16.19 \$0.00 \$61.17

For apprentice rates see "Apprentice- LABORER"

LABORER: MASON TENDER (HEAVY & HIGHWAY)
LABORERS - ZONE 3 (HEAVY & HIGHWAY) 12/01/2022 \$33.25 \$9.35 \$14.41 \$0.00 \$57.01

06/01/2023 \$33.87 \$9.35 \$14.41 \$0.00 \$57.63

12/01/2023 \$34.50 \$9.35 \$14.41 \$0.00 \$58.26

06/01/2024 \$35.70 \$9.35 \$14.41 \$0.00 \$59.46

12/01/2024 \$36.90 \$9.35 \$14.41 \$0.00 \$60.66

06/01/2025 \$38.15 \$9.35 \$14.41 \$0.00 \$61.91

12/01/2025 \$39.39 \$9.35 \$14.41 \$0.00 \$63.15

06/01/2026 \$40.69 \$9.35 \$14.41 \$0.00 \$64.45

12/01/2026 \$41.98 \$9.35 \$14.41 \$0.00 \$65.74

For apprentice rates see "Apprentice- LABORER (Heavy and Highway)"

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
LABORER: MULTI-TRADE TENDER <i>LABORERS - ZONE 3 (BUILDING & SITE)</i>	12/01/2022	\$33.63	\$9.10	\$16.19	\$0.00	\$58.92
	06/01/2023	\$34.25	\$9.10	\$16.19	\$0.00	\$59.54
	12/01/2023	\$34.88	\$9.10	\$16.19	\$0.00	\$60.17
For apprentice rates see "Apprentice- LABORER"						
LABORER: TREE REMOVER <i>LABORERS - ZONE 3 (BUILDING & SITE)</i>	12/01/2022	\$33.63	\$9.10	\$16.19	\$0.00	\$58.92
	06/01/2023	\$34.25	\$9.10	\$16.19	\$0.00	\$59.54
	12/01/2023	\$34.88	\$9.10	\$16.19	\$0.00	\$60.17
This classification applies to the removal of standing trees, and the trimming and removal of branches and limbs when related to public works construction or site clearance incidental to construction . For apprentice rates see "Apprentice- LABORER"						
LASER BEAM OPERATOR <i>LABORERS - ZONE 3 (BUILDING & SITE)</i>	12/01/2022	\$33.88	\$9.10	\$16.19	\$0.00	\$59.17
	06/01/2023	\$34.50	\$9.10	\$16.19	\$0.00	\$59.79
	12/01/2023	\$35.13	\$9.10	\$16.19	\$0.00	\$60.42
For apprentice rates see "Apprentice- LABORER"						
LASER BEAM OPERATOR (HEAVY & HIGHWAY) <i>LABORERS - ZONE 3 (HEAVY & HIGHWAY)</i>	12/01/2022	\$33.25	\$9.35	\$14.41	\$0.00	\$57.01
	06/01/2023	\$33.87	\$9.35	\$14.41	\$0.00	\$57.63
	12/01/2023	\$34.50	\$9.35	\$14.41	\$0.00	\$58.26
	06/01/2024	\$35.70	\$9.35	\$14.41	\$0.00	\$59.46
	12/01/2024	\$36.90	\$9.35	\$14.41	\$0.00	\$60.66
	06/01/2025	\$38.15	\$9.35	\$14.41	\$0.00	\$61.91
	12/01/2025	\$39.39	\$9.35	\$14.41	\$0.00	\$63.15
	06/01/2026	\$40.69	\$9.35	\$14.41	\$0.00	\$64.45
	12/01/2026	\$41.98	\$9.35	\$14.41	\$0.00	\$65.74
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)"						
MARBLE & TILE FINISHERS <i>BRICKLAYERS LOCAL 3 (SPR/PITT) - MARBLE & TILE</i>	02/01/2023	\$39.73	\$11.49	\$19.53	\$0.00	\$70.75
	08/01/2023	\$41.37	\$11.49	\$19.53	\$0.00	\$72.39
	02/01/2024	\$42.37	\$11.49	\$19.53	\$0.00	\$73.39
	08/01/2024	\$44.05	\$11.49	\$19.53	\$0.00	\$75.07
	02/01/2025	\$45.90	\$11.49	\$19.53	\$0.00	\$76.92
	08/01/2025	\$46.81	\$11.49	\$19.53	\$0.00	\$77.83
	02/01/2026	\$47.89	\$11.49	\$19.53	\$0.00	\$78.91
	08/01/2026	\$49.65	\$11.49	\$19.53	\$0.00	\$80.67
	02/01/2027	\$50.77	\$11.49	\$19.53	\$0.00	\$81.79

Classification

Effective Date Base Wage Health Pension Supplemental Unemployment Total Rate

Apprentice - MARBLE-TILE FINISHER-Local 3 Marble/Tile (Spr/Pitt)

Effective Date - 02/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$19.87	\$11.49	\$19.53	\$0.00	\$50.89
2	60	\$23.84	\$11.49	\$19.53	\$0.00	\$54.86
3	70	\$27.81	\$11.49	\$19.53	\$0.00	\$58.83
4	80	\$31.78	\$11.49	\$19.53	\$0.00	\$62.80
5	90	\$35.76	\$11.49	\$19.53	\$0.00	\$66.78

Effective Date - 08/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$20.69	\$11.49	\$19.53	\$0.00	\$51.71
2	60	\$24.82	\$11.49	\$19.53	\$0.00	\$55.84
3	70	\$28.96	\$11.49	\$19.53	\$0.00	\$59.98
4	80	\$33.10	\$11.49	\$19.53	\$0.00	\$64.12
5	90	\$37.23	\$11.49	\$19.53	\$0.00	\$68.25

Notes:

Apprentice to Journeyworker Ratio:1:5

MARBLE MASON/TILE LAYER(SP/PT)SeeBrick
BRICKLAYERS LOCAL 3 (SPR/PITT) - MARBLE & TILE

See "BRICK/STONE/ARTIFICIAL MASONRY(INCL.MASONRY WATERPROOFING)

MECH. SWEEPER OPERATOR (ON CONST. SITES) OPERATING ENGINEERS LOCAL 98	12/01/2022	\$38.21	\$13.38	\$15.00	\$0.00	\$66.59
	06/01/2023	\$39.16	\$13.38	\$15.00	\$0.00	\$67.54
	12/01/2023	\$40.11	\$13.38	\$15.00	\$0.00	\$68.49

For apprentice rates see "Apprentice- OPERATING ENGINEERS"

MECHANIC/WELDER/BOOM TRUCK OPERATING ENGINEERS LOCAL 98	12/01/2022	\$37.68	\$13.38	\$15.00	\$0.00	\$66.06
	06/01/2023	\$38.63	\$13.38	\$15.00	\$0.00	\$67.01
	12/01/2023	\$39.58	\$13.38	\$15.00	\$0.00	\$67.96

For apprentice rates see "Apprentice- OPERATING ENGINEERS"

MILLWRIGHT (Zone 3) MILLWRIGHTS LOCAL 1121 - Zone 3	01/02/2023	\$40.16	\$8.58	\$21.57	\$0.00	\$70.31
--	------------	---------	--------	---------	--------	---------

Apprentice - MILLWRIGHT - Local 1121 Zone 3

Effective Date - 01/02/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	55	\$22.09	\$8.58	\$5.72	\$0.00	\$36.39
2	65	\$26.10	\$8.58	\$17.93	\$0.00	\$52.61
3	75	\$30.12	\$8.58	\$18.98	\$0.00	\$57.68
4	85	\$34.14	\$8.58	\$20.01	\$0.00	\$62.73

Notes: Step 1&2 Appr. indentured after 1/6/2020 receive no pension, but do receive annuity. (Step 1 \$5.72, Step 2 \$6.66)
Steps are 2,000 hours

Apprentice to Journeyworker Ratio:1:4

MORTAR MIXER <i>LABORERS - ZONE 3 (BUILDING & SITE)</i>	12/01/2022	\$33.88	\$9.10	\$16.19	\$0.00	\$59.17
	06/01/2023	\$34.50	\$9.10	\$16.19	\$0.00	\$59.79
	12/01/2023	\$35.13	\$9.10	\$16.19	\$0.00	\$60.42

For apprentice rates see "Apprentice- LABORER"

OILER <i>OPERATING ENGINEERS LOCAL 98</i>	12/01/2022	\$33.37	\$13.38	\$15.00	\$0.00	\$61.75
	06/01/2023	\$34.32	\$13.38	\$15.00	\$0.00	\$62.70
	12/01/2023	\$35.27	\$13.38	\$15.00	\$0.00	\$63.65

For apprentice rates see "Apprentice- OPERATING ENGINEERS"

OTHER POWER DRIVEN EQUIPMENT - CLASS VI <i>OPERATING ENGINEERS LOCAL 98</i>	12/01/2022	\$32.80	\$12.47	\$14.50	\$0.00	\$59.77
	06/01/2023	\$33.75	\$12.47	\$14.50	\$0.00	\$60.72
	12/01/2023	\$34.70	\$12.47	\$14.50	\$0.00	\$61.67

For apprentice rates see "Apprentice- OPERATING ENGINEERS"

PAINTER (BRIDGES/TANKS) <i>PAINTERS LOCAL 35 - ZONE 3</i>	01/01/2023	\$56.06	\$8.65	\$23.05	\$0.00	\$87.76
	07/01/2023	\$57.26	\$8.65	\$23.05	\$0.00	\$88.96
	01/01/2024	\$58.46	\$8.65	\$23.05	\$0.00	\$90.16
	07/01/2024	\$59.66	\$8.65	\$23.05	\$0.00	\$91.36
	01/01/2025	\$60.86	\$8.65	\$23.05	\$0.00	\$92.56

Apprentice - PAINTER Local 35 - BRIDGES/TANKS

Effective Date - 01/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$28.03	\$8.65	\$0.00	\$0.00	\$36.68
2	55	\$30.83	\$8.65	\$6.27	\$0.00	\$45.75
3	60	\$33.64	\$8.65	\$6.84	\$0.00	\$49.13
4	65	\$36.44	\$8.65	\$7.41	\$0.00	\$52.50
5	70	\$39.24	\$8.65	\$19.63	\$0.00	\$67.52
6	75	\$42.05	\$8.65	\$20.20	\$0.00	\$70.90
7	80	\$44.85	\$8.65	\$20.77	\$0.00	\$74.27
8	90	\$50.45	\$8.65	\$21.91	\$0.00	\$81.01

Effective Date - 07/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$28.63	\$8.65	\$0.00	\$0.00	\$37.28
2	55	\$31.49	\$8.65	\$6.27	\$0.00	\$46.41
3	60	\$34.36	\$8.65	\$6.84	\$0.00	\$49.85
4	65	\$37.22	\$8.65	\$7.41	\$0.00	\$53.28
5	70	\$40.08	\$8.65	\$19.63	\$0.00	\$68.36
6	75	\$42.95	\$8.65	\$20.20	\$0.00	\$71.80
7	80	\$45.81	\$8.65	\$20.77	\$0.00	\$75.23
8	90	\$51.53	\$8.65	\$21.91	\$0.00	\$82.09

Notes:

Steps are 750 hrs.

Apprentice to Journeyworker Ratio:1:1

PAINTER (SPRAY OR SANDBLAST, NEW) *	01/01/2023	\$38.93	\$8.65	\$19.15	\$0.00	\$66.73
* If 30% or more of surfaces to be painted are new construction, NEW paint rate shall be used. PAINTERS LOCAL 35 - ZONE 3	07/01/2023	\$39.98	\$8.65	\$19.15	\$0.00	\$67.78
	01/01/2024	\$41.08	\$8.65	\$19.15	\$0.00	\$68.88
	07/01/2024	\$42.13	\$8.65	\$19.15	\$0.00	\$69.93
	01/01/2025	\$43.23	\$8.65	\$19.15	\$0.00	\$71.03

Classification

Effective Date Base Wage Health Pension Supplemental Unemployment Total Rate

Apprentice - PAINTER Local 35 Zone 3 - Spray/Sandblast - New

Effective Date - 01/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$19.47	\$8.65	\$0.00	\$0.00	\$28.12
2	55	\$21.41	\$8.65	\$4.13	\$0.00	\$34.19
3	60	\$23.36	\$8.65	\$4.50	\$0.00	\$36.51
4	65	\$25.30	\$8.65	\$4.88	\$0.00	\$38.83
5	70	\$27.25	\$8.65	\$16.90	\$0.00	\$52.80
6	75	\$29.20	\$8.65	\$17.28	\$0.00	\$55.13
7	80	\$31.14	\$8.65	\$17.65	\$0.00	\$57.44
8	90	\$35.04	\$8.65	\$18.40	\$0.00	\$62.09

Effective Date - 07/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$19.99	\$8.65	\$0.00	\$0.00	\$28.64
2	55	\$21.99	\$8.65	\$4.13	\$0.00	\$34.77
3	60	\$23.99	\$8.65	\$4.50	\$0.00	\$37.14
4	65	\$25.99	\$8.65	\$4.88	\$0.00	\$39.52
5	70	\$27.99	\$8.65	\$16.90	\$0.00	\$53.54
6	75	\$29.99	\$8.65	\$17.28	\$0.00	\$55.92
7	80	\$31.98	\$8.65	\$17.65	\$0.00	\$58.28
8	90	\$35.98	\$8.65	\$18.40	\$0.00	\$63.03

Notes:

Steps are 750 hrs.

Apprentice to Journeyworker Ratio:1:1

PAINTER (SPRAY OR SANDBLAST, REPAINT)	01/01/2023	\$36.25	\$8.65	\$19.15	\$0.00	\$64.05
PAINTERS LOCAL 35 - ZONE 3	07/01/2023	\$37.30	\$8.65	\$19.15	\$0.00	\$65.10
	01/01/2024	\$38.40	\$8.65	\$19.15	\$0.00	\$66.20
	07/01/2024	\$39.45	\$8.65	\$19.15	\$0.00	\$67.25
	01/01/2025	\$40.55	\$8.65	\$19.15	\$0.00	\$68.35

Classification

Effective Date Base Wage Health Pension Supplemental Unemployment Total Rate

Apprentice - PAINTER Local 35 Zone 3 - Spray/Sandblast - Repaint

Effective Date - 01/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$18.13	\$8.65	\$0.00	\$0.00	\$26.78
2	55	\$19.94	\$8.65	\$4.13	\$0.00	\$32.72
3	60	\$21.75	\$8.65	\$4.50	\$0.00	\$34.90
4	65	\$23.56	\$8.65	\$4.88	\$0.00	\$37.09
5	70	\$25.38	\$8.65	\$16.90	\$0.00	\$50.93
6	75	\$27.19	\$8.65	\$17.28	\$0.00	\$53.12
7	80	\$29.00	\$8.65	\$17.65	\$0.00	\$55.30
8	90	\$32.63	\$8.65	\$18.40	\$0.00	\$59.68

Effective Date - 07/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$18.65	\$8.65	\$0.00	\$0.00	\$27.30
2	55	\$20.52	\$8.65	\$4.13	\$0.00	\$33.30
3	60	\$22.38	\$8.65	\$4.50	\$0.00	\$35.53
4	65	\$24.25	\$8.65	\$4.88	\$0.00	\$37.78
5	70	\$26.11	\$8.65	\$16.90	\$0.00	\$51.66
6	75	\$27.98	\$8.65	\$17.28	\$0.00	\$53.91
7	80	\$29.84	\$8.65	\$17.65	\$0.00	\$56.14
8	90	\$33.57	\$8.65	\$18.40	\$0.00	\$60.62

Notes:
Steps are 750 hrs.

Apprentice to Journeyworker Ratio:1:1

PAINTER / TAPER (BRUSH, NEW) *	01/01/2023	\$37.53	\$8.65	\$19.15	\$0.00	\$65.33
* If 30% or more of surfaces to be painted are new construction, NEW paint rate shall be used. PAINTERS LOCAL 35 - ZONE 3	07/01/2023	\$38.58	\$8.65	\$19.15	\$0.00	\$66.38
	01/01/2024	\$39.68	\$8.65	\$19.15	\$0.00	\$67.48
	07/01/2024	\$40.73	\$8.65	\$19.15	\$0.00	\$68.53
	01/01/2025	\$41.83	\$8.65	\$19.15	\$0.00	\$69.63

Apprentice - PAINTER - Local 35 Zone 3 - BRUSH NEW

Effective Date - 01/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$18.77	\$8.65	\$0.00	\$0.00	\$27.42
2	55	\$20.64	\$8.65	\$4.13	\$0.00	\$33.42
3	60	\$22.52	\$8.65	\$4.50	\$0.00	\$35.67
4	65	\$24.39	\$8.65	\$4.88	\$0.00	\$37.92
5	70	\$26.27	\$8.65	\$16.90	\$0.00	\$51.82
6	75	\$28.15	\$8.65	\$17.28	\$0.00	\$54.08
7	80	\$30.02	\$8.65	\$17.65	\$0.00	\$56.32
8	90	\$33.78	\$8.65	\$18.40	\$0.00	\$60.83

Effective Date - 07/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$19.29	\$8.65	\$0.00	\$0.00	\$27.94
2	55	\$21.22	\$8.65	\$4.13	\$0.00	\$34.00
3	60	\$23.15	\$8.65	\$4.50	\$0.00	\$36.30
4	65	\$25.08	\$8.65	\$4.88	\$0.00	\$38.61
5	70	\$27.01	\$8.65	\$16.90	\$0.00	\$52.56
6	75	\$28.94	\$8.65	\$17.28	\$0.00	\$54.87
7	80	\$30.86	\$8.65	\$17.65	\$0.00	\$57.16
8	90	\$34.72	\$8.65	\$18.40	\$0.00	\$61.77

Notes:

Steps are 750 hrs.

Apprentice to Journeyworker Ratio:1:1

PAINTER / TAPER (BRUSH, REPAINT)	01/01/2023	\$34.85	\$8.65	\$19.15	\$0.00	\$62.65
PAINTERS LOCAL 35 - ZONE 3	07/01/2023	\$35.90	\$8.65	\$19.15	\$0.00	\$63.70
	01/01/2024	\$37.00	\$8.65	\$19.15	\$0.00	\$64.80
	07/01/2024	\$38.05	\$8.65	\$19.15	\$0.00	\$65.85
	01/01/2025	\$39.15	\$8.65	\$19.15	\$0.00	\$66.95

Classification

Effective Date Base Wage Health Pension Supplemental Unemployment Total Rate

Apprentice - PAINTER Local 35 Zone 3 - BRUSH REPAINT

Effective Date - 01/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$17.43	\$8.65	\$0.00	\$0.00	\$26.08
2	55	\$19.17	\$8.65	\$4.13	\$0.00	\$31.95
3	60	\$20.91	\$8.65	\$4.50	\$0.00	\$34.06
4	65	\$22.65	\$8.65	\$4.88	\$0.00	\$36.18
5	70	\$24.40	\$8.65	\$16.90	\$0.00	\$49.95
6	75	\$26.14	\$8.65	\$17.28	\$0.00	\$52.07
7	80	\$27.88	\$8.65	\$17.65	\$0.00	\$54.18
8	90	\$31.37	\$8.65	\$18.40	\$0.00	\$58.42

Effective Date - 07/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$17.95	\$8.65	\$0.00	\$0.00	\$26.60
2	55	\$19.75	\$8.65	\$4.13	\$0.00	\$32.53
3	60	\$21.54	\$8.65	\$4.50	\$0.00	\$34.69
4	65	\$23.34	\$8.65	\$4.88	\$0.00	\$36.87
5	70	\$25.13	\$8.65	\$16.90	\$0.00	\$50.68
6	75	\$26.93	\$8.65	\$17.28	\$0.00	\$52.86
7	80	\$28.72	\$8.65	\$17.65	\$0.00	\$55.02
8	90	\$32.31	\$8.65	\$18.40	\$0.00	\$59.36

Notes:

Steps are 750 hrs.

Apprentice to Journeyworker Ratio:1:1

PAINTER TRAFFIC MARKINGS (HEAVY/HIGHWAY)	12/01/2022	\$33.00	\$9.35	\$14.41	\$0.00	\$56.76
LABORERS - ZONE 3 (HEAVY & HIGHWAY)	06/01/2023	\$33.62	\$9.35	\$14.41	\$0.00	\$57.38
	12/01/2023	\$34.25	\$9.35	\$14.41	\$0.00	\$58.01
	06/01/2024	\$35.45	\$9.35	\$14.41	\$0.00	\$59.21
	12/01/2024	\$36.65	\$9.35	\$14.41	\$0.00	\$60.41
	06/01/2025	\$37.90	\$9.35	\$14.41	\$0.00	\$61.66
	12/01/2025	\$39.14	\$9.35	\$14.41	\$0.00	\$62.90
	06/01/2026	\$40.44	\$9.35	\$14.41	\$0.00	\$64.20
	12/01/2026	\$41.73	\$9.35	\$14.41	\$0.00	\$65.49

For apprentice rates see "Apprentice- LABORER (Heavy and Highway)

PANEL & PICKUP TRUCKS DRIVER	12/01/2021	\$35.78	\$13.41	\$16.01	\$0.00	\$65.20
TEAMSTERS JOINT COUNCIL NO. 10 ZONE B						

PIER AND DOCK CONSTRUCTOR (UNDERPINNING AND DECK)	08/01/2020	\$43.53	\$9.40	\$23.12	\$0.00	\$76.05
PILE DRIVER LOCAL 56 (ZONE 3)						

For apprentice rates see "Apprentice- PILE DRIVER"

PILE DRIVER	08/01/2020	\$43.53	\$9.40	\$23.12	\$0.00	\$76.05
PILE DRIVER LOCAL 56 (ZONE 3)						

Apprentice - PILE DRIVER - Local 56 Zone 3

Effective Date - 08/01/2020

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	0	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00

Notes: Apprentice wages shall be no less than the following Steps;
 (Same as set in Zone 1)
 1\$57.06/2\$61.96/3\$66.87/4\$69.32/5\$71.78/6\$71.78/7\$76.68/8\$76.68

Apprentice to Journeyworker Ratio:1:5

PIPELAYER <i>LABORERS - ZONE 3 (BUILDING & SITE)</i>	12/01/2022	\$33.88	\$9.10	\$16.19	\$0.00	\$59.17
	06/01/2023	\$34.50	\$9.10	\$16.19	\$0.00	\$59.79
	12/01/2023	\$35.13	\$9.10	\$16.19	\$0.00	\$60.42

For apprentice rates see "Apprentice- LABORER"

PIPELAYER (HEAVY & HIGHWAY) <i>LABORERS - ZONE 3 (HEAVY & HIGHWAY)</i>	12/01/2022	\$33.25	\$9.35	\$14.41	\$0.00	\$57.01
	06/01/2023	\$33.87	\$9.35	\$14.41	\$0.00	\$57.63
	12/01/2023	\$34.50	\$9.35	\$14.41	\$0.00	\$58.26
	06/01/2024	\$35.70	\$9.35	\$14.41	\$0.00	\$59.46
	12/01/2024	\$36.90	\$9.35	\$14.41	\$0.00	\$60.66
	06/01/2025	\$38.15	\$9.35	\$14.41	\$0.00	\$61.91
	12/01/2025	\$39.39	\$9.35	\$14.41	\$0.00	\$63.15
	06/01/2026	\$40.69	\$9.35	\$14.41	\$0.00	\$64.45
	12/01/2026	\$41.98	\$9.35	\$14.41	\$0.00	\$65.74

For apprentice rates see "Apprentice- LABORER (Heavy and Highway)"

PLUMBER & PIPEFITTER <i>PLUMBERS & PIPEFITTERS LOCAL 104</i>	09/17/2022	\$45.71	\$9.55	\$17.10	\$0.00	\$72.36
	03/17/2023	\$46.96	\$9.55	\$17.10	\$0.00	\$73.61
	09/17/2023	\$47.96	\$9.55	\$17.10	\$0.00	\$74.61
	03/17/2024	\$49.21	\$9.55	\$17.10	\$0.00	\$75.86

Classification

Effective Date Base Wage Health Pension Supplemental Unemployment Total Rate

Apprentice - PLUMBER/PIPEFITTER - Local 104

Effective Date - 09/17/2022

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	45	\$20.57	\$9.55	\$10.10	\$0.00	\$40.22
2	50	\$22.86	\$9.55	\$10.10	\$0.00	\$42.51
3	55	\$25.14	\$9.55	\$10.10	\$0.00	\$44.79
4	60	\$27.43	\$9.55	\$10.10	\$0.00	\$47.08
5	65	\$29.71	\$9.55	\$10.10	\$0.00	\$49.36
6	70	\$32.00	\$9.55	\$10.10	\$0.00	\$51.65
7	75	\$34.28	\$9.55	\$10.10	\$0.00	\$53.93
8	80	\$36.57	\$9.55	\$10.10	\$0.00	\$56.22
9	80	\$36.57	\$9.55	\$17.10	\$0.00	\$63.22
10	80	\$36.57	\$9.55	\$17.10	\$0.00	\$63.22

Effective Date - 03/17/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	45	\$21.13	\$9.55	\$10.10	\$0.00	\$40.78
2	50	\$23.48	\$9.55	\$10.10	\$0.00	\$43.13
3	55	\$25.83	\$9.55	\$10.10	\$0.00	\$45.48
4	60	\$28.18	\$9.55	\$10.10	\$0.00	\$47.83
5	65	\$30.52	\$9.55	\$10.10	\$0.00	\$50.17
6	70	\$32.87	\$9.55	\$10.10	\$0.00	\$52.52
7	75	\$35.22	\$9.55	\$10.10	\$0.00	\$54.87
8	80	\$37.57	\$9.55	\$10.10	\$0.00	\$57.22
9	80	\$37.57	\$9.55	\$17.10	\$0.00	\$64.22
10	80	\$37.57	\$9.55	\$17.10	\$0.00	\$64.22

Notes: **1:1,2:5,3:9,4:12

Apprentice to Journeyworker Ratio:**

PNEUMATIC CONTROLS (TEMP.) PLUMBERS & PIPEFITTERS LOCAL 104	09/17/2022	\$45.71	\$9.55	\$17.10	\$0.00	\$72.36
	03/17/2023	\$46.96	\$9.55	\$17.10	\$0.00	\$73.61
	09/17/2023	\$47.96	\$9.55	\$17.10	\$0.00	\$74.61
	03/17/2024	\$49.21	\$9.55	\$17.10	\$0.00	\$75.86

For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"

PNEUMATIC DRILL/TOOL OPERATOR (HEAVY & HIGHWAY) LABORERS - ZONE 3 (HEAVY & HIGHWAY)	12/01/2022	\$33.25	\$9.35	\$14.41	\$0.00	\$57.01
	06/01/2023	\$33.87	\$9.35	\$14.41	\$0.00	\$57.63
	12/01/2023	\$34.50	\$9.35	\$14.41	\$0.00	\$58.26
	06/01/2024	\$35.70	\$9.35	\$14.41	\$0.00	\$59.46
	12/01/2024	\$36.90	\$9.35	\$14.41	\$0.00	\$60.66
	06/01/2025	\$38.15	\$9.35	\$14.41	\$0.00	\$61.91
	12/01/2025	\$39.39	\$9.35	\$14.41	\$0.00	\$63.15
	06/01/2026	\$40.69	\$9.35	\$14.41	\$0.00	\$64.45
	12/01/2026	\$41.98	\$9.35	\$14.41	\$0.00	\$65.74

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)						
POWDERMAN & BLASTER <i>LABORERS - ZONE 3 (BUILDING & SITE)</i>	12/01/2022	\$34.63	\$9.10	\$16.19	\$0.00	\$59.92
	06/01/2023	\$35.25	\$9.10	\$16.19	\$0.00	\$60.54
	12/01/2023	\$35.88	\$9.10	\$16.19	\$0.00	\$61.17
For apprentice rates see "Apprentice- LABORER"						
POWDERMAN & BLASTER (HEAVY & HIGHWAY) <i>LABORERS - ZONE 3 (HEAVY & HIGHWAY)</i>	12/01/2022	\$33.75	\$9.35	\$14.41	\$0.00	\$57.51
	06/01/2023	\$34.37	\$9.35	\$14.41	\$0.00	\$58.13
	12/01/2023	\$35.00	\$9.35	\$14.41	\$0.00	\$58.76
	06/01/2024	\$36.20	\$9.35	\$14.41	\$0.00	\$59.96
	12/01/2024	\$37.40	\$9.35	\$14.41	\$0.00	\$61.16
	06/01/2025	\$38.65	\$9.35	\$14.41	\$0.00	\$62.41
	12/01/2025	\$39.89	\$9.35	\$14.41	\$0.00	\$63.65
	06/01/2026	\$41.19	\$9.35	\$14.41	\$0.00	\$64.95
	12/01/2026	\$42.48	\$9.35	\$14.41	\$0.00	\$66.24
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)						
PUMP OPERATOR (CONCRETE) <i>OPERATING ENGINEERS LOCAL 98</i>	12/01/2022	\$38.21	\$13.38	\$15.00	\$0.00	\$66.59
	06/01/2023	\$39.16	\$13.38	\$15.00	\$0.00	\$67.54
	12/01/2023	\$40.11	\$13.38	\$15.00	\$0.00	\$68.49
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
PUMP OPERATOR (DEWATERING, OTHER) <i>OPERATING ENGINEERS LOCAL 98</i>	12/01/2022	\$37.68	\$13.38	\$15.00	\$0.00	\$66.06
	06/01/2023	\$38.63	\$13.38	\$15.00	\$0.00	\$67.01
	12/01/2023	\$39.58	\$13.38	\$15.00	\$0.00	\$67.96
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
READY-MIX CONCRETE DRIVER <i>TEAMSTERS 404 - Construction Service (Northampton)</i>	05/01/2020	\$22.44	\$11.07	\$6.50	\$0.00	\$40.01
RIDE-ON MOTORIZED BUGGY OPERATOR <i>LABORERS - ZONE 3 (BUILDING & SITE)</i>	12/01/2022	\$33.88	\$9.10	\$16.19	\$0.00	\$59.17
	06/01/2023	\$34.50	\$9.10	\$16.19	\$0.00	\$59.79
	12/01/2023	\$35.13	\$9.10	\$16.19	\$0.00	\$60.42
For apprentice rates see "Apprentice- LABORER"						
ROLLER OPERATOR <i>OPERATING ENGINEERS LOCAL 98</i>	12/01/2022	\$37.07	\$13.38	\$15.00	\$0.00	\$65.45
	06/01/2023	\$38.02	\$13.38	\$15.00	\$0.00	\$66.40
	12/01/2023	\$38.97	\$13.38	\$15.00	\$0.00	\$67.35
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
ROOFER (Coal tar pitch) <i>ROOFERS LOCAL 248</i>	07/01/2022	\$38.16	\$10.35	\$17.25	\$0.00	\$65.76
	07/01/2023	\$38.66	\$10.35	\$18.75	\$0.00	\$67.76
For apprentice rates see "Apprentice- ROOFER"						
ROOFER (Inc.Roofing Waterproofing &Roofing Damproofg) <i>ROOFERS LOCAL 248</i>	07/01/2022	\$37.66	\$10.35	\$16.75	\$0.00	\$64.76
	07/01/2023	\$39.16	\$10.35	\$18.25	\$0.00	\$67.76

Classification

Effective Date Base Wage Health Pension Supplemental Unemployment Total Rate

Apprentice - ROOFER - Local 248

Effective Date - 07/01/2022

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	60	\$22.60	\$10.35	\$0.00	\$0.00	\$32.95
2	65	\$24.48	\$10.35	\$16.75	\$0.00	\$51.58
3	70	\$26.36	\$10.35	\$16.75	\$0.00	\$53.46
4	75	\$28.25	\$10.35	\$16.75	\$0.00	\$55.35
5	80	\$30.13	\$10.35	\$16.75	\$0.00	\$57.23
6	85	\$32.01	\$10.35	\$16.75	\$0.00	\$59.11
7	90	\$33.89	\$10.35	\$16.75	\$0.00	\$60.99
8	95	\$35.78	\$10.35	\$16.75	\$0.00	\$62.88

Effective Date - 07/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	60	\$23.50	\$10.35	\$0.00	\$0.00	\$33.85
2	65	\$25.45	\$10.35	\$18.25	\$0.00	\$54.05
3	70	\$27.41	\$10.35	\$18.25	\$0.00	\$56.01
4	75	\$29.37	\$10.35	\$18.25	\$0.00	\$57.97
5	80	\$31.33	\$10.35	\$18.25	\$0.00	\$59.93
6	85	\$33.29	\$10.35	\$18.25	\$0.00	\$61.89
7	90	\$35.24	\$10.35	\$18.25	\$0.00	\$63.84
8	95	\$37.20	\$10.35	\$18.25	\$0.00	\$65.80

Notes:
Steps are 750 hrs.Roofer(Tear Off)1:1; Same as above

Apprentice to Journeyworker Ratio:1:3

ROOFER SLATE / TILE / PRECAST CONCRETE <i>ROOFERS LOCAL 248</i>	07/01/2022	\$38.16	\$10.35	\$17.25	\$0.00	\$65.76
	07/01/2023	\$38.66	\$10.35	\$18.75	\$0.00	\$67.76
For apprentice rates see "Apprentice- ROOFER"						
SCRAPER <i>OPERATING ENGINEERS LOCAL 98</i>	12/01/2022	\$37.68	\$13.38	\$15.00	\$0.00	\$66.06
	06/01/2023	\$38.63	\$13.38	\$15.00	\$0.00	\$67.01
	12/01/2023	\$39.58	\$13.38	\$15.00	\$0.00	\$67.96
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
SELF-POWERED ROLLERS AND COMPACTORS (TAMPERS) <i>OPERATING ENGINEERS LOCAL 98</i>	12/01/2022	\$37.07	\$13.38	\$15.00	\$0.00	\$65.45
	06/01/2023	\$38.02	\$13.38	\$15.00	\$0.00	\$66.40
	12/01/2023	\$38.97	\$13.38	\$15.00	\$0.00	\$67.35
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
SELF-PROPELLED POWER BROOM <i>OPERATING ENGINEERS LOCAL 98</i>	12/01/2022	\$34.45	\$13.38	\$15.00	\$0.00	\$62.83
	06/01/2023	\$35.40	\$13.38	\$15.00	\$0.00	\$63.78
	12/01/2023	\$36.35	\$13.38	\$15.00	\$0.00	\$64.73
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
SHEETMETAL WORKER <i>SHEETMETAL WORKERS LOCAL 63</i>	01/01/2023	\$41.30	\$10.64	\$17.54	\$2.05	\$71.53
	07/01/2023	\$42.55	\$10.64	\$17.54	\$2.05	\$72.78
	01/01/2024	\$43.80	\$10.64	\$17.54	\$2.05	\$74.03
	07/01/2024	\$45.05	\$10.64	\$17.54	\$2.05	\$75.28
	01/01/2025	\$46.30	\$10.64	\$17.54	\$2.05	\$76.53

Apprentice - SHEET METAL WORKER - Local 63

Effective Date - 01/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	45	\$18.59	\$4.79	\$4.76	\$0.92	\$29.06
2	50	\$20.65	\$5.32	\$5.29	\$1.03	\$32.29
3	55	\$22.72	\$5.85	\$5.82	\$1.13	\$35.52
4	60	\$24.78	\$6.38	\$6.35	\$1.23	\$38.74
5	65	\$26.85	\$6.92	\$6.88	\$1.33	\$41.98
6	70	\$28.91	\$7.45	\$7.41	\$1.44	\$45.21
7	75	\$30.98	\$7.98	\$7.94	\$1.54	\$48.44
8	80	\$33.04	\$8.51	\$15.42	\$1.64	\$58.61
9	85	\$35.11	\$9.04	\$15.95	\$1.74	\$61.84
10	90	\$37.17	\$9.58	\$16.48	\$1.85	\$65.08

Effective Date - 07/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	45	\$19.15	\$4.79	\$4.76	\$0.92	\$29.62
2	50	\$21.28	\$5.32	\$5.29	\$1.03	\$32.92
3	55	\$23.40	\$5.85	\$5.82	\$1.13	\$36.20
4	60	\$25.53	\$6.38	\$6.35	\$1.23	\$39.49
5	65	\$27.66	\$6.92	\$6.88	\$1.33	\$42.79
6	70	\$29.79	\$7.45	\$7.41	\$1.44	\$46.09
7	75	\$31.91	\$7.98	\$7.94	\$1.54	\$49.37
8	80	\$34.04	\$8.51	\$15.42	\$1.64	\$59.61
9	85	\$36.17	\$9.04	\$15.95	\$1.74	\$62.90
10	90	\$38.30	\$9.58	\$16.48	\$1.85	\$66.21

Notes:

Apprentice to Journeyworker Ratio:1:3

SPECIALIZED EARTH MOVING EQUIP < 35 TONS <i>TEAMSTERS JOINT COUNCIL NO. 10 ZONE B</i>	12/01/2021	\$36.24	\$13.41	\$16.01	\$0.00	\$65.66
SPECIALIZED EARTH MOVING EQUIP > 35 TONS <i>TEAMSTERS JOINT COUNCIL NO. 10 ZONE B</i>	12/01/2021	\$36.53	\$13.41	\$16.01	\$0.00	\$65.95
SPRINKLER FITTER <i>SPRINKLER FITTERS LOCAL 669</i>	04/01/2021	\$43.14	\$10.55	\$16.41	\$0.00	\$70.10

Classification

Effective Date Base Wage Health Pension Supplemental Unemployment Total Rate

Apprentice - SPRINKLER FITTER - Local 669

Effective Date - 04/01/2021

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	45	\$19.41	\$7.75	\$0.00	\$0.00	\$27.16
2	50	\$21.57	\$7.75	\$0.00	\$0.00	\$29.32
3	55	\$23.73	\$10.55	\$8.15	\$0.00	\$42.43
4	60	\$25.88	\$10.55	\$8.15	\$0.00	\$44.58
5	65	\$28.04	\$10.55	\$8.40	\$0.00	\$46.99
6	70	\$30.20	\$10.55	\$8.40	\$0.00	\$49.15
7	75	\$32.36	\$10.55	\$8.40	\$0.00	\$51.31
8	80	\$34.51	\$10.55	\$8.40	\$0.00	\$53.46
9	85	\$36.67	\$10.55	\$8.40	\$0.00	\$55.62
10	90	\$38.83	\$10.55	\$8.40	\$0.00	\$57.78

Notes:

Apprentice to Journeyworker Ratio:1:1

TELECOMMUNICATION TECHNICIAN <i>ELECTRICIANS LOCAL 7</i>	01/01/2023	\$47.01	\$12.50	\$13.96	\$0.00	\$73.47
---	------------	---------	---------	---------	--------	---------

Apprentice - TELECOMMUNICATION TECHNICIAN - Local 7

Effective Date - 01/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	40	\$18.80	\$7.35	\$0.56	\$0.00	\$26.71
2	45	\$21.15	\$7.35	\$0.63	\$0.00	\$29.13
3	50	\$23.51	\$12.25	\$7.20	\$0.00	\$42.96
4	55	\$25.86	\$12.25	\$7.27	\$0.00	\$45.38
5	65	\$30.56	\$12.25	\$9.14	\$0.00	\$51.95
6	70	\$32.91	\$12.25	\$10.37	\$0.00	\$55.53

Notes:
Steps are 800 hours

Apprentice to Journeyworker Ratio:1:1

TERRAZZO FINISHERS <i>BRICKLAYERS LOCAL 3 (SPR/PITT) - MARBLE & TILE</i>	02/01/2023	\$59.29	\$11.49	\$22.34	\$0.00	\$93.12
	08/01/2023	\$61.34	\$11.49	\$22.34	\$0.00	\$95.17
	02/01/2024	\$62.59	\$11.49	\$22.34	\$0.00	\$96.42
	08/01/2024	\$64.69	\$11.49	\$22.34	\$0.00	\$98.52
	02/01/2025	\$65.99	\$11.49	\$22.34	\$0.00	\$99.82
	08/01/2025	\$68.14	\$11.49	\$22.34	\$0.00	\$101.97
	02/10/2026	\$69.49	\$11.49	\$22.34	\$0.00	\$103.32
	08/01/2026	\$71.69	\$11.49	\$22.34	\$0.00	\$105.52
	02/01/2027	\$73.09	\$11.49	\$22.34	\$0.00	\$106.92

Classification

Effective Date Base Wage Health Pension Supplemental Unemployment Total Rate

Apprentice - TERRAZZO FINISHER-Local 3 Marble/Tile (Spr/Ptt)

Effective Date - 02/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$29.65	\$11.49	\$22.34	\$0.00	\$63.48
2	60	\$35.57	\$11.49	\$22.34	\$0.00	\$69.40
3	70	\$41.50	\$11.49	\$22.34	\$0.00	\$75.33
4	80	\$47.43	\$11.49	\$22.34	\$0.00	\$81.26
5	90	\$53.36	\$11.49	\$22.34	\$0.00	\$87.19

Effective Date - 08/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$30.67	\$11.49	\$22.34	\$0.00	\$64.50
2	60	\$36.80	\$11.49	\$22.34	\$0.00	\$70.63
3	70	\$42.94	\$11.49	\$22.34	\$0.00	\$76.77
4	80	\$49.07	\$11.49	\$22.34	\$0.00	\$82.90
5	90	\$55.21	\$11.49	\$22.34	\$0.00	\$89.04

Notes:

Apprentice to Journeyworker Ratio:1:5

TERRAZZO MECHANIC	02/01/2023	\$60.37	\$11.49	\$22.31	\$0.00	\$94.17
BRICKLAYERS LOCAL 3 (SPR/PITT) - MARBLE & TILE	08/01/2023	\$62.42	\$11.49	\$22.31	\$0.00	\$96.22
	02/01/2024	\$63.67	\$11.49	\$22.31	\$0.00	\$97.47
	08/01/2024	\$65.77	\$11.49	\$22.31	\$0.00	\$99.57
	02/01/2025	\$67.07	\$11.49	\$22.31	\$0.00	\$100.87
	08/01/2025	\$69.22	\$11.49	\$22.31	\$0.00	\$103.02
	02/01/2026	\$70.57	\$11.49	\$22.31	\$0.00	\$104.37
	08/01/2026	\$72.77	\$11.49	\$22.31	\$0.00	\$106.57
	02/01/2027	\$74.17	\$11.49	\$22.31	\$0.00	\$107.97

Classification

Effective Date Base Wage Health Pension Supplemental Unemployment Total Rate

Apprentice - TERRAZZO MECH - Local 3 Marble/Tile (Spr/Pitt)

Effective Date - 02/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$30.19	\$11.49	\$22.31	\$0.00	\$63.99
2	60	\$36.22	\$11.49	\$22.31	\$0.00	\$70.02
3	70	\$42.26	\$11.49	\$22.31	\$0.00	\$76.06
4	80	\$48.30	\$11.49	\$22.31	\$0.00	\$82.10
5	90	\$54.33	\$11.49	\$22.31	\$0.00	\$88.13

Effective Date - 08/01/2023

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$31.21	\$11.49	\$22.31	\$0.00	\$65.01
2	60	\$37.45	\$11.49	\$22.31	\$0.00	\$71.25
3	70	\$43.69	\$11.49	\$22.31	\$0.00	\$77.49
4	80	\$49.94	\$11.49	\$22.31	\$0.00	\$83.74
5	90	\$56.18	\$11.49	\$22.31	\$0.00	\$89.98

Notes:

Apprentice to Journeyworker Ratio:1:5

TEST BORING DRILLER LABORERS - FOUNDATION AND MARINE	12/01/2022	\$46.58	\$9.35	\$17.97	\$0.00	\$73.90
	06/01/2023	\$47.58	\$9.35	\$17.97	\$0.00	\$74.90
	12/01/2023	\$48.83	\$9.35	\$17.97	\$0.00	\$76.15
	06/01/2024	\$50.31	\$9.35	\$17.97	\$0.00	\$77.63
	12/01/2024	\$51.78	\$9.35	\$17.97	\$0.00	\$79.10
	06/01/2025	\$53.28	\$9.35	\$17.97	\$0.00	\$80.60
	12/01/2025	\$54.78	\$9.35	\$17.97	\$0.00	\$82.10
	06/01/2026	\$56.33	\$9.35	\$17.97	\$0.00	\$83.65
	12/01/2026	\$57.83	\$9.35	\$17.97	\$0.00	\$85.15

For apprentice rates see "Apprentice- LABORER"

TEST BORING DRILLER HELPER LABORERS - FOUNDATION AND MARINE	12/01/2022	\$42.70	\$9.35	\$17.97	\$0.00	\$70.02
	06/01/2023	\$43.70	\$9.35	\$17.97	\$0.00	\$71.02
	12/01/2023	\$44.95	\$9.35	\$17.97	\$0.00	\$72.27
	06/01/2024	\$46.43	\$9.35	\$17.97	\$0.00	\$73.75
	12/01/2024	\$47.90	\$9.35	\$17.97	\$0.00	\$75.22
	06/01/2025	\$49.40	\$9.35	\$17.97	\$0.00	\$76.72
	12/01/2025	\$50.90	\$9.35	\$17.97	\$0.00	\$78.22
	06/01/2026	\$52.45	\$9.35	\$17.97	\$0.00	\$79.77
	12/01/2026	\$53.95	\$9.35	\$17.97	\$0.00	\$81.27

For apprentice rates see "Apprentice- LABORER"

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
TEST BORING LABORER <i>LABORERS - FOUNDATION AND MARINE</i>	12/01/2022	\$42.58	\$9.35	\$17.97	\$0.00	\$69.90
	06/01/2023	\$43.58	\$9.35	\$17.97	\$0.00	\$70.90
	12/01/2023	\$44.83	\$9.35	\$17.97	\$0.00	\$72.15
	06/01/2024	\$46.31	\$9.35	\$17.97	\$0.00	\$73.63
	12/01/2024	\$47.78	\$9.35	\$17.97	\$0.00	\$75.10
	06/01/2025	\$49.28	\$9.35	\$17.97	\$0.00	\$76.60
	12/01/2025	\$50.78	\$9.35	\$17.97	\$0.00	\$78.10
	06/01/2026	\$52.33	\$9.35	\$17.97	\$0.00	\$79.65
	12/01/2026	\$53.83	\$9.35	\$17.97	\$0.00	\$81.15
For apprentice rates see "Apprentice- LABORER"						
TRACTORS <i>OPERATING ENGINEERS LOCAL 98</i>	12/01/2022	\$37.07	\$13.38	\$15.00	\$0.00	\$65.45
	06/01/2023	\$38.02	\$13.38	\$15.00	\$0.00	\$66.40
	12/01/2023	\$38.97	\$13.38	\$15.00	\$0.00	\$67.35
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
TRAILERS FOR EARTH MOVING EQUIPMENT <i>TEAMSTERS JOINT COUNCIL NO. 10 ZONE B</i>	12/01/2021	\$36.82	\$13.41	\$16.01	\$0.00	\$66.24
TUNNEL WORK - COMPRESSED AIR <i>LABORERS (COMPRESSED AIR)</i>	12/01/2022	\$54.81	\$9.35	\$18.42	\$0.00	\$82.58
	06/01/2023	\$55.81	\$9.35	\$18.42	\$0.00	\$83.58
	12/01/2023	\$57.06	\$9.35	\$18.42	\$0.00	\$84.83
	06/01/2024	\$58.54	\$9.35	\$18.42	\$0.00	\$86.31
	12/01/2024	\$60.01	\$9.35	\$18.42	\$0.00	\$87.78
	06/01/2025	\$61.51	\$9.35	\$18.42	\$0.00	\$89.28
	12/01/2025	\$63.01	\$9.35	\$18.42	\$0.00	\$90.78
	06/01/2026	\$64.56	\$9.35	\$18.42	\$0.00	\$92.33
	12/01/2026	\$66.06	\$9.35	\$18.42	\$0.00	\$93.83
For apprentice rates see "Apprentice- LABORER"						
TUNNEL WORK - COMPRESSED AIR (HAZ. WASTE) <i>LABORERS (COMPRESSED AIR)</i>	12/01/2022	\$56.81	\$9.35	\$18.42	\$0.00	\$84.58
	06/01/2023	\$57.81	\$9.35	\$18.42	\$0.00	\$85.58
	12/01/2023	\$59.06	\$9.35	\$18.42	\$0.00	\$86.83
	06/01/2024	\$60.54	\$9.35	\$18.42	\$0.00	\$88.31
	12/01/2024	\$62.01	\$9.35	\$18.42	\$0.00	\$89.78
	06/01/2025	\$63.51	\$9.35	\$18.42	\$0.00	\$91.28
	12/01/2025	\$65.01	\$9.35	\$18.42	\$0.00	\$92.78
	06/01/2026	\$66.56	\$9.35	\$18.42	\$0.00	\$94.33
	12/01/2026	\$68.06	\$9.35	\$18.42	\$0.00	\$95.83
For apprentice rates see "Apprentice- LABORER"						
TUNNEL WORK - FREE AIR <i>LABORERS (FREE AIR TUNNEL)</i>	12/01/2022	\$46.88	\$9.35	\$18.42	\$0.00	\$74.65
	06/01/2023	\$47.88	\$9.35	\$18.42	\$0.00	\$75.65
	12/01/2023	\$49.13	\$9.35	\$18.42	\$0.00	\$76.90
	06/01/2024	\$50.61	\$9.35	\$18.42	\$0.00	\$78.38
	12/01/2024	\$52.08	\$9.35	\$18.42	\$0.00	\$79.85
	06/01/2025	\$53.58	\$9.35	\$18.42	\$0.00	\$81.35
	12/01/2025	\$55.08	\$9.35	\$18.42	\$0.00	\$82.85
	06/01/2026	\$56.63	\$9.35	\$18.42	\$0.00	\$84.40
	12/01/2026	\$58.13	\$9.35	\$18.42	\$0.00	\$85.90
For apprentice rates see "Apprentice- LABORER"						

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
TUNNEL WORK - FREE AIR (HAZ. WASTE) <i>LABORERS (FREE AIR TUNNEL)</i>	12/01/2022	\$48.88	\$9.35	\$18.42	\$0.00	\$76.65
	06/01/2023	\$49.88	\$9.35	\$18.42	\$0.00	\$77.65
	12/01/2023	\$51.13	\$9.35	\$18.42	\$0.00	\$78.90
	06/01/2024	\$52.61	\$9.35	\$18.42	\$0.00	\$80.38
	12/01/2024	\$54.08	\$9.35	\$18.42	\$0.00	\$81.85
	06/01/2025	\$55.58	\$9.35	\$18.42	\$0.00	\$83.35
	12/01/2025	\$57.08	\$9.35	\$18.42	\$0.00	\$84.85
	06/01/2026	\$58.63	\$9.35	\$18.42	\$0.00	\$86.40
	12/01/2026	\$60.13	\$9.35	\$18.42	\$0.00	\$87.90
For apprentice rates see "Apprentice- LABORER"						
VAC-HAUL <i>TEAMSTERS JOINT COUNCIL NO. 10 ZONE B</i>	12/01/2021	\$36.24	\$13.41	\$16.01	\$0.00	\$65.66
WAGON DRILL OPERATOR <i>LABORERS - ZONE 3 (BUILDING & SITE)</i>	12/01/2022	\$33.88	\$9.10	\$16.19	\$0.00	\$59.17
	06/01/2023	\$34.50	\$9.10	\$16.19	\$0.00	\$59.79
	12/01/2023	\$35.13	\$9.10	\$16.19	\$0.00	\$60.42
For apprentice rates see "Apprentice- LABORER"						
WAGON DRILL OPERATOR (HEAVY & HIGHWAY) <i>LABORERS - ZONE 3 (HEAVY & HIGHWAY)</i>	12/01/2022	\$33.25	\$9.35	\$14.41	\$0.00	\$57.01
	06/01/2023	\$33.87	\$9.35	\$14.41	\$0.00	\$57.63
	12/01/2023	\$34.50	\$9.35	\$14.41	\$0.00	\$58.26
	06/01/2024	\$35.70	\$9.35	\$14.41	\$0.00	\$59.46
	12/01/2024	\$36.90	\$9.35	\$14.41	\$0.00	\$60.66
	06/01/2025	\$38.15	\$9.35	\$14.41	\$0.00	\$61.91
	12/01/2025	\$39.39	\$9.35	\$14.41	\$0.00	\$63.15
	06/01/2026	\$40.69	\$9.35	\$14.41	\$0.00	\$64.45
12/01/2026	\$41.98	\$9.35	\$14.41	\$0.00	\$65.74	
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)"						
WATER METER INSTALLER <i>PLUMBERS & PIPEFITTERS LOCAL 104</i>	09/17/2022	\$45.71	\$9.55	\$17.10	\$0.00	\$72.36
	03/17/2023	\$46.96	\$9.55	\$17.10	\$0.00	\$73.61
	09/17/2023	\$47.96	\$9.55	\$17.10	\$0.00	\$74.61
	03/17/2024	\$49.21	\$9.55	\$17.10	\$0.00	\$75.86
For apprentice rates see "Apprentice- PLUMBER/PIPEFITTER" or "PLUMBER/GASFITTER"						

Additional Apprentice Information:

Minimum wage rates for apprentices employed on public works projects are listed above as a percentage of the pre-determined hourly wage rate established by the Commissioner under the provisions of the M.G.L. c. 149, ss. 26-27D. Apprentice ratios are established by the Division of Apprenticeship Training pursuant to M.G.L. c. 23, ss. 11E-11L.

All apprentices must be registered with the Division of Apprenticeship Training in accordance with M.G.L. c. 23, ss. 11E-11L.

All steps are six months (1000 hours.)

Ratios are expressed in allowable number of apprentices to journeymen or fraction thereof, unless otherwise specified.

** Multiple ratios are listed in the comment field.


*** APP to JM; 1:1, 2:2, 2:3, 3:4, 4:4, 4:5, 4:6, 5:7, 6:7, 6:8, 6:9, 7:10, 8:10, 8:11, 8:12, 9:13, 10:13, 10:14, etc.

**** APP to JM; 1:1, 1:2, 2:3, 2:4, 3:5, 4:6, 4:7, 5:8, 6:9, 6:10, 7:11, 8:12, 8:13, 9:14, 10:15, 10:16, etc.

**ATTACHMENT B:
Forms Used During Bidding**

- 1) Form for General Bid
- 2) Bidder Check list
- 3) Prevailing Wage Schedule/OSHA 10 Hours Acknowledgement (Attachment A)

**Executive Office for Health and Human Services
Department of Mental Health
Office of Engineering and Facilities Management
Hadley Building
167 Lyman Street
Westborough, MA 01581
Fred Bergstrom, DMH Project Engineer
Office Tel: (508) 616-2245**



**COMMONWEALTH OF MASSACHUSETTS
FORM FOR GENERAL BID**

**2023- 068B Flooring Abatement & Replacement
Haskell Building
1 Prince Street
Northampton, Massachusetts 01060**

The following **must** be uploaded into **COMMBUYS** as part of this bid:

1. A photo copy of the Bid deposit meeting the requirements of Section 5.13 and 5.14 of the Instructions to Bidders uploaded into COMMBUYS.
2. **(Not Applicable)** Complete Statement of Prior Relevant Experience, Facilities, Equipment, References and any other information called for as further set forth in Project Specifications.
3. Prevailing Wage Schedule/OSHA 10 Hours Acknowledgement (See Attachment A)

FORM FOR GENERAL BID

To the Awarding Authority: **DEPARTMENT OF MENTAL HEALTH (DMH)**

A. The undersigned proposes to furnish all labor and materials required for

Project Name: **2023- 068B Flooring Abatement & Replacement
Haskell Building
1 Prince Street
Northampton, Massachusetts 01060**

in accordance with the accompanying plans and specifications prepared by Fred Bergstrom, DMH Project Engineer, for the contract price specified below, subject to additions and deductions according to the terms of the specifications.

B. This bid includes addenda numbered: (please indicate by checking the box of each addenda number)

No. 1 No. 2 No. 3 No. 4 No. 5 No. 6

C. The proposed contract price is:

_____ (total bid in words)

dollars (\$ _____).

For Alternate No. 1: Add \$ _____ Subtract \$ _____

For Alternate No. 2: Add \$ _____ Subtract \$ _____

Name of General Bidder: _____

D. The undersigned agrees that, if it is selected as general contractor, it will within five days, Saturdays, Sundays and legal holidays excluded, after presentation thereof by the awarding authority, execute a contract in accordance with the terms of this bid and furnish a 50% payment bond from a surety company qualified to do business under the laws of the Commonwealth and satisfactory to the awarding authority and each in the sum of the contract price, the premiums for which are to be paid by the general contractor and are included in the contract price.

Bid Amount	Payment Bond Required	Performance Bond Required
Bid up to \$150,000	50% Payment Bond	No Performance Bond Required
Bid over \$150,000	100% Payment Bond	100% Performance Bond

The undersigned hereby certifies that it is able to furnish labor that can work in harmony with all other elements of labor employed or to be employed on the work; that all employees to be employed at the worksite will have successfully completed a course in construction safety and health approved by the United States Occupational Safety and Health Administration that is at least 10 hours in duration at the time the employee begins work and who shall furnish documentation of successful completion of said course with the first certified payroll report for each employee; and that it will comply fully with all laws and regulations applicable to awards made subject to section 39M of Chapter 30 of the General Laws.

The undersigned further certifies under the penalties of perjury that this bid is in all respects bona fide, fair and made without collusion or fraud with any other person. As used in this subsection the word "person" shall mean any natural person, joint venture, partnership, corporation or other business or legal entity.

The undersigned further certifies under penalty of perjury that the said undersigned is not presently debarred from doing public construction work in the Commonwealth under the provisions of section twenty-nine F of chapter twenty-nine, or any other applicable debarment provisions of any other chapter of the General Laws or any rule or regulation promulgated thereunder.

The undersigned further certifies under penalties of perjury that the undersigned is not debarred from doing public construction work under any law, rule or regulation of the federal government.

The undersigned hereby declares that the undersigned has carefully examined the Advertisement, Instructions to Bidders, Owner - Contractor Agreement, General Conditions of the Contract, Special Conditions (if any), Plans and Specifications, all other Contract Documents, and also the Site upon which the proposed work is to be performed. The undersigned further declares that in regard to the conditions affecting the work to be done and the labor and materials needed, this proposal is based solely on the undersigned's own investigation and research and not in reliance upon any representation of any employee, officer or agent of the Commonwealth.

The undersigned further certifies under the penalties of perjury that:

- 1) this bid is in all respects bona fide, fair and made without collusion or fraud with any other person;
- 2) we are the only persons interested in this proposal;
- 3) that it is made without any connection with any other person making any bid for the same work and without directly or indirectly influencing or attempting to influence any other person to bid to refrain from bidding or to influence the amount of the bid of any other person or corporation;
- 4) that no person acting for, or employed by, the Commonwealth of Massachusetts is directly or indirectly interested in this proposal, or in any contract which be made under it, or in expected profits to arise therefrom.

As used above the word "person" shall mean natural person, joint venture, partnership, corporation or other business or legal entity.

The undersigned certifies that it shall comply with the provisions of the Equal Employment Opportunity, Non-Discrimination, and Affirmative Action Program set forth in the General Conditions of the Contract.

Should the Contract Documents require submission of special data to accompany the bid, the Awarding Authority reserves the right to rule the bidder's failure to submit such data an informality and to receive said data subsequently within a reasonable time as set by the Awarding Authority.

Date _____, 2023.

(Name of General Bidder)

By _____
(Typed/Printed Name of Person & Title)

By _____
(Signed Name of Person)

(Business Address, City, State)

(Telephone Number)

(E-mail address)

The following information is furnished by the Bidder for the information of the Department of Mental Health.

Bidders Vendor Code / FEIN # _____

Is Bidder a corporation? ____ If so, incorporated in what state? _____

President _____

Secretary or Clerk _____

Treasurer _____

If Bidder is a foreign corporation, is it registered to do business in Massachusetts? _____

If Bidder is a foreign corporation and is selected, Bidder is required under M.G.L. c. 30, s. 39L to obtain from the Massachusetts Secretary of State, One Ashburton Place, 17th floor, a certificate stating that the corporation is registered to do business in Massachusetts, and to furnish said certificate to the awarding authority prior to the award.

Is Bidder a general partnership or joint venture? ____ If so, name each partner or venturer _____

Is Bidder a limited partnership? _____

Is Bidder registered in Massachusetts? ____ If so, name each general partner _____

If Bidder is a foreign limited partnership and is selected, Bidder is required under M.G.L. c. 30, s. 39L to obtain from the Massachusetts Secretary of State, One Ashburton Place, 17th floor, a certificate stating that the partnership is registered to do business in Massachusetts, and to furnish said certificate to the awarding authority prior to the award.

For each general partner or venturer that is a corporation, provide the following information (use additional sheets if necessary):

Name of corporation _____

State of incorporation _____

President _____

Secretary or Clerk _____

Treasurer _____

Name of corporation _____

State of incorporation _____

President _____

Secretary or Clerk _____

Treasurer _____

Is Bidder an individual? _____

Residence Address _____

Name under which Bidder does business _____

Business Address _____

If selected Bidder is an individual doing business under a different name then Bidder must furnish evidence of any required DBA filing.

BIDDER CHECKLIST

This is not a contract document. It is provided to help bidders avoid common mistakes that can result in the rejection of bids. It does not modify the Contract Documents.


*****Please note that all BID documents must be uploaded into COMMBUYS*****

To ensure that your bids are acceptable to the Department, and are not rejected due to errors or omissions, we are providing this Checklist for your convenience. It does not modify the Contract Documents.

- 1. Have you used the correct bid form provided in Attachment B ~~(and Attachment C if applicable)~~ to the Instructions to Bidders?
- 2. Have you properly identified the project, architect, etc., on your bid form?
- 3. Have you acknowledged receipt of the most current prevailing Wage Rates and/or Truck Rates which have been provided by the Awarding Authority? (Done by completing the bottom of Attachment A in this Part 1 packet.)
- 4. Are your bid amounts, as expressed in figures and words, consistent?
The amount expressed in words will control.
- 5. Have you acknowledged all addenda issued by placing the number of each addenda on the Bid Form and followed the instructions contained in each one?
- 6. If you are a General Bidder, have you responded to every alternate? ~~If you are a sub-bidder, have you responded to all of those alternates identified as applying to the filed sub-bid section you are bidding on?~~
- 7. If you are a general bidder ~~or a sub-bidder~~ affected by an alternate and an alternate price is requested and you estimate that there is no change in price, did you indicate by writing “no change”, “N/C”, or “0” ? Failure to provide a price, no change, N/C or 0 for an alternate by general bidders and sub-bidders when identified as part of a sub-bidders scope of work will result in rejection of your bid.
- 8. ~~If you are a sub-bidder and the alternate does not affect your category of work, have you left the alternate blank or written “N/A” and only “N/A”?~~
- 9. ~~If you are a sub-bidder and the bid documents request that you supply the name of the firm(s) that will do certain work identified as sub-subcontract paragraph E work, have you completed the Paragraph E section.~~
- 10. Have you added any information not called for, acknowledged an addendum that does not exist, or provided a price for an alternate not identified as part of your scope of work which can result in rejection of your bid?
- 11. Is your Bid Form **SIGNED** and dated?
- 12. **BID DEPOSITS**
 - a. **Have you uploaded your Bid Deposit onto COMMBUYS and FEDEXed your original bid bond to arrive prior to the bid opening date?**
 - b. Is your bid deposit, if in the form of a bid bond, issued from a bonding company licensed to do business in the Commonwealth of Massachusetts? **Is it signed by the contractor and the bonding company?**
 - c. Is your bid deposit made payable to the Commonwealth of Massachusetts? **Bid deposits made payable to any other entity may cause the bid to be rejected.**
 - d. Is your bid deposit five (5%) of the highest possible bid amount, considering all alternates being accepted in order?
- 13. If you are a General Contractor, have you included your current DCAMM Certificate of Eligibility and a completed, signed DCAMM Update Statement.
- 14. If you are a Sub-Contractor, have you included your current Certificate of Eligibility and a completed, signed DCAMM Update Statement?
- 15. Are all of your bid materials **uploaded into COMMBUYS** exactly as provided in the Instructions to Bidders?
- 16. Your bid **MUST** be **uploaded into COMMBUYS** prior to the deadline!

DOCUMENTS TO UPLOAD TO COMMBUYS CHECKLIST

- 1. **GENERAL BID FORM (PART 1 Attachment B)**
- 2. ~~SUB BID FORM (PART 1 Attachment C – NOT APPLICABLE)~~
- 3. **WAGE RATES ACKNOWLEDGEMENT (PART 1 ATTACHMENT A)**
(Complete the bottom of Attachment A in this Part 1 packet.)
- 4. **5% BID BOND**
- 5. ~~GENERAL CONTRACTOR – DCAMM UPDATE STATEMENT~~
- 6. ~~GENERAL CONTRACTOR – DCAMM CERTIFICATE OF ELIGIBILITY~~
- 7. ~~SUB CONTRACTOR – DCAMM UPDATE STATEMENT (NOT APPLICABLE)~~
- 8. ~~SUB CONTRACTOR – DCAMM CERTIFICATE OF ELIGIBILITY (NOT APPLICABLE)~~
- 9. ~~GENERAL CONTRACTOR – CHPT. 30 MassDOT PREQUALIFICATION STATEMENT (NOT APPLICABLE)~~



BID PACKAGE

PART II

Forms for Contract Execution

- Executive Order 481
- Executive Order 504 (2 pages)
- Owner- Contractor Agreement
- 50% Payment Bond
- Prompt Payment Discount
- Certificate of Compliance with State Tax Laws and With Unemployment Compensation Contribution Requirements
- Certificate of Compliance with Employment Eligibility Verification Requirements (I-9)
- Request for Taxpayer Identification Number and Certification (W-9) (2 pages)
- Commonwealth of Massachusetts Contractor Authorized Signatory Listing (2 pages)
- Electronic Funds Transfer Sign Up Form
- Insurance Document Required - Proof of Insurance amounts per Part 3 General Conditions of the Contract

**Forms are for Reference Only
To be used for contract award and execution**

COMMONWEALTH OF MASSACHUSETTS
EXECUTIVE ORDER 481 - CONTRACTOR CERTIFICATION
PROHIBITING THE USE OF UNDOCUMENTED WORKERS ON STATE CONTRACTS



CONTRACTOR LEGAL NAME:
CONTRACTOR VENDOR/CUSTOMER CODE:

INSTRUCTIONS:

Executive Order 481 applies to all state agencies in the Executive Branch, including all executive offices, boards, commissions, agencies, departments, divisions, councils, bureaus, and offices, now existing and hereafter established. As it is the policy of the Executive Branch to prohibit the use of undocumented workers in connection with the performance of state contracts, all contracts entered into after February 23, 2007 require that contractors, as a condition of receiving Commonwealth funds under any Executive Branch contract, make the following certification:

CONTRACTOR CERTIFICATION:

As evidenced by the signature of the Contractor's Authorized Signatory below, the Contractor certifies under the pains and penalties of perjury that the Contractor shall not knowingly use undocumented workers in connection with the performance of all Executive Branch contracts; that pursuant to federal requirements, the Contractor shall verify the immigration status of all workers assigned to such contracts without engaging in unlawful discrimination; and that the Contractor shall not knowingly or recklessly alter, falsify, or accept altered or falsified documents from any such worker(s). The Contractor understands and agrees that breach of any of these terms during the period of each contract may be regarded as a material breach, subjecting the Contractor to sanctions, including but not limited to monetary penalties, withholding of payments, contract suspension or termination.

Contractor Authorizing Signature

Date: _____

Print Name

Title: _____

Telephone: _____

Fax: _____

Email: _____

The Contractor is required to sign this Certification only once and may provide a copy of the signed Certification for any contract executed with an Executive Branch Department. A copy of this signed Certification must be attached to the "record copy" of all contracts with this Contractor that are filed with the contracting Department.

Executive Order 504 Contractor Certification Form

BIDDER/CONTRACTOR LEGAL NAME:

BIDDER/CONTRACTOR VENDOR/CUSTOMER CODE:

Executive Order 504: For all Contracts involving the Contractor's access to personal information, as defined in M.G.L. c. 93H, and personal data, as defined in M.G.L. c. 66A, owned or controlled by Executive Department agencies, or access to agency systems containing such information or data (herein collectively "personal information"), Contractor certifies under the pains and penalties of perjury that the Contractor (1) has read Commonwealth of Massachusetts Executive Order 504 and agrees to protect any and all personal information; and (2) has reviewed all of the Commonwealth of Massachusetts Information Technology Division's Security Policies available at www.mass.gov/ITD under Policies and Standards.

Notwithstanding any contractual provision to the contrary, in connection with the Contractor's performance under this Contract, for all state agencies in the Executive Department, including all executive offices, boards, commissions, agencies, departments, divisions, councils, bureaus, and offices, now existing and hereafter established, the Contractor shall:

(1) obtain a copy, review, and comply with the contracting agency's Information Security Program (ISP) and any pertinent security guidelines, standards and policies; (2) comply with all of the Commonwealth of Massachusetts Information Technology Division's Security Policies ("Security Policies") available at www.mass.gov/ITD under Policies and Standards;

(2) communicate and enforce the contracting agency's ISP and such Security Policies against all employees (whether such employees are direct or contracted) and subcontractors;

(3) implement and maintain any other reasonable appropriate security procedures and practices necessary to protect personal information to which the Contractor is given access by the contracting agency from the unauthorized access, destruction, use, modification, disclosure or loss;

(4) be responsible for the full or partial breach of any of these terms by its employees (whether such employees are direct or contracted) or subcontractors during or after the term of this Contract, and any breach of these terms may be regarded as a material breach of this Contract;

(5) in the event of any unauthorized access, destruction, use, modification, disclosure or loss of the personal information (collectively referred to as the "unauthorized use"): (a) immediately notify the contracting agency if the Contractor becomes aware of the unauthorized use; (b) provide full cooperation and access to information necessary for the contracting agency to determine the scope of the unauthorized use; and (c)

provide full cooperation and access to information necessary for the contracting agency and the Contractor to fulfill any notification requirements.

Breach of these terms may be regarded as a material breach of this Contract, such that the Commonwealth may exercise any and all contractual rights and remedies, including without limitation indemnification under Section 11 of the Commonwealth's Terms and Conditions, withholding of payments, contract suspension, or termination. In addition, the Contractor may be subject to applicable statutory or regulatory penalties, including and without limitation, those imposed pursuant to M.G.L. c. 93H and under M.G.L. c. 214, § 3B for violations under M.G.L. c. 66A.

Bidder/Contractor Name: _____

Bidder/Contractor Authorized Signature: _____

Print Name and Title of Authorized Signatory: _____

Date: _____

This Certification may be signed once and photocopied to be attached to any Commonwealth Contract that does not already contain this Certification Language and shall be interpreted to be incorporated by reference into any applicable contract subject to Executive Order 504 for this Contractor.

Contractor's Vendor Code Number: _____



**COMMONWEALTH OF MASSACHUSETTS
STANDARD CONTRACT
For Projects Not Exceeding \$150,000**

OWNER - CONTRACTOR AGREEMENT

Awarding Authority: **DEPARTMENT OF MENTAL HEALTH**

Department Code **DMH**

This agreement ("Contract") is made as of the ___ day of _____ by and between the **Department of Mental Health** acting by and through the Awarding Authority identified above with a principal place of business at **167 Lyman St., Westborough, MA 01581**, and _____, a **Contractor** with a principal place of business at _____ hereinafter called the "Contractor".

Terms used in this Owner - Contractor Agreement which are defined in the General Conditions of the Contract shall have the meanings designated therein.

The Awarding Authority and the Contractor agree as follows:

Article 1. Scope of Work. The Work under this Contract is defined as all work required by the Contract Documents for the **2023-068B Flooring Abatement & Replacement at the Haskell Building, One Prince Street, Northampton, MA 01060.**

Article 2. Time for Completion. The Contractor shall commence the Work under this Contract on the date specified in the written "Notice to Proceed," and shall bring work to substantial completion within **forty-five (45) calendar days.**

Article 3. Contract Price. The Awarding Authority shall pay the Contractor, in current funds, for the performance of the Work, subject to additions and deductions by Approved Change Order(s), the Contract Price of *** Dollars***(\$.xx). The Unit Prices, if any, approved by the Awarding Authority are those included in the Contractor's General Bid. The following Alternates have been accepted and their costs are included in the Contract Price:

Alternate No(s): **1 and 2**

Article 4. Approved Subcontractors. No Subcontractors shall be used for these or any other portions of the Work without the prior written approval of the Awarding Authority.

Article 5. Certifications. Pursuant to M.G.L. c. 62(c), §49 (a), the individual signing this Contract on behalf of the Contractor hereby certifies, under the penalties of perjury, that to the best of his or her knowledge and belief the Contractor has complied with any and all applicable state and federal tax laws. The individual signing this Contract on behalf of the Contractor further certifies under penalties of perjury that the Contractor is not presently debarred from doing public construction work in the Commonwealth under the provisions of M.G.L. c. 29, § 29F, or any other applicable debarment provisions of any other chapter of the General Laws or any rule or regulation promulgated thereunder and is not presently debarred from doing public construction work by any agency of the United States Government.

Article 6. The Contract Documents: The following documents form the Contract, are incorporated by reference herein, and are referred to as the "Contract Documents:"

- The Advertisement
- The Instructions to Bidders, Including Schedule of Prevailing Wages
- The General Bid submitted by the Contractor
- This Owner – Contractor Agreement
- The General Conditions of the Contract
- The Supplementary General Conditions [Note: the term “Supplementary General Conditions” may also refer to Division 1 of the Specifications.]
- The Plans and Specifications, including Addenda identified in Article 1 above
- All Approved Change Orders issued after execution of this Owner - Contractor Agreement
- Any other document that the State Agency deems necessary

Article 7. Liquidated Damages. For the purposes of Article 6 of the General Conditions of the Contract, liquidated damages for delay shall be as follows:

\$500.00/day

Article 8. Contractor’s and Awarding Authority’s Representatives. The Contractor’s Representative for this Contract is _____ . The

person administering this Contract on behalf of the Awarding Authority (the "Administrator") is Fred Bergstrom, Project Engineer

Article 9. Notices. Notices to the Contractor shall be deemed given when hand delivered to the Contractor's Representative in person, or when deposited in the U.S. mail addressed to the Contractor at the Contractor's address specified in the Owner - Contractor Agreement, or when delivered by courier to either location. Unless otherwise specified in writing by the Awarding Authority, notices and deliveries to the Awarding Authority shall be effective only when delivered to the Awarding Authority at the address specified in the Owner - Contractor Agreement and date-stamped at the reception desk or for which a receipt has been signed by the agent or employee designated by the Awarding Authority to receive official notices.

Article 10. Minority/Women Workforce Utilization Percentages: The applicable goals, for minority and women workforce utilization established for this Contract are as follows:

The applicable minority workforce utilization percentage, if any, is N/A .
The applicable women workforce utilization percentage, if any, is N/A .

Article 11. Additional Insurance Provisions.

N/A

The insurance requirements set forth in Article 7 of the General Conditions of the Contract are supplemented by the provisions, if any, appearing in Exhibit A attached hereto and incorporated herein.

In witness whereof, the parties hereto have caused this instrument to be executed in triplicate under seal as of the date set forth above.

CONTRACTOR:

By: _____ Date _____

Name: _____

Title: _____

AWARDING AUTHORITY: DEPARTMENT OF MENTAL HEALTH (DMH)

By executing this Agreement, the undersigned authorized signatory of the Awarding Authority, who incurs no personal liability by reason of the execution hereof or anything herein contained, hereby certifies under penalties of perjury that all the applicable provisions of M.G.L. c. 30, §39M and M.G.L. c149 , have been complied with.

Name (printed): Paul Truax _____ Date _____

Name (signed): _____

Title: Director, Office of Engineering & Facilities Management_____

PAYMENT BOND

Know all men by these presents, that

_____ as principal, and _____ as surety, are held and firmly bound unto the Commonwealth of Massachusetts in the sum of

_____ in lawful money of the United States of America, to be paid to the Commonwealth of Massachusetts, for which payments, well and truly to be made, we bind ourselves, our respective heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.

Whereas, the said principal has made a Contract with the Commonwealth acting through its _____ ("Awarding Authority") bearing date of _____, 20____, for the construction of Project No. _____ Contract No. _____ Project Name _____

Now the condition of this obligation is such that if the principal shall pay for all labor performed or furnished and for all materials used or employed in said Contract and in any and all duly authorized modifications, alterations, extensions of time, changes or additions to said Contract that may hereafter be made, notice to the surety of such modifications, alterations, extensions of time, changes or additions being hereby waived, the foregoing to include any other purpose or items set out in, and to be subject to, provisions of Massachusetts General Laws Chapter 30, section 39A, and Chapter 149, section 29, as amended, then this obligation shall become null and void; otherwise it shall remain in full force and virtue.

In witness whereof we hereunto set our hand and seals this _____ day of _____, 20__.


(Print Name of General Contractor) (Seal)

(Print Name of Surety) (Seal)

By _____
(Signature - Title)

(Signature - Title)

Surety Address _____



COMMONWEALTH OF MASSACHUSETTS
Prompt Pay Discount Form
(Invoice discounts for receiving fast payments)

Revised 3/9/07

Bidder Name: _____
Vendor Code (VCUST): _____
Contract/RFR Number(s): _____

Prompt Payment Discounts (PPD). All contractors/vendors doing business with the Commonwealth must provide a Prompt Payment Discount (PPD) for receiving early payments unless the Contractor/vendor can provide compelling proof that providing a prompt pay discount would be unduly burdensome. Contractors benefit from PPD by increased, usable cash flow as a result of fast and efficient payments for commodities or services rendered. Contractors who agree to accept Electronic Funds Transfer (EFT) increase the prompt pay benefit by ensuring that funds are paid directly to their designated bank accounts, thus eliminating the delay of check clearance policies and traditional mail lead time. Payments processed through the state accounting system (MMARS) can be tracked and verified through the Comptroller's [Vendor Web](#) system using the Vendor/Customer Code assigned to you by a Commonwealth department.

The Commonwealth benefits because contractors reduce the cost of products and services through the applied discount. While Bidders/Contractors have flexibility in determining the actual % discount(s) offered to the Commonwealth, the discount(s) must be identified for 10, 15, 20 and/or 30 days for payment issuance in the column entitled "% Discount Off Proposed Price" below. The Commonwealth may use the prompt pay discounts submitted as a basis for selection and may negotiate discounts as deemed in the best interest of the Commonwealth. The requirement to offer PPD discounts may be waived by the Commonwealth on a case-by-case basis if participation in the program would be unduly burdensome, provided the specific reason for the hardship is outlined below.

All discounts offered will be taken in cases where the payment issue date is within the specified number of days listed below and in accordance with the Commonwealth's Bill Paying Policy. Payment days will be measured **from** the date goods are received and accepted / performance was completed OR the date an invoice is received by the Commonwealth, **whichever is later to** the date the payment is issued as an EFT (preferred method) or mailed by the State Treasurer. The date of payment "issue" is the date a payment is considered "paid" not the date a payment is "received" by a Contractor.

If internal Bidder/Contractor systems require an alternate method of measuring payment issue dates, the Bidder/Contractor must note the issues below or on an attached page if necessary to be considered by the PMT. In cases where the Bidder/Contractor considers that offering a Prompt Payment Discount would be a hardship, the Bidder must clearly define the issues and reasons for said hardship. *Providing volume discounts or other discounts on prices is not considered a hardship, since the PPD provides the additional benefit of early cash flow for the Contractor.*

Enter the Prompt Payment Discount percentage (%) off the invoice payment, for each of the payment issue dates listed, if the payment is issued within the specified Payment Issue days. For example:

- 5% - 10 Days**
- 4% - 15 Days**
- 3% - 20 Days**
- 2% - 30 Days**

If no discount is offered enter 0%

Prompt Payment Discount %	Payment Issue Date w/in
%	10 Days
%	15 Days
%	20 Days
%	30 Days

The Contractor is unable to provide a prompt payment discount due to the following hardship:

Contractor/Bidder Authorized Signature _____ Date: _____

Contractor/ Bidder Authorized Signatory Print Name and Title: _____

**CERTIFICATE OF COMPLIANCE WITH STATE TAX LAWS AND
WITH UNEMPLOYMENT COMPENSATION CONTRIBUTION
REQUIREMENTS**

Pursuant to M.G.L., Ch. 62C, s. 49A and M.G.L., Ch. 151A, s. 19A, I,

_____ authorized signatory for

_____ whose principal place of business is at

_____ do hereby certify

under penalties of perjury that _____ has filed all
state tax returns and paid all taxes as required by law and has complied with all state laws
pertaining to contributions to the unemployment compensation fund and to payments in
lieu of contributions.

The Business Organization Social Security Number or Federal Identification Number is

_____.

Signed under the penalties of perjury the _____ day of _____

20 _____.

Signature: _____

Name and Title: _____

Request for Taxpayer Identification Number and Certification

Completed form should be given to the requesting department or the department you are currently doing business with.

Please print or type

Name (List legal name, if joint names, list first & circle the name of the person whose TIN you enter in Part I-See Specific Instruction on page 2)		
Business name , if different from above. (See Specific Instruction on page 2)		
Check the appropriate box: <input type="checkbox"/> Individual/Sole proprietor <input type="checkbox"/> Corporation <input type="checkbox"/> Partnership <input type="checkbox"/> Other ▶-----		
Legal Address: number, street, and apt. or suite no.	Remittance Address: if different from legal address number, street, and apt. or suite no.	
City, state and ZIP code	City, state and ZIP code	
Phone # ()	Fax # ()	Email address:

Part I Taxpayer Identification Number (TIN)

Enter your TIN in the appropriate box. For individuals, this is your social security number (SSN). However, for a resident alien, sole proprietor, or disregarded entity, see the Part I instruction on page 2. For other entities, it is your employer identification number (EIN). If you do not have a number, see **How to get a TIN** on page 2.

Social security number

□□□-□□-□□□□

OR

Employer identification number

□□-□□□□□□

DUNS

□□□□□□□□

Vendors:
Dunn and Bradstreet Universal Numbering System (DUNS)

Part II Certification

Under penalties of perjury, I certify that:

- The number shown on this form is my correct taxpayer identification number (or I am waiting for a number to be issued to me), **and**
- I am not subject to backup withholding because: **(a)** I am exempt from backup withholding, or **(b)** I have not been notified by the Internal Revenue Services (IRS) that I am subject to backup withholding as a result of a failure to report all interest or dividends, or **(c)** the IRS has notified me that I am no longer subject to backup withholding, **and**
- I am an U.S. person (including an U.S. resident alien).
- I am currently a Commonwealth of Massachusetts's state employee: (check one): No ___ Yes ___ If yes, **in compliance with** the State Ethics Commission **requirements**.

Certification instructions: You must cross out item 2 above if you have been notified by the IRS that you are currently subject to backup withholding because you have failed to report all interest and dividends on your tax return. For real estate transactions, item 2 does not apply.

Sign Here	Authorized Signature ▶	Date ▶
------------------	-------------------------------	---------------

Purpose of Form

A person who is required to file an information return with the IRS must get your correct taxpayer identification number (TIN) to report, for example, income paid to you, real estate transactions, mortgage interest you paid, acquisition or debt, or contributions you made to an IRA.

Use Form W-9 only if you are a U.S. person (including a resident alien), to give your correct TIN to the person requesting it (the requester) and, when applicable, to:

- Certify the TIN you are giving is correct (or you are waiting for a number to be issued).
- Certify you are not subject to backup withholding

If you are a foreign person, use the appropriate Form W-8. See Pub 515, Withholding of Tax on Nonresident Aliens and Foreign Corporations.

What is backup withholding? Persons making certain payments to you must withhold a designated percentage, currently 28% and pay to the IRS of such payments under certain

conditions. This is called "backup withholding." Payments that may be subject to backup withholding include interest, dividends, broker and barter exchange transactions, rents, royalties, nonemployee pay, and certain payments from fishing boat operators. Real estate transactions are not subject to backup withholding.

If you give the requester your correct TIN, make the proper certifications, and report all your taxable interest and dividends on your tax return, payments you receive will not be subject to backup withholding. **Payments you receive will be subject to backup withholding if:**

- You do not furnish your TIN to the requester, or
- You do not certify your TIN when required (see the Part II instructions on page 2 for details), or
- The IRS tells the requester that you furnished an incorrect TIN, or
- The IRS tells you that you are subject to backup withholding because you did not report all your interest and dividends only), or

5. You do not certify to the requester that you are not subject to backup withholding under 4 above (for reportable interest and dividend accounts opened after 1983 only).

Certain payees and payments are exempt from backup withholding. See the Part II instructions on page 2.

Penalties

Failure to furnish TIN. If you fail to furnish your correct TIN to a requester, you are subject to a penalty of \$50 for each such failure unless your failure is due to reasonable cause and not to willful neglect.

Civil penalty for false information with respect to withholding. If you make a false statement with no reasonable basis that results in no backup withholding, you are subject to a \$500 penalty.

Criminal penalty for falsifying information. Willfully falsifying certifications or affirmations may subject you to criminal penalties including fines and/or imprisonment.

Misuse of TINs. If the requester discloses or uses TINs in violation of Federal law, the requester may be subject to civil and criminal penalties.

Specific Instructions

Name. If you are an individual, you must generally enter the name shown on your social security card. However, if you have changed your last name, for instance, due to marriage without informing the Social Security Administration of the name change, enter your first name, the last name shown on your social security card, and your new last name.

If the account is in joint names, list first and then circle the name of the person or entity whose number you enter in Part I of the form.

Sole proprietor. Enter your **individual** name as shown on your social security card on the "Name" line. You may enter your business, trade, or "doing business as (DBA)" name on the "Business name" line.

Limited liability company (LLC). If you are a single-member LLC (including a foreign LLC with a domestic owner) that is disregarded as an entity separate from its owner under Treasury regulations section 301.7701-3, **enter the owner's name on the "Name" line.** Enter the LLC's name on the "Business name" line.

Caution: *A disregarded domestic entity that has a foreign owner must use the appropriate Form W-8.*

Other entities. Enter your business name as shown on required Federal tax documents on the "Name" line. This name should match the name shown on the charter or other legal document creating the entity. You may enter any business, trade, or DBA name on the "Business name" line.

Part I - Taxpayer Identification Number (TIN)

Enter your TIN in the appropriate box.

If you are a **resident alien** and you do not have and are not eligible to get an SSN, your TIN is your IRS individual taxpayer identification number (ITIN). Enter it in the social security number box. If you do not have an ITIN, see **How to get a TIN** below.

If you are a **sole proprietor** and you have an EIN, you may enter either your SSN or EIN. However, the IRS prefers that you use your SSN.

If you are an **LLC** that is **disregarded as an entity** separate from its owner (see **Limited liability company (LLC)** above), and are owned by an individual, enter your SSN (or "pre-LLC" EIN, if desired). If the owner of a disregarded LLC is a corporation, partnership, etc., enter the owner's EIN.

Note: See the chart on this page for further clarification of name and TIN combinations.

How to get a TIN. If you do not have a TIN, apply for one immediately. To apply for an SSN, get **Form SS-5**, Application for a Social Security Card, from your local Social Security Administration office. Get **Form W-7**, Application for IRS Individual Taxpayer Identification Number, to apply for an ITIN or **Form SS-4**, Application for Employer Identification Number, to apply for an EIN. You can get Forms W-7 and SS-4 from the IRS by calling 1-800-TAX-FORM (1-800-829-3676) or from the IRS's Internet Web Site www.irs.gov.

If you do not have a TIN, write "Applied For" in the space for the TIN, sign and date the form, and give it to the requester. For interest and dividend payments, and certain payments made with respect to readily tradable instruments, generally you will have 60 days to get a TIN and give it to the requester before you are subject to backup withholding on payments.

The 60-day rule does not apply to other types of payments. You will be subject to backup withholding on all such payments until you provide your TIN to the requester.

Note: Writing "Applied For" means that you have already applied for a TIN or that you intend to apply for one soon.

Part II - Certification

To establish to the paying agent that your TIN is correct or you are a U.S. person, or resident alien, sign Form W-9.

For a joint account, only the person whose TIN is shown in Part I should sign (when required).

Real estate transactions. You must sign the certification. You may cross out item 2 of the certification.

Dunn and Bradstreet Universal Numbering System (DUNS) number requirement –

The United States Office of Management and Budget (OMB) requires all vendors that receive federal grant funds have their DUNS number recorded with and subsequently reported to the granting agency. If a contractor has multiple DUNS numbers the contractor should provide the primary number listed with the Federal government's Central Contractor Registration (CCR) at www.ccr.gov. Any entity that does not have a DUNS number can apply for one on-line at www.DNB.com under the DNB D-U-N Number Tab.

Privacy Act Notice

Section 6109 of the Internal Revenue Code requires you to give your correct TIN to persons who must file information returns with the IRS to report interest, dividends, and certain other income paid to you, mortgage interest you paid, the acquisition or abandonment of secured property, cancellation of debt, or contributions you made to an IRA or MSA. The IRS uses the numbers for identification purposes and to help verify the accuracy of your tax return. The IRS may also provide this information to the Department of Justice for civil and criminal litigation, and to cities, states, and the District of Columbia to carry out their tax laws.

You must provide your TIN whether or not you are required to file a tax return. Payers must generally withhold a designated percentage, currently 28% of taxable interest, dividend, and certain other payments to a payee who does not give a TIN to a payer. Certain penalties may also apply.

What Name and Number to Give the Requester

For this type of account:	Give name and SSN of:
1. Individual	The individual
2. Two or more individuals (joint account)	The actual owner of the account or, if combined funds, the first individual on the account ¹ The minor ²
3. Custodian account of a minor (Uniform Gift to Minors Act)	The grantor-trustee ¹
4. a. The usual revocable savings trust (grantor is also trustee) b. So-called trust account that is not a legal or valid trust under state law	The actual owner ¹
5. Sole proprietorship	The owner ³
For this type of account:	Give name and EIN of:
6. Sole proprietorship	The owner ³
7. A valid trust, estate, or pension trust	Legal entity ⁴
8. Corporate	The corporation The organization
9. Association, club, religious, charitable, educational, or other tax-exempt organization	
10. Partnership	The partnership The broker or nominee
11. A broker or registered nominee	
12. Account with the Department of Agriculture in the name of a public entity (such as a state or local government, school district, or prison) that receives agricultural program payments	The public entity

¹ List first and circle the name of the person whose number you furnish. If only one person on a joint account has an SSN, that person's number must be furnished.

² Circle the minor's name and furnish the minor's SSN.

³ You must show your individual name, but you may also enter your business or "DBA" name. You may use either your SSN or EIN (if you have one).

⁴ List first and circle the name of the legal trust, estate, or pension trust. (Do not furnish the TIN of the personal representative or trustee unless the legal entity itself is not designated in the account title.)

Note: If no name is circled when more than one name is listed, the number will be considered to be that of the first name listed.

If you have questions on completing this form, please contact the Office of the State Comptroller. (617) 973-2468.

Upon completion of this form, please send it to the Commonwealth of Massachusetts Department you are doing business with.

**COMMONWEALTH OF MASSACHUSETTS
CONTRACTOR AUTHORIZED SIGNATORY LISTING**

Page 1 of 2

Issued May
2004



CONTRACTOR LEGAL NAME :
CONTRACTOR VENDOR/CUSTOMER CODE:

INSTRUCTIONS: **The second page of this form must be completed and notarized for each person listed in the table below.** Any Contractor (other than a sole-proprietor or an individual contractor) must provide a listing of individuals who are authorized as legal representatives of the Contractor who can sign contracts and other legally binding documents related to the contract on the Contractor's behalf. In addition to this listing, any state department may require additional proof of authority to sign contracts on behalf of the Contractor, or proof of authenticity of signature (a notarized signature that the Department can use to verify that the signature and date that appear on the Contract or other legal document was actually made by the Contractor's authorized signatory, and not by a representative, designee or other individual.)

NOTICE: *Acceptance of any payment under a Contract or Grant shall operate as a waiver of any defense by the Contractor challenging the existence of a valid Contract due to an alleged lack of actual authority to execute the document by the signatory.*

For privacy purposes **DO NOT ATTACH** any documentation containing personal information, such as bank account numbers, social security numbers, driver's licenses, home addresses, social security cards or any other personally identifiable information that you do not want released as part of a public record. The Commonwealth reserves the right to publish the names and titles of authorized signatories of contractors.

AUTHORIZED SIGNATORY NAME	TITLE

I certify that I am the President, Chief Executive Officer, Chief Fiscal Officer, Corporate Clerk or Legal Counsel for the Contractor and as an authorized officer of the Contractor I certify that the names of the individuals identified on this listing are current as of the date of execution below and that these individuals are authorized to sign contracts and other legally binding documents related to contracts with the Commonwealth of Massachusetts on behalf of the Contractor. I understand and agree that the Contractor has a duty to ensure that this listing is immediately updated and communicated to any state department with which the Contractor does business whenever the authorized signatories above retire, are otherwise terminated from the Contractor's employ, have their responsibilities changed resulting in their no longer being authorized to sign contracts with the Commonwealth or whenever new signatories are designated.

Signature

Date:

Title:

Telephone:

Fax:

Email:

[Listing can not be accepted without all of this information completed.]

A copy of this listing must be attached to the "record copy" of a contract filed with the department.

**COMMONWEALTH OF MASSACHUSETTS
CONTRACTOR AUTHORIZED SIGNATORY LISTING**

Page 2 of 2

Issued May
2004



CONTRACTOR LEGAL NAME :
CONTRACTOR VENDOR/CUSTOMER CODE:

PROOF OF AUTHENTICATION OF SIGNATURE

**This page is optional and is available for a department to authenticate contract signatures.
It is recommended that Departments obtain authentication of signature for the signatory
who submits the Contractor Authorized Listing.**

This Section MUST be completed by the Contractor Authorized Signatory in presence of notary.

Signatory's full legal name (print or type):

Title:

X _____

Signature as it will appear on contract or other document (**Complete only in presence of notary**):

AUTHENTICATED BY NOTARY OR CORPORATE CLERK (PICK ONLY ONE) AS FOLLOWS:

I, _____ (NOTARY) as a notary public certify that I witnessed the signature of the aforementioned signatory above and I verified the individual's identity on this date:

_____, 20 ____.

My commission expires on:

AFFIX NOTARY SEAL

I, _____ (CORPORATE CLERK) certify that I witnessed the signature of the aforementioned signatory above, that I verified the individual's identity and confirm the individual's authority as an authorized signatory for the Contractor on this date:

_____, 20 ____.

AFFIX CORPORATE SEAL



COMMONWEALTH OF MASSACHUSETTS
OFFICE OF THE COMPTROLLER

Electronic Funds Transfer (EFT) Authorization Agreement

Complete this form to enroll, modify, or terminate an existing in electronic funds transfer (EFT) agreement with the Commonwealth of Massachusetts Departments.

PART I: REASON FOR SUBMISSION – See Instructions on Page 2

New Enrollment	Change Enrollment	Cancel Enrollment	Document Included: Voided Check	Bank Letter
----------------	-------------------	-------------------	--	-------------

PART II: ACCOUNT HOLDER INFORMATION- See Instructions on Page 2

Account Holder Legal Name:		DBA Name:		
Street Address:	City:	State:	Zip Code:	
Account Holder Tax Identification Number (9 digits EIN or SSN)	EIN:	SSN:		

PART III: FINANCIAL INSTITUTION INFORMATION- See Instructions on Page 2

Financial Institution Name:		
Routing Number (only nine digits):	Account Number:	Account Type (Checking or Saving):

IF YOU ARE MODIFYING BANKING INFORMATION, YOU MUST INCLUDE YOUR OLD BANK INFORMATION OR YOUR REQUEST WILL BE RETURNED

Old Financial Institution Name:		
Old Routing Number (only 9 digits):	Old Account Number:	Old Account Type(Checking or Saving):

PART IV: VENDOR/CUSTOMER CONTACT INFORMATION: This is the person we will contact for any questions regarding this EFT – See Instructions on Page 2

Contact Person's Name:	Contact Person's Title:
Contact Person's Phone:	Contact Person's Email Address:

PART V: AUTHORIZATION- See Instructions on Page 2

By signing below, I hereby certify that the account(s) indicated on this form is under my direct control and access; therefore, I authorize the State Treasurer as fiscal agent for the Commonwealth of Massachusetts to initiate, change, or cancel credit entries to the account(s) as indicated on this form. For ACH debits consistent with the International ACH Transaction (IAT) rules check one:

- I affirm that payments authorized by this agreement are not to an account that is subject to being transferred to a foreign bank account.
- I affirm that payments authorized by this agreement are to an account that is subject to being transferred to a foreign bank account.

This authority is to remain in full force and effect until the Office of Comptroller (CTR) has received written notification from either me or an authorized officer of the organization of the account's termination in such time and in such a manner as to afford CTR a reasonable opportunity to act upon it.

Account Holder must sign and mail this EFT form and include a confirmation of account information on bank letterhead or a void check and mail to the Commonwealth Department you are doing business with.

Account Holder Authorized Signature:	Print Name:	Date:
	Title	

PART VI: VERIFICATION FROM THE COMMONWEALTH DEPARTMENT – See Instructions on Page 2

I hereby certify the Vendor/Customer is an authorized signatory and verified by internal records and verbal confirmation initiated by our department.

VCC/VCM Document ID:

Three letter Department Code:

Signature: _____

Title: _____

Date: _____

Print Name: _____

Phone # _____

INSTRUCTIONS FOR COMPLETING THE EFT AUTHORIZATION AGREEMENT

All EFT requests are subject to a 5 (five) day pre-certification period in which all accounts are verified by the qualifying financial institution before any direct deposits are made.

PART I: REASON FOR SUBMISSION

Indicate your reason for completing this form by checking the appropriate box: New EFT enrollment, a change to your EFT enrollment account information, or cancellation of your EFT enrollment.

PART II: ACCOUNT HOLDER INFORMATION

- Account Holder Name: Enter the accounts holder legal name (individual or business name), as reported to the Internal Revenue Service (IRS).
- DBA Name: Enter the DBA name if applicable.
- Street Address: Enter the account holder's street address.
- Enter the account holder's city, state, and zip code.
- Account Holder Tax Identification Number: Enter the tax identification number as reported to the IRS. If the business is a group, organization or corporation, provide the Federal employer identification number (EIN). If enrolling as an individual provide your Social Security Number.

PART III: FINANCIAL INSTITUTION INFORMATION

- Financial Institution Name: Enter your Financial Institution's name (this is the name of the bank or qualifying depository that will receive the funds).
 - **NOTE:** The account name to which EFT payments will be paid is to the name submitted on Part II of this form.
- Routing Number: Enter the bank or financial institutional nine-digit routing number, including applicable leading zeros.
- Account Number: Enter the account holder's account number with the financial institution, including applicable leading zeros.
- Account Type: Enter the account type (Checking or Saving).
- If account holder is changing the banking information, you must provide OLD banking information.
- Old Financial Institution Name: Enter your Financial Institution's name (this is the name of the bank or qualifying depository that will receive the funds).
- Old Routing Number: Enter the Old bank or financial institutional nine-digit routing number, including applicable leading zeros.
- Old Account Number: Enter the Old account holder's account number with the financial institution, including applicable leading zeros.
- Account Type: Enter the Old account type (Checking or Saving).
 - **NOTE:** Supporting bank documents must be in the account holder legal name only.
- If you do not submit this information, your EFT authorization agreement will be returned without further processing.

PART IV: CONTACT INFORMATION


- Enter the name and title of a contact person who can answer questions about the information submitted on this EFT form.
- Enter the contact person's telephone number. Enter the contact person's e-mail address.

PART V: AUTHORIZATION

- By your signature on this form, you are certifying that the account is drawn in the Name of an Individual, or the Legal Business Name of the person or entity who has sole control of the account to which EFT deposits are made.
- The EFT authorization form must be signed and dated by the same account holder name in Part II and include a title and telephone number.
- Mail this form with the original signature in black or blue ink (no facsimile signatures can be accepted) to the Commonwealth Department that you doing business with.

PART VI: VERIFICATION FROM THE COMMONWEALTH DEPARTMENT

By your signature on this form, you are certifying that authentication of the vendor/customer's authorized signatory was conducted by review of the Contractor Signatory Authorization Form (CASL) or by another internal verification process, and additional verification was conducted to confirm banking or address change request. Departments should have multiple known vendor contacts to confirm any registration change.




BID PACKAGE

PART III

GENERAL CONDITIONS OF THE CONTRACT

CHAPTER 149

**2023-068B FLOORING ABATEMENT & REPLACEMENT
HASKELL BUILDING
1 PRINCE STREET
NORTHAMPTON, MA 01060**



BID PACKAGE

PART III

GENERAL CONDITIONS OF THE CONTRACT

CHAPTER 149



**COMMONWEALTH OF MASSACHUSETTS
STANDARD VERTICAL CONSTRUCTION CONTRACT
For Projects Subject to M.G.L. c. 149, §§ 44A-F**

GENERAL CONDITIONS OF THE CONTRACT
TABLE OF CONTENTS

ARTICLE I: DEFINITION OF TERMS	6
ARTICLE II: EXECUTION OF THE CONTRACT, SCOPE OF WORK, INTERPRETATION OF CONTRACT DOCUMENTS	9
1. Execution.....	9
2. Scope of Work.....	9
3. Interpretation.....	9
4. Distribution of Work.....	10
ARTICLE III: CONTROL OF WORK / ADMINISTRATION OF THE CONTRACT	11
1. Designer.....	11
2. Right of Access to Work.....	11
3. Inspection No Waiver.....	11
ARTICLE IV: GENERAL PERFORMANCE OBLIGATIONS OF THE CONTRACTOR	12
1. Review of Contract Documents and Field Conditions.....	12
2. Supervision and Construction Procedures; Coordination; Cutting, and Patching.....	12
3. Superintendent.....	13
4. Labor.....	14
5. Notices and Permits.....	14
6. Lines, Marks Etc.	15
7. Excavation.....	15
8. Dewatering/Hoisting/Staging.....	15
9. Corrections to The Work; Inspection No Bar to Subsequent Corrections.....	15
10. Sanitary Facilities.....	16
11. Temporary Offices.....	16

12. Contract Documents and Samples at the Site.....	16
13. Telephones, Data Lines, and Wi-Fi.....	17
14. Health, Safety, and Accident Prevention.....	17
15. Debris and Chemical Waste.....	20
16. Weather Protection (M.G.L. c. 149, §§ 44F(1) and 44G)	20
17. Furnishings and Equipment.....	21
18. Form for Subcontract.....	21
19. Sales Tax Exemption and Other Taxes.....	21
20. Final Cleaning.....	21
21. Maintenance Data.....	22
22. Closeout Procedures.....	22
23. Risk of Loss.....	22
24. LEED Requirements.....	22
25. Electronic Project Management System.....	23
26. Drugs/Alcohol.....	23
ARTICLE V: MATERIALS AND EQUIPMENT	23
1. Materials Generally.....	23
2. Shop Drawings, Product Data, and Samples.....	23
3. Tests.....	25
4. "Or Equal" Submissions.....	25
5. Delivery and Storage of Materials; Inspection.....	26
6. Defective, Damaged, or Deteriorated Materials and Rejection Thereof.....	28
ARTICLE VI: PROSECUTION AND PROGRESS	28
1. Beginning, Progress Schedule, and Completion of Work.....	28
2. Failure To Complete Work On Time - Liquidated Damages.....	30
3. Delays; Statutory Provisions (M.G.L. c. 30, § 39O)	31
4. Use and Occupancy Prior to Final Acceptance.....	32
5. Certificate of Substantial Completion.....	32
6. Final Acceptance of the Work.....	34
7. One Year Warranty Repair List and Inspection.....	35
ARTICLE VII: CHANGES IN THE WORK	35
1. Change Orders Generally.....	35
2. Methods of Computing Equitable Adjustments.....	36
3. Work Performed under Protest.....	38
4. False Claims, Statutory Provisions Regarding Changes.....	39
5. Mandatory Mediation.....	41
ARTICLE VIII: PAYMENT PROVISIONS	41
1. Schedule of Values.....	41
2. Payment Liabilities of the Contractor.....	42
3. Retention of Moneys by Awarding Authority.....	42
4. Applications for Payment.....	43
5. Periodic Payments (M.G. L. c. 30, § 39K)	44
6. Payment of Subcontractors (M.G.L. c. 30, § 39F)	46
7. Contracts For Public Works governed by M.G.L. c. 30,	49

§39G.....	52
8. Final Payment; Release of Claims by Contractor.....	52
ARTICLE IX: GUARANTEES AND WARRANTIES	52
1. General Warranty.....	52
2. Special Guarantees and Warrantees.....	53
ARTICLE X: MISCELLANEOUS LEGAL REQUIREMENTS	53
1. Contractor to Be Informed.....	53
2. Compliance with All Laws.....	53
ARTICLE XI: CONTRACTOR'S ACCOUNTING METHOD REQUIREMENTS (M.G.L. c. 30, § 39R)	59
1. Definitions.....	59
2. Record Keeping.....	59
3. Statement of Management Controls.....	60
4. Annual Financial Statement.....	60
5. Bid Pricing Materials.....	60
ARTICLE XII: EQUAL EMPLOYMENT OPPORTUNITY, NON-DISCRIMINATION AND AFFIRMATIVE ACTION PROGRAM [EXECUTIVE ORDERS 524 & 565] (See Appendix A)	61
ARTICLE XIII: GOALS FOR PARTICIPATION BY MINORITY BUSINESS ENTERPRISES AND WOMEN BUSINESS ENTERPRISES [M.G.L. C. 7C, § 6 & EXECUTIVE ORDERS 524 & 565] (See Appendix B)	61
ARTICLE XIV: INSURANCE REQUIREMENTS	61
1. Insurance Generally.....	61
2. Contractor's Commercial General Liability.....	62
3. Automobile Liability.....	63
4. Contractor's Pollution Liability.....	63
5. Worker's Compensation.....	64
6. Builder's Risk/ Installation Floater/ Stored Materials.....	64
7. Umbrella Coverage.....	65
8. Additional Types of Insurance	65
ARTICLE XV: INDEMNIFICATION	66
1. Generally.....	66
2. Designer's Actions.....	66
3. Survival.....	66
ARTICLE XVI: PERFORMANCE AND PAYMENT BONDS	67
1. Contractor Bonds.....	67
2. Subcontractor Bonds.....	67
ARTICLE XVII: TERMINATION OF THE CONTRACT	68
1. Termination for Cause.....	68
2. Termination for Convenience.....	69

3. Contractor’s Duties upon Termination for Convenience....	70
ARTICLE XVIII: MISCELLANEOUS PROVISIONS	70
1. No Assignment by Contractor.....	70
2. Non-Appropriation.....	70
3. Claims by Others Not Valid.....	71
4. No Personal Liability by Public Officials.....	71
5. Severability.....	71
6. Choice of Laws.....	71
7. Standard Forms.....	71
8. No Waiver of Subsequent Breach.....	71
9. Remedies Cumulative.....	71
10. Notices.....	72
11. Additional Information.....	72
12. Information Confidential.....	72
13. Consequential Damages.....	73
14. Conflict of Interest.....	73
15. Sexual Harassment and Workplace Violence Prevention...	73

APPENDICES

APPENDIX A EQUAL EMPLOYMENT OPPORTUNITY, NON-DISCRIMINATION AND AFFIRMATIVE ACTION PROGRAM	75
1. Compliance Generally.....	75
2. Non-Discrimination and Affirmative Action.....	75
3. Liaison Committee, Reports and Records.....	76
4. Sanctions.....	77
APPENDIX B GOALS FOR PARTICIPATION BY MINORITY BUSINESS ENTERPRISES AND WOMEN BUSINESS ENTERPRISES	79
1. Goals.....	79
2. MBE/WBE Participation Credit.....	79
3. Establishing MBE/WBE Status.....	80
4. Subcontractors With MBE/WBEs.....	80
5. Performance of Contract Work by MBE/WBEs.....	80
6. Notification of Changes in MBE/WBE Work.....	80
7. Actions Required If There Is A Reduction in MBE/WBE Participation.....	81
8. Suspension of Payment and/or Performance for Noncompliance.....	82
9. Liquidated Damages; Termination.....	82
10. Reporting Requirements.....	83
11. Awarding Authority’s Right to Waive Provision of this Article.....	83

- ~~Form of Subcontract MGL c.149 §44F~~
- ~~Procedure for Payment to Contractors~~
- ~~Payment Voucher Input~~
- ~~Requisition for Payment (DCAMM Form S1b) and Instructions~~
- ~~DCAMM Instructions and Procedure for Payment for Construction Contractors, including sample Schedule of Values~~
- Instructions and Procedures Regarding Change Orders, Contract Modifications and Equitable Adjustments (DCAMM Form 13)
- Request for Approval of Wages and Rates for Change Order Pricing (DCAMM Form 14)
- Format for Submission of Change Order (DCAMM Form 15) (3 pages)
- Change Order Log (1 Page)
- ~~Daily Time and Material Report for Change Orders 109/17 rev~~
- ~~Request and Agreement for a Change in the Plans~~
- Request and Agreement for a Change in the Plans and/or, Specifications and/or Contract (DCAMM Form 5)
- Weekly Payroll Report Form and Statement of Compliance
- ~~Quarterly Projected Workforce Table~~
- ~~Veteran and Service Disabled Veteran Owned Business Enterprise (VBE/SDVOBE) Participation~~
- ~~Form for Transfer of Title (Work Not Incorporated, DCAMM Form 16)~~
- Payroll & Workforce Report
- Payment Requisition Transmittal (3 pages)
- ~~Submittal Transmittal (1 page)~~
- Submittal Log
- Request for Information Transmittal (1 page)
- Request for Information Log
- ~~Weekly Site Meeting Template (1 Page)~~
- Certificate of Substantial Completion -E-1
- Certificate of Final Inspection, Release and Acceptance - E-2
- Certificate of Payment MBE, WBE, Veteran, Etc.
- Certificate of Payment to Subcontractors, Sub-Bidders, suppliers

END OF APPENDIX C

**END OF TABLE OF CONTENTS.
REMAINDER OF PAGE INTENTIONALLY BLANK.**

ARTICLE I DEFINITION OF TERMS

Other terms, abbreviations and references are defined as they appear herein. Words and abbreviations that are not defined in the Contract Documents but which have recognized technical or trade meanings are used in accordance with those meanings.

The following words shall have the following meanings as used in this Contract:

Approval (or Approved): An approval in writing signed by the authorized signatory of the Awarding Authority.

Awarding Authority: The public agency awarding and administering this Contract identified as the Awarding Authority in the Contract. Where the Awarding Authority is an agency of the Commonwealth, references to the Awarding Authority shall also include the Commonwealth and its agencies.

Building Code: All applicable rules and regulations to which the Awarding Authority is subject and which are contained or referenced in the code authorized by M.G.L. c. 143, § 93 et seq., including all amendments thereto.

Certificate of Substantial Completion: A certificate signed by the Designer and the Awarding Authority pursuant to the requirements of Article VI of these General Conditions, indicating that the Awarding Authority has determined that (1) the Work has been completed in accordance with the Contract Documents, except for Punch List items, (2) certificates of inspection, testing and/or approval (including a certificate of occupancy under the Building Code), operating permits for any mechanical apparatus which may be required to permit full use and occupancy of the Work by its intended users (which in a Subcontractor's case may include the Contractor) have been delivered to the Awarding Authority, (3) any applicable written warranties, operating instructions and related materials have been delivered to the Awarding Authority, and (4) the Work may be used for its intended purpose without substantial inconvenience or interference.

Change Order: (1) A written order not requiring the consent of the Contractor, signed by an authorized representative of the Awarding Authority and designated as a Change Order, directing the Contractor to make changes in the Work within the general scope of the Contract, or (2) any written order from an authorized representative of the Awarding Authority that causes any change in the Work, provided that the Contractor has given the Awarding Authority written notice stating the date, circumstances, and source of the order and that the Contractor regards the order as a Change Order.

Change Order Request: Contractor's written request for a Change Order submitted in accordance with the requirements of Article VII of these General Conditions.

Contract: The Owner - Contractor Agreement executed between the Awarding Authority and the Contractor.

Contract Documents: The documents listed in Article 6 of the Contract.

Contract Modification: Any alteration of the Contract Documents accomplished by a written agreement properly executed by the parties to this Contract.

Contract Price: The Contract Price stated in Article 3 of the Contract which constitutes full compensation to the Contractor for everything to be performed and furnished in connection with the Work and for all damages arising out of the performance of the Work for which the Contractor is responsible, and constitutes the maximum compensation regardless of any difficulty incurred by the Contractor in connection with the Work or in consequence of any suspension or discontinuance of the Work.

Contractor: The person, corporation or other entity identified in the first page of the Contract as the “Contractor”.

DCAMM: The Division of Capital Asset Management and Maintenance of the Commonwealth of Massachusetts. Where DCAMM is an agency of the Commonwealth, references to DCAMM shall also include the Commonwealth and its agencies.

Designer: The architect or engineer identified as the Designer in Article 1 of the Contract.

Drawings: The Drawings are the graphic and pictorial portions of the Contract Documents, wherever located and whenever issued, showing the design, location and dimensions of the Work, generally including elevations, sections, details, schedules, and diagrams.

Final Acceptance: The written determination by the Awarding Authority that the Work has been 100% completed, except for the Contractor's indemnification obligations, warranty obligations, obligations to continue to maintain insurance coverage for the time periods provided in the Contract Documents, and any other obligations which are intended to survive Final Acceptance and/or the termination of the Contract.

General Bid: The completed bid form submitted by the Contractor in accordance with the requirements of M.G.L. c. 149.

Laws: All applicable statutes, regulations, ordinances, codes, laws, orders, decrees, approvals, certificates and requirements of governmental and quasi-governmental authorities.

Notice to Proceed: The written notice provided by the Awarding Authority to the Contractor which authorizes the Contractor to commence the Work as of a date specified therein, from which date the time of completion specified in Article 2 of the Contract is measured.

Or equal (or words of like import): Equal in the opinion of the Awarding Authority determined pursuant to the provisions of M.G.L. c.30, § 39M and the provisions of these General Conditions.

Owner: The Commonwealth of Massachusetts or political subdivision thereof, authority, or other instrumentality that will own the Work.

Product Data: Illustrations, standard schedules, performance charts, instructions, brochures, diagrams and other information furnished by the Contractor or its Subcontractors and suppliers to illustrate materials or equipment for some portion of the Work. Product data also include any such information or instructions produced by the manufacturer or distributor of such materials or equipment and made readily available by said manufacturer or distributor.

Progress Schedule: The progress schedule submitted by the Contractor Approved by the Awarding Authority in accordance with the Contract Documents.

Project: The Project is the total construction of which the Work performed under the Contract Documents may be the whole or a part and which may include construction by the Owner or by separate contractors.

Punch List: A list of items determined by the Awarding Authority to be minor incomplete or unsatisfactory work items that do not materially impair the usefulness of the Work for its intended purpose.

Resident Engineer: The on-Site representative of the Awarding Authority.

Samples: Physical examples, that illustrate materials, equipment, or workmanship and establish standards by which the Work will be judged.

Schedule of Values: The schedule Approved by the Awarding Authority pursuant to Article VIII of these General Conditions which allocates the Contract Price to the various portions of the Work and is used as a basis for payments to the Contractor.

Shop Drawings: Drawings, diagrams, details, schedules, and other data specially prepared for the Work by the Contractor or a Subcontractor, sub-Subcontractor, manufacturer, supplier, or distributor to illustrate a portion of the Work.

Site: The land and, if any, building(s) or space within any such building(s) on which or in which the Contractor is to perform the Work.

Specifications: The portion of the Contract Documents consisting of the written requirements for materials, equipment, construction systems, standards, and workmanship for the Work and performance of related services, including, without limitation, supplementary general conditions.

Subcontractor: Person or entity with whom the Contractor contracts in accordance with this Contract in order to perform the Work, except as otherwise specifically provided or required herein or by Law.

Substantial Completion: For work subject to M.G.L. c. 30, § 39K, "substantial completion" means that the value of the Work remaining to be done is, in the estimate of the Awarding Authority, less than one percent of the adjusted contract price and shall occur when (1) the Contractor fully completes the Work or substantially completes the Work, or (2) the Contractor substantially completes the work and the Awarding Authority takes possession for occupancy, whichever occurs first. For work subject to M.G.L. c. 30, § 39G "substantial completion" shall mean that the work required by the Contract has been fully completed, completed except for work having a Contract Price of less than one percent of the then adjusted total Contract Price, or substantially all of the Work has been completed and opened to public use except for minor incomplete or unsatisfactory work items that do not materially impair the usefulness of the Work.

Superintendent: The licensed construction supervisor who is an employee of the Contractor designated to be in full-time attendance at the Site throughout the prosecution and progress of the Work and who shall have complete authority to act for the Contractor.

User Agency: The department, county, commission, board, agency or other instrumentality of the Commonwealth of Massachusetts or political subdivision thereof which operates, or

which will operate, the facility at which the Work is undertaken or which comprises the completed Work.

Work: The Work consists of all the work identified in the Contract Documents, including, without limitation, as defined in Article 1 of the Contract and Article II, Section 2 of these General Conditions. The Work comprises the completed construction required by the Contract Documents and includes all labor, tools, materials supplies, equipment, permits and approvals, paperwork, calculations, submittals, and certificates necessary to develop, construct, and complete the Work in accordance with all Laws and all construction and other services required to be supervised, overseen, performed, or furnished by the Contractor or that the Contract Documents require the Contractor to cause to be supervised, overseen, performed or furnished.

ARTICLE II

EXECUTION OF THE CONTRACT, SCOPE OF WORK, INTERPRETATION OF CONTRACT DOCUMENTS

1. Execution.

The execution of the Contract by the Contractor is a representation that the Contractor has visited the Site, has become familiar with local conditions under which the Work is to be performed and has correlated personal observations at the Site with requirements of the Contract Documents.

2. Scope of Work.

The Work comprises the completed construction required by the Contract Documents and includes all labor, tools, materials, supplies, equipment, permits, approvals, paperwork, calculations, submittals, and certificates necessary to develop, construct and complete the Work in accordance with all Laws, and all construction and other services required to be supervised, overseen, performed or furnished by Contractor or that the Contract Documents require the Contractor to cause to be supervised, overseen, performed or furnished. The Contractor shall provide and perform for the Contract Price all of the duties and obligations set forth in the Contract Documents.

3. Interpretation.

- A.** The Drawings and Specifications and other Contract Documents are to be considered together and are intended to be mutually complementary, so that any work shown on the Drawings though not specified in the Specifications, and any work specified in the Specifications though not shown on the Drawings, is to be executed by the Contractor as a part of this Contract. Should a conflict occur in or between or among any parts of the Contract Documents that are entitled to equal preference, the better quality or greater quantity shall govern, unless the Awarding Authority directs otherwise. Figured dimensions shall take precedence over scaled dimensions.
- B.** All things that in the opinion of the Designer may be reasonably inferred from the Drawings, Specifications and other Contract Documents are to be executed by the Contractor. The Designer shall determine whether the detail Drawings conform to the general Drawings and Contract Documents, except as may be otherwise determined by the Awarding Authority.

- C. The tables of contents, titles, headings and marginal notes or sub-scripts contained herein are solely to facilitate references, are not intended to be construed as provisions of the Contract, and in no way affect the interpretation of the provisions to which they refer.
- D. Where reference is made in the Contract Documents to publications, standards, or codes issued by associations or societies, such reference shall be interpreted to mean the current edition of such publications, standards, or codes, including revisions in effect on the date of the issuance of the public notice inviting bids or proposals for the Work, notwithstanding any reference to a particular date. The foregoing sentence shall not apply to the dates, if any, specified with respect to insurance policy endorsement forms.
- E. In case of any conflict among the Contract Documents, unless the context clearly otherwise requires, the Contract Documents shall be construed according to the following priorities:
 - First Priority: Contract Modifications and Change Orders
 - Second Priority: Contract, as amended
 - Third Priority: General Conditions of the Contract, as amended
 - Fourth Priority: Drawings, as amended -- schedules take precedence over enlarged detail Drawings, and enlarged detail Drawings take precedence over reduced scale Drawings; figured dimensions shall prevail over scale.
 - Fifth Priority: Specifications, as amended
- F. The Contractor shall refer to all of the Drawings, and to all of the sections of the Specifications, and shall perform all work reasonably inferable therefrom as being necessary to produce the indicated results. Neither the Awarding Authority nor the Designer assumes any liability arising out of jurisdictional issues raised or claims advanced by Subcontractors, trade organizations or other interested parties based on the arrangement or manner of subdivision of the content of the Specifications and Drawings. In the event of any claim arising out of any duplication, conflict, inconsistency or discrepancy within the Specifications or on the Drawings as to the allocation of the Work among the Subcontractors the Contractor shall be solely responsible for resolving the claim and shall be responsible for ensuring that all of the Work is completed, regardless of where it appears in the Specifications or on the Drawings.

4. Distribution of Work.

The distribution of the Work is intended to be described under the appropriate trades and, except for filed sub-bid work, may be redistributed, except as directed herein or as required by any applicable Laws, provided that such redistribution shall cause no controversy among the trades and no delay in the progress of the Work and is in the best interests of the Project.

ARTICLE III

CONTROL OF WORK / ADMINISTRATION OF THE CONTRACT

1. Designer.

Notwithstanding anything to the contrary expressed or implied in this Contract, any of the powers, rights, and duties of the Designer may be exercised by the Awarding Authority, provided that the Awarding Authority shall be under no obligation to do so. The Awarding Authority may rely on the Designer for the performance and exercise of its rights and obligations hereunder and shall be presumed to so rely on the Designer in the absence of an

explicit written assumption by the Awarding Authority of any such rights and obligations, except that any Approval required to be obtained from the Awarding Authority hereunder shall not be valid without the signature of the Awarding Authority. The Awarding Authority may explicitly overrule in writing any action, determination or decision of the Designer should the Awarding Authority choose to do so, except to the extent that the same would violate applicable Law. Subject to the foregoing, the Designer shall be responsible for the general administration of the Contract and shall perform the duties and exercise the rights herein conferred on the Designer. Except as otherwise specifically provided herein, the Designer shall decide all questions which may arise as to the conduct, quantity, quality, equality, acceptability, fitness, and rate of progress of the several kinds of work and materials to be performed and furnished under this Contract, and shall decide all questions which may arise as to the interpretation of the Drawings and Specifications and as to the fulfillment of this Contract on the part of the Contractor. In the case of the death, resignation, inability or refusal of the Designer to act, or the termination of his or her or its employment, the Awarding Authority may appoint another person to act as Designer for the purposes of this Contract. The Awarding Authority shall give written notice to the Contractor of any such appointment.

2. Right of Access to Work.

The Awarding Authority, the User Agency and the Designer (and persons designated by them) may for any purpose enter upon the Work, the Site, and premises used by the Contractor, and the Contractor shall provide safe facilities therefor. Other contractors of the Awarding Authority may also enter upon the same for the purposes which may be required by their contracts or work. Any differences or conflicts which may arise between the Contractor and other contractors of the Awarding Authority with respect to their work shall be initially resolved by the Designer.

3. Inspection No Waiver.

No inspection by the Awarding Authority or the Designer or employees or agents of either of them, and no order, measurement, certificate, approval, payment order, payment, acceptance or any other action or inaction of any of them, shall operate as a waiver by the Awarding Authority of any provision of this Contract.

ARTICLE IV
GENERAL PERFORMANCE OBLIGATIONS OF THE CONTRACTOR

The Contractor shall complete for the Contract Price all Work in a proper, thorough, and workmanlike manner in accordance with the Contract Documents. Without limiting the foregoing and without limiting the Contractor's obligations under any other provision of the Contract Documents, the Contractor shall for the Contract Price perform the following general obligations:

1. Review of Contract Documents and Field Conditions.

A. Before commencing the Work, the Contractor shall carefully study the Contract Documents and carefully compare all Specifications, Drawings, figures, dimensions, lines, marks, scales, directions of the Designer and Awarding Authority, and any other

information provided by the Awarding Authority and shall at once report to the Designer and Awarding Authority any questions, errors, inconsistencies, or omissions.

- B.** Before commencing the Work, the Contractor shall take field measurements and verify field conditions and shall carefully compare such field measurements and conditions and other information known to the Contractor with the Contract Documents and shall at once report to the Designer and Awarding Authority any questions, errors, inconsistencies, or omissions.

2. Supervision and Construction Procedures; Coordination; Cutting, and Patching.

- A.** The Contractor shall supervise and direct the Work, using the Contractor's best skill and attention. The Contractor shall be solely responsible for, and shall have control over, construction means, methods, techniques, sequences and procedures, and shall be responsible for coordinating all portions of the Work under the Contract.
- B.** The Contractor shall be responsible for the proper fitting of all Work and the coordination of the operations of all trades, Subcontractors, and materialmen engaged in the Work. The Contractor shall guarantee to each of its Subcontractors all dimensions which they may require for the fitting of their Work to all surrounding Work.
- C.** All necessary cutting, coring, drilling, grouting, and patching required to fit together the several parts of the Work shall be done by the Contractor, except as may be specifically noted otherwise under any particular filed sub-bid section of the Specifications.
- D.** The Contractor shall be responsible to the Awarding Authority for the acts and omissions of the Contractor's employees, agents and Subcontractors, and their agents and respective contractors' employees, and other persons performing portions of the Work or supplying materials therefor.
- E.** The Contractor shall be responsible for the inspection of portions of the Work already performed under this Contract to determine that such portions are completed in accordance with industry standards of good workmanship and the Contract Documents and in proper condition to receive subsequent Work.
- F.** The Contractor shall employ a registered land surveyor to perform any engineering required for establishing grades, lines, levels, dimensions, layouts, and reference points for the trades. The Contractor shall be responsible for maintaining benchmarks and other survey marks and shall replace any benchmarks or survey marks that may have become disturbed or destroyed. The Contractor shall verify the materials shown on the Drawings before laying out the Work and shall be responsible for any error resulting from its failure to exercise this precaution.
- G.** Unless otherwise required by the Contract Documents, or directed in writing by the Designer or the Awarding Authority, Work shall be performed during regular working hours, which, unless prescribed otherwise by applicable Law, shall be 7:00 a.m. to 5:00 p.m.. If the Contractor desires to carry on the Work outside of regular working hours or on Saturdays, Sundays, or Massachusetts or federal holidays, then the Contractor shall provide at least forty-eight (48) hours' notice to the Awarding Authority and Designer to allow satisfactory arrangements to be made for inspecting Work in progress and shall bear the costs of such inspection. The Awarding Authority at its election shall be entitled either to issue a credit Change Order to cover such cost or to withhold such cost from any further payments due the Contractor and/or to receive a payment from the Contractor of the amount of such cost.

- H. Work performed outside of regular working hours set forth above without the consent or knowledge of the Designer and/or the Awarding Authority shall be subject to additional inspection and testing as directed by the Designer. The cost of this inspection and testing shall be borne by the Contractor whether the Work is found to be acceptable or not. The Awarding Authority at its election shall be entitled either to issue a credit Change Order to cover such cost or to withhold such cost from any further payments due the Contractor and/or to receive a payment from the Contractor of the amount of such cost.

3. Superintendent.

- A. The Contractor shall employ a Superintendent whose appointment shall be subject to the Approval of the Awarding Authority. The Superintendent shall be in attendance at the Site full-time during the performance of the Work. The Superintendent shall represent the Contractor. Communications given to and from the Superintendent shall be deemed given to and from the Contractor. Important communications shall be confirmed in writing. Other communications shall be similarly confirmed upon written request in each case. The Superintendent shall attend each job meeting. The Superintendent shall be responsible for coordinating all of the Work of the Contractor and the Subcontractors.
- B. The Superintendent shall be a competent employee regularly employed by the Contractor. The Superintendent shall be licensed in accordance with the Building Code and shall have satisfactorily performed similar duties on previous construction projects similar in type, complexity and scale to the Project. The Superintendent's resume shall be submitted to the Awarding Authority prior to commencement of construction together with such other information as the Awarding Authority may reasonably require in order to determine whether or not to Approve of his or her appointment. Any change in the Superintendent shall require the prior written consent of the Awarding Authority. The Contractor shall establish an emergency telephone line by which the Awarding Authority, the Designer, or their respective agents may contact the Superintendent during non-working hours.

4. Labor.

- A. The Contractor shall employ only competent workers on the Project. The Contractor shall enforce strict discipline and good order among the Contractor's employees and other persons carrying out the Work. The Contractor shall certify and ensure that all employees to be employed at the Site will have successfully completed a course in construction safety and health approved by the United States Occupational Safety and Health Administration that is at least ten (10) hours in duration at the time the employee begins work and the Contractor and each of its Subcontractors and others working on the Project shall furnish documentation of successful completion of said course by employees working with the first certified payroll report for each employee. The Contractor shall not permit employment of unfit persons or persons not skilled in tasks assigned to them. Whenever the Designer shall notify the Contractor in writing that any worker is, in the Designer's opinion, incompetent, unfaithful, disorderly, or otherwise unsatisfactory, such employee shall be discharged from the Work and shall not again be employed on the Project except with the written consent of the Designer.
- B. The Contractor shall employ a sufficient number of workers and shall ensure that all its Subcontractors employ a sufficient number of workers to carry on the Work with all

proper speed in accordance with Laws, the requirements of the Contract Documents, and the Progress Schedule.

- C. The Contractor shall procure materials from such sources and shall manage its own forces and the forces of its Subcontractors and any sub-Subcontractors in such a manner as will result in harmonious labor relations on the Site. If union and nonunion workers are employed to perform any part of the Work, the Contractor shall establish and maintain separate entrances to the Site for the use of union and nonunion workers. The Contractor shall cause persons to be employed in the Work who will work in harmony with others so employed. Should the Work be stopped or materially delayed in the Awarding Authority's reasonable judgment due to a labor dispute, the Awarding Authority shall have the right to require the Contractor to employ substitutes acceptable to the Awarding Authority.

5. Notices and Permits.

- A. The Contractor at its sole cost shall take out and pay for all approvals, permits, certificates and licenses required by Laws, pay all charges and fees, and pay for (or cause the appropriate Subcontractor to pay for) all utilities required for the proper execution of the Work.
- B. The Contractor shall comply with all Laws and shall give all notices required thereby.
- C. Except as otherwise specified in this Contract, it is not the Contractor's responsibility to ascertain that the Contract Documents are in accordance with applicable Laws. However, if the Contractor observes that portions of the Contract Documents are at variance with the requirements of Laws, the Contractor shall promptly notify the Designer and Awarding Authority in writing, and necessary changes shall be accomplished by an appropriate Contract Modification.
- D. If the Contractor performs Work knowing it to be contrary to Laws without giving such notice to the Designer and Awarding Authority, the Contractor shall bear full

responsibility for such Work and all costs attributable thereto, including, without limitation, corrections to the Work.

6. Lines, Marks etc.

The Contractor shall furnish batter boards and stakes and shall cause to be placed and maintained thereon so as to be easily read, such lines, marks and directions relating to the Work as the Designer shall from time to time direct. The Designer shall establish base lines and benchmarks on the Drawings for the locations of the Work but all other lines and grades shall be determined by the Contractor.

7. Excavation.

The Contractor shall prevent by sheeting and shoring or bracing, if necessary, any caving or bulging of the sides of any excavation made by the Contractor, leaving sheeting and shoring in place, or if any is removed, filling solid the spaces left thereby.

8. Dewatering/Hoisting/Staging.

The Contractor shall provide pumping, drainage, and disposal of all water and other flows so that no puddle, nuisance, or damage will be caused by water or flooding. The Contractor shall provide all hoisting equipment and machinery required for the proper execution of the Work. The Contractor shall provide all exterior and interior staging required to be over eight feet in height, except as may be otherwise provided in the Contract Documents.

9. Corrections to the Work; Inspection No Bar to Subsequent Corrections.

The inspection of the Work by the Designer, the Awarding Authority or their respective consultants shall not relieve the Contractor of its responsibilities to fulfill the Contract obligations. Defective work may be rejected by the Designer, the Awarding Authority, or their respective designated consultants, whether or not such work and/or materials have been previously overlooked or misjudged by the Designer, the Awarding Authority, or their respective consultants and accepted for payment. If the Work or any part thereof shall be found defective at any time before the Final Acceptance of the whole Work, the Contractor shall forthwith cease the performance of any defective work in progress and, whether or not such work is still in progress, shall forthwith correct such defect in a manner satisfactory to the Designer, the Awarding Authority, or their respective designated consultants. If any material brought upon the Site for use in the Work, or selected for the same, is rejected by the Designer, the Awarding Authority, or their respective consultants as unsuitable or not in conformity with the Contract Documents, or as damaged by casualty or deteriorated due to improper storage at the Site or to any other factor, the Contractor shall forthwith remove such materials from the Site. The Contractor shall pay for the cost of making good all work or property of other contractors or of the Owner destroyed or damaged by such removal or replacement; repair, finish and immediately make good any injury, defect, omission or mistake in the Work as soon as it is discovered; and complete and leave the Work in perfect condition.

10. Sanitary Facilities.

- A. The Contractor shall provide and maintain sanitary facilities for all persons employed on the Work, beginning with the first worker at the Site. Said facilities shall meet the following requirements unless otherwise specified in the Specifications.
- B. There shall be no fewer facilities than the number required by applicable Laws.
- C. Facilities shall be kept in a clean sanitary condition at all times and shall be adequately screened to be inaccessible to flies.

(Note: If existing sanitary facilities at the Site are to be used by the Contractor, this requirement will be modified accordingly in the Specifications.)

11. Temporary Offices.

- A. Except as otherwise specified in the Contract Documents, the Contractor shall erect the following temporary offices near the Site as directed by the Designer and adequately furnish and maintain them in a clean, orderly condition:
 - (1) A Contractor's field office at which Contractor's authorized representative shall be present at all times while work is in progress. Instructions, notices, and other communications delivered there by the Designer or the Awarding Authority shall be deemed delivered to the Contractor.
 - (2) The Contractor shall provide a separate conference room space with a conference table and chairs sufficient to accommodate 12 persons at one time.
- B. The Contractor shall relocate the Resident Engineer's trailer, as well as services connected with said trailer, at no additional cost to the Owner if the need for relocation arises as determined by the Designer.

12. Contract Documents and Samples at the Site.

A reasonable number of sets of Contract Documents will be furnished to the Contractor by the Awarding Authority immediately after signing of the Contract, one of which shall be maintained at the Site for reference by authorized representatives of the Awarding Authority. The Contractor shall maintain at the Site for the use and information of the Awarding Authority one record copy of the Drawings, Specifications, addenda, Change Orders, Approved Shop Drawings, Product Data, Samples, updated Progress Schedule, and all other submittals, all in good order and marked currently to record changes and selections made during construction. These shall be available to the Designer and the Awarding Authority and shall be delivered to the Designer for submittal to the Awarding Authority upon completion of the Work. The Drawings, Specifications, and other documents prepared by the Designer and copies thereof furnished to the Contractor are for use solely with respect to this Project. The Contractor shall not permit their release to other parties except as may be necessary in dealing with governmental authorities in the ordinary course of permitting and constructing the Project. Further, they are not to be used by the Contractor or any Subcontractor or supplier on other projects without the specific written consent of the Awarding Authority and the Designer.

13. Telephones, Data Lines, and Wi-Fi.

The Contractor shall provide and maintain separate individual telephone, data and wi-fi service and pay for all calls, data service, and wi-fi service relating to the Work. Service and equipment shall meet the requirements, if any, of the Contract Documents and shall include provisions for incoming and outgoing calls and continually available wi-fi: (1) in the Contractor's field office for the use of its authorized agents and (2) in the Resident Engineer's office for the use of the Designer and authorized agents of the Owner.

14. Health, Safety, and Accident Prevention

A. In performing the Work, the Contractor shall:

- (1) Ensure that no laborer or mechanic shall be required to work in surroundings or under working conditions which are unsanitary, hazardous, or dangerous to his/her health and/or safety as determined under construction safety and health standards promulgated by the U.S. Secretary of Labor by regulation;
- (2) Protect the lives, health, and safety of other persons; and
- (3) Prevent damage to property, materials, supplies, and equipment.

B. For these purposes, the Contractor shall:

- (1) Comply with 84 Stat. 1590, the "Occupational Safety and Health Act of 1970" (OSHA) and with regulations and standards issued by the U.S. Secretary of Labor at 29 CFR Part 1926; and
- (2) Comply with the trench safety law set forth in M.G.L. c. 82A and regulations promulgated by the Departments of Public Safety and Occupational Safety in 520 CMR 14.00 et. seq., which require at a minimum that: 1) all excavators obtain a permit for all trenches as defined; 2) all excavators must provide protections when trenches are unattended; and 3) authorizes fines for violations; the Contractor shall execute a "Trench Application and Permit" form included in Appendix C with the execution of this Contract.
- (3) Include the terms of this Article IV.14 in every Subcontractor contract so that such terms will be binding on each Subcontractor.
- (4) Designate by written notice to the Awarding Authority a responsible member of its organization at the Site whose duties shall include ensuring safety, implementation of Contractor's safety plan referenced below and preventing accidents.

C. The Contractor shall maintain an accurate record of exposure data on all accidents incident to the Work resulting in death, traumatic injury, occupational disease, or damage to property, materials, supplies, or equipment, and shall report this data in the manner prescribed by 29 CFR Part 1904. Without limiting the foregoing, the Contractor shall submit to the Awarding Authority without delay verbal and written reports of all accidents involving bodily injury or property damage arising in connection with the Work.

D. In any emergency affecting the safety of persons or property the Contractor shall immediately act in the exercise of reasonable judgment to prevent threatened damage, injury, or loss. The Contractor shall immediately notify the Awarding Authority of such emergency.

E. The Contractor shall be responsible for its Subcontractors' compliance with the provisions of this Article IV.14.

- F.** Before commencing any portion of the Work on Site, the Contractor shall submit a written Project-specific plan for implementing this Article IV.14. The plan shall include an analysis of the significant hazards to life, limb and property inherent in the performance of the Work and a plan for controlling these hazards.
- G.** Without limiting the foregoing provisions of this Article IV.14, the Contractor shall comply with all health and safety Laws applicable to the Work. Without limitation:
- (1) If the Contractor uses, stores or encounters toxic or hazardous substances it shall comply with M.G.L. c. 111F, § 2, the "Right to Know" law and regulations promulgated by the Department of Public Health, 105 CMR 670, the Department of Environmental Protection, 310 CMR 33, and the Department of Labor and Workforce Development, 441 CMR 21; and shall post a "workplace notice" obtainable from the Department of Labor and Workforce Development.
 - (2) The Contractor shall comply with the Federal Resource Conservation and Recovery Act, the Federal Comprehensive Environmental Response, Compensation and Liability Act, M.G.L. c. 21C, M.G. L. c. 21E, and any other Laws affecting toxic or hazardous materials, solid, special or hazardous waste. Should the Contractor discover unforeseen materials subject to the aforementioned hazardous materials laws at the Site, the Contractor shall immediately comply with any and all requirements for dealing with such materials and notify all required governmental authorities and the Awarding Authority of such discovery.
 - (3) The Contractor shall be responsible for the location of all utilities in connection with the Work. Without limiting the foregoing, the Contractor shall comply with Dig-Safe Laws. Dig-Safe is the Utility Underground Plant Damage Prevention System, 331 Montvale Road, Woburn, MA, 01801, 1-888-344-7233. The Contractor shall notify Dig-Safe of contemplated excavation, demolition, or explosive work in public or private ways, and in any utility company right of way or easement, by certified mail, with a copy to Department of Environmental Protection. This notice shall be given at least 72 hours prior to the work, but not more than sixty days before the work is to be done. Such notice shall state the name of the street or the route number of the way and shall include an accurate description of the location and nature of the proposed work. Dig-Safe is required to respond to the notice within 72 hours of receipt by designating the location of pipes, mains, wires or conduits at the Site. The Contractor shall not commence work until Dig-Safe has responded. The work shall be performed in such manner and with reasonable precautions taken to avoid damage to utilities under the surface at the work location. The Contractor shall provide the Superintendent with current Dig-Safe regulations, and a copy of M.G.L. c. 82, § 40. Any costs related to the services performed by Dig-Safe shall be borne by the Contractor.
 - (4) The Contractor shall comply with M.G.L. c. 149, § 129A, relative to shoring and bracing of trenches.
- H.** Without limiting the Contractor's responsibilities described above, the Contractor shall take all reasonable precautions for the safety of, and the prevention of injury or damage to (i) all agents and employees and contractors on the Work and all other persons who may be affected thereby including the general public, (ii) all the Work and all materials and equipment to be incorporated therein, whether in storage on or off the Site, under the care custody or control of the Contractor or any of its Subcontractors or any contractors directly or indirectly contracting through any of them, and (iii) other property at the Site

or adjacent thereto, including but not limited to trees, shrubs, lawns, walks, pavements, roadways, structures and utilities not designated for removal, relocation or replacement in the course of the Work. The Contractor shall promptly remedy all damage or loss to any such property caused in whole or in part by the Contractor, any Subcontractor, or anyone directly or indirectly contracted or employed by any of them or by anyone for whose acts any of them may be liable. Without limiting the foregoing, the Contractor shall:

- (1) post and maintain adequate danger signs and other warnings against hazards;
 - (2) promulgate safety regulations and give appropriate notices to the Awarding Authority and users of adjacent utilities and property;
 - (3) ensure the adequate strength and safety of all scaffolding, staging and hoisting equipment, temporary shoring, bracing and tying;
 - (4) protect adjoining private or public property;
 - (5) provide barricades, temporary fences, and covered walkways required by prudent construction practices, Laws and/or the Contract Documents;
 - (6) furnish approved hard hats and other personal protective equipment, furnish approved first aid supplies, furnish the name of the first aid attendant, and maintain a posted list of emergency facilities;
 - (7) provide proper means of access to property where the existing access is cut off by the Contractor;
 - (8) maintain from the beginning of any darkness or twilight through the whole of every night sufficient lights on or near any obstruction so as to guard and protect travelers from injury from such obstruction;
 - (9) maintain adequate security at the Site so as not to expose the Work and surrounding property to vandalism or malicious mischief;
 - (10) provide adequate fire protection procedures during the use of cutting torches, welding equipment, plumbers' torches and other flame and spark producing apparatus;
 - (11) take prompt action to correct any dangerous or hazardous conditions.
- I.** The Contractor shall not use or store explosives in the performance of the Work unless the Contractor first obtains the Awarding Authority's prior written specific Approval. If the Awarding Authority Approves the use or storage of explosives during the performance of the Work, the Contractor shall first comply with all Laws and obtain all permits, approvals, and certificates required in connection with the same and shall exercise best efforts, including but not limited to the employment and supervision of properly qualified personnel, to prevent damage, injuries, and accidents involving said explosives.
- J.** The Contractor shall not permit cutting or welding in or immediately adjacent to existing property of the Owner, Awarding Authority or of anyone else without the Awarding Authority's prior Approval in each instance.

15. Debris and Chemical Waste.

- A.** The Contractor shall not permit the accumulation of interior or exterior debris. The Contractor shall keep the Work area clean at all times. Without limitation, garbage shall be removed daily.

- B.** The Contractor shall properly classify and remove debris and waste from the Site and transport and dispose of it, all in accordance with Laws, employing a qualified and properly licensed transporter, at any landfill, disposal or recycling facility licensed under applicable Laws, including without limitation, hazardous materials Laws. The Contractor shall make all arrangements and give and obtain all notices, communications, documentation, permits, certificates, and approvals necessary for said disposal from the owner or officials in charge of such landfills, disposal or recycling facilities. The Contractor shall bear all fees and costs in connection with such classification, removal, transportation, disposal and storage. The Contractor shall not permit any storage of debris or waste except in accordance with Laws.
- C.** The Contractor shall not permit any open fire on the Site.
- D.** Chemical waste shall be stored in corrosion resistant containers, removed from the Site, and disposed of not less frequently than monthly unless more frequently required by Laws, including without limitation hazardous materials laws, or by the Contract Documents. Disposal of chemical waste shall be performed in accordance with requirements of the U.S. Environmental Protection Agency and the Massachusetts Department of Environmental Protection. Fueling and lubricating of vehicles and equipment shall be conducted in a manner that affords the maximum protection against spills and evaporation. Lubricants shall be disposed of in accordance with procedures meeting all applicable Laws. The Contractor shall immediately notify the Designer and Awarding Authority of any hazardous materials release large enough to require reporting under applicable Laws. The Contractor shall be responsible for immediately cleaning up in accordance with Laws any oil or hazardous materials releases resulting from its operations. Any costs incurred in cleaning up any such releases shall be borne by the Contractor.

16. Weather Protection (M.G.L. c. 149, §§ 44F(1) and 44G).

The Contractor shall furnish and install "weather protection," which means temporary protection of that Work adversely affected by moisture, wind and cold. Weather protection shall be achieved in accordance with the Specifications, and at a minimum shall include covering, enclosing and/or heating working areas such that a minimum temperature of 40 degrees Fahrenheit (or higher temperature, if so stated in the Specifications) is maintained at the working surface during the months of November through March in order to permit construction to be carried on during such period in accordance with the Progress Schedule. After the building or portion thereof is completely enclosed by either permanent construction or substantial temporary materials having a resistance comparable to the specified permanent construction, the Contractor shall provide heat in accordance with the Specifications; if the Specifications do not specify a temperature range for this phase, the Contractor shall provide heat of not less than 55 degrees F. nor more than 75 degrees F. The foregoing provisions do not supersede any specific requirements for methods of construction, curing of materials and the like. Such weather protection shall be consistent with the Progress Schedule, shall permit the continuous progress of the Work necessary to maintain an orderly and efficient sequence of construction operations, shall include one thermometer for every two-thousand (2,000) square feet of floor space or fraction thereof (or as otherwise stated in the Specifications), shall be subject to the Approval of the Awarding Authority, and shall meet such additional requirements as may be specified by the Awarding Authority and by the Contract Documents.

17. Furnishings and Equipment.

When, in the opinion of the Designer, any portion of the Work is in a reasonable condition to receive fittings, furniture, or other property of the Owner not covered by this Contract, the Contractor shall allow the Awarding Authority to bring such fittings, furniture, and/or other property into such portions of the Work and shall provide all reasonable facilities and protection thereof. No such occupancy shall be construed as interfering with the provisions relating to time of completion, or as constituting an acceptance of the whole or any part of the Work. Any furniture or fittings so installed shall be placed in the Work at the risk of the Awarding Authority except that the Contractor shall be liable for damages or losses to such furniture or fittings to the extent such damages or losses arise in whole or in part from the negligence or intentional misconduct of Contractor, Subcontractors, their agents and/or employees, or anyone for whose acts Contractor is responsible.

18. Form for Subcontract.

The Contractor when subcontracting with sub-bidders filed pursuant to M.G.L. c. 149, § 44F shall use the form for subcontract in M.G.L. c. 149, § 44F(4)(c). The Contractor shall not interpret paragraph 3 of the statutory form of subcontract to require such sub-bidders to provide insurance with limits higher than the limits that are required by Article XIV of these General Conditions, assuming that the term “Contractor” therein refers to the sub-bidder and that the term “Contract Price” refers to the sub-bidder’s price stated in paragraph 1 of the statutory form of subcontract.

19. Sales Tax Exemption and Other Taxes.

All building materials and supplies as well as the rental charges for construction vehicles, equipment and machinery rented exclusively for use on the Site, or while being used exclusively for the transportation of materials for the Work are entitled to an exemption from sales taxes under M.G.L. c. 64H, § 6(f). The Contractor shall take all action required to obtain the benefit of such sales tax exemption. The Contractor shall bear the cost of any sales taxes that Contractor incurs in connection with the Work and the Awarding Authority shall not reimburse the Contractor for any such taxes. The exemption number assigned to the Contractor as an exempt purchaser shall be provided to the Contractor by the Awarding Authority upon the written request of the Contractor.

20. Final Cleaning.

At the completion of the Work, the Contractor shall remove all waste materials, rubbish, tools, equipment, machinery and surplus materials, and professionally clean all sight-exposed surfaces so that the Work is clean and ready for occupancy. Subsequent to installation of User Agency furniture, telephones, and equipment, the Contractor shall provide such additional cleaning as may be necessary to remove any soil resulting from installation of such furniture, telephones and equipment. The Contractor shall comply with the detailed final cleaning requirements of the Specifications; in the event of any conflict

between the Specifications and this Section specifically with respect to cleaning at or after the completion of the Work, the Specifications shall apply.

21. Maintenance Data.

Subject to such additional requirements as may be provided in the Contract Documents, the Contractor shall compile four complete and identical binders of operating and maintenance

data for the entire Work, which shall include, at a minimum for all equipment and systems installed, complete operation and maintenance programs, including but not limited to operation and maintenance (O&M) manuals, records of any and all maintenance performed (whether by the Contractor or Subcontractors) between equipment installation and Final Acceptance, all as may be further detailed in the Specifications. The Contractor shall submit record maintenance data to the Designer for approval, shall submit approved maintenance data to the Awarding Authority, and shall instruct and train the User Agency's personnel in proper inspection and maintenance procedures in accordance with the training plan developed and Approved in accordance with the Specifications. If requested by the Awarding Authority, the Contractor shall also submit information on equipment and systems installed as the Work is performed in a format acceptable to the Awarding Authority, which shall be compatible for entry in the Capital Asset Management Information System (CAMIS), as may be further detailed in the Specifications.

22. Closeout Procedures.

The Contractor shall take all actions and submit all items required for the issuance of the Certificate of Substantial Completion and Final Acceptance as specified in the Contract Documents.

23. Risk of Loss.

The Contractor shall bear all risk of loss to the Work during the term of the Contract except for any portion of the Work as to which the Certificate of Substantial Completion has been issued pursuant to Article VI of these General Conditions of the Contract. Nothing herein shall limit the Contractor's responsibilities under Article IX or XV of these General Conditions of the Contract.

24. LEED Requirements.

Contractor understands that, pursuant to Executive Order No. 484, all new construction and renovation projects over 20,000 square feet must, at a minimum, meet a Massachusetts LEED Plus building standard, and that smaller projects must meet the minimum energy performance standards for advanced buildings established by the Commonwealth of Massachusetts Sustainable Design Roundtable. Furthermore, Contractor understands that the Massachusetts LEED Plus standard or a higher LEED standard applies to all projects overseen by DCAMM, as well as all projects built on state land for use by state agencies. Contractor must document compliance with this executive order and Project LEED certification standards as described in the Specifications.

25. Electronic Project Management System.

If so requested by the Awarding Authority, the Contractor and Subcontractors shall be required to use the Awarding Authority's electronic web-based project management information system as a repository for Project correspondence, documentation, budgeting, and scheduling, and all submittals and processes under this Contract, as directed by the Awarding Authority.

26. Drugs/Alcohol.

The Contractor shall direct that all persons coming onto the Site are free of drugs and alcohol. The Contractor shall dismiss from the Project any individual employed by the Contractor or any Subcontractor or suppliers who is found by the Contractor, the Awarding Authority, or the User Agency to be in violation of this provision or in any other way incompetent, guilty of misconduct, or detrimental to the Project.

ARTICLE V **MATERIALS AND EQUIPMENT**

1. Materials Generally.

- A.** Unless otherwise specifically provided in the Contract Documents, the Contractor shall provide and pay for materials, equipment, tools, construction equipment and machinery, water, heat, utilities, transportation, and other facilities and services necessary for proper execution and completion of the Work, whether temporary or permanent and whether or not incorporated or to be incorporated in the Work.
- B.** Materials and equipment to be installed as part of the Work (both or either of which are hereinafter referred to as "materials") shall be new, unused, of recent manufacture, assembled, and used in accordance with the best construction practices. The Contractor shall inform himself as to, and shall comply with, the provisions of M.G.L. c. 7, § 23A, as amended, and shall abide by the same and all applicable rules, regulations and orders made thereunder in relation to the purchase of supplies and materials in the execution of the Work, including the provisions of M.G.L. c.7, § 22, paragraph 17 which provides that there be "*a preference in the purchase of supplies and materials, other considerations being equal, in favor, first, of supplies and materials manufactured and sold within the Commonwealth, and, second, of supplies and materials manufactured and sold elsewhere within the United States.*"

2. Shop Drawings, Product Data, and Samples.

- A.** The Contractor shall furnish to the Designer all Samples of the materials to be used in the execution of the Work as required by the Contract Documents. The Contractor shall furnish to the Designer in a timely manner all coordination Drawings, shop details, Shop Drawings, and setting diagrams which may be necessary for acquiring and installing materials. These shall be reviewed as required by the Designer. Unless otherwise specified by the Awarding Authority, the Contractor shall provide a minimum of four (4) copies when submitting for final approval by the Designer, one of which shall be returned to the Contractor, one to the Resident Engineer, one to the Awarding Authority and one filed with the Designer. The inspection and approval by the Designer of Shop Drawings and setting diagrams shall be general and shall in no way relieve the Contractor from responsibility for proper fitting, coordinating, construction, and construction sequencing. The Contractor shall furnish to the Designer such information and vouchers relative to the Work, the materials therefor, and the persons employed thereon, as the Designer shall from time to time request.
- B.** Shop Drawings, Product Data, Samples, and similar submittals are not Contract Documents. The purpose of their submission is to demonstrate for those portions of the Work for which submittals are required the way the Contractor proposes to conform to the information given and the design concept expressed in the Contract Documents.

- C. The Contractor shall review, approve, and submit to the Designer, Shop Drawings, Product Data, Samples and similar submittals required by the Contract Documents with reasonable promptness and in such sequence as to cause no delay in the Work or in the activities of the Awarding Authority or of separate contractors. Submittals made by the Contractor which are not required by the Contract Documents or which do not comply with the Contract Documents may be returned without action. The Contractor's attention is directed to the provisions of Section 4 of this Article V and to the Specifications.
- D. The Contractor shall prepare and keep current for the Designer's approval a schedule of submittals which is coordinated with the Progress Schedule and allows the Designer reasonable time to review submittals.
- E. The Contractor shall perform no portion of the Work requiring submittal and review of Shop Drawings, Product Data, Samples or similar submittals until the respective submittal has been approved by the Designer. Such Work shall be in accordance with approved submittals.
- F. By submitting Shop Drawings, Product Data, Samples and similar submittals, the Contractor represents that the Contractor has determined and verified materials, field measurements, and field construction criteria related thereto and has checked and coordinated the information contained within such submittals with the requirements of the Work and of the Contract Documents.
- G. The Contractor shall not be relieved of responsibility for deviations from requirements of the Contract Documents by the Designer's approval of Shop Drawings, Product Data, Samples or similar submittals unless the Contractor has specifically informed the Designer in writing of such deviation at the time of submittal and the Awarding Authority has given explicit written approval to the specific deviation. The Contractor shall not be relieved of responsibility for errors or omissions in Shop Drawings, Product Data, Samples, or similar submittals by the Designer's or the Awarding Authority's actions.
- H. The Contractor shall direct specific attention, in writing or on resubmitted Shop Drawings, Product Data, Samples or similar submittals, to revisions other than those requested by the Designer on previous submittals.
- I. Informational submittals upon which the Designer is not expected to take responsive action may be so identified in the Contract Documents.
- J. When professional certification of performance criteria of materials, systems or equipment is required by the Contract Documents, such certification must be stamped by a registered Massachusetts professional in the discipline required. The Designer shall be entitled to rely upon the accuracy and completeness of such calculations and certifications.
- K. Materials furnished or used or employed under the Contract must be equal in quality to the Samples furnished and be satisfactory to the Designer.

3. Tests.

- A. Any material to be used in the Work may be tested or inspected at any time by the Designer with the prior Approval of the Awarding Authority and may be rejected if it fails to comply with specified tests. The Awarding Authority shall pay for all testing of specified material, except as provided herein. If the Contractor requests permission to use a material that was not specified, then the Contractor shall pay for such testing. The cost of testing of materials that fail the testing criteria shall be borne by the Contractor

- B.** The Contractor shall notify the Designer and the Awarding Authority of the proposed sources of materials in time to permit all required testing and inspection before the material is needed for incorporation into the Work. The Contractor shall have no claim arising from Contractor's failure to designate the proposed source or to order the material in time for adequate testing and inspection. Necessary arrangements shall be made to permit the Designer to make factory, shop or other inspection of materials or equipment ordered for the Work in process of manufacture or fabrication, or in storage elsewhere than the Site.

4. "Or Equal" Submissions.

- A.** Where products or materials are prescribed by manufacturer name, trade name, or catalog reference, the words "or Approved equal" shall be understood to follow. An item shall be considered equal to the item so named or described if in the opinion of the Awarding Authority (a) it is at least equal in quality, durability, appearance, strength and design, (b) it performs at least equally the function imposed in the general design for the Work, and (c) it conforms substantially, even with deviations, to the detailed requirements for the items as indicated by the Specifications. Any changes in the Work made necessary to accommodate products or materials substituted as an "or equal" shall be at the expense of the Contractor. "Approved equal" shall mean an item with respect to which the Awarding Authority shall have issued a written statement to the Contractor to the effect that the item is, in the Awarding Authority's opinion, equal within the meaning of this paragraph to that prescribed in the Contract Documents.
- B.** The Contractor shall be responsible for providing the Designer with any information and test results that the Designer reasonably requires to determine whether or not a material is equal to a material named or described in the Contract Documents.
- C.** Whenever the Contractor submits a material for Approval as a substitute for a material named or described in the Contract Documents, such submission shall be made at least one hundred twenty (120) days prior to the date the materials will be used in the Work. In no event shall the Contractor maintain a claim for delays based upon the Designer's review of such substituted materials if the Contractor has failed to comply with the one hundred twenty (120) day submission requirement.
- D.** The Contractor shall save the written calculations, pricing information, and other data that the Contractor used to calculate the General Bid (the "Bid Pricing Materials") for at least six years after the Awarding Authority makes final payment under this Contract. No increase in the Contract Price shall be allowed for any material later found to have been improperly rejected as not being equal unless the Contractor can show persuasive evidence that the rejection increased the Contractor's costs over those provided for in the Bid Pricing Materials, net of all savings the Contractor obtained by substituting other "or-equal" items. Without limiting the foregoing, if the Awarding Authority rejects a proposed substitution on the basis that the item is not equal and if after the Contractor complies with the appeal procedures required by law, DCAMM regulation, and by the Contract Documents, the appropriate authority finds that the proposed substitution was equal, the Contract Price may be increased only to the extent that:
- (1) the item that the Contract Documents specifically require costs more than the item later approved as equal;
 - (2) the Bid Pricing Materials prove that the Contractor calculated its bid using the cost of the item later found as equal;

- (3) any increase is reduced by any cost that the Contractor would have incurred for structural or mechanical changes necessary to accommodate the substitute item;
- (4) the Contractor shall not be entitled to any adjustment for overhead and profit;
- (5) any increase must exceed the aggregate amount that the Contractor saved using products or materials that the Awarding Authority approved as equal under this Contract.

In calculating the Contractor's aggregate saving under the preceding clause (5), the Contractor shall provide the Awarding Authority with the Bid Pricing Materials and a calculation based on the Bid Pricing Materials that compare the price (stated in the Bid Pricing Materials) of each item replaced with an "or equal" item, with the cost of the approved equal item, specifically describes all costs that Contractor would have incurred making structural or mechanical changes to include within the Work the item later found to have been improperly rejected and copies of all plans, specifications, shop drawings, and other design documents that the Awarding Authority deems necessary or desirable.

5. Delivery and Storage of Materials; Inspection.

- A.** Materials and equipment shall be progressively delivered to the Site so that there will be neither delay in the progress of the Work nor an undue accumulation of materials that are not to be used within a reasonable time and so that their security, quality, and fitness of the materials for the Work is preserved.
- B.** Materials stored off Site shall be insured and stored at the expense of the Contractor so as to guarantee the preservation of their security, quality and fitness for the Work. Without derogating from the Contractor's responsibilities in the previous sentence, when necessary to avoid deterioration or damage, material (on or off Site) shall be placed on wooden platforms or other hard clean surfaces and not on the ground and shall be properly protected.
- C.** The Contractor shall obtain prior written Approval for permission to store materials or equipment to be incorporated into the Work for which progress payments will be requested at off-Site locations. Any and all charges for storage, inspection, and verification by the Designer and Awarding Authority, including insurance, shall be borne solely by the Contractor. Before Approval, the Awarding Authority may require, without limitation
 - (1) evidence that the off-Site location is properly secure;
 - (2) proper proof of insurance and proof of satisfactory contractual arrangement for transportation to the Site; and
 - (3) a certificate from the Contractor stating: (i) the name of the member of the Contractor or Subcontractor that leases or owns the warehouse or other storage facility; (ii) the location of such storage facility, including the storage space (i.e. the entire premises or certain areas of a warehouse giving the number of floors or portions thereof) and a certification that the Contractor has visited such location, verified the storage of such materials or equipment therein or thereon (including confirmation that the materials or equipment are marked and segregated as provided below) and verified payment of all current storage charges; (iii) the date(s) on which the materials or equipment is first stored at such facility; and (iv) a description of the materials or equipment stored, including quantities, types, manufacturers and other identification information, such as serial numbers.

The Contractor shall furnish to DCAMM, not less often than once per month, a current inventory of all materials or equipment being stored at any off-Site location. The Contractor shall mark each sealed carton or other item with the name of the Project and the Awarding Authority, and all materials or equipment stored off-Site shall be segregated to the extent required by the Awarding Authority or the Designer. Payment for materials or equipment stored off-Site shall be at the reasonable discretion of the Awarding Authority, taking into account the schedule requirements of the Work. Title to materials or equipment stored off-Site shall be transferred at the time at which the Awarding Authority pays for them, free of any lien or other interest of the supplier or any other lien or encumbrance. Notwithstanding such transfer of title, the Contractor shall retain sole care, custody and control of, and shall have complete responsibility for the security and protection of, all materials or equipment included in any application for payment which are stored at locations other than the Site, and the Contractor assumes all risk of loss or damage to such materials or equipment, and the Contractor shall hold harmless the Awarding Authority from and against all liabilities arising out of or resulting from loss or damage, from any cause, to such materials or equipment for which payment is requested, including liens, security interests or other claims of any kind by suppliers or other third parties relating to such materials or equipment.

- D. Expenses for inspection of material by the Designer and/or the Awarding Authority personnel including travel, quarters, and subsistence shall be borne by the Contractor requesting the inspection of material stored outside the Commonwealth of Massachusetts as part of the Contract Price. The policy of the Awarding Authority precludes the payment for material stored outside the boundaries of Massachusetts except in extremely limited circumstances with the express written consent of the Awarding Authority. If the Contractor requests an inspection of material stored outside the Commonwealth of Massachusetts, the Awarding Authority will initially pay for all expenses of inspecting the material incurred by the Designer and/or Awarding Authority's personnel including travel, quarters, and subsistence. The Awarding Authority will then give Contractor an invoice for those costs and the Contractor shall submit a credit Change Order in the amount of those expenses.
- E. Stored materials either at the Site or at some other location agreed upon in writing shall be so located as to facilitate prompt inspection and even though approved before storage, may again be inspected prior to their use in the Work.
- F. All storage sites shall be restored to their original condition by the Contractor at the Contractor's expense.
- G. The Contractor shall take charge of and be liable for any loss of or injury to the materials for his use delivered to or in the vicinity of the place where the Work is being done, whether furnished by the Owner or otherwise; the Contractor shall notify the Designer as soon as any such materials are so delivered, allow them to be examined by the Designer, and furnish workers to assist therewith.

6. Defective, Damaged, or Deteriorated Materials and Rejection Thereof.

The Designer may reject materials if the Designer reasonably determines that such materials do not conform to the Contract Documents in any manner, including but not limited to materials that have become damaged or deteriorated from improper storage whether or not such materials have previously been accepted. The Contractor at its own expense shall remove rejected materials from the Work. No rejected material, the defects of which have been

subsequently corrected, shall be used except with the written permission of the Designer. Should the Contractor fail to remove rejected material within a reasonable time, the Designer and/or Awarding Authority may, in addition to any other available remedies, remove and/or replace the rejected material, and deduct the cost of such removal and/or replacement from any moneys due or to become due the Contractor. No extra time shall be allowed for completion of Work by reason of such rejection. The inspection of the Work shall not relieve the Contractor of any of its obligations herein prescribed, and any defective Work shall be corrected. Work not conforming to the Contract Documents may be rejected notwithstanding that such Work and materials have been previously overlooked or misjudged by the Designer and accepted for payment. If the Work or any part thereof shall be found defective at any time before Final Acceptance of the whole Work, the Contractor shall forthwith make good such defect in a manner satisfactory to the Designer. Nothing in the Contract shall be construed as vesting in the Contractor any property rights in the materials used after they have been attached or affixed to the Work or the Site; but all such materials shall upon being so attached or affixed become a property of the Owner.

ARTICLE VI **PROSECUTION AND PROGRESS**

1. Beginning, Progress Schedule, and Completion of Work.

- A.** The Contract time shall commence upon the date specified in the Notice to Proceed. The Contractor shall begin Work at the Site within ten days of said date unless otherwise ordered in writing by the Awarding Authority.
- B.** Prior to the submission of the first progress payment, the Contractor shall submit to the Designer and to the Awarding Authority, a progress schedule for the term of the Contract as required by the Contract Documents, showing in detail his proposed progress for the construction of the various parts of the Work and the proposed times for receiving required materials. Upon Approval by the Awarding Authority, said schedule shall constitute the Progress Schedule. The Contractor shall at the end of each month, or more often if required, furnish to the Designer and to the Awarding Authority a schedule meeting the requirements of the Specifications showing the actual progress of the parts of the Work in comparison with the Progress Schedule.
- C.** Time is of the essence of this Contract. The Work shall be completed within the time specified in Article 2 of the Contract. Should the Contractor require additional time to complete the Work, the Contractor shall document the reasons therefor and submit a written request for an extension of time within 20 days of the occurrence of the event alleged to be the cause of the delay, as provided in this Article and in Article VII of these General Conditions. Failure to submit said written request within the time required by the preceding sentence shall preclude the Contractor from subsequently claiming any time extension due to said delay.
- D.** If, in the opinion of the Designer or the Awarding Authority, the Contractor fails to comply with the Progress Schedule, the Awarding Authority may give the Contractor a written notice to that effect whereupon (1) the Contractor shall, if the notice requires, discontinue all or any portion of the Work (which discontinuance shall neither terminate the Contract nor give the Contractor any claim for an increase in the Contract Price, damages, or an extension of any completion deadlines); or (2) at Contractor's sole cost increase the work force, equipment and plant, or any of them, employed on the whole or any part of the Work, to the extent required by such notice, and employ the same from

day to day until the completion of the Work or such part thereof, or until the failure regarding the rate of progress, in the opinion of the Designer or the Awarding Authority, shall have been sufficiently corrected.

- E. If, in the opinion of the Awarding Authority, the Contractor fails to comply with the Progress Schedule, and whether or not the Awarding Authority shall have given the Contractor a notice described in D above, the Awarding Authority may (but shall not be required to) give the Contractor notice of such failure and five days to cure the same. Unless the Contractor shall within that five days take all necessary steps to do so (including, if the Awarding Authority requires, increasing its forces, equipment and plant) and continue to do so until in the opinion of the Awarding Authority the failure is corrected, the Awarding Authority may at the Contractor's expense and without terminating this Contract take exclusive or joint possession of all or a portion of the Site and employ and direct the labors of existing or such additional forces, equipment and plant as may in the Designer's or Awarding Authority's opinion be necessary to ensure the completion of the Work or such part thereof within the time specified in the Contract Documents or at the earliest possible date thereafter. The Awarding Authority may exercise its rights under this Article at any time and from time to time without waiving any of its rights under this Contract, at law or in equity, including, without limitation, the right to deem this Contract terminated or to order the Contractor to discontinue the Work at any time thereafter. The Contractor shall continue to perform the remaining Work under this Contract even if the Awarding Authority elects to have another contractor perform a portion of the Work under this Article.
- F. The Awarding Authority shall deduct the cost of any actions the Awarding Authority takes under this Article from any amount then due or which might have become due to the Contractor under this Contract had the Contractor performed as required. On demand, the Contractor shall pay the Awarding Authority any amount by which the cost of completing all or any portion of the Work exceeds the amount attributable to that Work under the Contract Documents. The Awarding Authority's sole goal will be to complete the Work that it elects to complete within the time limits stated in the Contract or at the earliest possible date thereafter. Consequently, the Awarding Authority shall have no obligation to obtain competitive bids or the lowest cost for completing the Work or any part thereof, except when it is required by Law. The Awarding Authority's election to complete all or part of the Work shall not release the Contractor from any liability for failure to complete the Work as the Contract Documents require, and shall not entitle the Contractor to a claim for an increase in the Contract Price or an extension of the time for completing the Work. If the cost that the Awarding Authority incurs in completing all or any portion of the Work is less than the amount that the Contract Documents attribute to that Work, the Awarding Authority will pay or credit the difference to the Contractor, less any other costs and expenses that the Awarding Authority incurs, including the cost of supervision, and the Designer's and attorneys' fees and costs.

2. Failure to Complete Work on Time - Liquidated Damages.

- A. If the Contractor shall neglect, fail or refuse to achieve the Substantial Completion Date, the Contractor and the Contractor's surety agree, as a part of the consideration for the execution of this Contract by the Awarding Authority, to pay the Awarding Authority the amounts set forth in Article 2 of the Contract, not as a penalty, but as liquidated damages to cover certain losses, expenses, and damages of the Awarding Authority for such breach of this Contract as herein set forth. The Contractor acknowledges that delay of the

Substantial Completion Date will cause disruption of the Awarding Authority's operations and those of the User Agency. Such disruptions include without limitation, loss of productivity and efficiency and duplication of effort of the User Agency and of employees and contractors engaged by the User Agency and the Awarding Authority for operation of the completed facility. The Awarding Authority and the User Agency will incur other direct administrative, professional, rental, storage, moving, transportation, and other costs in the event of such delay. Delay of the Substantial Completion Date will also require the Awarding Authority to incur additional costs for compensation to the Designer and other consultants or contractors for extended or additional services on the Project. In light of the costs, damages, losses, risks and liabilities described above, the parties agree upon the liquidated damages stated below. Such damages have been fixed and agreed upon because of the impracticability and extreme difficulty of fixing and ascertaining the actual damages the Awarding Authority and the Commonwealth would, in such event, sustain. Said amounts may be retained by the Awarding Authority on or after the scheduled Substantial Completion Date from current progress payments or any other amounts owing to the Contractor.

- B.** Similarly, if the Contract states that by a specified date a designated portion of the Work shall be prosecuted to the point at which it qualifies for the issuance of a Certificate of Substantial Completion, and if such portion has not been prosecuted to such point by said date, the Contractor shall pay to the Awarding Authority the sum designated in the Contract for each calendar day that the Contractor is in default in completing such portion of the Work to such point. Such moneys shall also be paid as liquidated damages not as a penalty, to cover losses and expenses to the Owner resulting solely from the fact that the Work is not completed on time.
- C.** The Awarding Authority may recover such liquidated damages by deducting the amount thereof from any moneys due or that might become due the Contractor, and if such moneys shall be insufficient to cover the liquidated damages, then the Contractor or the Surety shall pay to the Awarding Authority the amount due.
- D.** Except as otherwise expressly provided, none of the following shall constitute a waiver of the Contractor's or its surety's obligations to pay liquidated damages or any portion thereof or of any of the Owner's rights hereunder at law or in equity:
 - (1) Acceptance of any portion of the Work or payment to the Contractor or its surety therefor;
 - (2) Completion of a portion of the Work or the use and occupancy thereof by the Awarding Authority or others; or
 - (3) The Awarding Authority's requiring or allowing the Contractor or its surety to complete the Work.
- E.** Liquidated damages or a portion thereof may be waived by the Awarding Authority if the Contractor submits evidence satisfactory to the Awarding Authority that the delay was caused solely by conditions beyond the control of the Contractor and that the Awarding Authority has not suffered any damages as a result of said delay.
- F.** Failure by the Awarding Authority to specify a sum as liquidated damages in the Contract, or the insertion of "N/A" or "none" in the space provided therein for liquidated damages, shall not be deemed a waiver of the Awarding Authority's right to recover actual damages arising from the Contractor's failure to complete the Work on time.

3. Delays; Statutory Provisions (M.G.L. c. 30, § 39O).

- A.** Notwithstanding any provision of this Contract to the contrary, except as otherwise provided by Law as set forth in paragraph B below, the Contractor shall not be entitled to increase the Contract Price or to receive damages on account of any hindrances or delays, avoidable or unavoidable, including damages for compression or acceleration of Work, or loss of productivity; but if any delay is caused, in the opinion of Awarding Authority, by the Awarding Authority, the Contractor shall be entitled to an extension of time. The length of the extension shall be sufficient in the opinion of the Awarding Authority or the Contractor to complete the Work. Although no delay shall increase the Contract Price, the Awarding Authority may require that any change in the date by which the Contractor must complete all or any part of the Work be processed on a standard Change Order form.
- B.** If a suspension, delay, interruption or failure to act of the Awarding Authority increases the cost of performance to any Subcontractor, that Subcontractor shall have the same rights against the Contractor with respect to such increase as the Contractor shall have against the Awarding Authority by virtue of (a) and (b) of M.G.L. c. 30, § 390 set forth below, but nothing in provisions (a) and (b) shall alter any other rights which the Contractor or the subcontractor may have against each other. As used in the statutory language of (a) and (b) below, "contract" means this Contract, "general contractor" means the Contractor and "awarding authority" means the Awarding Authority:

"(a) The awarding authority may order the general contractor in writing to suspend, delay, or interrupt all or any part of the work for such period of time as it may determine to be appropriate for the convenience of the awarding authority; provided, however, that if there is a suspension, delay or interruption for fifteen days or more or due to a failure of the awarding authority to act within the time specified in this contract, the awarding authority shall make an adjustment in the contract price for any increase in the cost of performance of this contract but shall not include any profit to the general contractor on such increase; and provided further, that the awarding authority shall not make any adjustment in the contract price under this provision for any suspension, delay, interruption or failure to act to the extent that such is due to any cause for which this contract provides for an equitable adjustment of the contract price under any other contract provisions.

(b) The general contractor must submit the amount of a claim under provision (a) to the awarding authority in writing as soon as practicable after the end of the suspension, delay, interruption or failure to act and, in any event, not later than the date of final payment under this contract and except for costs due to a suspension order, the awarding authority shall not approve any costs in the claim incurred more than twenty days before the general contractor notified the awarding authority in writing of the act or failure to act involved in the claim."

4. Use and Occupancy Prior to Final Acceptance.

- A.** The Contractor agrees to the use and occupancy of the Project or any portion thereof before Final Acceptance of the Work by the Awarding Authority.
- B.** The Awarding Authority and the User Agency will cooperate with the Contractor with respect to the completion of the Work by taking such reasonable steps as may be possible to avoid interference with the Contractor's Work provided that they do not interfere with the proper functioning of the facility.

- C. The Contractor shall not be responsible for wear and tear or damage resulting solely from temporary occupancy.
- D. Use and occupancy of any part of the Work prior to Final Acceptance by the Awarding Authority shall not relieve the Contractor from maintaining the required payment and performance bonds and insurance (to the extent that insurance is required to be maintained after Substantial Completion) required by this Contract.

5. Certificate of Substantial Completion.

- A. When the Work, or portion thereof which the Awarding Authority agrees to accept separately has reached the state of Substantial Completion as shown on Approved payment request, the Contractor shall develop, with the participation of the Designer and the Awarding Authority, the Punch List identifying those items of unfinished or unacceptable Work that remain to be performed or corrected under the Contract.
- B. Before the Work shall be deemed completed to the point where it is ready for the issuance of a Certificate of Substantial Completion, the Contractor shall:
 - (1) Provide Contractor's proposed Punch List containing a statement of the reason for each item listed thereon;
 - (2) Advise the Awarding Authority of proposed changes in insurance in accordance with the provisions of this Contract, and provide to the Awarding Authority evidence of Contractor's completed operations insurance coverage to the extent required by the Contract Documents;
 - (3) Execute and submit a notarized warranty on a form provided by the Awarding Authority or otherwise acceptable to the Awarding Authority meeting the requirements of Article IX of these General Conditions, to commence upon the date of the issuance of the Certificate of Substantial Completion for the Work or the designated portion thereof, unless otherwise provided in the Certificate of Substantial Completion;
 - (4) Submit signed special warranties and warranties of longer than one year as required by the Contract Documents;
 - (5) Submit signed maintenance agreements for all portions of the Work specified to receive maintenance after the issuance of the Certificate of Substantial Completion;
 - (6) Submit all preliminary record Drawings and documents and framed data in the forms required by the Contract Documents;
 - (7) Complete all items required to be completed by the Department of Public Safety and obtain a Certificate of Occupancy from the Department of Public Safety (or, if the Awarding Authority is a municipality, the building department having jurisdiction) and similar releases which permit the User Agency and the Awarding Authority full and unrestricted use of the areas claimed to be ready for occupancy;
 - (8) Deliver specified maintenance stocks of materials, required spare parts, and all special tools furnished by manufacturers to persons designated by the Awarding Authority and obtain written receipts for same;
 - (9) Make final changes of lock cylinders or cores and advise the Awarding Authority of the change of project security responsibility;

- (10) Complete start-up of systems and instruct User Agency personnel on proper operation and routine maintenance of all systems and equipment; obtain and submit to User Agency personnel that start-up and instruction have been completed;
- (11) Remove all remaining temporary facilities that are no longer needed, surplus materials, and debris (provided, however, that the Contractor shall not remove construction offices and trailers without the prior Approval of the Awarding Authority);
- (12) Submit final utility meter readings and similar information and advise the User Agency and the Awarding Authority of the change of responsibility for utility charges and payments upon the issuance of the Certificate of Substantial Completion;
- (13) Complete final clean-up of all Work, restoration of damaged finishes, and replacement of all damaged and broken glass not listed on the Contractor's Punch List.
- (14) Complete such other items as may be called for in the Contract Documents, if any, including without limitation the Specifications.

C. After completing the items specified in subsections A and B above, the Contractor shall make a written request for the Designer's inspection for a Certificate of Substantial Completion in accordance with the Contract Documents. The Designer shall review the submittals and the Work and shall either 1) sign a Certificate of Substantial Completion or 2) notify the Contractor of incomplete and/or incorrect Work that must be completed and corrected prior to the issuance of the Certificate of Substantial Completion. The Designer shall notify the Contractor of any additions to the Punch List. In connection with the execution of the Certificate of Substantial Completion the Designer shall assign dollar values to each item on the Punch List. Failure to include any incomplete or defective item on the Punch List shall not relieve the Contractor of the obligation to complete all Work in accordance with the Contract Documents.

6. Final Acceptance of the Work.

A. **Prerequisites for Final Acceptance.** After the issuance of a Certificate of Substantial Completion for the entire Work, and after the Contractor has completed all of the Work required by this Contract, including Change Orders and Punch List items, the Contractor shall submit the following completed items to the Awarding Authority together with such additional items as may be specified in the Contract Documents:

- (1) A completed final application for payment showing a final accounting of all changes in the Work, on the form provided by the Awarding Authority.
- (2) Certification and satisfactory evidence that all taxes, fees, and similar obligations have been paid.
- (3) Consent of the Contractor's surety to final payment executed by applicable bonding companies.
- (4) Certified copy of the Punch List stating that the Contractor has completed or corrected every item listed.
- (5) Evidence of Contractor's continuing completed operations insurance coverage to the extent required by the Contract Documents.

- (6) All final record Drawings and documents in the forms specified by the Contract Documents.
- (7) A notarized certification that all purchases made under the tax exemption certificate were legitimate and entitled to exemption.
- (8) Written certifications from the Department of Public Safety (or if the Awarding Authority is a municipality, the building department having jurisdiction) and the Designer to the effect that: a) the Work has been inspected for compliance with the Contract Documents and has satisfied the Department of Public Safety; b) all equipment and systems included in the Work have been tested in the presence of the Designer and are operational and satisfactory; c) the Work is completed and ready for final inspection.
- (9) Such other items as may be required by the Contract Documents.

B. Reinspection; Final Acceptance. After notification from the Contractor that all remaining Contract exceptions, omissions and incompletions have been completed (with the exception of Contractor's continuing warranty, insurance, indemnification, and such other obligations as are intended by the terms of the Contract Documents to extend beyond the date of Final Acceptance), the Awarding Authority and the Designer shall inspect the Work to verify the completion of the same. If the Work is satisfactory, the Awarding Authority shall prepare a Certificate of Final Acceptance or shall notify Contractor in writing of items which remain to be completed prior to Final Acceptance.

7. One-Year Warranty Repair List and Inspection.

Approximately 30 days prior to the expiration of the comprehensive one-year warranty period, the Contractor shall schedule an appointment with the Awarding Authority for a re-inspection of the Work with the Awarding Authority, and shall thereafter inspect the work at the time scheduled. Based on this inspection and on prior inspections, the Awarding Authority shall issue a "Warranty Repair List" of items to be corrected by the Contractor. The Contractor shall make the repairs and/or replacements listed within 30 days of the issuance of the "Warranty Repair List" unless otherwise agreed by the Awarding Authority in writing.

ARTICLE VII **CHANGES IN THE WORK**

1. Change Orders Generally.

- A.** No changes in the Work, the Contract Price, the Substantial Completion date, the Final Acceptance date, or any other provision of an Approval by the Awarding Authority of the Contract Documents shall be made in absence of a Change Order as defined in Article I of these General Conditions, directing the Contractor to perform such changes. Any request for a change in the provisions of this Contract submitted by the Contractor must be made in writing and in accordance with the provisions of this Contract, including the procedures of the Awarding Authority.
- B.** A request for a change in the provisions of this Contract may be submitted to the Awarding Authority by the Contractor, Designer, Resident Engineer or User Agency. The request must be made in writing and in accordance with the provisions of this Contract, Laws, and the procedures of the Awarding Authority. When the Contractor believes that

an event or circumstance gives rise to an adjustment in the Contract Price and/or the Contract time it shall submit a Change Order Request in accordance with the forms and procedures required by the Awarding Authority.

- C.** A written directive may be issued by the Awarding Authority instructing the Contractor to make changes in the Work within the general scope of the Contract, including but not limited to, changes in: (1) the Drawings and Specifications; (2) the method or manner of performance of the Work; (3) the Owner-furnished facilities, equipment, materials, services or Site; (4) the schedule for performance of the Work.
- D.** Whenever a Change Order or written directive will cause a change in the Contractor's cost, the Contractor or the Awarding Authority may request an adjustment in the Contract Price. Such request shall be in writing and shall be submitted by the party making such claim to the other party before commencement of the pertinent work.
- E.** The Awarding Authority and the Contractor shall negotiate in good faith an agreement on an equitable adjustment in the Contract Price, and/or time if appropriate, before commencement of the pertinent Work. In the absence of an agreement for an equitable adjustment, the Awarding Authority shall unilaterally determine the costs attributable to the change and provide the Contractor with a written notice to that effect. The Contractor may appeal the decision of the Awarding Authority within thirty days of receipt of said notice, to the chief executive official of the Awarding Authority (in the case of DCAMM, the DCAMM commissioner) or the chief executive's designee, and the Contractor shall have the right to such further appeal as is provided in M.G.L. c.30, § 39Q set forth in Article VII.4.D. However, if the Contractor shall exercise its rights to appeal the decision of the Awarding Authority as aforesaid, the Contractor shall be required to engage in the mandatory mediation procedures set forth in Article VII.5.
- F.** During the negotiation of an equitable adjustment in the Contract Price, the Contractor shall provide the Awarding Authority with all cost, pricing data and any other information or documentation used by the Contractor in computing the amount of the equitable adjustment, and the Contractor shall certify that the pricing data used was accurate, complete, and current. If the Awarding Authority subsequently determines that the data submitted by the Contractor was inaccurate, incomplete, or not current, the Awarding Authority may exclude such data from consideration under the equitable adjustment request.
- G.** Whenever the Contractor is entitled or believes it is entitled to a Change Order adjusting the Contract Price, the Contractor shall maintain separate accounts (by job order or other suitable accounting procedure) of all costs incurred and attributable to such work and schedule. The Contractor shall maintain a computerized accounting system, acceptable to the Awarding Authority, in which current information as to the status of all such Work and schedule is maintained. The Contractor shall maintain such contemporaneous records as are necessary to provide a clear distinction between the costs of all Change Order Work and proposed Change Order Work, and the costs of other Work and schedule.
- H.** Notwithstanding any provisions in the Contract Documents to the contrary, no additional general conditions cost shall be due for any Change Order or portion of a Change Order resulting from or attributable to:

 - (1) Increases in the cost of allowance items;
 - (2) Substitutions of equipment or materials which are functionally similar to equipment or materials specified in the Contract Documents; or

(3) Sales and use taxes.

- I. The Contractor shall reasonably investigate the validity of Subcontractor and supplier change order requests before agreeing to pass them through to the Awarding Authority. For all Change Order Requests submitted, the Contractor shall certify that: the Change Order Request is made in good faith; the validity of the Contractor's and any Subcontractor and supplier Change Order Requests have been verified; the supporting data is accurate and complete to the best of the Contractor's knowledge and belief; and the Contractor believes the Awarding Authority to be liable for the add amount, or entitled to the deduct amount of the Change Order Request, whichever is applicable.

2. Methods of Computing Equitable Adjustments.

A. Equitable adjustments in the Contract Price shall be determined according to one of the following methods, or a combination thereof, as determined by the Awarding Authority:

- (1) fixed price basis, provided that the fixed price shall be inclusive of items (a) through (g) below and shall be computed in accordance with those provisions and as detailed in the Awarding Authority's instructions and procedures regarding Change Order Request submissions, Contract Modifications and equitable adjustments (For DCAMM Projects, DCAMM Form 13 included in Appendix C to these General Conditions);
- (2) estimated lump sum basis to be adjusted in accordance with Contract unit prices or other agreed upon unit prices provided that the unit prices shall be inclusive of all costs related to such equitable adjustment;
- (3) time and materials basis to be subsequently adjusted based upon of actual costs (but subject to a predetermined "not to exceed limit") calculated as follows:
 - (a) the direct cost (or credit) for labor at the minimum wage rates established for this Contract pursuant to M.G.L. c. 149, §§ 26-27H;
 - (b) plus (or minus) the cost of workmen's compensation insurance, liability insurance, federal social security and Massachusetts unemployment compensation, which are to be calculated using an allowance equal to 40% applied to said rate. The rate of 40 percent is inclusive of all insurances, taxes, general conditions, overhead, superintendence, fee, and profit. No other expenses are allowed; for example, sick time, vacation time, etc. are included in the all-inclusive rate. Documentation must be provided if a higher percentage is requested and will only be accepted for workmen's compensation over 12.5%.
 - (c) plus (or minus) the actual direct additional premium costs and expenses incurred as a result of collective bargaining agreements or other agreements between organized labor. No allowance for markups is allowed on these costs.
 - (d) plus the direct cost of materials and use of equipment; an allowance equal to 15% of the amount of materials and equipment for general conditions, overhead, superintendence, fee, and profit can be applied.
 - (e) plus certain miscellaneous services Approved in advance by the Awarding Authority (e.g. police details, utilities, etc.) and provided, which may be subject to a 5% markup.
 - (f) plus (or minus) the actual direct premium cost of payment and performance bonds required of the Contractor and certain Subcontractors for this Contract.

- (g) the Contractor shall receive an allowance equal to 5% of the sum of items (a) through (e) above for overhead, superintendence, fee, and profit when the work is performed by Subcontractors. Subcontractors can also apply an allowance equal to 5% of the sum of items (a) through (e) above for overhead, superintendence, fee, and profit when the work is performed by sub-Subcontractors.
- (4) The Contractor and its Subcontractors are required to anticipate annual updated minimum wage schedules in accordance with M.G.L. c. 149, § 27 and shall not be entitled to claim additional compensation for base bid contract Work due to updated minimum wage schedules.
- B.** If the net change is an increase to the Contract Price, it shall include the value of the Contractor's overhead, superintendence, fee and profit. On any change that involves a net credit, the amount of the credit shall include the hard cost of the work being credited and the value of the overhead, superintendence, fee and profit applicable thereto (calculated as an agreed upon percentage multiplied by such hard cost of the work). Charges for small tools known as "tools of the trade" are not to be computed in the amount of any change in the Contract Price.
- C.** Substitutions in Subcontractors made in accordance with the provisions of M.G.L. c. 149, § 44F shall not be considered Change Orders and shall not entitle the Prime Contractor to any adjustments for overhead, profit, and superintendence, although the Awarding Authority may require that such Contract adjustments be processed on standard Change Order and equitable adjustment forms.
- D.** For DCAMM Projects, refer to Appendix C (Commonly Used Forms) to these General Conditions for instructions regarding Change Orders, Contract Modifications, and equitable adjustments (DCAMM Form 13), form for request for Approval of wages and rates for Change Order pricing (DCAMM Form 14) and format for submission of Change Order (DCAMM Form 15). Section 2 (Directions for Computing Costs for Changes in the Work) of DCAMM Form 13 contains specific information for computing the cost of changes. DCAMM Form 14 and DCAMM Form 15 are available electronically and will be provided to the Contractor prior to the start of construction. The Contractor, all Subcontractors, and sub-Subcontractors shall utilize DCAMM Form 15 when submitting Change Order Requests.

3. Work Performed under Protest.

The Contractor agrees to perform all Work as directed by the Awarding Authority, and if the Awarding Authority determines that certain Work that the Contractor believes to be or to warrant a Change Order under this Article does not represent a change in the Work, the Contractor shall perform said Work. The Contractor shall be deemed to have concurred with the Awarding Authority's determination as aforesaid unless the Contractor shall perform Work under protest in compliance with the following sub-paragraphs (1) and (2) below. Any disputed order, decision or action by the Awarding Authority or its authorized representative shall be fully performed or complied with pending resolution of the dispute.

- (1) If the Contractor claims compensation for a change in the Work that is not deemed by the Awarding Authority to be a change or to warrant additional compensation as claimed by the Contractor, the Contractor shall on or before the first working day following the commencement of any such Work or the sustaining of any such damage submit to the Awarding Authority a written statement of the nature of such Work or

claim. The Contractor shall not be entitled to additional compensation for any Work performed or damage sustained for which written notice is not given within the time limit specified in the preceding sentence, even though similar in character to work or damage with respect to which notice is timely given.

- (2) On or before the second working day after the commencement of such Work or the sustaining of such damage, for each day upon which work occurs or damage is sustained, the Contractor shall file to the extent possible with the Resident Engineer, the Designer, and the Awarding Authority, itemized statements of the details and costs of such Work performed or damage sustained. Unless otherwise indicated by the Awarding Authority in writing, the Contractor shall use the Awarding Authority's "Daily Time and Materials Report" form found in Appendix C to these General Conditions to record all labor and material used. If the Contractor shall fail to make such statements, then the Contractor shall not be entitled to additional compensation for any such work or damages.

4. False Claims, Statutory Provisions Regarding Changes.

- A. Criminal Penalties.** The Contractor's attention is directed to M.G.L. c. 30, § 39I which provides criminal penalties for unauthorized deviations from the Drawings and Specifications, and to M.G.L. c. 30, § 39J and M.G.L. c. 7C, §§ 17-21. The Contractor's attention is also directed to M.G.L. c. 266, § 67B which provides criminal penalties for false claims by Contractor under this Contract:

"Whoever makes or presents to any employee, department, agency or public instrumentality of the commonwealth, or of any political subdivision thereof, any claim upon or against any department, agency, or public instrumentality of the commonwealth, or any political subdivision thereof, knowing such claim to be false, fictitious, or fraudulent, shall be punished by a fine of not more than ten thousand dollars or by imprisonment in the state prison for not more than five years, or in the house of correction for not more than two and one-half years, or both."

B. Differing Site Conditions (M.G.L. c. 30, § 39N).

"If, during the progress of the work, the contractor or the Awarding Authority discovers that the actual subsurface or latent physical conditions encountered at the Site differ substantially or materially from those shown on the plans or indicated in the contract documents either the contractor or the contracting authority may request an equitable adjustment in the contract price of the contract applying to work affected by the differing site conditions. A request for such an adjustment shall be in writing and shall be delivered by the party making such claim to the other party as soon as possible after such conditions are discovered. Upon receipt of such a claim from a contractor, or upon its own initiative, the contracting authority shall make an investigation of such physical conditions, and, if they differ substantially or materially from those shown on the plans or indicated in the contract documents or from those ordinarily encountered and generally recognized as inherent in work of the character provided for in the plans and contract documents and are of such a nature as to cause an increase or decrease in the cost of performance of the work or a change in the construction methods required for the performance of the work which results in an increase or decrease in the cost of the work, the contracting authority shall make an equitable adjustment in the contract price and the contract shall be modified in writing accordingly."

C. Timely Decision By the Awarding Authority (M.G.L. c. 30, § 39P).

"Every contract subject to section thirty-nine M of this chapter or section forty-four A of chapter one hundred forty-nine which requires the awarding authority, any official, its architect or engineer to make a decision on interpretation of the specifications, approval of equipment, material or any other approval, or progress of the work, shall require that the decision be made promptly and, in any event, no later than thirty days after the written submission for decision; but if such decision requires extended investigation and study, the awarding authority, the official, architect or engineer shall, within thirty days after the receipt of the submission, give the party making the submission written notice of the reasons why the decision cannot be made within the thirty day period and the date by which the decision will be made."

D. Change Order / Contract Interpretation Appeal Procedure (M.G.L. c. 30, § 39Q).

The following provisions apply to every contract awarded by any state agency as defined by M.G.L. c. 7C, § 1 for the construction, reconstruction, alteration, remodeling, repair or demolition of any capital facility as defined by the aforesaid section 39A:

"(a) Disputes regarding changes in and interpretations of the terms or scope of the contract and denials of or failures to act upon claims for payment for extra work or materials shall be resolved according to the following procedures, which shall constitute the exclusive method for resolving such disputes. Written notice of the matter in dispute shall be submitted promptly by the claimant to the chief executive official of the state agency which awarded the contract or his designee. No person or business entity having a contract with a state agency shall delay, suspend, or curtail performance under that contract as a result of any dispute subject to this section. Any disputed order, decision or action by the agency or its authorized representative shall be fully performed or complied with pending resolution of the dispute.

"(b) Within thirty days of submission of the dispute to the chief executive official of the state agency or his designee, he shall issue a written decision stating the reasons therefore, and shall notify the parties of their right of appeal under this section. If the official or his designee is unable to issue a decision within thirty days, he shall notify the parties to the dispute in writing of the reasons why a decision cannot be issued within thirty days and of the date by which the decision shall issue. Failure to issue a decision within the thirty-day period or within the additional time period specified in such written notice shall be deemed to constitute a denial of the claim and shall authorize resort to the appeal procedure described below. The decision of the chief executive official or his/her designee shall be final and conclusive unless an appeal is taken as provided below.

"(c) Within twenty-one calendar days of the receipt of a written decision or of the failure to issue a decision as stated in the preceding subparagraph, any aggrieved party may file a notice of claim for an adjudicatory hearing with the division of hearing officers or the aggrieved party may file an action directly in a court of competent jurisdiction and shall serve copies thereof upon all other parties in the form and manner prescribed by the rules governing the conduct of adjudicatory proceedings of the division of hearing officers. In the event an aggrieved party exercises his option to file an action directly in court as provided in the previous sentence, the twenty-one day period shall not apply to such filing and the period of filing such action shall be the same period otherwise applicable for filing a civil action in superior court. The appeal shall be referred to a hearing officer experienced in construction law and shall be prosecuted in accordance with the formal rules of procedure for the conduct of adjudicatory hearings of the division of hearing officers, except as provided below. The hearing officer shall issue a final decision as expeditiously as possible, but in no event more than one hundred and

twenty calendar days after conclusion of the adjudicatory hearing, unless the decision is delayed by a request for extension of time for filing post-hearing briefs or other submissions assented to by all parties. Whenever, because an extension of time has been granted, the hearing officer is unable to issue a decision within one hundred and twenty days, s/he shall notify all parties of the reasons for the delay and the date when the decision will issue. Failure to issue a decision within the one hundred and twenty-day period or within the additional period specified in such written notice shall give the petitioner the right to pursue any legal remedies available to him without further delay.

"(d) When the amount in dispute is less than ten thousand dollars, a contractor who is party to the dispute may elect to submit the appeal to a hearing officer experienced in construction law for expedited hearing in accordance with the informal rules of practice and procedure of the division of hearing officers. An expedited hearing under this subparagraph shall be available at the sole option of the contractor. The hearing officer shall issue a decision no later than sixty days following the conclusion of any hearing conducted pursuant to this subparagraph. The hearing officer's decision shall be final and conclusive, and shall not be set aside except in cases of fraud."

5. Mandatory Mediation.

In the case of every dispute where the dollar amount in dispute (or the estimated dollar value of the extension of time in dispute) is \$50,000 or more and the Contractor appeals the decision of the chief executive official of the Awarding Authority or his/her designee as required by M.G.L. c.30, § 39Q, quoted in Article VII.4.D.(b) above, the Awarding Authority and the Contractor shall engage in good faith in a non-binding mediation process, which process shall be concluded within sixty days from the date that the Contractor files an appeal from said decision as provided in M.G.L. c.30, § 39Q. In the case of such disputes where the dollar amount in dispute (or the estimated dollar value of the extension of time in dispute) is \$500,000 or more, if the mediation process fails, the Awarding Authority may, in its sole discretion, elect to submit the dispute to an impartial third party, not having an interest in the Owner, the Designer, the Program Manager, the Contractor, or the Project, which shall within sixty (60) days render a non-binding advisory opinion. Unless the parties have previously agreed in writing to a process for submitting disputes to mediation, the Awarding Authority shall determine in its reasonable discretion the procedures to be followed and shall give the Contractor notice of the same in writing within seven (7) days of the date that the Awarding Authority receives notice of the Contractor's appeal from the decision of the chief executive officer of the Awarding Authority or his designee. The cost of the services of any mediator selected by one party to this Contract shall be borne by the party making the selection. The cost of the services of any mediator selected jointly by the parties to this Contract or jointly by mediators selected by the parties to this Contract shall be borne equally by the Contractor and the Awarding Authority.

ARTICLE VIII **PAYMENT PROVISIONS**

1. Schedule of Values.

Before the first application for payment the Contractor shall submit to the Designer and the Awarding Authority for its Approval, a schedule of values in a form acceptable to the Awarding Authority and allocated to various portions of the Work in sufficient detail to reflect the various major components of each trade (with filed Subcontractors as well as MBE/WBE

noted), including quantities when requested, aggregating the total Contract Price and divided so as to facilitate payments for work under each section of the Specifications. The schedule shall be prepared in such form and supported by such data to substantiate its accuracy as the Awarding Authority may require. Each item in the schedule shall include its proper share of overhead and profit. When Approved by the Awarding Authority, it shall constitute the Schedule of Values and shall be used only as a basis for the Contractor's requests for payments and credits, the first of which payments shall not be made until such Schedule of Values is Approved by the Awarding Authority.

2. Payment Liabilities of Contractor.

- A.** The Contractor shall pay to the Owner all expenses, losses and damages, as determined by the Awarding Authority or the Designer, incurred in consequence of any default, defect, omission or mistake of the Contractor or the Contractor's employees or Subcontractors or the making good thereof.
- B.** If the Work (or a portion thereof) is not completed to Substantial Completion and the Contractor has not satisfied the requirements for the issuance of a Certificate of Substantial Completion in accordance with Article VI.5 of these General Conditions, by the date specified in Article 2 of the Contract, the Contractor shall pay to the Owner liquidated damages as provided in Article VI.2 of these General Conditions.

3. Retention of Moneys by Awarding Authority.

- A.** The Awarding Authority may keep any moneys which would otherwise be payable at any time hereunder and apply the same, or so much as may be necessary therefor, to (1) the Owner 's expenditures for the Contractor's account, (2) to secure the Awarding Authority's remedies against the Contractor for the Contractor's breach of its obligations under this Contract or the breach of any person performing any part of the Work and (3) the payment of any expenses, losses or damages incurred by the Awarding Authority or any agency of the Commonwealth as a result of the failure of the Contractor to perform its obligations hereunder. The Awarding Authority may retain, until all claims are settled, such moneys as the Awarding Authority estimates to be the fair value of the Awarding Authority's claims against the Contractor, and of all claims for labor performed or furnished and for materials used or employed in or in connection with the Work and for the rental of vehicles, appliances and equipment employed and for the employment of substitute contractors and labor in connection with the Work filed in accordance with M.G.L. c. 30, § 39A and § 39F. The Awarding Authority may make such settlements and apply thereto any moneys retained under this Contract.
- B.** The Contractor shall each week examine all claims so filed, and if the same are in any respect incorrect or do not correctly show the amount due from the Contractor to the claimant for such labor and materials, the Contractor shall forthwith file with the Awarding Authority a separate written statement of all inaccuracies in each claim and of the correct amount due from the Contractor to each claimant therefor, and shall immediately file a statement of all payments thereafter made to such claimants. Each such statement shall be sworn to and contain a detailed breakdown required by M.G.L. c. 30, § 39F (d) and (e). Unless such statements are so filed by the Contractor the amount shown by the claims filed shall, at the option of the Awarding Authority, be conclusively deemed to be the accurate amount due from the Contractor therefor in all accounting with the Awarding Authority. If the moneys retained under this Contract are insufficient to pay

the sums found by the Awarding Authority to be due under the claims for labor and materials filed as aforesaid, the Awarding Authority may, at its discretion, pay the same, and the Contractor shall repay to the Awarding Authority all sums paid out. The Awarding Authority may also at its discretion use any moneys retained, due or to become due under this Contract for the purpose of paying for both labor and materials used or employed in the Work for which claims have not been filed with the Awarding Authority.

- C. No moneys retained under the provisions of this Article shall be held to be statutory security for the payment of claims filed in accordance with the provisions of M.G.L. c. 149, § 29, as amended, for which security is provided by bond.

4. Applications for Payment.

A. The Contractor shall, once in each month on the day of the month corresponding to the day of the month specified in the Notice to Proceed, unless otherwise directed by the Awarding Authority in writing, on forms provided and in the manner prescribed by the Awarding Authority, submit to the Awarding Authority a statement showing the total amount of Work done to the time of such estimate and the value thereof as approved by the Resident Engineer and the Designer. It shall be the sole responsibility of the Contractor to deliver or cause to be delivered to the "designee" as provided by M.G.L. c. 30, § 39K indicated by the Awarding Authority in writing, said periodic estimate in proper form, approved as provided above and arithmetically correct. For DCAMM projects, the "designee" as provided by M.G.L. c. 30, § 39K shall be the DCAMM Office of Finance Payment Unit, and requests for payment shall be submitted thereto in accordance with the "DCAMM Instructions and Procedures for Payment for Construction Contracts" included in Appendix C to these General Conditions. For other projects, unless otherwise indicated by the Awarding Authority in writing, said "designee" shall be the Resident Engineer, or, if there is no Resident Engineer, the Designer; if there is neither a Resident Engineer nor a Designer the designee shall be a person designated by the Awarding Authority at the project field office or alternatively the home office of the Awarding Authority. All periodic estimates shall contain such certifications and other evidence supporting the Contractor's right to payment as the Awarding Authority may require, including without limitation, lien waivers and other evidence, on such forms as the Awarding Authority may require, establishing that title to the equipment or materials is unencumbered and has been transferred to the Owner.. The Contractor shall include in such periodic estimate only such materials as are incorporated in the Work, except as provided in Article VIII.4.C below. The Awarding Authority shall retain five (5) percent of such estimated value as security for the completion of the Work and while the Contractor continues to carry on the Work, will pay to the Contractor the Approved balance, net of the five (5) percent, all previous payments, and all sums which may be otherwise retained under the provisions of this Contract.

B. Each periodic estimate shall constitute the Contractor's representation that:

- (1) the payment then requested to be disbursed has been incurred by the Contractor on account of the Work and is justly due to Subcontractors or, to the Contractor in the case of other Work performed by the Contractor on account thereof (if the Contractor's self-performance has been previously Approved in accordance with the Contract);
- (2) the materials, supplies and equipment for which application for payment is being submitted have been installed or incorporated into the Work or have been stored at the

Site or at such off Site storage locations as the Awarding Authority shall have Approved;

- (3) the materials, supplies and equipment are insured in accordance with the provisions of this Contract;
- (4) the materials, supplies and equipment are owned by the Owner and are not subject to any liens or encumbrances;
- (5) the Work which is the subject of such periodic estimate has been performed in accordance with the Contract Documents; and
- (6) that all due and payable bills with respect to the Work have been paid to date or shall be paid from the proceeds of such periodic estimate.

The Contractor's attention is directed to the criminal penalties for false claims referenced in Article VII above.

- C. The Contractor may include in a periodic estimate the value of materials or equipment delivered at the Site (or at some location agreed to in writing by the Awarding Authority) only upon delivery to the Awarding Authority of:
- (1) an acceptable transfer of title on the form provided by the Awarding Authority;
 - (2) written certification by the Contractor (or applicable Subcontractor) on the form provided by the Awarding Authority that the Contractor (or the Subcontractor which executed the transfer of title) is the lawful owner and that the materials or equipment are free from all encumbrances, accompanied by receipted invoices or other acceptable proof of prior payment for such materials;
 - (3) a stored materials insurance binder that covers the materials for which payment is requested, that names the Owner as an insured party should the stored materials be subjected to any casualty, loss, or theft prior to their inclusion in the Work. The material(s) or equipment must, in the judgment of the Designer, (a) meet the requirements of the Contract, including prior Shop Drawing, Product Data, and Sample Approval, (b) be ready for use, and (c) be properly stored by the Contractor and be adequately protected until incorporated into the Work. See also Article V.5.D of these General Conditions concerning the cost of inspections.
- D. The Awarding Authority may make changes in any periodic estimate submitted by the Contractor in accordance with M.G.L. c.30, §39K (see below) and the payment due shall be computed in accordance with the changes so made. The provisions of said section 39K shall govern payments on which the Awarding Authority has made changes.
- E. No certificate for payment and no progress payment shall constitute acceptance of Work that is not in accordance with the Contract Documents.

5. Periodic Payments (M.G. L. c. 30, § 39K).

The Awarding Authority shall make payment to the Contractor in accordance with M.G.L. c. 30, § 39K, which provides as follows (for the purposes of the below language, the Awarding Authority shall be considered the “awarding authority”, the Designer shall be considered the “architect” or “engineer”, the Contractor shall be considered the “contractor” and Subcontractors shall be considered “subcontractors”):

"Within fifteen days (30 days in the case of the commonwealth, including local housing authorities) after receipt from the contractor, at the place designated by the awarding

authority if such a place is so designated, of a periodic estimate requesting payment of the amount due for the preceding month, the awarding authority will make a periodic payment to the contractor for the work performed during the preceding month and for the materials not incorporated in the work but delivered and suitably stored at the site (or at some location agreed upon in writing) to which the contractor has title or to which a subcontractor has title and has authorized the contractor to transfer title to the awarding authority upon certification by the contractor that he is the lawful owner and that the materials are free from all encumbrances, but less (1) a retention based on its estimate of the fair value of its claims against the contractor and less (2) a retention for direct payments to subcontractors based on demands for same in accordance with the provisions of section thirty-nine F, and less (3) a retention not exceeding five percent of the approved amount of the periodic payment. After the receipt of a periodic estimate requesting final payment and within sixty-five days after (a) the contractor fully completes the work or substantially completes the work so that the value of the work remaining to be done is, in the estimate of the awarding authority, less than one percent of the original contract price, or (b) the contractor substantially completes the work and the awarding authority takes possession for occupancy, whichever occurs first, the awarding authority shall pay the contractor the entire balance due on the contract less (1) a retention based on its estimate of the fair value of its claims against the contractor and of the cost of completing the incomplete and unsatisfactory items of work and less (2) a retention for direct payments to subcontractors based on demands for same in accordance with the provisions of section thirty-nine F, or based on the record of payments by the contractor to the subcontractors under this contract if such record of payment indicates that the contractor has not paid subcontractors as provided in section thirty-nine F. If the awarding authority fails to make payment as herein provided, there shall be added to each such payment daily interest at the rate of three percentage points above the rediscount rate then charged by the Federal Reserve Bank of Boston commencing on the first day after said payment is due and continuing until the payment is delivered or mailed to the contractor; provided, that no interest shall be due, in any event, on the amount due on a periodic estimate for final payment until fifteen days (twenty-four days in the case of the commonwealth) after receipt of such period estimate from the contractor, at the place designated by the awarding authority if such a place is so designated. The contractor agrees to pay to each subcontractor a portion of any such interest paid in accordance with the amount due each subcontractor.

The awarding authority may make changes in any periodic estimate submitted by the contractor and the payment due on said periodic estimate shall be computed in accordance with the change so made, but such changes or any requirement for a corrected periodic estimate shall not affect the due date for the periodic payment or the date for the commencement of interest charges on the amount of the periodic payment computed in accordance with the changes made, as provided herein; provided, that the awarding authority may, within seven days after receipt, return to the contractor for correction, any periodic estimate which is not in the required form or which contains computations not arithmetically correct and, in that event, the date of receipt of such periodic estimate shall be the date of receipt of the corrected periodic estimate in proper form and with arithmetically correct computations. The date of receipt of a periodic estimate received on a Saturday shall be the first working day thereafter. The provisions of section thirty-nine G shall not apply to any contract for the construction, reconstruction, alteration, remodeling, repair or demolition of any public building to which this section applies.

All periodic estimates shall be submitted to the awarding authority, or to its designee as set forth in writing to the contractor, and the date of receipt by the awarding authority or its

designee shall be marked on the estimate. All periodic estimates shall contain a separate item for each filed subtrade and each sub-subtrade listed in sub-bid form as required by specifications and column listing the amount paid to each filed subcontractor as of the date of the periodic estimate is filed. The person making payment for the awarding authority shall add the daily interest provided for herein to each payment for each day beyond the due date of receipt marked on the estimate.

A certificate of the architect to the effect that the contractor has fully or substantially completed the work shall, subject to the provisions of section thirty-nine J, be conclusive for the purposes of this section.

Notwithstanding the provisions of this section, at any time after the value of the work remaining to be done is, in the estimation of the awarding authority, less than 1 per cent of the adjusted contract price, or the awarding authority has determined that the contractor has substantially completed the work and the awarding authority has taken possession for occupancy, the awarding authority may send to the general contractor by certified mail, return receipt requested, a complete and final list of all incomplete and unsatisfactory work items, including, for each item on the list, a good faith estimate of the fair and reasonable cost of completing such item. The general contractor shall then complete all such work items within 30 days of receipt of such list or before the contract completion date, whichever is later. If the general contractor fails to complete all incomplete and unsatisfactory work items within 45 days after receipt of such items furnished by the awarding authority or before the contract completion date, whichever is later, subsequent to an additional 14 days' written notice to the general contractor by certified mail, return receipt requested, the awarding authority may terminate the contract and complete the incomplete and unsatisfactory work items and charge the cost of same to the general contractor and such termination shall be without prejudice to any other rights or remedies the awarding authority may have under the contract. The awarding authority shall note any such termination in the evaluation form to be filed by the awarding authority pursuant to the provisions of section 44D of chapter 149."

6. Payment of Subcontractors (M.G.L. c. 30, § 39F).

The Contractor shall make payments to Subcontractors in accordance with M.G.L c.30, § 39F which is quoted in this section below. For the purposes of this Contract, the word "forthwith" appearing in paragraph (1)(a) of the quoted provision shall be deemed to mean "within five (5) business days."

"1(a) Forthwith after the general contractor receives payment on account of a periodic estimate, the general contractor shall pay to each subcontractor the amount paid for the labor performed and the materials furnished by that subcontractor, less any amount specified in any court proceedings barring such payment and also less any amount claimed due from the subcontractor by the general contractor.

(b) Not later than the sixty-fifth day after each subcontractor substantially completes his work in accordance with the plans and specifications, the entire balance due under the subcontract less amounts retained by the awarding authority as the estimated cost of completing the incomplete and unsatisfactory items of work, shall be due the subcontractor; and the awarding authority shall pay that amount to the general contractor. The general contractor shall forthwith pay to the subcontractor the full amount received from the awarding authority less any amount specified in any court proceedings barring such payment and also less any amount claimed due from the subcontractor by the general contractor.

(c) Each payment made by the awarding authority to the general contractor pursuant to subparagraphs (a) and (b) of this paragraph for the labor performed and the materials furnished by a subcontractor shall be made to the general contractor for the account of that subcontractor; and the awarding authority shall take reasonable steps to compel the general contractor to make each such payment to each such subcontractor. If the awarding authority has received a demand for direct payment from a subcontractor for any amount which has already been included in a payment to the general contractor or which is to be included in a payment to the general contractor for payment to the subcontractor as provided in subparagraphs (1) and (2) the awarding authority shall act upon the demand as provided in this section.

(d) If, within seventy days after the subcontractor has substantially completed the subcontract work, the subcontractor has not received from the general contractor the balance due under the subcontract including any amount due for extra labor and materials furnished to the general contractor, less any amount retained by the awarding authority as the estimated cost of completing the incomplete and unsatisfactory items of work, the subcontractor may demand direct payment of that balance from the awarding authority. The demand shall be by a sworn statement delivered to or sent by certified mail to the awarding authority, and a copy shall be delivered to or sent by certified mail to the general contractor at the same time. The reply shall contain a detailed breakdown of the balance due under the subcontract and also a statement of the status of completion of the subcontract work. Any demand made after substantial completion of the subcontract work shall be valid even if delivered or mailed prior to the seventieth day after the subcontractor has substantially completed the subcontract work. Within ten days after the subcontractor has delivered or so mailed the demand to the awarding authority and delivered or so mailed a copy to the general contractor, the general contractor may reply to the demand. The reply shall be by a sworn statement to or sent by certified mail to the awarding authority and a copy shall be delivered to or sent by certified mail to the subcontractor at the same time. The reply shall contain a detailed breakdown of the balance due under the subcontract including any amount due for extra labor and materials furnished to the general contractor and of the amount due for each claim made by the general contractor against the subcontractor.

(e) Within fifteen days after receipt of the demand by the awarding authority, but in no event prior to the seventieth day after substantial completion of the subcontract work, the awarding authority shall make direct payment to the subcontractor of the balance due under the subcontract including any amount due for extra labor and materials furnished to the general contractor, less any amount (i) retained by the awarding authority as the estimated cost of completing the incomplete or unsatisfactory items of work, (ii) specified in any court proceedings barring such payment, or (iii) disputed by the general contractor in the sworn reply; provided that the awarding authority shall not deduct from a direct payment any amount as provided in part (iii) if the reply is not sworn to, or for which the sworn reply does not contain the detailed breakdown required by subparagraph (d). The awarding authority shall make further direct payments to the subcontractor forthwith after the removal of the basis for deduction from direct payments made as provided in parts (i) and (ii) of this subparagraph.

(f) The awarding authority shall forthwith deposit the amount deducted from a direct payment as provided in part (iii) of subparagraph (5) in an interest-bearing joint account in the names of the general contractor and the subcontractor in a bank in Massachusetts selected by the awarding authority or agreed upon by the general contractor and the subcontractor and shall notify the general contractor and the subcontractor of the date of the deposit and the bank receiving the deposit. The bank shall pay the amount in the account,

including accrued interest, as provided in an agreement between the general contractor and the subcontractor or as determined by decree of a court of competent jurisdiction.

(g) All direct payments and all deductions from demands for direct payments deposited in an interest bearing account or accounts in a bank pursuant to subparagraph (6) shall be made out of amounts payable to the general contractor at the time of receipt of a demand for direct payment from a subcontractor and out of amounts which later become payable to the general contractor and in the order of receipt of such demands from subcontractors. All direct payments shall discharge the obligation of the awarding authority to the general contractor to the extent of such payment.

(h) The awarding authority shall deduct from payments to a general contractor amounts which, together with the deposits in interest bearing accounts pursuant to subparagraph (6) are sufficient to satisfy all unpaid balances of demands for direct payment received from subcontractors. All such amounts shall be earmarked for such direct payments, and the subcontractors shall have a right in such deductions prior to any claims against such amounts by creditors of the general contractor.

(i) If the subcontractor does not receive payment as provided in subparagraph (1) or if the general contractor does not submit a periodic estimate for the value of the labor or materials performed or furnished by the subcontractor and the subcontractor does not receive payment for same when due less the deductions provided for in subparagraph (1), the subcontractor may demand direct payment by following the procedure in subparagraph (4) and the general contractor may file a sworn reply as provided in that same subparagraph. A demand made after the first day of the month following that for which the subcontractor performed or furnished the labor and materials for which the subcontractor seeks payment shall be valid even if delivered or mailed prior to the time payment was due on a periodic estimate from the general contractor. Thereafter the awarding authority shall proceed as provided in subparagraph (e), (f), (g) and (h)."

(2) Any assignment by a subcontractor of the rights under this section to a surety company furnishing a bond under the provisions of section twenty-nine of chapter one hundred forty-nine shall be invalid. The assignment and subrogation rights of the surety to amounts included in a demand for direct payment which are in the possession of the awarding authority or which are on deposit pursuant to subparagraph (6) shall be subordinate to the rights of all subcontractors who are entitled to be paid under this section and who have not been paid in full.

(3) "subcontractor" as used in this section (I) for contracts awarded as provided in sections forty-four A to forty-four L, inclusive, of chapter one hundred forty-nine shall mean a person who files a sub-bid and received a subcontract as a result of that filed sub-bid or who is approved by the awarding authority in writing as a person performing labor or both performing labor and furnishing materials pursuant to a contract with the general contractor, (ii) for contracts awarded as provided in paragraph (1) of section thirty-nine M of chapter thirty shall mean a person approved by the awarding authority in writing as a person performing labor or both performing labor and furnishing materials pursuant to a contract with the general contractor, and (iii) for contracts with the commonwealth not awarded as provided in sections forty-four A to forty-four L, inclusive, of chapter one hundred forty-nine shall also mean a person contracting with the general contractor to supply materials used or employed in a public works project for a price in excess of five thousand dollars.

(4) A general contractor or a subcontractor shall enforce a claim to any portion of the amount of a demand for direct payment deposit as provided in subparagraph (6) by a petition in equity in the superior court against the other and the bank shall not be a necessary party. A subcontractor shall enforce a claim for direct payment or a right to require a deposit as provided in subparagraph (6) by a petition in equity in the superior court against the awarding authority and the general contractor shall not be a necessary party. Upon motion of any party the court shall advance for speedy trial any petition filed as provided in this paragraph. Sections fifty-nine and fifty-nine B of chapter two hundred thirty-one shall apply to such petitions. The court shall enter an interlocutory decree upon which execution shall issue for any part of a claim found due pursuant to sections fifty-nine and fifty-nine B and, upon motion of any party, shall advance for speedy trial the petition to collect the remainder of the claim. Any party aggrieved by such interlocutory decree shall have the right to appeal therefrom as from a final decree. The court shall not consolidate for trial the petition of any subcontractor with the petition of one or more subcontractors or the same general Contract unless the court finds that a substantial portion of the evidence of the same events during the course of construction (other than the fact that the claims sought to be consolidated arise under the same general contract) is applicable to the petitions sought to be consolidated and that such consolidation will prevent unnecessary duplication of evidence. A decree in any such proceeding shall not include interest on the disputed amount deposited in excess of the interest earned for the period of any such deposit. No person except a subcontractor filing a demand for direct payment for which no funds due the general contractor are available for direct payment shall have a right to file a petition in court of equity against the awarding authority claiming a demand for direct payment is premature and such subcontractor must file the petition before the awarding authority has made a direct payment to the subcontractor and has made a deposit of the disputed portion as provided in part (iii) of subparagraph (5) and in subparagraph (6).

(5) In any petition to collect any claim for which a subcontractor has filed a demand for direct payment the court shall, upon motion of the general contractor, reduce by the amount of any deposit of a disputed amount by the awarding authority as provided in part (iii) of subparagraph (5) and in subparagraph (6) any amount held under a trustee writ or pursuant to a restraining order or injunction.”

7. Contracts for Public Works Governed by M.G.L. c. 30, § 39G.

The following statutory provision applies only to contracts for public works governed by M.G.L. c. 30, § 39G:

"Upon substantial completion of the work required by a Contract with the Owner, or any agency or political subdivision thereof, for the construction, reconstruction, alteration, remodeling, repair or improvement of public ways, including bridges, and other highway structures, sewers and water mains, airports and other public works, the contractor shall present in writing to the awarding authority its certification that the work has been substantially completed. Within twenty-one days thereafter, the awarding authority shall present to the contractor either a written declaration that the work has been substantially completed or an itemized list of incomplete or unsatisfactory work items required by the contract sufficient to demonstrate that the work has not been substantially completed. The awarding authority may include with such a list a notice setting forth a reasonable time, which shall not in any event be prior to the contract completion date, within which the contractor must achieve substantial completion of the work. In the event that the awarding authority fails to respond, by presentation of a written declaration or itemized list as

aforesaid, to the contractor's certification within the twenty-one day period, the contractor's certification shall take effect as the awarding authority's declaration that the work has been substantially completed.

Within sixty-five days after the effective date of a declaration of a substantial completion, the awarding authority shall prepare and forthwith send to the contractor for acceptance a substantial completion estimate for the quantity and price of the work done and all but one percent retainage of that undisputed part of each work item and extra work item in dispute but excluding the disputed part thereof, less the estimated cost of completing all incomplete and unsatisfactory work items and less the total periodic payments made to date for the work. The awarding authority also shall deduct from the substantial completion estimate an amount equal to the sum of all demands for direct payments filed by subcontractors and not yet paid to subcontractors or deposited in joint accounts pursuant to section thirty-nine F, but no Contract subject to said section thirty-nine F shall contain any other provision authorizing the awarding authority to deduct any amount by virtue of claims asserted against the contract by subcontractors, material suppliers or others.

If the awarding authority fails to prepare and send to the contractor any substantial completion estimate required by this section on or before the date herein above set forth, the awarding authority shall pay to the contractor interest on the amount which would have been due to the contractor pursuant to such substantial completion estimate at the rate of three percentage points above the rediscount rate then charged by the Federal Reserve Bank of Boston from such date to the date on which the awarding authority sends that substantial completion estimate to the contractor for acceptance or to the date of payment therefor, whichever occurs first. The awarding authority shall include the amount of such interest in the substantial completion estimate.

Within fifteen days after the effective date of the declaration of substantial completion, the awarding authority shall send to the contractor by certified mail, return receipt requested, a complete list of all incomplete or unsatisfactory work items, and, unless delayed by causes beyond his control, the contractor shall complete all such work items within forty-five days after the receipt of such list or before the then contract completion date, whichever is later. If the contractor fails to complete such work within such time, the awarding authority may, subsequent to seven days' written notice to the contractor by certified mail, return receipt requested, terminate the contract and complete the incomplete or unsatisfactory work items and charge the cost of same to the contractor.

Within thirty days after receipt by the awarding authority of a notice from the contractor stating that all of the work required by the contract has been completed, the awarding authority shall prepare and forthwith send to the contractor for acceptance a final estimate for the quantity and price of the work done and all retainage on that work less all payments made to date, unless the awarding authority's inspection shows that work items required by the contract remain incomplete or unsatisfactory, or that documentation required by the contract has not been completed. If the awarding authority fails to prepare and send to the contractor the final estimate within thirty days after receipt of notice of completion, the awarding authority shall pay to the contractor interest on the amount which would have been due to the contractor pursuant to such final estimate at the rate hereinabove provided from the thirtieth day after such completion until the date on which the awarding authority sends the final estimate to the contractor for acceptance or the date of payment therefore, whichever occurs first, provided that the awarding authority's inspection shows that no work items required by the contract remain incomplete or unsatisfactory. Interest shall not be paid

hereunder on amounts for which interest is required to be paid in connection with the substantial completion estimate as hereinabove provided. The awarding authority shall include the amount of the interest required to be paid hereunder in the final estimate.

The awarding authority shall pay the amount due pursuant to any substantial completion or final estimate within thirty-five days after receipt of written acceptance for such estimate from the contractor and shall pay interest on the amount due pursuant to such estimate at the rate hereinabove provided from that thirty-fifth day to the date of payment. Within 15 days, 30 days in the case of the commonwealth, after receipt from the contractor, at the place designated by the awarding authority, if such place is designated, of a periodic estimate requesting payment of the amount due for the preceding periodic estimate period, the awarding authority shall make a periodic payment to the contractor for the work performed during the preceding periodic estimate period and for the materials not incorporated in the work but delivered and suitably stored at the Site, or at some location agreed upon in writing, to which the contractor has title or to which a subcontractor has title and authorized the contractor to transfer title to the awarding authority, upon certification by the contractor that he is the lawful owner and that the materials are free from all encumbrances. The awarding authority shall include with each such payment interest on the amount due pursuant to such periodic estimate at the rate herein above provided from the due date. In the case of periodic payments, the contracting authority may deduct from its payment a retention based on the estimate of the fair value of its claims against the contractor, a retention for direct payments to subcontractors based on demands for same in accordance with the provisions of section thirty-nine F, and a retention to secure satisfactory performance of the contractual work not exceeding five per cent of the approved amount of any periodic payment, and the same right to retention shall apply to bonded subcontractors entitled to direct payment under section thirty-nine F of chapter thirty; provided that a five per cent value of all items that are planted in the ground shall be deducted from the periodic payments until final acceptance.

No periodic, substantial completion or final estimate or acceptance or payment thereof shall bar a contractor from reserving all rights to dispute the quantity and amount of, or the failure of the awarding authority to approve a quantity and amount of, all or part of any work item or extra work item.

Substantial completion, for the purposes of this section, shall mean either that the work required by the contract has been completed except for work having a contract price of less than one percent of the then adjusted total contract price, or substantially all of the work has been completed and opened to public use except for minor incomplete or unsatisfactory work items that do not materially impair the usefulness of the work required by the contract”

8. Final Payment; Release of Claims by Contractor.

Upon Final Acceptance of the Work the Contractor shall be entitled to payment of the balance of the Contract Price. Final payment shall be as provided in this Article above and in accordance with any process set forth in the Contract Documents. The Contractor agrees to execute a Certificate of Final Inspection, Release and Acceptance in the form provided in Appendix C to these General Conditions to the Contract (with Contractor’s own exceptions listed thereon) as a condition precedent to final payment. The acceptance by the Contractor of the final payment made as aforesaid, or the execution of the “Certificate of Final Inspection, Release and Acceptance” (included in Appendix C to these General Conditions) by the Contractor, shall constitute a release of the Owner, the Awarding Authority, the Designer, and every member, officer, employee and agent of any of them, from all claims of

and liability to the Contractor for anything done or furnished for or relating to the Work, or for any act or neglect of the Owner, the Designer, or of any person relating to or affecting the Work, except the claim against the Owner or the Designer for the remainder, if any, of the amounts set forth by the Contractor in the “Certificate of Final Inspection, Release and Acceptance”. Final Acceptance shall not relieve Contractor of the requirements of Articles IX, XIV, and XV of these General Conditions, or of other provisions of this Contract, to the extent that the same are intended to survive Final Acceptance.

ARTICLE IX **GUARANTEES AND WARRANTIES**

1. General Warranty.

If at any time during the period of one (1) year from the date of the issuance of the Certificate of Substantial Completion by the Awarding Authority or the date of Final Acceptance, whichever occurs first, any part of such Work shall in the reasonable opinion of the Awarding Authority be defective or require replacing or repairing, or damage to other property of the Owner is caused by any defect in the Work, the Awarding Authority shall notify the Contractor in writing to make the required repairs or replacements and repair such damage. If the Contractor shall neglect to commence such repairs or replacements to the satisfaction to the Awarding Authority within ten (10) days from the date of the giving of such notice, then the Awarding Authority may employ other persons to make the same. The Contractor agrees, upon demand, to pay to the Awarding Authority all amounts which it expends for such repairs, replacements, and/or damages. During this one-year guarantee period, any corrective work shall be performed under all the applicable terms of this Contract,. This one-year guarantee shall not limit any express guaranty or warranty provided elsewhere in the Contract.

2. Special Guarantees and Warrantees.

- A. The Contractor's obligation to correct Work as set forth in Article IX above is in addition to, and not in substitution of, such guarantees or warranties as may be required in the various sections of the Specifications.
- B. Guarantees and warranties required in the various sections of the Specifications must be delivered to the Designer or, if directed by the Awarding Authority, to the Awarding Authority before final payment to the Contractor may be made, or in the case of guarantees and warranties which originate with a Subcontractor’s section of the Work, before final payment for the amount of that subtrade or for the phase of Work to which the guarantee or warranty relates.
- C. The failure to deliver a required guarantee or warranty shall constitute a failure to fully complete the Work in accordance with the Contract Documents.

ARTICLE X **MISCELLANEOUS LEGAL REQUIREMENTS.**

1. Contractor to be Informed.

The Contractor shall inform itself of all existing and future Laws in any manner affecting those engaged or employed in the Work, or the materials used or employed in the Work, or in a any way affecting the conduct of the Work, and of all orders and decrees of bodies or tribunals having any applicable jurisdiction or authority over the Work.

2. Compliance with all Laws.

The Contractor shall cause all persons employed in the performance of the Work to comply with, all existing and future Laws, including but not limited to those set forth below:

A. Corporate Disclosures. The Contractor, if a foreign corporation, shall comply with M.G.L. c. 181, § 3 and § 5, and M.G.L. c. 30, § 39L.

B. Workforce Certification: Certification of Compliance with Workforce Related Legal Requirements. The Contractor shall comply with the following legal requirements for any and all employees to be employed in the Project who are required to be listed in the certified payroll reports for the Project: 1) Federal Department of Homeland Security Requirements in hiring such employees including, but not limited to, the faithful completion of the Federal Department of Homeland Security Form I-9 process by the Contractor; 2) proper classification of individuals employed on the Project; 3) all Laws concerning workers' compensation insurance coverage, unemployment insurance, social security taxes, and income taxes; and 4) all Laws concerning hospitalization and medical benefits that meet the minimum requirements of the connector board established in M.G.L. c. 176Q. The Contractor shall execute a "Workforce Certification" form provided in Exhibit B to the Contract with the execution of this Contract. The Contractor shall require each Subcontractor and sub-Subcontractor working on the Project to execute and provide to Contractor such "Workforce Certification" form in the form provided in Exhibit B to the Contract with the execution of each subcontract, and Contractor shall immediately provide a copy to the Awarding Authority. The Contractor shall require each of its Subcontractors and sub-Subcontractors to execute and provide to Contractor such "Workforce Certification" form in the form provided in Exhibit B to the Contract with the execution of each subcontract, and the Contractor shall immediately provide a copy to the Awarding Authority. Contractor acknowledges that with the weekly workforce reports it must submit on a weekly basis, in the form and format required by the Awarding Authority, including, but not limited to, by electronic reporting through the requested means. Contractor and all Subcontractors must also report on gender, race/ethnicity of its workforce through the requested means, including the Awarding Authority's online workforce reporting system. Contractor and all Subcontractors on the Project are required to certify that the Form I-9 process was faithfully completed and that all other legal requirements related to its workforce referenced above were followed for all employees listed on each certified payroll report when submitted. The Contractor and all Subcontractors must: comply with the legal requirements of this section; must not knowingly use undocumented workers in connection with the performance of this Contract; pursuant to federal requirements must verify the immigration status of all workers assigned to the Contract without engaging in unlawful discrimination; and must not knowingly or recklessly alter, falsify, or accept altered or falsified documents from any such worker. Breach of any of the terms of the workforce certification legal requirements during the period of the Contract may be regarded as a material breach,

subjecting the Contractor and Subcontractors to sanctions, including but not limited to monetary penalties, withholding of payments, contract suspension or termination.

- C. Veterans and Other Preference.** In the employment of mechanics and apprentices, teamsters, chauffeurs, and laborers in the performance of Work in the Commonwealth, preference shall first be given to citizens of the Commonwealth who have been residents of the Commonwealth for at least six (6) months at the commencement of their employment and who are veterans as defined in M.G.L. c. 4, § 7(34), and who are qualified to perform the work to which the employment relates and, within such preference, preference shall be given to service-disabled veterans; and secondly, to citizens of the Commonwealth generally who have been residents of the Commonwealth for at least six (6) months at the commencement of their employment, and if they cannot be obtained in sufficient numbers, then to citizens of the United States.

The Awarding Authority encourages and monitors the participation of veteran business enterprises ("VBE") and service-disabled veteran-owned business enterprises ("SDVOBE") in its construction and design projects pursuant to Chapter 108 of the Acts of 2012 and Executive Order 565. The benchmark for combined SDVOBE and VBE participation on the Project is 3% of the Contract Price. For the Commonwealth's VBE and SDVOBE program purposes, a VBE or SDVOBE is a firm so certified directly by the Massachusetts Supplier Diversity Office ("SDO") www.mass.gov/sdo or is: 1) certified by a certifying agency that's certification is accepted by the SDO; 2) the firm has submitted its existing certification credentials directly to the SDO by submitting an application for verification of certification to the SDO; 3) the SDO has reviewed and granted the application for verification; and 4) the SDO has certified the firm as a VBE or SDVOBE for purposes of the Commonwealth's program as evidenced by a letter issued by the SDO to the firm. VBEs and SDVOBEs shall be provided opportunities to participate in the Project and Contractor shall within 30 days of Contract execution submit its "Anticipated Veteran Owned Business and Service-Disabled Veteran-Owned Business Enterprise Participation" plan to the Awarding Authority's Compliance Office. Contractor shall report on the amount of VBE and SDVOBE participation on the Project on a regular basis, in the form, format and frequency requested by the Awarding Authority, including, for DCAMM projects, through the requested means including the Awarding Authority's online compliance reporting system. The Commonwealth also encourages the participation of Portuguese Business Enterprises (PBE), Lesbian, Gay, Bisexual, and Transgender Business Enterprises (LGBTBE); and Disability-Owned Business Enterprises (DOBE) on its contracts.

- D. Prevailing Wages.** The Contractor shall comply with M.G.L. c. 149, §§ 26-27H. The prevailing wage schedule is found in Exhibit A to the "Instructions to Bidders" included in the public solicitation of bids for this Project, listing the prevailing minimum wage rates that must be paid to all workers employed in the Work. The Awarding Authority is not responsible for any errors, omissions, or misprints in said schedule. Such prevailing wage schedule shall continue to be the minimum rate wages payable to workers employed in the Work throughout the term of this Contract, subject to the exceptions provided in M.G.L. c. 149, §§ 26-27H. The Contractor shall not have any claim for extra compensation from the Owner if the actual wages paid to workers employed in the Work exceeds the rates listed on the schedule or as otherwise provided by Law. The Contractor shall cause a copy of said schedule to be kept in a conspicuous place at the Site during the term of the Contract. If reserve police officers are employed by the Contractor, they shall be paid the prevailing wage of regular police officers. (See M.G.L. c. 149, § 34B). In accordance with M. G. L. c. 149, §27 the Contractor shall obtain from the Awarding Authority annual updates to prevailing wage schedules for all public construction projects lasting longer than one year. The Contractor is required to obtain the

wage schedules from awarding authorities, and to pay no less than these rates to covered workers. The Contractor and all Subcontractors are required to anticipate such annual updated prevailing wage schedules and neither the Contractor nor any Subcontractors shall be entitled to claim additional compensation for base contract work due to updated prevailing wage schedules.

- E. Payroll Records and Statement of Compliance.** The Contractor shall comply and shall cause its Subcontractors to comply with M.G.L. c. 149, § 27B, which requires that a true and accurate record be kept of all persons employed on the Project for which the prevailing wage rates have been provided. The Contractor and all Subcontractors shall keep these records and preserve them for a period of three years from the date of completion of the Contract. Such records shall be open to inspection by any authorized representative of the Owner at any reasonable time, and as often as may be necessary. The Contractor shall, and shall cause its Subcontractors to, submit weekly certified copies of their weekly payroll records to the Awarding Authority at no additional expense to the Awarding Authority. The Awarding Authority may at all reasonable times audit such reports. DCAMM requires submission of weekly payroll reports and related information through DCAMM's online compliance reporting system. In addition, the Contractor and each Subcontractor shall furnish to the Executive Department of Labor within fifteen (15) days after completion of its portion of the Work a signed statement in the form required by the Awarding Authority.
- F. Vehicle operators.** If the Director of the Department of Labor and Workforce Development has established a schedule of wage rates to be paid to the operators of trucks, vehicles or equipment for the Work, the Contractor shall be obligated to pay such operators at least the minimum wage rate contained on such schedule. (See M.G.L. c.149, §§ 26-27H).
- G. Eight Hour Day.** The Contractor shall comply with M.G.L. c. 149, §§ 30, 34 and 34A which provide that no laborer, workman, mechanic, foreman or inspector working within the Commonwealth in the employ of the Contractor, Subcontractor or other person doing or contracting to do the whole or part of the Work shall be required or permitted to work more than eight (8) hours in any one day or more than forty-eight (48) hours in any one week, or more than six (6) days in any one week, except in cases of extraordinary emergency.
- H. Timely Payment of Wages.** The Contractor shall comply with, and shall cause its Subcontractors to comply with M.G.L. c. 149, § 148 which requires the weekly or biweekly payment of employees within six (6) days of the end of the pay period during which wages were earned if employed for five or six days of a calendar week, and within other periods of time under certain circumstances as set forth therein.
- I. Lodging, etc.** The Contractor shall comply with, and shall cause its Subcontractors to comply with, M.G.L. c. 149, § 25 which provides that every employee under this Contract shall lodge, board and trade where and with whom he elects, and neither the Contractor nor his agents or employees shall, either directly or indirectly, require as a condition of the employment of any person that the employee shall lodge, board or trade at a particular place or with a particular person.
- J. Truck Rates.** The use by the Contractor of trucks or other motor vehicles hired from either common or contract motor carriers in the course of performance of this Contract is subject to such minimum rates and charges, and rules and regulations as may from time to time be promulgated by the Department of Public Utilities of the Commonwealth of Massachusetts or other agency of the State or Federal government which may be

authorized by Law to set rates or otherwise regulate the use of such vehicles. The Contractor expressly assumes the risk of any additional expense that may arise by reason of any change in such minimum rates and charges, and rules and regulations, and shall be entitled to no additional compensation or reimbursement by reason thereof.

K. Anti-Boycott Covenant (Executive Order 130). The Contractor warrants, represents and agrees that during the time this Contract is in effect, neither it or any affiliated company, as hereafter defined, participates in or cooperates with an international boycott, as defined in Section 999(b) (3) and (4) of the Internal Revenue Code of 1954, as amended, or engages in conduct declared to be unlawful by M.G.L. c. 151E, § 2. If there shall be a breach in the warranty, representation or agreement contained in this paragraph, then without limiting such other rights as it may have the Awarding Authority shall be entitled to rescind this Contract. As used herein, an affiliated company shall be any business entity of which at least 51% of the ownership interests are directly or indirectly owned by the Contractor or by a person or persons or business entity or entities directly or indirectly owning at least 51% of the ownership interests of the Contractor; or which directly or indirectly owns at least 51% of the Ownership interests of the Contractor.

L. Contractor's Agreements with Suppliers--Anti-Boycott Provisions.

- (1) The Contractor shall not purchase or rent any materials, equipment, machinery, vehicles, or supplies for or in connection with the Work from any person or entity who does not sign, under pains and penalties of perjury, a certificate that recites: "The undersigned warrants, represents and agrees that during the time its agreement with {insert contractor's name} is in effect for materials, supplies or equipment to be used in connection with the {insert the name of the Awarding Authority} Project No. {insert project number}, neither the undersigned or any affiliated company, as hereafter defined, participates in or cooperates with an international boycott, as defined in Section 999(b)(3) and (4) of the Internal Revenue Code of 1954, as amended, or engages in conduct declared to be unlawful by M.G.L. c.151E, § 2. As used herein, an affiliated company shall be any business entity of which at least 51% of the ownership interests are directly or indirectly owned by the undersigned or by a person or persons or business entity or entities directly or indirectly owning at least 51% of the ownership interests of the undersigned; or which directly or indirectly owns at least 51% of the ownership interests of the undersigned."
- (2) The Awarding Authority shall not be obligated to pay the Contractor for the cost of any materials, supplies, or equipment purchased or rented from any individual or entity from whom the Contractor has not previously obtained and delivered to the Awarding Authority the certificate that the previous paragraph requires. The Contractor will immediately terminate its contract with any supplier who breaches the warranty, representation and agreement contained in the previous paragraph.
- (3) The Contractor shall include in the Contractor's agreement with any person or entity from whom the Contractor intends to purchase or rent any materials, equipment, machinery, vehicles or supplies for or in connection with the Work: (a) a notice that this Contract obligates the Contractor to terminate the supply contract upon discovery of such breach of the sworn certificate delivered under subparagraph (1) above and such termination shall be without liability to the Contractor or the Awarding Authority; and (b) a provision which states: "The Governor or his designee, the secretary of administration and finance, and the state auditor or his designee shall have the right at reasonable times and upon reasonable notice to examine the books,

records and other compilations of the undersigned vendor which pertain to the performance and requirements of this agreement to provide materials of any nature to the undersigned contractor in connection with State Project No. (insert project number)."

- M. Access to Contractor's Records (Executive Order 195).** The Governor of the Commonwealth or his/her designee, the secretary of administration and finance, and the state auditor or his/her designee shall have the right at reasonable times and upon reasonable notice to examine the books, records and other compilations of data of the Contractor which pertain to the performance and requirements of this Contract.
- N. Northern Ireland (M.G.L. c. 7, § 22C).** Pursuant to M.G.L. c. 7, § 22C for state agencies, state authorities, the House of Representatives or the state Senate, the Contractor certifies that it does not employ ten (10) or more employees in an office or other facility in Northern Ireland and if the Contractor employs ten (10) or more employees in an office or other facility located in Northern Ireland the Contractor certifies that it does not discriminate in employment, compensation, or the terms, conditions and privileges of employment on account of religious or political belief; and it promotes religious tolerance within the work place, and the eradication of any manifestations of religious and other illegal discrimination; and the Contractor is not engaged in the manufacture, distribution or sale of firearms, munitions, including rubber or plastic bullets, tear gas, armored vehicles or military aircraft for use or deployment in any activity in Northern Ireland.
- O. Data Security Certifications.** For all contracts involving the Contractor's access to personal information, as defined in M.G.L. c. 93H, and personal data, as defined in M.G.L. c. 66A or access to agency systems containing such information or data, the Contractor certifies under the pains and penalties of perjury that the Contractor (a) has read M.G.L. c. 93H and c. 66A and agrees to protect any and all personal information and personal data; and (b) has reviewed all of the "Enterprise Information Security Policies and Standards" published by the Executive Office for Technology Services and Security ("TSS"), or stricter standards prescribed by Owner. Notwithstanding any contractual provision to the contrary, in connection with the Contractor's performance under this Contract, for all state agencies in the Executive Department, including all offices, boards, commissions, agencies, departments, divisions, councils, bureaus, and offices, now existing and hereafter established, the Contractor shall:
- (1) obtain a copy, review, and comply with the pertinent security guidelines, standards and policies;
 - (2) comply with the "Enterprise Information Security Policies and Standards" published by TSS, or a comparable set of policies and standards ("Information Security Policy") as prescribed by the Owner;
 - (3) communicate and enforce such security guidelines, standards, policies and the applicable Information Security Policy among all employees (whether such employees are direct or contracted) and Subcontractors;
 - (4) implement and maintain any other reasonable appropriate security procedures and practices necessary to protect personal information and data to which the Contractor is given access by the Awarding Authority from the unauthorized access, destruction, use, modification, disclosure or loss;
 - (5) be responsible for the full or partial breach of any of these terms by its employees (whether such employees are direct or contracted) or Subcontractors during or after

the term of this Contract, and any breach of these terms may be regarded as a material breach of this Contract;

- (6) in the event of any unauthorized access, destruction, use, modification, disclosure or loss of the personal information or personal data (collectively referred to as the "unauthorized use"): (a) immediately notify the Awarding Authority if the Contractor becomes aware of the unauthorized use; (b) provide full cooperation and access to information necessary for the Awarding Authority to determine the scope of the unauthorized use; and (c) provide full cooperation and access to information necessary for the Awarding Authority and the Contractor to fulfill any notification requirements.

Breach of these terms may be regarded as a material breach of this Contract, such that the Commonwealth may exercise any and all contractual rights and remedies, including without limitation indemnification, withholding of payments, Contract suspension, or termination. In addition, the Contractor may be subject to applicable statutory or regulatory penalties, including and without limitation, those imposed pursuant to M.G.L. c. 93H and under M.G.L. c. 214, § 3B for violations under M.G.L. c. 66A.

ARTICLE XI

CONTRACTOR'S ACCOUNTING METHOD REQUIREMENTS

(M.G.L. c. 30, § 39R)

1. Definitions.

The words defined herein shall have the meaning stated below whenever they appear in this Article XI:

"Independent Certified Public Account" means a person duly registered in good standing and entitled to practice as a certified public accountant under the Laws of the place of his/her residence or principal office and who is in fact independent. In determining whether an accountant is independent with respect to a particular person, appropriate consideration should be given to all relationships between the accountant and that person or any affiliate thereof. Determination of an accountant's independence shall not be confined to the relationships existing in connection with the filing of reports with the Awarding Authority.

"Records" means books of original entry, accounts, checks, bank statements and all other banking documents, correspondence, memoranda, invoices, computer printouts, tapes, discs, papers and other documents or transcribed information of any type, whether expressed in ordinary or machine language.

"Audit", when used in regard to financial statements, means an examination of records by an independent certified public accountant in accordance with generally accepted accounting principles and auditing standards for the purpose of expressing a certified opinion thereon, or, in the alternative, a qualified opinion or a declination to express an opinion for stated reasons or other person or persons primarily responsible for the financial and operational policies and practices of the Contractor.

Accounting terms, unless otherwise defined herein, shall have a meaning in accordance with generally accepted accounting principles and auditing standards.

2. Record Keeping.

- A.** The Contractor shall make, and keep for at least six (6) years after final payment, books, records, and accounts that in reasonable detail accurately and fairly reflect the transactions and dispositions of the Contractor.
- B.** Until the expiration of six (6) years after final payment, the Inspector General, DCAMM, and the Awarding Authority shall have the right to examine any books, documents, papers or records of the Contractor and Subcontractors that directly pertain to, and involve transactions relating to the Contractor and Subcontractors.
- C.** The Contractor shall describe any change in the method of maintaining records or recording transactions which materially affects any statements filed with the Awarding Authority including the date of the change and reasons therefor, and shall accompany said description with a letter from the Contractor's independent certified public accountant approving or otherwise commenting on the changes.
- D.** The Contractor represents that it has, prior to the execution of the Contract, filed a statement of management on internal accounting controls as set forth in Article XI.3 below.
- E.** The Contractor represents that it has, prior to the execution of the Contract, filed an audited financial statement for the most recent completed fiscal year as set forth in Article XI.4 below and will continue to file such statement annually during the term of the Contract.

3. Statement of Management Controls.

- A.** The Contractor shall file with the Awarding Authority a statement of management as to whether the system of internal accounting controls of the Contractor and its subsidiaries reasonably assures that:
 - (1) transactions are executed in accordance with management's general and specific authorization;
 - (2) transactions are recorded as necessary to: (a) to permit preparation of financial statements in conformity with generally accepted accounting principles, and (b) to maintain accountability for assets;
 - (3) access to assets is permitted only in accordance with management's general or specific authorization; and
 - (4) the recorded accountability for assets is compared with the existing assets at reasonable intervals and appropriate action was taken with respect to any difference.
- B.** The Contractor shall file with the Awarding Authority a statement prepared and signed by an independent certified public accountant, stating that the accountant has examined the statement of management on internal accounting controls, and expressing an opinion as to:
 - (1) whether the representations of management in response to Article XI.3 above are consistent with the results of management's evaluation of the system of internal accounting controls; and
 - (2) whether such representations of management are reasonable with respect to transactions and assets in amounts which would be material when measured in relation to the applicant's financial statement.

4. Annual Financial Statement.

- A. The Contractor shall annually file with DCAMM during the term of the Contract a financial statement prepared by an independent certified public accountant based on an audit by such accountant. The final statement filed shall include the date of final payment. All statements shall be accompanied by an accountant's report.
- B. The office of Inspector General and DCAMM shall have the right to enforce the provisions of this Article. A Contractor's failure to satisfy any of the requirements of this section may be grounds for debarment pursuant to M.G.L. c. 149, § 44C.

5. Bid Pricing Materials.

The Contractor shall save the written calculations, pricing information, and other data that the Contractor used to calculate the bid that induced the Awarding Authority to enter into this Contract (the "Bid Pricing Materials") for at least six (6) years after the Awarding Authority makes final payment under this Contract.

ARTICLE XII
**EQUAL EMPLOYMENT OPPORTUNITY, NON-DISCRIMINATION
AND AFFIRMATIVE ACTION PROGRAM.**
[EXECUTIVE ORDERS 524 & 565] (See Appendix A)

This Contract includes the provisions of the Awarding Authority's "Equal Employment Opportunity, Non-Discrimination, and Affirmative Action Program" attached as Appendix A to these General Conditions and incorporated herein by reference.

ARTICLE XIII
**GOALS FOR PARTICIPATION BY MINORITY BUSINESS
ENTERPRISES AND WOMEN BUSINESS ENTERPRISES**
[M.G.L. c. 7C, § 6 & EXECUTIVE ORDERS 524 & 565]

This Contract includes the provisions of the Awarding Authority's program relating to "Goals for Participation by Minority Business Enterprises and Women Business Enterprises" attached as Appendix B to these General Conditions and incorporated herein by reference.

ARTICLE XIV
INSURANCE REQUIREMENTS

1. Insurance Generally.

- A. The Contractor shall purchase and maintain insurance of the type and limits listed in this Article with respect to the operations as well as the completed operations of this Contract. This insurance shall be provided at the Contractor's expense and shall be in full force and effect for the full term of the Contract or for such longer period as this Article requires.
- B. All policies shall be written on an occurrence basis and be issued by companies lawfully authorized to write that type of insurance under the laws of the Commonwealth with a financial strength rating of "A-" or better as assigned by AM Best Company, or an equivalent rating assigned by a similar rating agency acceptable to the Awarding Authority, or otherwise acceptable to the Awarding Authority.
- C. Contractor shall submit each certificate of insurance, acceptable to the Awarding Authority, simultaneously with the execution of this Contract. Certificates shall show each type of insurance, insurance company, policy number, amount of insurance, deductibles and/or

self-insured retentions, and policy effective and expiration dates. Certificates shall show the Awarding Authority, the Owner and anyone else the Awarding Authority requests as an additional insured as to all policies of liability insurance. Certificates shall specifically note the following:

- (1) that the general liability policy includes contractual liability.
- (2) that the general liability policy includes the Owner and Awarding Authority as additional insureds for ongoing operations (CG 20 10) and for completed operations (CG 37 10) or equivalent endorsements.
- (3) that the automobile liability, umbrella liability and pollution liability policies include the Owner and Awarding Authority as an additional insured;
- (4) that the general liability policy includes endorsement CG 24 04 or equivalents, a waiver of subrogation in favor of the Owner and Awarding Authority.
- (5) that the builders' risk or installation floater is on an all risk basis including earthquake and flood, and includes the Awarding Authority, Owner, Contractor, Subcontractors and suppliers of any tier as a named insured or loss payee as their interests may appear; and
- (6) that none of the coverages shall be cancelled, terminated, or materially modified unless and until thirty (30) days prior notice is given in writing to the Awarding Authority.

Contractor shall submit updated certificates prior to the expiration of any of the policies referenced in the certificates so that the Awarding Authority shall at all times possess certificates indicating current coverage.

- D.** The Contractor shall file one certified complete copy of all policies and endorsements with the Awarding Authority within sixty (60) days after Contract award. If the Awarding Authority is damaged by the Contractor's failure to maintain such insurance and to comply with the terms of this Article, then the Contractor shall be responsible for all costs and damages to the Awarding Authority attributable thereto.
- E.** Termination, cancellation, or material modification of any insurance required by this Contract, whether by the insurer or the insured, shall not be valid unless written notice thereof is given to the Awarding Authority at least thirty(30) days prior to the effective date thereof, which shall be expressed in said notice.
- F.** The Contractor is responsible for the payment of any and all deductibles under all of the insurance required below. The Awarding Authority shall not in any instance be responsible for the payment of deductibles, self-insured retentions, or any portion thereof.

2. Contractor's Commercial General Liability.

- A.** The Contractor shall purchase and maintain general liability coverage on the ISO form CG 00 01 or equivalent, including products and completed operations, on an occurrence basis. The form must be amended to state that the aggregate limit applies on a per location/project basis. The policy shall provide the following minimum coverage to protect the Contractor from claims with respect to the operations performed by Contractor and any employee, Subcontractor, or supplier, or by anyone for whose acts they may be liable unless a higher coverage is specified in Exhibit A to the Contract, in which case the Contractor shall provide the additional coverage:

Bodily Injury &	\$1,000,000 each occurrence
Property Damage	\$2,000,000 general aggregate per project
Products & Completed Operations	\$1,000,000 annual aggregate
Personal & Advertising Injury	\$1,000,000 each occurrence
Medical Expenses	\$10,000

- B. This policy shall include coverage relating to explosion, collapse, and underground property damage.
- C. This policy shall include contractual liability coverage.
- D. The completed operations coverage shall be maintained for a period of three (3) years after Substantial Completion and acceptance by the Awarding Authority. The Contractor shall provide renewal certificates of insurance to the Awarding Authority as evidence that this coverage is being maintained.
- E. If the Work includes work to be performed within 50 feet of a railroad, any exclusion for liability assumed under contract for work within 50 feet of a railroad shall be deleted.
- F. This policy shall include the Awarding Authority, the Owner and anyone else requested by the Awarding Authority as an additional insured via endorsements CG 20 10 for ongoing operations and CG 20 37 for completed operations. This policy shall be primary and non-contributory with respect to any other insurance available to additional insureds.
- G. The policy shall include endorsement CG 24 04, a waiver of subrogation in favor of the Awarding Authority and Owner.

3. Automobile Liability.

- A. The Contractor shall purchase and maintain the following minimum coverage with respect to the operations of any owned, non-owned, and hired vehicles including trailers used in the performance of the work, unless a higher coverage is specified in Exhibit A to the Contract, in which case the Contractor shall provide the additional coverage:

Bodily Injury & Property Damage	\$1,000,000 combined single limit
---------------------------------	-----------------------------------

- B. The policy shall include a CA 99 48 Broadened Pollution Endorsement. If specified in Exhibit A to the Contract, the Contractor, if hauling contaminants and/or pollutants, must adhere to Sections 29 and 30 of the Motor Carrier Act of 1980, which shall include coverage Form MCS-90.
- C. The policy shall name the Awarding Authority and Owner as additional insureds.
- D. The policy shall contain a waiver of subrogation in favor of the Awarding Authority and Owner.

4. Contractor's Pollution Liability.

The Contractor shall purchase and maintain coverage for bodily injury and property damage resulting from liability arising out of pollution related exposures such as asbestos abatement, lead paint abatement, tank removal, removal of contaminated soil, etc. The insurance policy shall cover the liability of the Contractor during the process of removal, storage, transport and disposal of hazardous waste and contaminated soil and/or asbestos abatement. The policy shall include coverage for on-Site and off-Site bodily injury and loss of, damage to, or loss of use of

property, directly or indirectly arising out of the discharge, dispersal, release or escape of smoke, vapors, soot, fumes, acids, alkalis, toxic chemicals, liquids or gas, waste materials or other irritants, contaminants or pollutants into or upon the land, the atmosphere or any water course or body of water, whether it be gradual or sudden and accidental. The policy shall also include defense and clean-up costs. The Awarding Authority and Owner shall be named as an additional insureds and coverage must be on an occurrence basis. The amount of coverage shall be as follows unless a higher amount is specified in Exhibit A to the Contract, in which case the Contractor shall provide the additional coverage:

Limit of liability	\$1,000,000 per occurrence
	\$3,000,000 aggregate

5. Worker's Compensation.

A. The Contractor shall provide the following coverage in accordance with M.G.L. c.149, § 34A and c. 152, as amended, unless a higher coverage is specified in Exhibit A to the Contract, in which case the Contractor shall provide the higher coverage:

Worker's Compensation	Statutory limits
Employer's Liability	\$ 500,000 each accident
	\$ 500,000 disease per employee
	\$ 500,000 disease policy aggregate

B. If specified in Exhibit A to the Contract the policy must be endorsed to cover United States Longshoremen & Harborworkers Act (USLHW), Maritime Liability for \$1,000,000/\$1,000,000 or Federal Employer’s Liability Act liability.

C. The policy shall contain a waiver of subrogation in favor of the Awarding Authority and Owner.

6. Builder's Risk/ Installation Floater/Stored Materials.

A. The Contractor shall purchase and maintain coverage against loss or damage on all Work included in this Contract in an amount equal to the Contract Price. Such coverage shall be written on an all risks basis or equivalent form and shall include, without limitation, insurance against perils of fire (with extended coverage) and physical loss or damage including, without duplication of coverage, theft, vandalism, malicious mischief, terrorism (“certified” and “non-certified”), collapse, earthquake, flood (if the project is not in an "A" or a "V" flood zone), windstorm, falsework, testing and startup, temporary buildings and debris removal including demolition occasioned by enforcement of any applicable legal requirements, and shall cover reasonable compensation for Designer’s and Contractor's services and expenses required as a result of such insured loss. Unless otherwise specified in this Contract, the limits for earthquake and flood shall be the lesser of the Contract Price or \$10,000,000. This policy and/or installation floater shall include transportation and stored materials coverage in an amount equal to the value of the stored materials as required in Article XIV.6.C. below.

B. When Work will be completed on existing buildings owned by the Owner, the Contractor shall provide an installation floater, in the full amount of the Contract Price. Such coverage shall be written on an all risks basis or equivalent form and shall include, without limitation, insurance against perils of fire (with extended coverage) and physical loss or

damage including, without duplication of coverage, theft, vandalism, malicious mischief, collapse, earthquake, flood (if the project is not in an "A" or a "V" flood zone), windstorm, falsework, testing and startup, temporary buildings and debris removal including demolition occasioned by enforcement of any applicable legal requirements, and shall cover reasonable compensation for Designer's and Contractor's services and expenses required as a result of such insured loss. Unless otherwise specified in this Contract, the limits for earthquake and flood shall be the lesser of the Contract Price or \$10,000,000. This policy and/or installation floater shall include transportation and Stored Materials coverage in an amount equal to the value of the stored materials as required in Article XIV.6.C. below.

- C. The Contractor shall maintain insurance on delivered and/or stored material designated to be incorporated in the Work against fire, theft or other hazards. Any loss or damage of whatever nature to such material while stored at an off -Site location shall be forthwith replaced by the Contractor at no expense to the Awarding Authority.
- D. The policy or policies shall specifically state that they are for the benefit of and payable to the Awarding Authority, the Owner, the Contractor, Subcontractors, and all persons furnishing labor or labor and materials for the Work, as their interests may appear. The policy or policies shall list the Awarding Authority, the Owner, the Contractor, and Subcontractors of any tier as named insureds.
- E. Coverage shall include any costs for work performed by the Designer or any consultant as the result of a loss experienced during the term of this Contract.
- F. Coverage shall include permission for temporary occupancy and a waiver of subrogation in favor of the Awarding Authority and Owner
- G. Coverage shall be maintained until Final Acceptance by the Awarding Authority and Owner of the Contract and final payment has been made.
- H. A loss under the property insurance shall be adjusted by the Contractor as fiduciary and made payable to the Contractor as fiduciary for the insureds. The Contractor shall pay the Subcontractors their just shares of insurance proceeds received by the Contractor and shall require Subcontractors to make payments to their sub-Subcontractors in similar manner.

7. Umbrella Coverage.

The Contractor shall provide umbrella coverage in a form at least as broad as primary coverages required by subparagraphs 2, 3 and 5 of this Article in the following amount unless a higher amount is specified in Exhibit A to the Contract, in which case the Contractor shall provide the higher amount:

<u>Contract Price:</u>	<u>Limit of Liability:</u>
Under \$1,000,000	\$2,000,000 per occurrence
\$1,000,001 -- \$5,000,000	\$5,000,000 per occurrence
\$5,000,001-- \$10,000,000	\$10,000,000 per occurrence
\$10,000,001 and over	\$25,000,000 per occurrence

8. Additional Types of Insurance.

The Contractor shall provide such other types of insurance as may be required by Exhibit A to the Contract.

ARTICLE XV
INDEMNIFICATION

1. Generally.

To the fullest extent permitted by law, the Contractor shall indemnify, defend (with counsel appointed as a Special Assistant Attorney General and subject to the supervision of the Attorney General of the Commonwealth of Massachusetts as required by M.G.L. c. 12, § 3) and hold harmless the Owner, Awarding Authority and Designer and their officers, agents, divisions, agencies, employees, representatives, successors and assigns from and against all claims, damages, losses and expenses, including but not limited to court costs and attorneys' fees, arising out of or resulting from the performance of the Work, including but not limited to those arising or resulting from: labor performed or furnished and/or materials used or employed in the performance of the Work; violations by Contractor, any Subcontractor, or by any person directly or indirectly employed or used by any of them in the performance of the Work (including, without limitation, suppliers) or anyone for whose acts any of them may be liable (Contractor, Subcontractor and all such persons herein collectively called "Contractor's Personnel") of any Laws; violations of any provision of this Contract by any of Contractor's Personnel; injuries to any persons or damage to any property in connection with the Work; any act, omission, or neglect of Contractor's Personnel.

The Contractor shall be obligated as provided above, regardless of whether or not such claims, damages, losses and/or expenses, are caused in whole or in part by the actions or inactions of a party indemnified hereunder. In any and all claims by Contractor's Personnel against parties indemnified hereunder, the Contractor's indemnification obligation set forth above shall not be limited in any way by any limitation on the amount or type of damages, compensation or benefits payable by or for the Contractor or any Subcontractor under workers' or workmen's compensation acts, disability benefit acts or other employee benefit acts. Such obligation shall not be construed to negate, abridge, or otherwise reduce any other right or obligation of indemnity which would otherwise exist as to any party or person described in this Article XV.

2. Designer's Actions.

The obligations of the Contractor under Section 1 above shall not extend to the liability of the Designer, its agents or employees, arising out of (i) the preparation or approval of maps, Drawings, opinions, reports, surveys Change Orders, designs, or Specifications, or (ii) the giving of or the failure to give directions or instructions by the Designer, its agents or employees provided such giving or failure to give is the primary cause of the injury or damage.

3. Survival.

The provisions of this Article XV are intended to survive Final Acceptance and/or any termination of this Contract.

ARTICLE XVI
PERFORMANCE AND PAYMENT BONDS

1. Contractor Bonds.

- A.** The Contractor shall provide performance and payment (labor and materials) bonds in the form provided by the Awarding Authority, executed by a surety licensed by the Commonwealth of Massachusetts Division of Insurance and whose name appears on United States Treasury Department Circular 570. Each such bond shall be in the amount of the Contract Price.
- B.** If at any time prior to final payment to the Contractor, the Contractor's surety:
- (1) is adjudged bankrupt or has made a general assignment for the benefit of its creditors;
 - (2) has liquidated all assets and/or has made a general assignment for the benefit of its creditors;
 - (3) is placed in receivership;
 - (4) otherwise petitions a state or federal court for protection from its creditors; or
 - (5) allows its license to do business in Massachusetts to lapse or be revoked;
- then the Contractor shall, within twenty-one (21) days of any such action listed above, provide the Awarding Authority with new performance and payment bonds as described in Article XVI.1.A above. Such bonds shall be provided solely at the Contractor's expense.

2. Subcontractor Bonds.

- A.** If the Contractor provided in its General Bid that any or all filed Subcontractors shall provide the Contractor with payment and performance bonds for the full amount of their respective Subcontracts, then the costs for said bonds shall be the responsibility of the Contractor. Irrespective of whether the Contractor requests payment and performance bonds from their respective Subcontractors, the Contractor understands that if the Subcontractor defaults or is terminated, the Contractor shall have full responsibility for all costs and expenses related to said default or termination.
- B.** If the Contractor provided in its General Bid that filed Subcontractors shall provide bonds, and subsequently waives the requirement, the Contractor shall give the Awarding Authority a written certification that the Contractor understands that if the filed Subcontractor defaults or is terminated, the Contractor shall have full responsibility for all costs and expenses related to said default or termination and the Awarding Authority shall be entitled to a credit adjustment to the Contract Price in an amount equal to the bond premium Contractor would have paid had Contractor required the filed Subcontractor to provide such bonds. The Awarding Authority may, at its election, either issue a credit Change Order, withhold such amount from any payments due the Contractor and/or receive a payment from the Contractor for such amount.

ARTICLE XVII
TERMINATION OF CONTRACT

1. Termination for Cause.

- A.** The Awarding Authority may without prejudice to any other right or remedy deem this Contract terminated for cause if any of the following defaults shall occur and not be cured within three (3) days after the giving of notice thereof by the Awarding Authority to the Contractor and any surety that has given bonds in connection with this Contract:
- (1) The Contractor has filed a petition, or a petition has been filed against the Contractor with its consent, under any federal or state law concerning bankruptcy, reorganization, insolvency or relief from creditors, or if such a petition is filed against the Contractor without its consent and is not dismissed within sixty (60) days; or if the Contractor is generally not paying its debts as they become due; or if the Contractor becomes insolvent; or if the Contractor consents to the appointment of a receiver, trustee, liquidate, custodian or the like of the Contractor or of all or any substantial portion of its assets and such appointment or possession is not terminated within sixty (60) days; or if the Contractor makes an assignment for the benefit of creditors;
 - (2) The Contractor refuses or fails, except in cases for which extension of time is provided under this Contract's express terms, to supply enough properly skilled workers or proper materials to perform its obligations under this Contract, or the Awarding Authority as determined that the rate of progress required for the timely completion of the Work is not being met;
 - (3) The Contractor fails to make prompt payment to Subcontractors or for materials, equipment, or labor;
 - (4) All or a part of the Work has been abandoned;
 - (5) The Contractor has sublet or assigned all or any portion of the Work, the Contract, or claims thereunder, without the prior written consent of the Owner, except as expressly permitted in this Contract;
 - (6) The Contractor has failed to comply with Laws;
 - (7) The Contractor fails to maintain or provide to the Awarding Authority evidence of the insurance or bonds required by this Contract, or
 - (8) The Contractor has failed to prosecute the Work or any portion thereof as required under this Contract or has otherwise breached any material provision of this Contract.
- B.** The Awarding Authority shall give the Contractor and any surety notice of such termination for cause, but the giving of notice of such termination shall not be a condition precedent or subsequent to the termination's effectiveness. In the event of such termination, and without limiting any other available remedies, the Awarding Authority may, at its option:
- (1) hold the Contractor and its sureties liable in damages for a breach of Contract;
 - (2) notify the Contractor to discontinue all work, or any part thereof, and the Contractor shall discontinue all work, or any part thereof, as the Owner may designate;
 - (3) complete the Work, or any part thereof, and charge the expense of completing the Work or part thereof, to the Contractor;
 - (4) require the surety or sureties to complete the Work and perform all of the Contractor's obligations under this Contract;

- (5) take such other lawful action as is deemed by the Awarding Authority to be in the best interest of the Owner.

If the Awarding Authority elects to complete all or any portion of the Work as specified in Article XVII.1.B.(3) above, it may take possession of all materials, equipment, tools, machinery, implements at or near the Site owned by the Contractor and finish the Work at the Contractor's expense by whatever means the Awarding Authority may deem expedient; and the Contractor shall cooperate at its expense in the orderly transfer of the same to a new contractor or to the Awarding Authority as directed by the Awarding Authority. In such case, the Awarding Authority shall not make any further payments to the Contractor until the Work is completely finished. The Owner shall not be liable for any depreciation, loss or damage to said materials, machinery, implements or tools during said use and the Contractor shall be solely responsible for their removal from the Site after the Owner has no further use for them. Unless so removed within fifteen days after notice to the Contractor to do so, they may be sold at public auction, after publication of notice thereof at least twice in any newspaper published in the county where the Work is being performed, and the proceeds credited to the Contractor's account; or they may, at the option of the Awarding Authority, be stored at the Contractor's expense subject to a lien for the storage charges.

- C. Damages and expenses incurred under Article XVII.1.B above shall include, but not be limited to, costs for the Designer's extra services required, in the opinion of the Awarding Authority, to successfully inspect and administer the construction contract through Final Acceptance of the Work.
- D. Expenses charged under Article XVII.1.B above may be deducted and paid by the Awarding Authority out of any moneys then due or to become due the Contractor under this Contract.
- E. All sums damages, and expenses incurred by the Owner to complete the Work shall be charged to the Contractor. In case the damages and expenses charged are less than the sum that would have been payable under this Contract if the same had been completed by the Contractor, the Contractor shall be entitled to receive the difference. In case such expenses shall exceed the said sum, the Contractor shall pay the amount of the excess to the Owner.

2. Termination For Convenience.

- A. The Awarding Authority may terminate this Contract for convenience even though the Contractor is not in default by giving notice to the Contractor specifying in said notice the date of termination.
- B. In case of such termination without cause, the Contractor shall be paid:
 - (1) all sums due and owing under this Contract through the date of termination, including any retainage withheld to the date of termination, less any amount which the Awarding Authority determines is necessary to correct or complete the Work performed to the date of termination; plus
 - (2) a reasonable sum to cover the expenses which Contractor would not have incurred but for the early termination of the Contract, such as demobilization of the work force, restocking charges, termination fees payable to Subcontractors.
- C. Lost profits shall not be payable. The payment provided in Article XVII.2.B above shall be considered to fully compensate the Contractor for all claims and expenses and those of

any consultants, Subcontractors, and suppliers, directly or indirectly attributable to the termination.

3. Contractor's Duties Upon Termination For Convenience.

Upon termination of this Contract for convenience as provided above in Article XVII.2, the Contractor shall: (1) stop the Work; (2) stop placing orders and subcontracts in connection with this Contract; (3) cancel all existing orders and subcontracts; (4) surrender the Site to the Awarding Authority in a safe condition; (5) transfer to the Awarding Authority all materials, supplies, work in process, appliances, facilities, equipment and machinery of this Contract, and all plans, Drawings, Specifications and other information and documents used in connection with this Contract.

ARTICLE XVIII **MISCELLANEOUS PROVISIONS**

1. No Assignment by Contractor.

The Contractor shall not assign by power of attorney or otherwise, or sublet or subcontract, the Work or any part thereof, without the previous written consent of the Awarding Authority and shall not, either legally or equitably, assign any of the moneys payable under this Contract, or Contractor's claims hereunder, unless with the like consent of the Awarding Authority, whether said assignment is made before, at the time of, or after the execution of the Contract. The Contractor shall remain responsible for satisfactory performance of all Work sublet or assigned. Consent of the Awarding Authority shall not be deemed to constitute a representation or waiver of any right hereunder by the Awarding Authority as to the qualifications or the responsibility of the Contractor or Subcontractor(s).

2. Non-Appropriation.

The Awarding Authority certifies that at the time of the execution of this Contract, sufficient appropriations exist and shall be encumbered to fund the Contract Price. Payments are subject to appropriation and shall be made only for work performed in accordance with the terms of this Contract. The Contractor shall not be obligated to perform and shall not perform work outside the scope of this Contract without an appropriate amendment to this Contract, and a sufficient appropriation(s) to support such additional work. The Awarding Authority may immediately terminate or suspend this Contract in the event that the appropriation(s) funding this Contract is eliminated or reduced to an amount which will be insufficient to support anticipated future obligations under this Contract. Such termination shall be deemed a termination for convenience subject to the provisions of Article XVII.2 of these General Conditions.

3. Claims by Others Not Valid.

No person other than the Contractor shall acquire any interest in this Contract or claim against the Awarding Authority or Owner hereunder, and no claim by any other person shall be valid except as provided in M.G.L. c. 30, § 39F.

4. No Personal Liability of Public Officials.

No public official, employee, or agent of the Awarding Authority or Owner shall have any personal liability for the obligations of the Awarding Authority or Owner set forth in this Contract.

5. Severability.

The provisions of this Contract are severable, and if any of these provisions shall be held unconstitutional or unenforceable by any court of competent jurisdiction, the decision of such court shall not affect or impair any of the other provisions of this Contract.

6. Choice of Laws.

This Contract shall be governed by the Laws of the Commonwealth of Massachusetts for all purposes, without regard to its Laws on choice of law. All proceedings under this Contract or related to the Project shall be brought in the courts of the Commonwealth of Massachusetts.

7. Standard Forms.

Unless directed otherwise in writing by the Awarding Authority, Contractor shall use the standard forms in use by Awarding Authority appearing in Appendix C to these General Conditions.

8. No Waiver of Subsequent Breach.

No waiver of any breach or obligation of this Contract shall constitute a waiver of any other or subsequent breach or obligation.

9. Remedies Cumulative.

All remedies of the Awarding Authority provided in this Contract shall be construed as cumulative and may be exercised simultaneously or in any order as determined by the Awarding Authority in its sole discretion. The Awarding Authority shall also be entitled as of right to specific performance and equitable relief including the right to an injunction against any breach of any of the provisions of this Contract.

10. Notices.

Notices to the Contractor shall be deemed given when hand delivered to the Contractor's temporary field office at or near the Site, or when deposited in the U.S. mail addressed to the Contractor at the Contractor's address specified in the Contract, or when delivered by courier to either location. Unless otherwise specified in writing by the Awarding Authority, notices and deliveries to the Awarding Authority shall be effective only when delivered to the Awarding Authority at the address specified in the Contract and date-stamped at the reception desk or for which a receipt has been signed by the agent or employee designated by the Awarding Authority to receive official notices.

11. Additional Information.

Recognizing that the Awarding Authority may find it necessary during the progress of the Work to establish the current status of performance under the Contract Documents, the Contractor shall, without limitation of any other requirements of the Contract Documents, promptly provide upon request statements, documents, or information to the Awarding Authority or others regarding the status of the Work, compliance of the Work with the Contract Documents, compliance by the Contractor or any Subcontractor with the Contract Documents, the names of Subcontractors or suppliers, amounts due or to become due, amounts previously paid to Subcontractors or suppliers, estimates of the portion of the Work completed and the cost of completing the Work, and such other matters within the scope of the Contractor's performance under the Contract Documents as the Awarding Authority may reasonably require.

12. Information Confidential.

Except as required for the discharge of its duties to the Awarding Authority under this Contract, or required by subpoena or court order, the Contractor and any of its Subcontractors agree to hold all information, documents, and materials obtained or developed in connection with its performance under this Contract (including, without limitation, all prints, plans, policies, procedures, studies, specifications and drawings, which relate to internal layout and structural elements, electrical and mechanical systems, security measures, emergency preparedness, threat or vulnerability assessments, and any other records relating to the security or safety of persons or buildings, structures, facilities, utilities, transportation or other infrastructure located within the Commonwealth) that the Contractor and any of its Subcontractors should reasonably know to be of a confidential or sensitive nature ("Confidential Information") in the strictest confidence, and shall not communicate, release, or disclose Confidential Information in any to any third party without the prior written Approval by the Awarding Authority. The Contractor shall not use any Confidential Information other than for the performance of the Work under this Contract. The Contractor shall inform all persons to whom any such Confidential Information has been or will be communicated, released, or disclosed of the privileged and confidential nature of Confidential Information, and shall ensure that all necessary steps are taken so that such Confidential Information is treated confidentially. Without limiting the foregoing, if the Project is a designated "Security Sensitive Information" project, the Contractor shall execute separate "Security Sensitive Information Procedures" and confidentiality agreements and shall comply with such document protection requirements as may be referenced in said agreement.

13. Consequential Damages.

In no event shall DCAMM be liable to the Contractor except for obligations expressly assumed by the Awarding Authority or the Designer under the Contract Documents, nor shall the Awarding Authority ever be liable to the CM for indirect, special or consequential damages.

14. Conflict of Interest.

The Contractor shall familiarize its employees assigned to perform services under this Contract with the provisions of M.G.L. c. 268A (the Massachusetts conflict-of-interest statute). The Contractor that the CM is an "interested party" for purposes of the aforementioned statute. Accordingly, if the Awarding Authority is a "state agency" for

purposes of the aforementioned statute, the Contractor and its employees and agents shall not offer or provide any employee of the Awarding Authority any gift, gratuity, favor, meal, entertainment, loan or other item of monetary value. The Contractor warrants and represents that it currently has no interest and shall not acquire any interest, direct or indirect, which would be adverse to or conflict in any manner with the performance of its services under this Contract or with the interest of the Awarding Authority or the Project. The Contractor further agrees that in the performance of this Contract no person or entity having any such adverse or conflicting interest shall be employed or granted a Subcontract. Except with the Awarding Authority's knowledge and express consent, the Contractor shall not engage in any activity, or accept any employment, interest or contribution that would reasonably appear to be adverse to the interests of the Awarding Authority or to compromise the Contractor's professional judgment with respect to the Project. The Contractor has a continuing obligation to divulge to the Awarding Authority all circumstances of its relationships with third parties, as well as any other interests that may have an effect on the Awarding Authority or the Project at the time of execution of this Contract or during its effectiveness. If the Awarding Authority believes that there is or has been a conflict of interest, or the appearance of a conflict of interest, it will so notify the Contractor. The Contractor shall make full disclosure of all material facts, and shall have a period of thirty (30) days after receipt of such notice to cure the conflict of interest or the appearance of conflict of interest, including the right to request a meeting with the Awarding Authority to explain its position. If the conflict of interest or appearance of conflict of interest is not cured to the satisfaction of the Awarding Authority or the controversy otherwise resolved prior to expiration of such thirty (30) days period, the Contractor shall be deemed to be in default of this Contract and the Awarding Authority may exercise any remedies available to it under this Contract or applicable law.

15. Sexual Harassment and Workplace Violence Prevention.

The Contractor shall promote a workplace that is free from sexual harassment and workplace violence, and to require all of its subcontractors to agree to the same. The Commonwealth does not tolerate sexual harassment, workplace violence, or a hostile work environment. It is the goal of the Commonwealth of Massachusetts to promote a workplace where people treat each other with dignity and respect. This applies to all Commonwealth employees, consultants, contractors and subcontractors regardless of tier, and covers actions within, by, among, and across these groups as they interact with each other. Without limiting its other rights and remedies of removal and/or termination, the Awarding Authority reserves the right to remove or terminate individuals and/or contractors whose conduct violates any of the provisions of this paragraph.

**END OF GENERAL CONDITIONS
APPENDICES APPEAR ON THE FOLLOWING PAGES**

APPENDIX A to General Conditions of the Contract

The following provisions form Article XII of the General Conditions of the Contract where DCAMM is the Awarding Authority.

EQUAL EMPLOYMENT OPPORTUNITY, NON-DISCRIMINATION AND AFFIRMATIVE ACTION PROGRAM.

1. Compliance Generally.

For purpose of this Article, "minority" refers to Asians, Blacks, Western Hemisphere Hispanics, Native Americans, and Cape Verdeans; "Commission" refers to the Massachusetts Commission Against Discrimination. During the performance of this Contract, the Contractor and all of its Subcontractors (hereinafter collectively referred to as the Contractor) shall comply with all applicable equal employment opportunity, non-discrimination and affirmative action requirements, including but not limited to the following:

2. Non-Discrimination and Affirmative Action.

A. The Contractor shall not discriminate against any employee or applicant for employment because of race, color, religious creed, national origin, ancestry, sex, gender identity, sexual orientation, age, handicap, mental illness, genetic information or active military duty. The aforesaid provision shall include, but not be limited to, the following: employment upgrading, demotion or transfer; recruitment advertising; recruitment layoff; termination; rates of pay or other forms of compensation; conditions or privileges of employment; and selection for apprenticeship. The Contractor shall comply with the provisions of M.G.L. c.151B and all other applicable anti-discrimination and equal opportunity laws.

B. The Contractor shall comply with the provisions of Executive Order 526, entitled Order Regarding Nondiscrimination, Diversity, Equal Opportunity and Affirmative Action, which prohibits unlawful discrimination based on race, color, age, gender, ethnicity, sexual orientation, gender identity or expression, religion, creed, ancestry, national origin, disability, veteran's status (including Vietnam-era veterans), or background. Executive Order 526 is herein incorporated by reference and made a part of this Contract.

Pursuant to Executive Order 526 the Contractor and any subcontractors may not engage in discriminatory employment practices; and the Contractor must certify that it is in compliance with all applicable federal and state laws, rules, and regulations governing fair labor and employment practices; and commit to purchasing supplies and services from certified minority or women-owned businesses, small businesses, or businesses owned by socially or economically disadvantaged persons or persons with disabilities. These provisions shall be enforced through the contracting agency, the Operational Services Division, and/or the Massachusetts Commission Against Discrimination. Any breach shall be regarded as a material breach of Contract that may subject Contractor to appropriate sanctions.

C. In connection with the performance of the Work, the Contractor shall undertake in good faith affirmative action measures designed to eliminate any discriminatory barriers in the terms and conditions of employment on the grounds of race, color, religious creed, national origin, age, sexual orientation, or sex, and to eliminate and remedy any effects of such discrimination in the past. Such affirmative action shall entail positive and aggressive measures to ensure equal opportunity in the areas of hiring, upgrading, demotion or transfer, recruitment, layoff or termination, rate of compensation, and in-service or apprenticeship training programs. This affirmative action shall include all action required to guarantee equal employment opportunity for all persons, regardless of race, color, religious creed, national origin, age, sexual orientation, or sex. A purpose of this provision is to ensure to the fullest

extent possible an adequate supply of skilled tradesmen for future public construction projects.

D. If the Contractor shall use any subcontractor on any work performed under this Contract, the Contractor shall take affirmative steps to negotiate with qualified minority and women subcontractors. These affirmative steps shall cover both pre-bid and post-bid periods. It shall include notification to the State Office of Minority and Women Business Assistance or its designee, while bids are in preparation, of all products, work or services for which the Contractor intends to negotiate bids. In all solicitations either by competitive bidding or negotiation made by the Contractor either for work to be performed under a subcontract or for the procurement of materials or equipment, each potential subcontractor or supplier shall be notified in writing by the Contractor of the Contractor's obligations under this Contract relative to non-discrimination and affirmative action.

E. As part of its obligation of remedial action under this Article, the Contractor shall maintain on this project not less than the percent ratio set forth in the Owner - Contractor Agreement of minority employee worker hours to total worker hours in each job category including but not limited to bricklayers, carpenters, cement masons, electricians, ironworkers, operating engineers, and those "classes of work" enumerated in M.G. L. c. 149, s. 44F.

G. In the hiring of minority journeypersons, apprentices, trainees and advanced trainees, the Contractor shall rely on referrals from a multi-employer affirmative action program approved by the Commission, traditional referral methods utilized by the construction industry, and referrals from agencies, not more than three in number at any one time, designated by the Liaison Committee or the Awarding Authority.

3. Liaison Committee, Reports and Records.

A. At the option of the Awarding Authority, there may be established for the term of this Contract a body to be known as the Liaison Committee. The Liaison Committee shall be composed of one representative each from the Awarding Authority, the Commission and such other representatives as may be designated by the Commission in conjunction with the Awarding Authority. The Contractor (or his agent, if any, designated by him as the on-Site equal employment opportunity officer) shall recognize the Liaison Committee as an affirmative action body, and shall establish a continuing working relationship with the Liaison Committee, consulting with the Liaison Committee on all matters related to minority recruitment, referral, employment and training.

B. The Contractor shall prepare projected staffing tables on a quarterly basis. These shall be broken down into projections, by week, of workers required in each trade. Copies shall be furnished one week in advance of the commencement of the period covered, and also when updated, to the Awarding Authority and Liaison Committee. The Contractor shall prepare weekly reports in a form approved by the Awarding Authority of hours worked in each trade by each employee, identified as minority or non-minority. Copies of these shall be provided at the end of each such week to the Awarding Authority and to the Liaison Committee.

C. Records of employment referral orders, prepared by the Contractor, shall be made available to the Awarding Authority and to the Liaison Committee on request.

D. A designee of the Awarding Authority and a designee of the Liaison Committee shall each have right to access to the Site.

E. The Contractor shall comply with the provisions of M.G.L. c. 151B as amended, of the Massachusetts General Laws, both of which are herein incorporated by reference and made a part of this Contract.

F. The Contractor shall provide all information and reports required by the Awarding Authority or the Commission on forms and in accordance with instructions issued by either

of them and will permit access to its facilities and any books, records, accounts and other sources of information which may be determined by the Awarding Authority or the Commission to affect the employment of personnel. This provision shall apply only to information pertinent to the Owner's supplementary affirmative action Contract requirements. Where information required is in the exclusive possession of another who fails or refuses to furnish this information, the Contractor shall so certify to the Awarding Authority or the Commission as appropriate and shall set forth what efforts he has made to obtain the information.

4. Sanctions.

A. Whenever the Awarding Authority, the Commission, or the Liaison Committee believes the Contractor or any Subcontractor may not be operating in compliance with the terms of this Article, the Commission shall directly, or through its designated agent, conduct an appropriate investigation, and may confer with the parties, to determine if such Contractor is operating in compliance with the terms of this Article. If the Commission or its agent finds the Contractor or any Subcontractor not in compliance, it may make a preliminary report on non-compliance, and notify such Contractor in writing of such steps as will in the judgment of the Commission or its agent bring such Contractor into compliance. In the event that such Contractor fails or refuses to fully perform such steps, the Commission **may** make a final report of non-compliance, and recommend to the Awarding Authority the imposition of one or more of the sanctions listed below. If, however, the Commission believes the Contractor or any Subcontractor has taken or is taking every possible measure to achieve compliance, it shall not make a final report of non-compliance. Within fourteen days of the receipt of the recommendations of the Commission, the Awarding Authority shall move to impose one or more of the following sanctions, as it may deem appropriate to attain full and effective enforcement:

- (1) The recovery by the Awarding Authority from the Contractor of 1/100 of 1% of the Contract award price or \$1,000 whichever sum is greater, in the nature of liquidated damages or, if a Subcontractor is in non-compliance, the recovery by the Awarding Authority from the Contractor, to be assessed by the Contractor as a back charge against the subcontractor, of 1/10 of 1% of the sub-Contract Price, or \$400 whichever sum is greater, in the nature of liquidated damages, for each week that such party fails or refuses to comply;
- (2) The suspension of any payment or part thereof due under the Contract until such time as the Contractor or any subcontractor is able to demonstrate his compliance with the terms of the Contract;
- (3) The termination or cancellation of the Contract, in whole, or in part, unless the Contractor or any Subcontractor is able to demonstrate within a specified time his compliance with the terms of the contract;
- (4) The denial to the Contractor or any subcontractor of the right to participate in any future contracts awarded by the Awarding Authority for a period of up to three years.

B. If at any time after the imposition of one or more of the above sanctions a Contractor is able to demonstrate that it is in compliance with this Article, the Contractor may request the Awarding Authority, in consultation with the Commission, to suspend the sanctions conditionally, pending a final determination by the Commission as to whether the Contractor is in compliance. Upon final determination of the Commission, the Awarding Authority, based on the recommendation of the Commission, shall either lift the sanctions or reimpose them.

C. Sanctions recommended by the Commission and enumerated under Section 4 above shall not be imposed by the Awarding Authority except after an adjudicatory proceeding, as that term is used M.G.L. c. 30A, has been conducted. No investigation by the Commission

or its agent shall be initiated without prior notice to the Contractor. **D.** Notwithstanding the provisions of 4A-4C above, if the Awarding Authority determines after investigation that the Contractor or any Subcontractor is not in compliance with the terms of this Article, it may suspend any payment or portion thereof due under the Contract until the contractor demonstrates to the satisfaction of the Awarding Authority compliance with the terms of this Article. This temporary suspension of payments by the Awarding Authority is separate from the sanctions set forth in Section 4A-4C of this Article above, which are determined by MCAD and recommend to the Awarding Authority. Payment may be suspended only after the Contractor and any other interested party shall have been given the opportunity to present evidence in support of its position at an informal hearing held by the Awarding Authority, and the Awarding Authority has concluded upon review of all the evidence that such penalty is justified. Payment shall not be suspended if the Awarding Authority finds that the Contractor made its best efforts to comply with this Article, or that some other justifiable reason exists for waiving the provisions of this Article in whole or in part.

END OF APPENDIX A

APPENDIX B to General Conditions of the Contract

The following provisions form Article XIII of the General Conditions of the Contract where DCAMM is the Awarding Authority.

GOALS FOR PARTICIPATION BY MINORITY BUSINESS ENTERPRISES AND WOMEN BUSINESS ENTERPRISES (M.G.L. c. 7C, § 6 and EXECUTIVE ORDERS 526 & 565)

1. Goals.

A. The goals for minority business enterprise and woman business enterprise participation established for this Contract are as set forth in the Owner - Contractor Agreement.

B. The Contractor and all Subcontractors, sub-subcontractors, and materials suppliers shall comply with all of the terms and conditions of this Article, which include the provisions pertaining to MBE/WBE participation set forth in the Owner - Contractor Agreement in order to meet the MBE/WBE participation goals established for this Contract.

2. MBE/WBE Participation Credit.

A. If the Contractor is itself an MBE or WBE, MBE or WBE participation credit shall be given in an amount equal to the entire Contract Price less the value of the work actually performed by other MBE or WBE firms on the Contract. If the Contractor is not an MBE or WBE, then MBE/WBE participation credit will be given for the value of the Work that is actually performed by each MBE or WBE subcontractor or sub-subcontractor.

B. If the Contractor is a joint venture with one or more MBE/WBE joint venturers, MBE/WBE participation credit shall be given to the joint venture as follows:

(1) If the joint venture is certified by the Massachusetts Supplier Diversity Office (SDO) as an MBE or WBE, MBE/WBE participation credit shall be given in an amount equal to the entire Contract Price.

(2) If the joint venture is not certified as an MBE or WBE by the SDO, MBE/WBE participation credit shall be given to the joint venture for the value of the Work that is performed by the MBE/WBE joint venturer(s), and for the value of the Work that is actually performed by each MBE or WBE subcontractor or sub-subcontractor.

C. If an MBE/WBE supplies but does not install equipment or materials, MBE/WBE participation credit shall be given only if the MBE/WBE supplier is regularly engaged in sales of equipment or supplies to the construction industry from an established place of business. MBE/WBE participation credit shall be given the full amount of the purchase order only if the MBE/WBE supplier manufactures the goods or substantially alters them before resale. In all other cases, MBE/WBE participation credit shall be given for 15% of the purchase order.

D. MBE participation credit shall be given for the work performed by MBEs only, and WBE participation credit shall be given for the work performed by WBEs only. MBE participation may not be substituted for WBE participation, nor may WBE participation be substituted for MBE participation.

3. Establishing MBE/WBE Status.

A. A minority owned business shall be considered an MBE only if it has been certified as a minority business enterprise by the Supplier Diversity Office (“SDO”).

B. A woman owned business shall be considered a WBE only if it has been certified as a woman business enterprise by SDO.

C. Certification as a disadvantaged business enterprise (“DBE”), certification as an MBE/WBE by any agency other than SDO, or submission of an application to SDO for certification as an MBE/WBE shall not confer MBE/WBE status on a firm for the purposes of this Contract. Please note that only firms SDO certified as MBE or WBEs can be credited toward meeting project MBE or WBE goals.

4. Subcontracts With MBE/WBEs.

Within thirty (30) days after the award of this Contract, the Contractor shall (i) execute a subcontract with each MBE/WBE Subcontractor which has executed a Letter of Intent Approved by the Awarding Authority, (ii) cause its Subcontractors to execute a sub-subcontract with each MBE/WBE sub-subcontractor they committed to utilize, and (iii) furnish the Awarding Authority with a signed copy of each such subcontract and sub-subcontract through DCAMM's Online Compliance Reporting System.

5. Performance of Contract Work by MBE/WBEs.

A. The Contractor shall not perform with its own organization, or subcontract or assign to any other firm, work designated to be performed by any MBE/WBE in the Letters of Intent or Schedule for MBE/WBE Participation without the prior written Approval of the Awarding Authority, nor shall any MBE/WBE assign or subcontract to any other firm, or permit any other firm to perform any of its MBE/WBE Work without the prior written Approval of the Awarding Authority. Any such unapproved assignment, subcontracting, sub-subcontracting, or performances of MBE/WBE Work by others shall be a change in the MBE/WBE Work for the purposes of this Contract. The Awarding Authority WILL NOT APPLY TO THE MBE OR WBE PARTICIPATION GOAL(S) ANY SUMS ATTRIBUTABLE TO SUCH UNAPPROVED ASSIGNMENTS, SUB-CONTRACTS, SUB-SUBCONTRACTS, OR PERFORMANCE OF MBE/WBE WORK BY OTHERS.

B. The Contractor shall be responsible for monitoring the performance of MBE/WBE Work to ensure that each scheduled MBE/WBE performs its own MBE/WBE Work with its own workforce.

C. The Contractor and each MBE/WBE shall provide the Awarding Authority with all information and documentation that the Awarding Authority determines is necessary to ascertain whether or not an MBE/WBE has performed its own MBE/WBE Work. At the discretion of the Awarding Authority, failure to submit such documentation to the Awarding Authority shall establish conclusively for the purpose of giving MBE/WBE participation credit under this Contract that such MBE/WBE did not perform such work.

6. Notification of Changes in MBE/WBE Work.

A. If at any time during the performance of the Contract the Contractor determines or has reason to believe that a scheduled MBE/WBE is unable or unwilling to perform its MBE/WBE Work, or that there has been or will be a change in any MBE/WBE Work, or that the Contractor will be unable to meet the MBE/WBE participation goal(s) for this Contract for any reason, the Contractor shall immediately notify the Awarding Authority Contract Compliance Office in writing of such circumstances.

B. Any notice of a change in MBE/WBE Work pursuant to subparagraph “A” above shall include a revised Schedule for MBE/WBE Participation, and additional or amended Letters of Intent and subcontracts, as the case may be.

7. Actions Required If There is a Reduction in MBE/WBE Participation.

A. In the event there is a change or reduction in any MBE/WBE Work which will result in the Contractor failing to meet the MBE/WBE participation goal(s) for this Contract, other than a reduction in MBE/WBE Work resulting from a Change Order initiated by the Awarding Authority, then the Contractor shall immediately undertake a diligent, good faith effort to make up the shortfall in MBE/WBE participation as follows:

(1) The Contractor shall identify all items of the Work remaining to be performed under the Contract that may be made available for subcontracting to MBE/WBEs. The Contractor shall send a list of such items of work to the Awarding Authority, together with a list of the remaining items of the Work that were not made available to MBE/WBEs and the reason for not making such work available for subcontracting to MBE/WBEs.

(2) The Contractor shall send written notices soliciting proposals to perform the items of the Work that may be made available for subcontracting to MBE/WBEs to all MBE/WBEs qualified to perform such work. The Contractor shall advise the Awarding Authority of (i) each MBE/WBE solicited, and (ii) each MBE/WBE listed in the SDO directory under the applicable trade category who was not solicited and the reasons therefor. The Contractor shall also advise the Awarding Authority of the dates notices were mailed and provide a copy of the written notice(s) sent.

(3) The Contractor shall make reasonable efforts to follow up the written notices sent to MBE/WBEs with telephone calls or personal visits in order to determine with certainty whether the MBE/WBEs were interested in performing the work. Phone logs or other documentation must be submitted to the Awarding Authority evidencing this effort.

(4) The Contractor shall make reasonable efforts to assist MBE/WBEs that need assistance in obtaining insurance, bonds, or lines of credit in order to perform work under the Contract, and shall provide the Awarding Authority with evidence that such efforts were made.

(5) The Contractor shall provide the Awarding Authority with a statement of the response received from each MBE/WBE solicited, including the reason for rejecting any MBE/WBE who submitted a proposal, if applicable.

(6) The Contractor shall take any additional measures reasonably requested by the Awarding Authority to meet the MBE/WBE participation goal(s) established for this Contract, including, without limitation, placing advertisements in appropriate media and trade association publications announcing the Contractor's interest in obtaining proposals from MBE/WBEs, and/or sending written notification to MBE/WBE economic development assistance agencies, trade groups and other organizations notifying them of the project and of the work available to be subcontracted by the Contractor to MBE/WBEs.

B. If the Contractor is unable to meet the MBE/WBE participation goals for this Contract after complying fully with each of the requirements of paragraph “A” above, and the Contractor is otherwise in full compliance with the terms of this Article, the Awarding Authority may reduce the MBE/WBE participation goals for this Contract to the extent that such goals cannot be achieved.

8. Suspension of Payment and/or Performance for Noncompliance.

A. If at any time during the performance of this Contract, the Awarding Authority determines or has reason to believe that (1) there has been a change or reduction in any MBE/WBE Work which will result in the Contractor failing to meet the MBE/WBE

participation goal(s) for this Contract, other than a reduction in MBE/WBE Work resulting from a change in the Contract work ordered by the Awarding Authority, and (2) the Contractor has failed to comply fully with all of the terms and conditions of paragraphs 1 through 7 above, the Awarding Authority may:

(1) suspend payment to the Contractor of an amount up to the full value of the work which was to have been performed by an MBE/WBE pursuant to the Contractor's Schedule for MBE/WBE Participation but which was not so performed, in order to ensure that sufficient Contract funds will be available if liquidated damages are assessed pursuant to paragraph 9, and/or

(2) suspend the Contractor's performance of this Contract in whole or in part.

B. The Awarding Authority shall give the Contractor prompt written notice of any action taken pursuant to paragraph A above and shall give the Contractor and any other interested party, including any MBE/WBEs, an opportunity to present evidence to the Awarding Authority that the Contractor is in compliance with the requirements of this Article, or that there is some justifiable reason for waiving the requirements of this Article in whole or in part. The Awarding Authority may invite SDO and the Massachusetts Commission Against Discrimination to participate in any proceedings undertaken pursuant to this paragraph.

C. Upon a showing that the Contractor is in full compliance with the requirements of this Article, or that the Contractor has met or will meet the MBE/WBE participation goals for this Contract, the Awarding Authority shall release any funds withheld pursuant to clause A(1) above, and lift any suspension of the Contractor's performance under clause A(2) above.

9. Liquidated Damages; Termination.

A. If payment by the Awarding Authority or performance by the Contractor is suspended by the Awarding Authority as provided in paragraph 8 above, the Awarding Authority shall have the following rights and remedies if the Contractor thereafter fails to take all action necessary to bring the Contractor into full compliance with the requirements of this Article, or if full compliance is no longer possible because the default of the Contractor is no longer susceptible to cure, if the Contractor fails to take such other action as may be required by the Awarding Authority to meet the MBE/WBE participation goals set forth in this Contract:

(1) the Awarding Authority may terminate this Contract, and/or

(2) the Awarding Authority may retain from final payment to the Contractor, as liquidated damages, an amount equal to the difference between (x) the total of the MBE/WBE participation goals set forth in this Contract, and (y) the amount of MBE/WBE participation credit given to the Contractor for MBE/WBE Work performed under this Contract as determined by the Awarding Authority, the parties agreeing that the damages for failure to meet the M/BE/WBE participation goals are difficult to determine and that the foregoing amount to be retained by the Awarding Authority represents the parties' best estimate of such damages. Any liquidated damages will be assessed separately for MBE and WBE participation.

B. Before exercising its rights and remedies hereunder, the Awarding Authority may, but the Awarding Authority shall not be obligated to, give the Contractor and any other interested party another opportunity to present evidence to the Awarding Authority that

the Contractor is in compliance with the requirements of this Article or that there is some justifiable reason for waiving the requirements of this Article in whole or in part. The Awarding Authority may invite SDO and the Massachusetts Commission Against Discrimination to participate in any proceedings undertaken hereunder.

10. Reporting Requirements.

The Contractor shall submit to the Awarding Authority all information or documentation that is necessary in the judgment of the Awarding Authority to ascertain whether or not the Contractor has complied with any of the provisions of this Article.

11. Awarding Authority's Right to Waive Provisions of this Article in Whole or In Part.

The Awarding Authority reserves the right to waive any provision or requirement of this Article if the Awarding Authority determines that such waiver is justified and in the public interest. No such waiver shall be effective unless in writing and signed by a representative of the Awarding Authority's Compliance Office or the Office of its General Counsel. No other action or inaction by the Awarding Authority shall be construed as a waiver of any provision of this Article.

END OF APPENDIX B

APPENDIX C to the General Conditions of the Contract

INDEX OF REQUIRED CONTRACT ADMINISTRATION FORMS

(Forms used during bidding are located in Attachment B to the Instructions to Bidders)

- ~~Form of Subcontract MGL c.149 §44F~~
- ~~Procedure for Payment to Contractors~~
- ~~Payment Voucher Input~~
- ~~Requisition for Payment (DCAMM Form S1b) and Instructions~~
- ~~Instructions and Procedures Regarding Change Orders, Contract Modifications and Equitable Adjustments (DCAMM Form 13)~~
- ~~Request for Approval of Wages and Rates for Change Order Pricing (DCAMM Form 14)~~
- ~~Format for Submission of Change Order (DCAMM Form 15) (3 pages)~~
- ~~Change Order Log (1 Page)~~
- ~~Daily Time and Material Report for Change Orders 10/17 rev~~
- ~~Request and Agreement for a Change in the Plans~~
- ~~Request and Agreement For Change In the Plans And/Or Specifications and/or Contract (DCAMM Form 5)~~
- ~~Weekly Payroll Report Form and Statement of Compliance~~
- ~~Quarterly Projected Workforce Table~~
- ~~Veteran and Service Disabled Veteran Owned Business Enterprise~~
- ~~(VBE/SDVOBE) Participation~~
- ~~Form for Transfer of Title (Work Not Incorporated, DCAMM Form 16)~~
- ~~Payroll & Workforce Report~~
- ~~Payment Requisition Transmittal (3 pages)-~~
- ~~Submittal Transmittal (1 page)-~~
- ~~Submittal Log~~
- ~~Request for Information Transmittal (1 page)~~
- ~~Request for Information Log~~
- ~~Weekly Site Meeting Template (1 Page)~~
- ~~Certificate of Substantial Completion (E-1)~~
- ~~Certificate of Final Inspection, Release and Acceptance (E-2)~~
- ~~Certificate of Payment MBE, WBE, Veteran, Etc.~~
- ~~Certificate of Payment to Subcontractors, Sub-bidders, suppliers~~

END OF APPENDIX C

DCAMM General Conditions of the Contract c. 149 Rev. 06/2020
DMH Revised 8/24/2021

THE COMMONWEALTH OF MASSACHUSETTS
EXECUTIVE OFFICE FOR ADMINISTRATION AND FINANCE
DIVISION OF CAPITAL ASSET MANAGEMENT
ONE ASHBURTON PLACE, 15th Floor
BOSTON, MASSACHUSETTS 02108

**INSTRUCTIONS AND PROCEDURES REGARDING CHANGE ORDERS, CONTRACT
MODIFICATIONS AND EQUITABLE ADJUSTMENTS**

SECTION 1. STATUTORY AND CONTRACTUAL PROVISIONS

1.01 These procedures and instructions (hereinafter "Procedures") supplement Article VII of DCAMM's General Conditions of the Contract. These Procedures and Article VII are to be considered together and are intended to be mutually complementary, so that all terms are to be considered as part of this Contract. All provisions are intended to be consistent with the Massachusetts Laws governing Change Orders and Equitable Adjustments. Those laws include, but are not limited to: M.G.L. Chapter 7C, Sections 17-21; M.G.L. Chapter 30, Sections 39I, 39J, 39N, 39O, 39P, and 39Q. All parties must keep themselves informed of these laws and any amendments affecting said statutes.

NO CHANGES (ADDITIONS, SUBSTITUTIONS OR ELIMINATIONS) IN THE PLANS, SPECIFICATIONS OR CONTRACT SHALL BE COMMENCED UNTIL RECEIPT BY THE CONTRACTOR OF: (a) AN APPROVED DCAMM FORM 5 (Gold Sheet Change Order) OR (b) a WRITTEN DIRECTIVE from the DCAMM PROJECT MANAGER AUTHORIZING or DIRECTING such CHANGE. A Directive issued by the Deputy Commissioner, Director, or Deputy Director shall carry the same force as though issued by the Project Manager.

1.02 The purpose of these instructions and procedures is to provide additional detail for calculating equitable adjustments and outlining the change order submission process. The Contractor must provide satisfactory documentation supporting the nature and cost of each change, for an informed decision to be made on whether or not the change order is necessary, justified and priced properly. All parties that utilize the POTENTIAL CHANGE ORDER PROCESS explained in section 3 below, as well as maintain a POTENTIAL CHANGE ORDER LOG.

1.03 All requests for changes modifying the contract price must be submitted on DCAMM Form 5, prior to the final acceptance of the project. The Contractor waives all rights against the Commonwealth if it fails to comply with this requirement. DCAMM shall be under no obligation to process a request for change after final acceptance of the project.

1.04 The term "request for change" is used throughout these procedures and applies to every request to revise the contract requirements. The request for change must be made in writing, and in accordance with the provisions of the Contract, the General laws, rules, regulations and other procedures of DCAMM.

1.05 If the request for a change is deemed a Life Safety Issue by DCAMM, or if waiting for a formal change order approval will cause damage or increase the cost of the Work, the DCAMM Project Manager may deem the change "Urgent" and issue an email to the Contractor, Deputy Director, Designer, Resident Engineer and any other parties that are involved in the potential change. The email will outline the scope of work, a Not to Exceed dollar value, and a deadline for the paperwork to be submitted to substantiate the cost and completion of the work. The Contractor will add this "Urgent" Potential Change Order to the Log with a status of URGENT and proceed with the work in accordance with the email. If the costs to complete the "Urgent" work are expected to exceed the stated Not to Exceed value, then the Contractor shall advise the DCAMM Project Manager of the anticipated extra costs as soon as known, and shall await further written direction from DCAMM before proceeding with work above the Not to Exceed value.

1.06 Prior to any change order work being performed, the DCAMM Project Manager must have all quotes, estimates and potential costs identified to determine if the change order work should be performed as a lump sum cost to the project, or if the nature of the change is difficult to quantify, then it may be determined to perform the work on a Time and Material basis.

SECTION 2. DIRECTIONS FOR COMPUTING COSTS FOR CHANGES IN THE WORK

2.01 Construction Managers, General Contractors, Subcontractors, Sub-tier Subcontractors and service providers must submit for approval the DCAMM Wage Rate Form (Form 14) at the time their contract is awarded and prior to any change order work being started. DCAMM has changed the calculation for establishing **LABOR BILLING RATES**. Billing rates are calculated by taking the job specific **published** Prevailing Wage Rate for each trade classification and multiplying it by 1.40. Union Contractors may submit their collective bargaining agreement if there are excess fringe expenses over the published prevailing wage rate. These excess fringes will be applied with no mark-ups. The attached forms (as noted in Article VII) will automatically calculate rates as described. That rate calculation establishes the **LABOR BILLING RATE** for the project by trade and classification. If a contractor or subcontractor submits documentation from their insurance company that identifies their Workmen's Compensation rate is greater than 12.5% then the multiplier of 1.40 will be adjusted to include the percentage over 12.5%. For example, an Iron Worker's Workmen's compensation percentage is 14.5%; the calculation for that Trade's **LABOR BILLING RATE** would become 1.42 rather than 1.40. In the case of Premium Time, Time and Half, or Double Time DCAMM will accept a multiplier of 1.40 on the premium portion of wages over the approved prevailing wage rate only. These **LABOR BILLING RATES** are inclusive of overhead, profit, and all other expenses incurred. No additional markups on labor are allowed. If a credit is due to the project a percentage of 85% of the approved labor billing rate is to be credited to the project. The **LABOR BILLING RATES** will be established for each trade and classification at the beginning of the project. If there are any disputes regarding the **LABOR BILLING RATES** they must be resolved prior to change order work being started.

2.02 Equipment Schedules and associated rates must be submitted at the beginning of the project for any contractor that anticipates renting or using equipment as part of their scope of work for approval of desired rates to be used on change orders. If the contractor cannot provide an equipment schedule, including established rates, DCAMM has elected to use *R.S. Means* to determine fair market value rates. When computing the cost of equipment the rate resulting in the lowest value (daily, weekly, monthly) is to be used. The Contractor can add 15% for overhead and profit mark up to the equipment rental cost as part of the final change order pricing. The allowance for overhead and profit shall be considered to include all additional expenses associated with hand and power tools normally required in the performance of the base bid work, "tools of the trade".

2.03 Back up for material costs is required and shall be a formal quote from the supplier providing the materials or an agreed upon industry standard determined at the beginning of the project, for example, NECA, MCCA, or Harrison. The Contractor may add 15% overhead and profit mark up to the material cost as part of the final change order pricing.

2.04 Miscellaneous Items and Services such as Police or Fire details, utility charges, and attic stock charges must be identified and estimated as part of the initial change request and back up for the cost is required. For any change that does not include labor performed, Equipment used, or materials installed in the project that results in a net increase in the contract price is considered a miscellaneous item or service. Shipping, handling and fuel surcharges must be estimated prior to orders being placed. Expedited shipping costs must be approved before an order is placed, otherwise normal shipping cost will be paid. The Contractor may add 5% for overhead and profit mark up to Miscellaneous Items and Services as part of the final change order pricing.

2.05 For changes that involve work performed by Subcontractors the Prime Contractor may add 5% markup on all subcontracted work. Subcontractors also shall be permitted to add 5% markup on all work subcontracted to Sub-tier subcontractors. Any work self-performed by either the Prime Contractor or Subcontractor is not subject to the additional 5% markup.

2.06 Travel expenses are only paid in accordance with Union Agreements or documented costs and no additional overhead and profit will be allowed on these costs. Travel will only be paid when requested on changes that result in additional time subject to the approval of the Project Manager on a case by case basis.

2.07 The General Contractor, Construction Manager, or Sub Contractor's (if applicable) bond premium shall be included at the following rates. If a Contractor's bond rate differs from this list verification from the bond carrier must be submitted showing the actual rates prior to any change order work starting on the Project.

	Contract Price	Rates per Thousand
(a)	Contracts up to \$500,000.....	\$14.40
(b)	\$500,000 to \$2,500,000.....	\$ 8.70
(c)	\$2,500,000 to \$5,000,000.....	\$ 6.90
(d)	\$5,000,000 to \$7,500,000.....	\$ 6.30
(e)	\$7,500,000 and up.....	\$ 5.76

2.08 Changes which involve Time and Material slips must have DCAMM Daily Time and Material Reports attached, verified, and signed by the Resident Engineer or authorized representative beginning on the day the work commences, and continuing every day work occurs thereafter until the work is complete. Timesheets verifying labor hours and classification
 Form 13 – Instructions regarding change orders and contract modifications (rev. 10/2017)

and invoices verifying actual material cost from vendors are required when submitting the change to substantiate all costs being billed. Costs without back up will be deducted and not reimbursed.

2.09 The Project Manager may approve lump sum change order requests on changes costing \$2,000 or less, without requiring the Contractor to provide a detailed breakdown for the costs incurred on the change order. A basic level breakdown of Labor, material, and equipment on the contractors letterhead is still required.

SECTION 3. PROCESSING CHANGE REQUESTS AND EQUITABLE ADJUSTMENTS

3.01 Article VII of the Contract outlines the notification requirements for any potential change order. Time is of the essence with every potential change order and all parties, Contractors, Subcontractors, User Agency Representatives, Architect/Designer and DCAMM project team members are obligated by the Contract to expedite processing of these potential changes in an efficient and timely manner. The Prime Contractor must maintain a Potential Change Order (PCO) log for the entire project. A sample PCO log is included in the Contract Documents. The PCO log will be reviewed at each weekly Owner Meeting and have status changes updated in writing on a weekly basis.

3.02 If a request for a change has been identified, then the Prime Contractor must create a draft request for equitable adjustment referred to as a Change Order Request (COR) from their own project management system for review by the Architect/Designer and the DCAMM project team. The draft COR shall include requests for equitable adjustment from affected subcontractors, if any. The Prime Contractor's COR form must be approved in writing by the DCAMM project team prior to the first COR submission, otherwise the DCAMM Form 15 shall be used.

Each COR shall be for a specific scope of work and it shall be identified as an extra service with an explanation of reasons the change is not included in the base scope of work, such as; change in plans and specifications or other scope as outlined in Article VII. The Prime contractor shall also review each COR in accordance with Article VII of the Contract General Conditions. A COR may include multiple subcontractors for one scope of work, however all of their back up, including quotes, estimates and labor estimates must be attached to the COR for review. Having more than one COR for the same scope of work because subcontractors are late in submitting is not recommended, however there are times it is necessary. If a time extension to the contract is part of the change request, a critical path schedule from the Prime Contractor must be included in the COR. DCAMM requires all project schedules to be submitted in an electronic format as required by the Specifications of the project.

Each COR will be reviewed by the Architect/Designer, the Resident Engineer, and the Project Manager. If there is additional information required or a correction needs to be made a notification will be sent in a timely manner to the Prime Contractor with all parties copied. The Architect/Designer, Resident Engineer and Project Manager shall request any necessary additional information or corrections within 30 days of when the COR is submitted. If additional time is required to evaluate a COR, then the Contractor shall be notified within the same 30 days of the extended date by which a decision will be made. The Prime Contractor can resubmit the COR with the original COR number with an "R1" noted for the revision. This revision should be noted on the PCO log for tracking purposes and updated each time a revision is needed. No work shall begin until the COR is signed by all parties.

3.03 If the COR is complete and acceptable the Architect/Designer and DCAMM project team will advise the Prime Contractor of its acceptance consistent with section 3.05, below. Once the COR is accepted, the Prime Contractor is authorized to start the work and immediately initiate the formal Change Order ("The Gold Sheet"), Form 5, for billing purposes. Multiple signed CORs may be incorporated into one formal Change Order (Form 5) for approval; however, the original COR and all back up information must be provided. If the formal Change Order (Form 5) is incomplete or incorrect, the entire Change Order will be returned to the contractor. In such a case when multiple CORs are submitted together into one formal Change Order and the submission is either incomplete or incorrect, no single COR will be processed. Prime Contractors cannot bill for the work until a formal Change Order (Form 5) is signed by all parties and a double digit CO number is issued by the DCAMM Project Controls team. This number is to be displayed on the Schedule of Values with the change description when billing.

3.04 If the COR is not acceptable, all parties must work in good faith, and in a timely manner to resolve any issues prior to any work starting. If the issues cannot be resolved at the Project Manager or Deputy Director level within 30 days, a Project Executive from the Prime Contractor and the Director or Deputy Commissioner for Design and Construction will meet in order to reach final resolution. If the issues still cannot be resolved, the Project Manager may issue a unilateral Change Order and the Prime Contractor must commence work in accordance with Article VII of the Contract General Conditions and should refer to Article VII of the Contract General Conditions for performing work under protest and the dispute resolution process. This status will be updated on the PCO log and the Prime Contractor and DCAMM Project Team will continue to work to resolve the issues as outlined in Article VII.

3.05 The Architect/Designer and the Resident Engineer will provide written back up, either in an email or memorandum, approving the Prime Contractor's submitted COR and Form 5 Change Order. They are not required to sign the actual form submitted. The following approvers must sign the actual Change Order for it to be a binding Contract amendment based on the delegation authority granted by the Commissioner of DCAMM:

The Director or Deputy Commissioner for Design and Construction approval shall be required whenever:

- a. the estimate for the work on the Form 5's (CORs) exceeds \$50,000 (absolute value); OR
- b. the cumulative cost of previously approved Form 5's (CORs) exceeds five percent of the original contract award price (or the amount of the GMP amendment in the case of a Chapter 149A project) and the amount of the Form 5 (COR) being approved is greater than \$2,000.00; OR
- c. The change order includes a time extension.

A Deputy Director of Design and Construction shall approve change orders for DCAMM when:

- a. The cumulative cost of previously approved Form 5's (CORs) is less than five percent of the original contract award price and the value of the Form 5 (COR) does not exceed \$50,000.00 (absolute value).

With the prior written approval of the Director or Deputy Commissioner for Design and Construction, the Project Manager shall approve change orders for DCAMM when:

- a. The cumulative cost of previously approved Form 5's (CORs) is less than five percent of the original contract award price and the value of the Form 5 does not exceed \$5,000.00 (absolute value); OR
- b. The estimate for the Form 5 is less than \$2,000.00 (absolute value).

BILLING FOR CHANGE ORDERS PRIOR TO RECEIVING THE CHANGE ORDER NUMBER FROM THE DCAMM PROJECT CONTROLS TEAM WILL RESULT IN THE PAYMENT APPLICATION BEING REJECTED.

SECTION 4. RESPONSIBILITY FOR PROCESSING AND APPROVING CHANGES

4.01 The Prime Contractor is responsible for verifying and validating all subcontractor, vendor and supplier costs and time extensions being requested as part of any change in the work. Refer to Contract General Conditions at Article VII.

4.02 The Prime Contractor, Architect/Designer, and DCAMM project team will review all PCO, COR, and Change Orders during the weekly Owner Meetings. There may be additional time needed to approve the changes and a timeframe for resolution are to be noted in the meeting minutes and on the PCO log.

PROJECT NAME

PROJECT NO.

P. C.

REQUEST FOR APPROVAL OF WAGES AND RATES FOR CHANGE ORDER PRICING

NAME OF SUBCONTRACTOR:

This form must be completed, submitted and approved prior to the submission of any change order price proposals. Complete the below for every Trade and Classification that is likely to work on the project. If any contractor seeks to utilize a total hourly wage rate (wages plus benefits) for change order pricing that is in excess of the applicable published prevailing wage rate, then this form must be completed, submitted (with backup documentation - i.e. union agreement) and approved prior to the submission of any change order price proposals. The information supplied below must be consistent with certified payroll submissions.

	Employee 1	Employee 2	Employee 3	Employee 4	Employee 5	Employee 6	Employee 7
1 Rate (Select type from drop down) ----->	Straight Time	Straight Time	Straight Time	2x Differential	1/2 Differential	Double Time	Time & Half
2 Trade Description (c.g., Carpenter, Pipefitter, Electrician, etc.)							
3 Classification (Foreman, Journeyman, Apprentice)	Journeyman	Foreman	Apprentice Step 1	Apprentice Step 3	Apprentice Step 5	Apprentice Step 7	Apprentice Step 9
4 Prevailing Wage Rate (Per Contract Specifications)							
Subcontractor Proposed Rates For Approval							
5 Requested Published Rate ² (must match certified payroll)				Premium	Premium	Premium	Premium
6 Enter Premium Portion of Base Rate (If Applicable)							
7 O&P, Insurance, and Taxes Base Prevailing Markups ^{1,4,4} (Multiply by Item 4 and Item 6 when applicable)	40.00%	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
8 Workmen's Compensation Insurance Above 12.5% (applicable to straight time only, Multiply by Item 4)	0.00%	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Subtotal All Inclusive Markups	40.00%	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
9 Excess Wages/Fringes ³ (Item 5 minus Item 4)		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Subcontractor Proposed Rate		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Loaded Rate		\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Credit Change Order Value	85.00%	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -

Effective Dates From To

The Above Total Loaded Rate is Being Requested For Approval For Use On Change Orders Expected to Be Performed Prior To The Noted Effective Date:

ENTER EFFECTIVE DATES ABOVE BEFORE SUBMITTING FOR APPROVAL

Sub-contractor Authorized Representative _____

Prime Contractor Authorized Representative _____

DCAMM Authorized Representative _____

NOTES:

- Contractor may utilize a rate of 40% for insurance/taxes without providing documentation. If a rate in excess of 40% is requested, documentation must be provided and is only applicable to Workmen's
- Attach all relevant supporting documentation such as union wage rate sheets and workers compensation rate tables.
- Excess wages/fringes are those fringes required to be paid which exceed the contract prevailing wage. DCAMM will reimburse these costs, once approved, as cost only (i.e., no markups allowed). Not all excess fringe benefits are reimbursable by DCAMM. Note that the following benefits are explicitly not allowed as part of the Published Rate: Union Dues, Vacation Funds, Uniforms, Earned Sick Leave, Etc.
- Time and a Half, Double Time, and Differential rates are calculated with 40% markup on the portion of wages above the straight time wage.

DIVISION OF CAPITAL ASSET MANAGEMENT & MAINTENANCE

c.30, c.149, c.149A ONLY

PROJECT NAME

PROJECT NO.

P. C. :

PCO NUMBER
PCO DATE

PCO DESC.

FORMAT FOR SUBMISSION OF CHANGE ORDER

WORK OF SUBCONTRACTOR AND/OR PRIME CONTRACTOR

NAME OF FIRM SUBMITTING CHANGE ORDER

1. DIRECT LABOR: "CONTRACTOR":

Use only DCAM-Approved Billing Rates
Applicable Billing Rate for each Trade and Classification **MUST** be completed!

Trade	Classification	Total Hrs. Worked	Fully Loaded Wage Rate (per Wage Rate Approval Form) THIS FIELD IS REQUIRED	Total Direct Labor Cost (Includes All Markups as Approved by DCAMM on the Wage Rate Approval Form)
				\$ -
				\$ -
				\$ -
				\$ -
				\$ -
				\$ -

TOTAL BASE, EXCESS AND DIRECT LABOR COSTS

2. MATERIALS: "CONTRACTOR" :

(For extensive material lists, attach detailed backup and enter as a lump sum below)

Material Description	Qty	Unit	Cost Per Unit	Total
				\$ -
				\$ -
				\$ -
				\$ -
				\$ -
				\$ -

TOTAL MATERIALS COST:

DIVISION OF CAPITAL ASSET MANAGEMENT & MAINTENANCE

c.30, c.149, c.149A ONLY

PROJECT NAME

PROJECT NO.

P. C. :

PCO NUMBER
PCO DATE

PCO DESC.

FORMAT FOR SUBMISSION OF CHANGE ORDER

WORK OF SUBCONTRACTOR AND/OR PRIME CONTRACTOR

NAME OF FIRM SUBMITTING CHANGE ORDER

3. EQUIPMENT: "CONTRACTOR" :

(For extensive equipment lists, attached detailed backup and enter as a lump sum below)

Equipment Description	Qty	Unit	Cost Per Unit	Total
				\$ -
				\$ -
				\$ -
				\$ -
				\$ -
				\$ -

TOTAL EQUIPMENT COST: \$ -

4. SUB TOTAL "CONTRACTOR" DIRECT COST FOR ITEMS 2 & 3:

SUB TOTAL: \$ -

5. MISC. LUMP SUM SERVICES (POLICE DETAIL, UTILITIES, ETC.) OR SUBCONTRACTED WORK PROVIDED TO "CONTRACTOR":

Description of Miscellaneous Lump Sum Service - attach backup	Total
	\$ -
	\$ -
	\$ -
	\$ -
	\$ -
	\$ -

TOTAL MISC. LUMP SUM SERVICES COST: \$ -

6. "CONTRACTOR" ALLOWED 5% O&P Mark Up - MISC. LUMP SUM SERVICES:

5.00% \$ -

7. SUB TOTAL "CONTRACTOR" LINE ITEMS 4., 5. & 6.:

SUB TOTAL: \$ -

DIVISION OF CAPITAL ASSET MANAGEMENT & MAINTENANCE

c.30, c.149, c.149A ONLY

PROJECT NAME

<project-name>

PROJECT NO.

<project-number>

P. C. :

<Prime Contractor>

PCO NUMBER

PCO DESC.

PCO DATE

FORMAT FOR SUBMISSION OF CHANGE ORDER

WORK OF SUBCONTRACTOR AND/OR PRIME CONTRACTOR

NAME OF FIRM SUBMITTING CHANGE ORDER

8. OVERHEAD AND PROFIT OF "CONTRACTOR":

The "Contractor" shall receive 15% of actual total cost of Item 4. For a net CREDIT change order amount, use 0%

Contractor

15.00%

x ITEM 4:

\$ -

9. TOTAL OF ITEMS 1., 7. and 8.

TOTAL COST OF WORK PERFORMED BY "CONTRACTOR":

\$ -

9a. CONTRACTOR PREMIUM FOR BOND

Only allowed for "Filed Sub Contractor" if required by Page "F." of the Contract. Percentage of bond per contract or verified/approved amount:

Percentage of approved bond x item 9.

0.00%

x ITEM 9:

\$ -

10 TOTAL COST OF WORK PERFORMED BY PRIME CONTRACTOR, including bond cost

\$0.00

Enter the Value of Item 10 on the Summary Sheet

NOTE:

ALL change order proposals and invoices from the PRIME CONTRACTOR AND/OR SUBCONTRACTORS must include a cover letter on company letterhead identifying the PCO number, a description of the scope of work and the total cost of the proposed change order from the company. This information must be completed by every contractor doing work created by the change.

FOR DCAMM USE ONLY

CHANGE ORDER LOG
 CONTRACT NO.: 2022-0XX
 CONTRACT TITLE: JOHN SMITH PROJECT

CHANGE ORDER TYPE		DATE SUBMITTED to PM	INCREASE TO CONTRACT			CHANGE ORDER TYPE				AMOUNT			DESCRIPTION OF CHANGE ORDER	REASON FOR INCREASE	DATE OF Approval	
CO NO.	Rev. qty		Extra work	Alter- ation	Time ext.	Rev. qty	Extra work	Alter- ation	Time ext.	Financed from contract	Funding Item	ITEM NUMBER				
	RQ#	EWQ#	ALT#	TM#	co items	co subtotal	co total	RQ#	EWQ#	ALT#	TM#					
1		1														
2-1		2														
2-2																
3-1		3														
3-2																
3-3																
3-4																
3-5																
3-6																

DIVISION OF CAPITAL ASSET MANAGEMENT & MAINTENANCE

CONTRACTOR CHANGE REQUEST NO. _____ Rev. _____

Request and Agreement For Change in The Plans And/Or Specifications And/Or Contract

Project No. _____ Contract No. _____ Project Name _____
 Location _____

I. PROPOSED CHANGE

(a) Requested BY _____
 (b) Proposed Scope/Description: _____

II. CONTRACTOR PRICE PROPOSAL

For all costs involved in this change including extensions of time herein requested, the undersigned Contractor/CM proposes to perform the work described above in accordance with the provisions of Article VII of the General Conditions and certifies that: The Change Order Request is made in good faith; The validity of the Contractor/CM/Subcontractor/supplier change requests have been verified; the supporting data is accurate and complete to the best knowledge and belief of the Contractor/CM; and the Contractor/CM actually believes DCAMM is liable for the add amount, or entitled to the deduct amount of the Change Order Request, whichever is applicable. Any attempted amendment to this form shall be interpreted as superseded by the original printed language in the executed contract documents.

Request payment be made on the basis of:

- (a) _____ Predetermined lump sum total of \$ _____
- (b) _____ Lump sum not to exceed \$ _____
 (max price based on contract unit prices or negotiated agreed unit prices)
- (c) _____ Time and Materials Basis Not to Exceed \$ _____
 (computed in accordance with Article VII of the General Conditions)

Place X beside selected proposal method and identify (add) or (deduct) which ever applies. Attach detailed estimates and breakdown for above in accordance with change order instructions. If additional time is requested, furnish an explanation with the breakdown. A claim for work performed under protest shall be submitted per (c) above.

An extension of contract time of _____ Calendar days is requested.

Contractor _____ By _____
 Firm Name Authorized Signature Date

III. DCAMM REVIEW *(This Section To Be Completed By DCAMM/EM Team)*

- (a) _____ Approved as Submitted
- (b) _____ Unilaterally Approved as Adjusted
 Revised Price *add / (deduct)* _____
 Revised Time Extension _____ Calendar Days
- (c) _____ Disapproved; Returned to Plans Contractor by _____
- (d) Operating Agency letter Attached _____
- (e) Resident Engineer letter Attached _____
- (f) Lead Design firm letter Attached _____

IV. CONTRACT MODIFICATION *(This section To Be Completed By Project Controls)*

- (a) The Original Contract Value \$ _____
- (b) Net Change by previously authorized Change Orders \$ _____
- (c) The Contract Value prior to this Change Order was \$ _____
- (d) The Contract Value will be *add / (deduct)* By this Change Order
 in the Amount of \$ _____
- (e) *The new Contract Value including this Change Order will be* \$ _____
- (f) The Contract Time will be *add / (deduct)* by _____ Calendar Days
- (g) The New contract Completion date is therefore revised from _____ To _____

Approval Recommended By (initial/Date If Applicable): Deputy Director _____ Project Manager _____ Project Engineer _____

This change is in the best interest of the Commonwealth and constitutes an equitable adjustment of the Contract in compliance with Art. VII

DCAMM Authorized Signature _____ Date _____

Project Manager Deputy Director Director Deputy Commissioner

DCAMM Change Order Number _____

WEEKLY PAYROLL REPORT FORM
 THE COMMONWEALTH OF MASSACHUSETTS
 DEPARTMENT OF MENTAL HEALTH

DMH Project No. _____ Project Name _____
 Project Location _____
 Name of General Contractor _____
 Name of Contractor Filing Report _____
 Address _____
 Week Ending _____ Date Work Began _____ Date work completed _____
 Report No. _____ Check here if this is a final report

Employee Name & Address	Work Classification	Hours Worked							(A) Total Hours	(B) Hourly Base Wage	Employer Contributions			(F) [B+C+D+E] Hourly Total Wage (prev.)	(G) [A*F] Weekly Total Amount
		S	M	T	W	T	F	S			(C) Health & Welfare	(D) Pension	(E) Supp. Unemp.		

NOTE: Every contractor and subcontractor is required to submit a copy of their weekly payroll records to DCR. The undersigned states under the pains & penalties of perjury that the above provided and attached information is a true and accurate record of each person employed on the project and the hours worked and wages paid to each such employee, including payments to the referenced benefits. M.G.L. c. 149 §27B.

Authorized signature _____ Print Name _____
 Print Title _____

Mail to: Department of Mental Health
 Mariana G. O'Brien
 167 Lyman Street
 Westborough, MA 01581

WEEKLY PAYROLL RECORDS REPORT & STATEMENT OF COMPLIANCE

In accordance with Massachusetts General Law c. 149, §27B, a true and accurate record must be kept of all persons employed on the public works construction project for which the enclosed rates have been provided. The *Weekly Payroll Report Form* includes all the information required to be kept by law. Every contractor or subcontractor is required to keep these records and preserve them for a period of three years from the date of completion of the project.

In addition, every contractor and subcontractor is required to submit a copy of their weekly payroll records to the awarding authority. This is required to be done on a weekly basis. Once collected, the awarding authority is also required to preserve those records for three years.

In addition, each such contractor, subcontractor, or public body shall furnish to the **Executive Office of Labor**, within fifteen days after completion of its portion of the work, a statement, executed by the contractor, subcontractor or public body who supervises the payment of wages, in the following form:

STATEMENT OF COMPLIANCE

Date: _____ / _____, 200_____

I, _____, _____
(Name of signatory party) (Title)

do hereby state:

That I pay or supervise the payment of the persons employed by

_____ on the _____
(Contractor, subcontractor or public body) (Building or project)

and that all mechanics and apprentices, teamsters, chauffeurs and laborers employed on said project have been paid in accordance with wages determined under the provisions of sections twenty-six and twenty-seven of chapter one hundred and forty nine of the General Laws.

Signature _____

Title _____

PAYROLL & WORKFORCE REPORT CONTRACT NO.: 2022-0XX CONTRACT: JOHN SMITH PROJECT	Legend: ps Professional services claiming exemption io Independent oper. Claiming exemption rec DCR received dpr disputing payroll require. diss received letter of dissolution
---	--

Week ending	General Contractor	Sub-bidder #01	Sub-bidder #02	Sub-bidder #03	Sub-bidder #04	Sub-bidder #05	Sub-contractor non-filed #1	Sub-contractor non-filed #2	Sub-contractor non-filed #3	Sub-contractor non-filed #4			
	PR WF	PR WF	PR WF	PR WF	PR WF	PR WF	PR WF	PR WF	PR WF	PR WF	PR WF	PR WF	PR WF
9/13/2014													
9/20/2014													
9/27/2014													
10/4/2014													
10/11/2014													
10/18/2014													
10/25/2014													
11/1/2014													
11/8/2014													
11/15/2014													
11/22/2014													
11/29/2014													
12/6/2014													
12/13/2014													
12/20/2014													
12/27/2014													
1/3/2015													
1/10/2015													
1/17/2015													
1/24/2015													

PAYROLL & WORKFORCE REPORT CONTRACT NO.: 2022-0XX CONTRACT: JOHN SMITH PROJECT	Legend: ps Professional services claiming exemption io Independent oper. Claiming exemption rec DCR received dpr disputing payroll require. diss received letter of dissolution
---	--

Week ending	General Contractor	Sub-bidder #01	Sub-bidder #02	Sub-bidder #03	Sub-bidder #04	Sub-bidder #05	Sub-contractor non-filed #1	Sub-contractor non-filed #2	Sub-contractor non-filed #3	Sub-contractor non-filed #4			
	PR WF	PR WF	PR WF	PR WF	PR WF	PR WF	PR WF	PR WF	PR WF	PR WF	PR WF	PR WF	PR WF
1/31/2015													
2/7/2015													
2/14/2015													
2/21/2015													
2/28/2015													
3/7/2015													
3/14/2015													
3/21/2015													
3/28/2015													
4/4/2015													
4/11/2015													
4/18/2015													
4/25/2015													

PAYMENT SUMMARY

PROJECT NAME: 2022-0XX CONTRACT FULL NAME
LOCATION OF WORK: SOMEPLACE MENTAL HEALTH FACILITY
ADDRESS: STREET NAME, TOWN, STATE, ZIPCODE
CONTRACTOR: JOHN SMITH CONSTRUCTION, INC

start date	end date	Payment	Utilization current period	Utilization previous period	Utilization to date	5% retainage current period	retainage previous periods	retainage paid current period	retainage paid to date	retainage held to date	Paid Current Period	Previous payment Paid	Total Paid to date
1/1/2021	2/1/2021	1	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
		2	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
		3	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
		4											
		5											
		6											
		7											
		8											
		9											
		10											
		11											
		12											
		13											
		14											
		15											
		16											
		17											
		18											
		19											
		20											
		21											
		22											
		23											
		24											
			Award + Extras: \$ 100,000.00										
			Utilization remaining: \$ 100,000.00										

SUBMITTAL LOG - SHOP DRAWINGS AND SAMPLES												
CONTRACT NO.: 2022-0XX												
CONTRACT TITLE: JOHN SMITH PROJECT												
Submittal NO.	DATE OF SUBMITTAL	DATE Received by PM	DATE Received by Consult.	DATE Returned by Consult.	DATE Returned by PM	Turn-around (days)	SPEC. ITEM NUMBER	DESCRIPTION OF SHOP DRAWING, SAMPLE, OR PROCEDURE WITH NAME OF VENDOR	No of pages including covers	DATE NO EXCEPTION TAKEN	DATE MAKE CORRECTIONS AS NOTED	DATE REVISE AND RESUBMIT
1												
2												
3												
4												
5												
6												
7												
8												
9												
10												
11												
11A												

CONTRACT NO.: 2022-0XX

PROJECT NAME: John Smith Project

AGENCY: Massachusetts Department of Mental Health

REQUEST FOR INFORMATION

DATE: 00/00/2021

TO: DMH Project Engineer, first name last name

FROM: General Contractor name

RFI No.: #0xx Item or Section No - Title

REQUESTED INFORMATION:

RESPONSE:

Response prepared by (Name): _____

Signed: _____ Date: _____

RFI#0XX RFI Title

REQUEST FOR INFORMATION LOG
CONTRACT NO.: 2022-0XX
CONTRACT TITLE: JOHN SMITH PROJECT

RFI NO.	DATE OF RFI	PREPARED BY	DATE SUBMITTED by RE or update info	SPEC. ITEM NUMBER	DESCRIPTION OF REQUEST FOR INFORMATION	DATE OF RESPONSE	DESCRIPTION OF RESPONSE	Change Order No. required

**COMMONWEALTH OF MASSACHUSETTS
EXECUTIVE OFFICE OF ADMINISTRATION AND FINANCE
DIVISION OF CAPITAL ASSET MANAGEMENT AND MAINTENANCE
ONE ASHBURTON PLACE, BOSTON, MA 02108**

E-1 CERTIFICATE OF SUBSTANTIAL COMPLETION (M.G.L. C.30, Section 39K)

FROM AWARDING AUTHORITY: Commonwealth of Massachusetts, Division of Capital Asset Management and Maintenance

TO: General Contractor: {Company.Name}

RE: Mass. State Project No.: {Projects.Sequence} {Projects.SuffixID}
Title: {Projects.Name}
Location: {Projects.Territory}, MA

AUTHORITY: 1) ARTICLE VI of Standard Construction Contract
2) M.G.L. Chapter 30, Section 39K

Pursuant to the authority noted above you are notified that the Commonwealth of Massachusetts, through its Division of Capital Asset Management and Maintenance, is satisfied that the portion of the above noted project, as hereinafter enumerated, is substantially complete. [IDENTIFY PORTIONS TO BE USED AND/OR OCCUPIED – IF APPLICABLE]

The Commonwealth of Massachusetts, through its undersigned representatives, hereby accepts from the Contractor, subject to contract stipulation, said portion of the project effective as of Midnight, the [INSERT DAY] day of [INSERT MONTH], 20[INSERT YEAR]. The Contractor is relieved of responsibility for performing further work or supplying further materials, equipment or items, with the exception of the attached. (Append a complete list of all incomplete or unsatisfactory items of contract work which in the opinion of the Commonwealth are attributable to the fault, negligence or oversight of the Contractor, his sub-contractor, material suppliers, agents, servants or employees.)

The use of any portion of the project or the occupancy of any building or portion thereof by the Commonwealth shall not constitute a final acceptance of any work not performed in accordance with the Contract, nor relieve the Contractor of liability to perform any work required by the Contract or of liabilities with respect to any warranties or guarantees required by the Contract.

The undersigned recommend the issuance of this Certificate of Substantial Completion.

	Signature	Date
Designer: {LegalDocInfo.ArchName}	by: _____	
Operating Agency: {LegalDocInfo.owner}	by: _____	
DCAMM Resident Engr.: {Projects.ProjectExecutive}	by: _____	
DCAMM Project Engr.: {Projects.ProjectExecutive}	by: _____	
DCAMM Project Mgr.: {Projects.ProjectManager}	by: _____	

APPROVED _____
Jay Mitchell, Deputy Commissioner, Design and Construction Date

<p>original: Operating Agency Project Manager Contracts Manager Contractor (include original E1 cover letter)</p>	<p>ecc: Deputy Director Project Engineer Designer Resident Engineer Economist, OFA Director of Finance, OFA Bid Room Manager, OFA Deputy Director, Certification</p>
---	--

**E-2 Final Acceptance
Certificate of Final Inspection, Release and Acceptance**

Title: _____

Location: _____

Contractor: _____

This is to certify that a complete inspection of the above-referenced project was made on _____ by the undersigned, and that the entire work was completed in accordance with the plans and specifications. The undersigned recommends acceptance of the project.

_____ by: _____ Title: _____ Date: _____
 _____ Designer Authorized
 Signature

 Resident Engineer Date Project Manager Date

 Project Engineer Date

CERTIFICATE OF RELEASE

1.) The undersigned hereby certifies that all work has been completed in accordance with the plans, specifications and contract documents and that all change orders have been supported pursuant to Article VII of the General Conditions of the Contract.

2.) Contract Award Price: \$	Adjusted Contract Price: \$
Authorized Additions: \$	Paid to Date:\$
Authorized Deductions:\$	Balance Due: \$

3.) The undersigned further certifies that in addition to the amount set forth above, there are outstanding and unsettled the following change orders as submitted to the DCR.

Request No.	Date:	Amount:
Request No.	Date:	Amount:
Request No.	Date:	Amount:

Subject to satisfactory disposition of change orders listed in Item 3 above, the undersigned releases the Commonwealth of Massachusetts from all further claims for wages or payments to subcontractors or suppliers except: (list on attached sheet).

_____ by: _____
 Contractor Authorized Signature

The above-referenced project is accepted as of _____
 Date

Deputy Commissioner, Engineering
 Deputy Director
 Project Manager
 Resident Engineer
 Office of Contract Administration
 Contractor

CERTIFICATE OF PAYMENT

BY CONTRACTOR/DESIGNER TO MINORITY, WOMEN BUSINESS
& VETERAN OWNED BUSINESS ENTERPRISES

TO: Supplier Diversity Reports
 Department of Mental Health
 Office of Engineering and Facilities Management
 167 Lyman Street
 Westborough, MA 01581

Reporting Period: Fiscal Year 20__

RE: Project:
 Project Number:

Contract Start Date:

The undersigned hereby certifies under the pains and penalties of perjury that the vendor named below has made the following payments to the named Minority, Women Business and Veteran Owned Enterprises for work performed on the above project:

Firm Name of General Contractor:

Authorized Signature

Date

Print Name

Print Title

Phone Number

Email address

Work performed/payments made (use additional pages if needed):

	Firm Name	Work Performed	Subcontract Amount	Payments This Quarter	FY Payments to date (this fiscal year 7/1/2018 - 6/30/2019)	Cumulative Payments (total payments over the life of the contract)
MBE WBE VOBE			\$	\$	\$	\$
MBE WBE VOBE			\$	\$	\$	\$
MBE WBE VOBE			\$	\$	\$	\$
MBE WBE VOBE			\$	\$	\$	\$
MBE WBE VOBE			\$	\$	\$	\$
MBE WBE VOBE			\$	\$	\$	\$
MBE WBE VOBE			\$	\$	\$	\$

* MBE, WBE and VOBE payment reports are required for each quarter of the fiscal year for each of your DMH projects. Reports are to cover the following three month periods: 1st quarter, July 1st – September 30th; 2nd quarter, October 1st – December 31st; 3rd quarter, January 1st – March 31st; 4th quarter, April 1st – June 30th. Reports must be submitted within 10 business days of your receipt of this form.

NOTICE: *Intentionally submitting false information in this document may subject the contractor/ designer to criminal prosecution and/ or debarment from public contracting.*

INSTRUCTIONS FOR COMPLETING CERTIFICATE OF PAYMENT

As part of its effort to ensure reliable, up-to-date information concerning the actual payments made to certified MBE, WBE and VOB E subcontractors on all DMH projects, we have prepared these instructions to assist you in completing the enclosed form. **PLEASE READ THESE INSTRUCTIONS CAREFULLY. DMH WILL RETURN ANY CERTIFICATION OF PAYMENT THAT IS INCOMPLETE OR INACCURATE.**

PLEASE NOTE: IF THIS PROJECT IS COMPLETE, ON HOLD, OR YOUR FIRM PREVIOUSLY SUBMITTED A **FINAL** CERTIFICATION OF M/WBE/VOBE PAYMENT FOR THIS PROJECT, PLEASE SO INDICATE ON THE FORM AND RETURN IT TO: SUPPLIER DIVERSITY REPORTS, DEPARTMENT OF MENTAL HEALTH, OFFICE OF ENGINEERING AND FACILITIES MANAGEMENT, 167 LYMAN STREET WESTBOROUGH, MA 01581

PLEASE INCLUDE THE FOLLOWING INFORMATION IN THE DESIGNATED SECTIONS OF THE FORM:

FIRM NAME: Include the M/WBE/VOBEs listed on the project's approved Schedule For Participation and any additional M/WBE/VOBEs that worked on the project. Be sure to check M/WBE/VOBE category for which they are certified. Note that any change in M/WBE/VOBEs participation used to meet the project goals must be pre-approved by the Project Manager or Engineer responsible for this project and a revised M/WBE/VOBE Schedule of Participation will be required. Contact the DMH Supplier Diversity coordinator immediately if you anticipate or have any changes in M/WBE/VOBE participation on this project.

WORK PERFORMED: Include a brief description of the work performed by each subcontractor listed. The description should match the M/WBE/VOBE Letter of Intent and approved Schedule of Participation. M/WBE/VOBEs must be certified in the category of work performed on this project for firms used to meet the project M/WBE/VOBE goals.

SUBCONTRACT AMOUNT: Include the contract or subcontract amounts listed on the M/WBE/VOBE Letters of Intent and approved Schedule of Participation. If the value of a MBE/WBE/VOBE contract or subcontract has decreased or increased for any reason, you must contact the Project Manager or Engineer responsible for this project immediately. If additional M/WBE/VOBE firms not listed on the Schedule for Participation worked on this project list the amount of their subcontracts.

PAYMENTS THIS QUARTER: Include the amount you paid the M/WBE/VOBE subcontractor, either directly or indirectly, for work performed on this project during the three month period covered by this Certification of Payment. If the amount paid was zero, please indicate that. Do not include payments from previous periods or estimated future payments in this column. Please note that you may be required to submit copies of cancelled checks to verify the amounts reported for firms used to meet the project's M/WBE/VOBE goals.

FY PAYMENTS TO DATE: Include the total amount you paid the M/WBE/VOBE subcontractor, either directly or indirectly, for work performed on this project for all quarters in **this fiscal year.** To ensure accurate reporting, please review the prior Certifications of Payments previously submitted for this project. Where necessary, correct any earlier mathematical or reporting errors and submit revised Certifications of Payment.

CUMULATIVE PAYMENTS: Include the total amount you paid the M/WBE/VOBE subcontractor, either directly or indirectly, for work performed over the entire life of this project (all quarters).

IF YOU HAVE ANY QUESTIONS CONTACT DMH Supplier Diversity coordinator.

INSTRUCTIONS FOR COMPLETING CERTIFICATE OF PAYMENT

As part of its effort to ensure reliable, up-to-date information concerning the actual payments made to certified Sub-bidder (SB), Non Sub-bidder (NSB) and Supplier (S) subcontractors on all DMH projects, we have prepared these instructions to assist you in completing the enclosed form. PLEASE READ THESE INSTRUCTIONS CAREFULLY. DMH WILL RETURN ANY CERTIFICATION OF PAYMENT THAT IS INCOMPLETE OR INACCURATE.

PLEASE NOTE: IF THIS PROJECT IS COMPLETE, ON HOLD, OR YOUR FIRM PREVIOUSLY SUBMITTED A **FINAL** CERTIFICATION OF SB/NSB/S PAYMENT FOR THIS PROJECT, PLEASE SO INDICATE ON THE FORM AND RETURN IT TO: DEPARTMENT OF MENTAL HEALTH, OFFICE OF ENGINEERING AND FACILITIES MANAGEMENT, 167 LYMAN STREET WESTBOROUGH, MA 01581.

PLEASE INCLUDE THE FOLLOWING INFORMATION IN THE DESIGNATED SECTIONS OF THE FORM:

FIRM NAME: Include the SB/NSB/S listed on the project's approved Schedule For Participation and any additional SB/NSB/Ss that worked on the project.

WORK PERFORMED: Include a brief description of the work performed listed.

SUBCONTRACT AMOUNT: Include the contract or subcontract amounts listed.

PAYMENTS THIS QUARTER: If applicable, include the amount, either directly or indirectly, for work performed on this project during the three month period covered by this Certification of Payment. If the amount paid was zero, please indicate that. Do not include payments from previous periods or estimated future payments in this column.

FY PAYMENTS TO DATE: Include the total amount you paid, either directly or indirectly, for work performed on this project for all quarters in **this fiscal year**. To ensure accurate reporting, please review the prior Certifications of Payments previously submitted for this project. Where necessary, correct any earlier mathematical or reporting errors and submit revised Certifications of Payment.

CUMULATIVE PAYMENTS: Include the total amount you paid, either directly or indirectly, for work performed over the entire life of this project (all quarters).

IF YOU HAVE ANY QUESTIONS, CONTACT DMH OFFICE OF ENGINEERING AND FACILITIES MANAGEMENT.

CERTIFICATE OF PAYMENT

BY CONTRACTOR/DESIGNER

to Sub-Bidder(s), Non-Sub-bidder(s), and Supplier(s)

TO: Department of Mental Health
Office of Engineering and Facilities Management
167 Lyman Street
Westborough, MA 01581

Reporting Period: Fiscal Year 20__

RE: Project:
Project Number:

Contract Start Date:

The undersigned hereby certifies under the pains and penalties of perjury that the vendor named below has made the following payments to the named SB, NSB, AND S companies for work performed on the above project:

Firm Name of General Contractor:

Authorized Signature

Date

Print Name

Print Title

Phone Number


Email address

Work performed/payments made (use additional pages if needed):

	Firm Name	Work Performed	Subcontract Amount	Payments This Quarter	FY Payments to date (this fiscal year 7/1/2018 - 6/30/2019)	Cumulative Payments (total payments over the life of the contract)
SB NSB S			\$	\$	\$	\$
SB NSB S			\$	\$	\$	\$
SB NSB S			\$	\$	\$	\$
SB NSB S			\$	\$	\$	\$
SB NSB S			\$	\$	\$	\$
SB NSB S			\$	\$	\$	\$
SB NSB S			\$	\$	\$	\$

* Sub Bidder (SB), Non Sub-Bidder (NSB), and Supplier (S) payment reports are required for each quarter of the fiscal year for each of your DMH projects. Reports are to cover the following three month periods: 1st quarter, July 1st – September 30th; 2nd quarter, October 1st – December 31st; 3rd quarter, January 1st – March 31st; 4th quarter, April 1st – June 30th. Reports must be submitted within 10 business days of your receipt of this form.

NOTICE: *Intentionally submitting false information in this document may subject the contractor/ designer to criminal prosecution and/ or debarment from public contracting.*



BID PACKAGE

PART IV

PROJECT SPECIFICATIONS

**DMH PROJECT #2023-068B
FLOORING ABATEMENT & REPLACEMENT
HASKELL BUILDING
ONE PRINCE STREET
NORTHAMPTON, MA 01060**

**THE COMMONWEALTH OF MASSACHUSETTS
EXECUTIVE OFFICE OF HUMAN SERVICES
DEPARTMENT OF MENTAL HEALTH**

S P E C I F I C A T I O N S

FOR

FLOORING ABATEMENT AND REPLACEMENT

AT

**HASKELL BUILDING
1 PRINCE & WEST STREET
NORTHAMPTON, MA 01061**

.....
PROJECT NO. 2023-068B
.....

**DEPARTMENT OF MENTAL HEALTH
OFFICE OF FACILITIES MANAGEMENT
167 LYMAN STREET
WESTBOROUGH, MA 01581**

PREPARED BY: FRED BERGSTROM

REVIEWED BY: PAUL TRUAX

DATE: MARCH 8, 2023

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

TABLE OF CONTENTS

<u>DIVISION 1</u>	<u>CONTENTS</u>	<u>PAGE</u>
011000	SUMMARY OF THE WORK	3 TO 14
012300	ALTERNATES	15 TO 16
013300	SUBMITTALS	17 TO 19
015000	CONSTRUCTION FACILITIES AND TEMPORARY CONTROLS	20 TO 22
016000	MATERIALS AND EQUIPMENT	23 TO 24
017000	CONTRACT CLOSEOUT	25 TO 26
 <u>DIVISION 2</u>		
024119	SELECTIVE DEMOLITION	27 TO 30
025000	ASBESTOS ABATEMENT	31 TO 54
 <u>DIVISION 9</u>		
096813	TILE CARPETING	55 TO 61
	DRAWING	A-3
	ATTACHMENT A	

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

FlooringAbatementandReplacementHaskell.doc/FEB

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

**SECTION 011000
SUMMARY OF THE WORK**

PART 1 – GENERAL

1.1 CONTRACT REFERENCES

- A. Attention is directed to the CONTRACT and GENERAL CONDITIONS and all Sections within Division 1 – GENERAL REQUIREMENTS that are hereby made a part of this Section of the Specifications.
- B. Equality of material, article, assembly or system other than those named or described in this Section shall be determined in accordance with the provisions of the CONTRACT and GENERAL CONDITIONS.

1.2 DEFINITIONS

- A. The following terms shall be applicable to these Specifications:
 - 1. **DMH Project Manager:** Refers to Fred Bergstrom, Massachusetts Department of Mental Health, Engineering and Facilities Management, 167 Lyman Street, Westborough, MA 01581. (508) 616-2245.
 - 2. **DMH Facility Manager:** Refers to Paul Henderson, Massachusetts Department of Mental Health, 1 Prince Street, Northampton, MA 01060. (413) 587-6370.
 - 3. **Contractor:** Refers to the Contractor who has been awarded the overall contract for the work outlined by the Contract Documents.
 - 4. **Subcontractor:** Refers to any contractor who is working under the direct supervision of the Contractor including but not limited to: steel erector, mason, electrician, carpenter, painter, and trucking/transport companies.
 - 5. **Site:** Refers to the three residences located on the Haskell Building 1 Prince Street Northampton, MA 01060.
- B. The terms are provided to facilitate communication but do not supersede the legal definitions provided in the Contract.

1.3 WORK UNDER THIS CONTRACT

- A. The work described under this Contract pertains to the abatement and replacement of flooring on the second floor of the Haskell Building located at 1 Prince Street, Northampton, MA. The abatement and replacement of the specified flooring shall be in conformity with applicable sections of MassDLS 454 CMR 28.0, Mass DEP 310 CMR 7.15, the International Existing Building Code, (IEBC), 2015 Edition, the

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

International Building Code, (IBC) 2015 Edition, Massachusetts Amendments to the International Building Code 2015, Ninth Edition.

B. The work includes:

1. Application of, paying for, and securing any and all permits required from local, state and federal agencies, and other authorities having jurisdiction over construction on the Site, including submitting, revising, and resubmitting all required plans, permits, and notifications.
2. Preparation and submission of project work plan and schedules. The Plan shall include a time frame for abatement work to be completed during off hours and all requirements necessary to keep the facility open but keep work area secured during carpet installation maintaining safe public access and use.
3. Selective Demolition specifically focused around the abatement of floor tile containing asbestos, existing carpet and any other flooring material to prepare for installation of carpet squares.
4. Establish work area perimeter and dust control measures.
5. All floor preparation to ensure level and secure surfaces free of defects to ensure a proper installation of carpet squares as per manufacturer's instructions
6. Furnish and install carpet squares as per manufacturers specifications.
7. Contractor shall be responsible for making all necessary adjustments to doors, etc. in order to allow correct performance with any changes created by the carpet installation.

1.4 CONTRACT INTENT

- A. Intent of these specifications is to cover proper abatement, renovation and repair to floor work, and warranty complete and operable in every respect as well as standby and access for other contractor's completion of their work in proximity to the work specified under this Contract all related work. It is not intended to give every detail in the specifications. DMH and DMH's Project Manager are not responsible for the absence of unknown existing conditions or any specific details the Contractor may require within the demolition of the existing conditions or the installation of the new construction scope of work. Furnish all material and equipment usually furnished with such an assembly and/or needed to make a complete and code compliant installation, whether specifically mentioned or not, omitting only such parts as are specific exceptions from the specifications.
- B. The required materials for the construction will be of non-proprietary design and shall meet all the specific guidelines as described within the supplied specifications and drawings. The scope of work as described within the bid documents shall be considered as an integral part of the construction of the project and changes in the design will be considered unacceptable unless a written submittal has been approved before the actual changes are made to the design. It also must be noted that no

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

substitutions will be allowed where the suggested product is of less quality than what has been specified within the bid documents, only products meeting the base standard as noted will be considered.

1.5 EXISTING CONDITIONS

- A. The project site is a three-story business structures with a full basement. The facility was constructed approximately in 1959 and the construction is original to the property with some upgrades completed over the years. The facility is fully occupied at this time and the staff occupy the building during normal business hours between the hours of 8:00 AM and 5:00 PM. For work to be completed after normal business hours sufficient notification of at least 48 hours should be made to ensure there will not be staff in the areas to receive abatement.

1.6 EXAMINATION OF SITE AND DOCUMENTS

- A. A mandatory pre-bid conference will be held at the job site on the date and time indicated within the Invitation to Bid.
- B. The bidders are expected to examine and to be thoroughly familiar with all contract documents and with the conditions under which the work is to be carried out. The Commonwealth will not be responsible for errors, omissions, and/or charges for extra work arising from the Contractors or Subcontractors failure to familiarize themselves with the contract documents, that he is familiar with the conditions and requirements of both where they require, in any part of the work a given result to be produced, that the contract documents are adequate and he will produce the required results.

1.7 CONTRACTOR QUALIFICATIONS

- A. The Contractor shall be a Division of Capital Asset Management and Maintenance (DCAMM) certified general contractor with a current certification.
- B. Within three business days from the bid opening, the apparent low bidder shall submit a certification in writing that it has successfully performed at least three recent (within last three years) projects of similar size, scope, and cost. The apparent low bidder shall submit the following information for each project:
 - 1. Project Description
 - 2. Project Value
 - 3. Date was conducted
 - 4. Reference with contact information for the Owner who was the recipient of the work.
- C. The Contractor's Updated Statement is not a public record as defined in M.G.L., Chapter 4, Section 7, and will not be open to public inspection.

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

1.8 CONTRACT METHOD

- A. Work under this Contract shall be broken down into three sections a Base Bid, an Alternate Number One and an Alternate Number Two for the scope of work included and described in these Specifications and attached plan. Refer to Specification Section 012300 – Alternates for additional explanation for Alternates One and Two.
- B. Should additional work be required, the procedures specified in the Contract shall apply.
- C. The Massachusetts Standard Labor Wage rates, as included in the Contract exhibits, will be used for base contract work, as well as any change order work.

1.9 SUPERVISION OF THE WORK

- A. The Contractor shall be held directly responsible for the correct installation of all work performed under this Contract. The Contractor must make good repair, without expense to the Commonwealth, of any part of the new work, or existing work to remain, which may become inoperative on account of leaving the work unprotected or unsupervised during construction of the system or which may break or give out in any manner by reason of poor workmanship, defective materials or any lack of space to allow for expansion and contraction of the work during the Contractor's warranty period, from the date of final acceptance of the work by DMH.
- B. The Contractor shall be responsible for initiating, maintaining and supervising all safety precautions and programs in connection with his direct work.

1.10 CONTRACTOR'S USE OF THE PREMISES

- A. The Contractor can gain access to the premises during the hours specified below and will require approval of the afterhours access for abatement by submitting a detailed schedule for the work. In addition, the Contractor and his personnel will limit themselves to only within the working premises during working hours. If additional work needs to be scheduled during times other than those listed below, Contractor shall inform the DMH Project Manager one week prior to work.
 - 1. Deliveries: 7:00 am to 8:30 am and after 1:00 pm.
 - 2. General Access: 8:00 am to 4:00 pm.
- B. Confine operations at the site to areas permitted by:
 - 1. Laws
 - 2. Ordinances
 - 3. Permits

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

4. Contract Documents
 5. DMH Requirements
- C. All on-site workers will be required to wear identifying name badges.
- D. The Contractor shall supervise the use of the Site related to construction and be responsible for correcting any damage identified by DMH to DMH's satisfaction.
1. An existing conditions survey shall be conducted prior to any work being performed with the DMH Project Manager and the DMH Site Director or their representatives.
- E. All available existing utilities adjacent to the construction site will be available for use during construction unless indicated otherwise. These utilities would include water, sewer, and electricity. Temporary connections to these utilities, all metering, transformers, removal, usage, and their associated costs will be the responsibility of the Contractor.
- F. All apparatus, storage, and the operation of workmen in connection with activities under this Section shall be confined to limits of the Contract. Storage will not be permitted on the property without the approval of the DMH Project Manager.
- G. All parking regulations shall be observed.
- H. All vehicles carrying loose, dry material or refuse, construction debris, etc., shall be covered by tarpaulins to prevent blowing away or spillage of contents. All spillage of whatever nature shall be promptly taken up and removed.

1.11 COORDINATION

- A. The Contractor shall be responsible for the proper fitting of all the work and for the coordination of the operations of all trades, subcontractors or material and men engaged upon the work. The Contractor shall do, or cause his agents to do, all cutting, fitting, adjusting, and repair necessary in order to make the several parts of the work come together properly.
1. Examine Contract Documents in advance of start of construction and identify in writing questions, irregularities or interference to the DMH Project Manager in writing. Failure to identify and address such issues in advance becomes the sole responsibility of the Contractor.
- B. Execute the work in an orderly and careful manner with due regard to the occupants of the facility, the public, the employees, and the normal function of the facility.
- C. The work sequence shall follow the planning of the schedule established by the

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

Contractor and as approved by the DMH Project Manager. The work upon the site of the project shall commence promptly and be executed with full simultaneous progress. Work operations which require the interruption of utilities, service, and access shall be scheduled so as to involve minimum disruption and inconvenience, and to be expedited so as to insure minimum duration of any periods of disruption or inconvenience.

- D. The Contractor shall review the tolerances established in the specifications for each type of work and as established by trade organizations. The Contractor shall coordinate the various trades and resolve any conflicts that may exist between trade tolerances without additional cost to DMH. The Contractor shall provide any chipping, leveling, shoring or surveys to ensure that the various materials align.
- E. The Contractor shall coordinate all work that impacts the fire suppression and alarm system with the Fire Alarm Company including preparation, demolition, modernization, and testing. Costs associated with the Fire Alarm Company that are directly related to this Contract are to be included in the Contract price.
- F. The Contractor shall coordinate all work that impacts the emergency generator system with the Emergency Generator Company including preparation, demolition, modernization, and testing. Costs associated with the Emergency Generator that are directly related to this Contract are to be included in the Contract price.

1.12 REFERENCE STANDARDS

- A. For products specified by association or trade standards, comply with requirements for the standard, except where more rigid requirements are specified or are required by codes. Refer to the specific Specification for specific references.
- B. Where reference is made in the Contractual Documents to Publications and Standards issued by Associations or Societies, the intent shall be understood to specify the current edition of such Publications or Standards (including tentative revision) in effect on the date of the contract advertisement notwithstanding any reference to a particular date.

1.13 PRECONSTRUCTION CONFERENCE

- A. In accordance with Article V of the CONTRACT AND GENERAL CONDITIONS, a pre-construction conference to review the work will be conducted by the DMH Project Manager.
- B. Representatives of the following shall be required to attend this conference:
 - 1. DMH Project Manager
 - 2. DMH Site Director
 - 3. Contractor

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

- 4. All Subcontractors
- C. The Contractor shall have a responsible representative at the pre-construction conference to be called by the DMH Project Manager following the award of the Contract, as well as representatives of field or office forces and major subcontractors. All such representatives shall have authority to act for their respective firms. The pre-construction conference is to be held within five days of Notice to Proceed, or as otherwise determined by DMH.

1.14 WORK BY DMH

- A. DMH will provide Site Access
- B. DMH will designate parking and staging areas.
- C. DMH will provide access to water, electrical, with sanitary facilities being supplied by the Contractor. If the Contractor requires additional power, the Contractor is responsible to provide the additional power under the base contract fee.

1.15 SUBCONTRACTORS

- A. After selection, the successful Bidder shall submit a list of subcontractors proposed for the performance of the Work to DMH for approval. The list shall include the name, address, contact person, and MA tax identification number for each subcontractor.

1.16 PROJECT MEETINGS

- A. Project meetings shall be held on a weekly basis and as required subject to the discretion of the DMH Project Manager.
- B. As a prerequisite for monthly payments, ordering schedules, shop drawing schedules, and coordination meeting schedules shall be prepared and maintained by the Contractor and shall be revised and updated on a monthly basis, and a copy shall be submitted to the DMH Project Manager.
- C. In order to expedite construction progress on this project, the Contractor shall order all materials immediately after the approval of shop drawings and shall obtain a fixed date of delivery to the project site for all materials ordered which shall not impede or otherwise interfere with construction progress. The Contractor shall present a list and written proof of all materials and equipment ordered (through purchase orders). Such list shall be presented at the meetings and shall be continuously updated.
- D. Scheduling shall be discussed with all concerned parties, and methods shall be presented by the Contractor which shall reflect construction completion not being

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

deferred or foreshortened. Identify critical long-lead items and other special scheduling requirements. The project schedule is to include time for submission of shop drawing submittals, time for review, and allowance for resubmittal and review.

- E. Project meetings shall be chaired by the DMH Project Manager.
- F. Minutes of the project meetings shall be prepared by the DMH Project Manager and shall be distributed to all present within 72 hours of the Project Meeting.

1.17 PERMITS, INSPECTION AND TESTING REQUIRED BY GOVERNING AUTHORITIES

- A. If the Contract Documents, laws, ordinances, rules, regulations or orders of any public authority having any jurisdiction require any portion of the Work to be inspected, tested, or approved, the Contractor shall give the DMH Project Manager or his/her designated representative, and such Authority timely notice of its readiness so the DMH Project Manager may observe such inspecting, testing, or approval.
- B. Prior to the start of construction, the Contractor shall complete application to the applicable Building Code enforcement authority for a Building Permit. Such Permit shall be displayed in a conspicuous location at the project site.
- C. Unless otherwise specified under the Sections of the Specifications, the Contractor shall pay such proper and legal fees to public officers and others as may be necessary for the due and faithful performance of the work and which may arise incidental to the fulfilling of this Contract. As such, all fees, charges and assessments in connection with the above shall be paid by the Contractor.

1.18 CUTTING, CORING, AND PATCHING, UNLESS OTHERWISE INDICATED

- A. The Contractor shall do all cutting, coring, fitting and patching of his work that may be required to make its several parts come together properly and fit it to receive or be received by work of the Subcontractors as indicated in the Specifications.
- B. The Contractor shall not endanger any work by cutting, coring, excavating or otherwise altering the work and shall not cut or alter the work of any other Subcontractor except with the written consent of the DMH Project Manager.
- C. Submit a written request to the DMH Project Manager well in advance of executing any cutting or alteration which affects:
 - 1. Work of DMH or separate contractor.
 - 2. Structural value or integrity of any element of the Project.
 - 3. Integrity or effectiveness of weather-exposed or moisture-resistant elements or systems.
 - 4. Efficiency, operational life, maintenance, or safety of operational elements.

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

5. Visual qualities of sight-exposed elements.
6. Request shall include:
 - a. Identification of the Project.
 - b. Description of affected work.
 - c. The necessity for cutting, alteration, or excavation.
 - d. Effect on work of DMH or any separate contractor, or on structural or weatherproof integrity of Project.
 - e. Description of proposed work:
 - f. Alternatives to cutting and patching.
 - g. Cost proposal, when applicable.
 - h. Written permission of any separate contractor whose work will be affected.
7. Should conditions of Work or the schedule indicate a change of products from original installation, Contractor shall submit request for substitution to the DMH Project Manager.
8. Submit written notice to the DMH Project Manager designating date and time the work will be uncovered a minimum of three business days in advance.

D. Performance:

1. Execute cutting and patching by methods which will prevent damage to other work and will provide proper surfaces to receive installation of repairs.
 - a. In general, where mechanical cutting is required, cut work with sawing and grinding tools, not with hammering and chopping tools. Core drill openings through concrete work.
 - b. Prior to cutting and structural steel or concrete work, contact the DMH Project Manager in writing. Do not cut any structural steel and concrete work until approval has been granted by the DMH Project Manager.
2. Execute fitting and adjustment of products to provide a finished installation to comply with specified products, functions, tolerances, and finishes.
3. Restore work which has been cut or removed; install new products to provide completed Work in accordance with requirements of Contract Documents.
4. Fit work airtight to pipes, sleeves, ducts, conduit, and other penetrations through surfaces.
5. Patch with seams which are durable and as invisible as possible. Comply with specified tolerances for the work.
6. Restore exposed finishes of patched areas; and, where necessary extend finish restoration onto retained work adjoining, in a manner which will eliminate evidence of patching.
 - a. Where patch occurs in a smooth painted surface, extend final paint coat over the entire unbroken surface containing the patch.
7. Refinish entire surfaces as necessary to provide an even finish to match adjacent finishes:
 - a. For continuous surfaces, refinish to nearest intersection.
 - b. For an assembly, refinish entire unit.

E. Existing Utilities Services:

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

1. Interruptions to critical existing utility services will not be allowed.
2. The Contractor shall locate and record on Drawings all existing utilities along the course of the work by such means as the DMH Project Manager may approve, and shall preserve such marked locations until the work has progressed to the point where the encountered utility is fully exposed and protected as required. It shall be the Contractor's responsibility to notify the proper authorities and/or utility company before interfering therewith.
3. All exposed conduits, wires, and/or cables shall be provided with sufficient protection and support to prevent failure, fraying, or damage due to backfilling or other construction operations.
4. The Contractor shall not obstruct access to existing active utility system manholes and catch basins which continue to serve facilities other than the project construction site. The Contractor shall exercise measures as necessary to prevent the placement of impediments that limit continuous access by authorized utility company or DMH maintenance personnel and shall be required to reimburse the utility company or DMH for any expense incurred as a result of need to remove any such impediments to access.

**1.19 PERMITS, INSPECTION AND TESTING REQUIRED BY GOVERNING
AUTHORITIES**

- A. If the contract documents, laws, ordinances, rules, regulations or orders of any public authority having jurisdiction required any portion of the work to be inspected, tested or approved, the Contractor shall give the DMH Project Manager notice of its readiness so the DMH Project Manager may observe such inspection and testing.
- B. Prior to the start of construction, the Contractor shall complete application to the applicable Building Code enforcement authority for a Building Permit. Such Permit shall be displayed in a conspicuous location at the project site. The Contractor shall pay all costs associated with the Building Permit.

1.20 SECURITY REQUIREMENTS

- A. The Contractor shall familiarize himself with DMH's security requirements and shall always abide by and conform with such established regulations. The Contractor shall submit a list of personnel who will be responsible for the rehabilitation work and the maintenance service. List shall be kept current by Contractor.
- B. Proper identification must always be worn.

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

1.21 SAFETY REQUIREMENTS

- A. OSHA Safety and Health Course Documentation Records: Chapter 306 of the Massachusetts Acts of 2004 requires that everyone employed at the jobsite must complete a minimum 10-hour long course in construction safety and health approved by the U.S. Occupational Safety and Health Administration (OSHA) prior to working at the jobsite. Compliance is required for the Contractor's and subcontractors' on-site employees at all levels. This requirement does not apply to home-office employees visiting the Site or to suppliers' employees who are making deliveries.

- B. Documentation records shall be initially complied by the Contractor and subcontractors as part of certified payrolls, and the Contractor shall create and maintain a copy of the documentation on-site at all times.

- C. Building will be occupied during execution of work. Work shall be conducted in a manner to afford maximum protection of building, facilities, employees and the public and to prevent unreasonable delay or interference with normal functioning of the residences.

- D. Provide fire extinguishers so that they shall always be readily available.

- E. All accident reports are to be transmitted to the DMH Project Manager within 24 hours of occurrences.

- F. The Contractor shall be responsible for initiating, maintaining, and supervising all safety precautions and programs in connection with his direct work.

- G. The Contractor shall take all reasonable precautions for the safety of, and shall provide all reasonable protection to prevent damage, injury or loss to:
 - 1. All employees on the Work and all other persons who may be affected thereby.
 - 2. All the work and all materials and equipment to be incorporated therein, whether in storage on or off site, under the care, custody or control of the subcontractors.
 - 3. Other property at the site or adjacent thereto, including trees, shrubs, lawns, walks, pavements, roadways, structures and utilities not designated for removal, relocation or replacement in the course of construction.

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

- H. Provide screens, partitions or other approved barricades to effectively isolate building personnel and public from the work areas that are necessary during the demolition and reconstruction of the main entry and ancillary areas affected by the main entry upgrading during its time of closure. In addition, provide any and all necessary safety barriers within the surrounding construction area due to the demolition and ongoing construction
- I. It shall be the obligation of the general contractor to maintain secure and safe control of parts, tools, etc., and shall be kept within the confines of the safety barricades of the construction area.
- J. The Contractor shall comply with all applicable laws, ordinances, rules, regulations, and lawful orders of any public authority having jurisdiction for the safety of persons or property or to protect them from damage, injury or loss. He shall erect and maintain, as required by existing conditions and progress of the work, all reasonable safeguards and protection, including barricades, posting danger signs and other warnings against hazards, promulgating safety regulations and notifying owners and users of adjacent utilities.
- K. The Contractor shall not load or permit any part of the work to be loaded to endanger its safety.
- L. In any emergency affecting the safety of persons or property, the Contractor shall act to prevent threatened damages, injury, or loss.

****** END OF SECTION ******

**SECTION 012300
ALTERNATES**

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

- A Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for alternates.

1.3 DEFINITIONS

- A. Alternate: An amount proposed by bidders and stated on the Bid Form for certain work defined in the bidding requirements that may be added to or deducted from the base bid amount if Owner decides to accept a corresponding change either in the amount of construction to be completed or in the products, materials, equipment, systems, or installation methods described in the Contract Documents.
 - 1. Alternates described in this Section are part of the Work only if enumerated in the Agreement.
 - 2. The cost or credit for each alternate is the net addition to or deduction from the Contract Sum to incorporate alternate into the Work. No other adjustments are made to the Contract Sum.

1.4 PROCEDURES

- A. Coordination: Revise or adjust affected adjacent work as necessary to completely integrate work of the alternate into the Project.
 - 1. Include as part of each alternate, miscellaneous devices, accessory objects, engineering, and similar items incidental to or required for a complete installation whether or indicated as part of the alternate.
- B. Notification: immediately following award of the Contract, notify each party involved, in writing, of the status of each alternate. Indicate if alternates have been accepted, rejected, or deferred for later consideration. Include a complete description of negotiated revisions or alternates.
- C. Execute accepted alternates under the same conditions as other work of the Contract.

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

- D. Schedule: A schedule of alternates is included at the end of this Section.
Specification Sections referenced in schedule contain requirements for materials necessary to achieve the work described under each alternate.

PART 2 – PRODUCTS (Not Used)

PART 3 – EXECUTION

3.1 SCHEDULE OF ALTERNATES

- A. Add Alternate No. 1: Room # 227
 - 1. Remove existing carpet, prepare floor beneath and install new carpet squares as specified in the base bid. Refer to Sheet A3 – Second Floor Plan for location.

- B. Add Alternate No. 2 West Wing Corridor
 - 2. Remove existing carpet, prepare floor beneath and install new carpet squares as specified in the base bid. Refer to Sheet A3 – Second Floor Plan for location.

******END OF SECTION******

**SECTION 013300
SUBMITTALS**

PART 1 – GENERAL

1.1 PROVISIONS INCLUDED

Attention is directed to the CONTRACT and GENERAL CONDITIONS and all Sections within DIVISION 1 – GENERAL REQUIREMENTS which are hereby made a part of this Section of the specification.

1.2 REQUIREMENTS

Shop drawings, product data, samples, and schedules of values.

1.3 SHOP DRAWINGS, PRODUCT DATA AND SAMPLES

A. General:

Review and submit to the Project Engineer, shop drawings, product data and samples required by specification Section.

B. Shop Drawings:

1. Original drawings shall be prepared by General Contractor, Subcontractor, supplier or distributor, which illustrate some portion of the work; showing fabrication, layout, setting or erection details.

- a. Shop drawings shall be prepared by a qualified detailer.
- b. Details shall be identified by reference to sheet and detail number shown on contract drawings.
- c. Maximum sheet size shall be 30 inch by 42 inch.
- d. Reproductions for submittals shall be reproducible transparencies with the required number of opaque prints specified herein.

C. Project Data:

1. Manufacturer's standard schematic drawings:

- a. Modify drawings to delete information which is not applicable to project.
- b. Supplement standard information to provide additional information applicable to project.

2. Manufacturer's catalog sheets, brochures, diagrams, schedules, performance charts, illustrations and other standard descriptive data:

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

- a. Clearly mark each copy to identify pertinent materials, products or models.
 - b. Show dimensions and clearances required.
 - c. Show performance characteristics and capacities.
 - d. Show wiring diagrams and controls.
- D. Samples: Physical examples to illustrate materials, equipment or workmanship, and to establish standards by which completed work is judged.
1. Office Samples: Of sufficient size and quantity to clearly illustrate:
 - a. Functional characteristics of product or materials, with integrity related parts and attachment devices.
 - b. Full range of color samples.
 - c. After review, approved samples may be incorporated into the project construction if not retained for comparison.
- E. General Contractors Responsibilities:
1. Coordinate each submittal with requirements of work and contract documents.
 2. The General Contractors responsibility for errors and omissions in submittals is not relieved by Project Engineer's review of submittals.
 3. Notify the Project Engineer in writing at time of submission, of deviations in submittals from requirements of contract documents or previous submissions.
 4. Work that requires submittals shall not commence unless submittals have Project Engineer's stamp and initials or signature indicating review and approval.
 5. After Project Engineer's review, distribute required copies.
- F. Submission Requirements:
1. Make submittals promptly and in such sequence as to cause no delay in the work.
 2. Submit one (1) electronic file and four (4) opaque copies of shop drawings, and number of copies of product data which contractor requires for distribution, plus two (2) copies which will be retained by the Project Engineer.
 3. Submit number of samples specified in each specification Section.
 4. Forward submittals with transmittal letter.
 5. Submittals shall include:
 - a. Date and revision date.
 - b. Project title.
 - c. The names of:
 1. General Contractor
 2. Subcontractor

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

3. Supplier
4. Manufacturer
- d. Identification of product or material.
- e. Relation to adjacent structure of materials.
- f. Field dimensions, clearly defined as such.
- g. Specification Section number.
- h. Applicable standards, such as ASTM number.
- i. A blank space 5 inches by 4 inch, for the Engineer's stamp.
- j. Identification of deviations from contract document.
- k. General Contractors stamp, initialized or signed, certifying review and approval of submittals.

G. Resubmission Requirements:

1. Shop Drawings:
 - a. Drawings, data or samples shall be designated approved, approved as noted, revise and resubmit or rejected.
 - b. Revise drawings as required and resubmit as specified for previous submittal.
2. Product Data and Samples: Submit new data and samples as required from previous submittals.

H. Distribution of Submittals after Review:

1. Distribute copies of shop drawings and project data which display Project Engineer's stamp to appropriate Subcontractors.

1.4 SCHEDULE OF VALUES

Prior to the first request for payment, the General Contractor shall submit to the Project Engineer a Schedule of Values of the various portions of the work in sufficient detail to reflect various major components of each trade, including quantities when requested, aggregating the total contract sum, and divided so as to facilitate payments for work under each Section. Each item in the Schedule of Values shall include its proper share of overhead and profit. This schedule shall be used only as a basis for the contractor's request for payment.

****** END OF SECTION ******

**SECTION 015000
CONSTRUCTION FACILITIES AND TEMPORARY CONTROLS**

PART 1 – GENERAL

1.1 GENERAL PROVISIONS

Attention is directed to the CONTRACT and GENERAL CONDITIONS and all Sections within DIVISION 1 – GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 DESCRIPTION

The contractor shall be responsible for providing and maintaining temporary construction facilities and controls as specified herein.

1.3 HOISTING EQUIPMENT AND MACHINERY

All hoisting equipment and machinery required for the proper and expeditious prosecution and progress of the work shall be furnished, installed, operated and maintained in safe condition by the General Contractor for the use of all Subcontractor's material and/or equipment delivered to the designated hoisting area except that which is specifically required to be provided by the Subcontractors themselves and is so stated in each appropriately related Section of the Specifications. All costs for hoisting operating services shall be borne by the General Contractor unless specifically excepted in the Contract Documents.

1.4 STAGING AND TEMPORARY LADDERS, RAMPS, RUNWAYS, ETC.

All staging, exterior and interior, required to be over eight feet in height, shall be furnished and erected by the General Contractor and maintained in safe condition by him without change to, and for the use of all trades as needed by them for proper execution of their work, except where specified to the contrary in any filed sub-bid Section of the Specifications.

1.5 DUST CONTROL

- A. The General Contractor shall provide adequate means for the purpose of preventing dust caused by construction operations throughout the period of the construction contract.
- B. This provision does not supersede any specific requirements for methods of construction or applicable general conditions set forth in the contract articles with added regard to performance obligations of the General Contractor.

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

- C. The General Contractor shall provide and maintain floor mats at access points to prevent the tracking of dust.

1.6 NOISE CONTROL

- A. Develop and maintain a noise-abatement program and enforce strict discipline over all personnel to keep noise to a minimum.
- B. Execute construction work by methods and by use of equipment which will reduce excess noise.
 - 1. Equip air compressors with silencers and power equipment with mufflers.

1.7 ENCLOSURES

- A. Provide temporary, insulated, weather tight closures of openings in exterior surfaces for providing acceptable working conditions and protection of materials, allowing for heating during construction, and preventing entry of unauthorized persons. Provide doors with self-closing hardware and locks.
- B. Provide temporary partitions and ceilings as required to separate work areas from User Agency's occupied areas, to prevent penetration of dust and moisture into User Agency's occupied areas, to prevent damage to existing areas and equipment. Construction shall be framing and sheet materials with closed joints and sealed edges at intersections with existing surfaces; STC rating 35 in accordance with ASTM E90.
- C. Provide sheet material and tape to seal HVAC supplies and exhaust. Insure that dust does not enter the ductwork.

1.8 CLEANING DURING CONSTRUCTION

- A. Unless otherwise specified under the various trade Sections of the Specifications, the General Contractor shall perform clean-up operations during construction as herein specified.
- B. Control accumulation of waste materials and rubbish periodically dispose of off-site. The general contractor shall bear all costs, including fees resulting from such disposal.
- C. Store volatile wastes in covered metal containers and remove from premises.
- D. Prevent accumulation of wastes which create hazardous conditions.
- E. Provide adequate ventilation during use of volatile or noxious substances.

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

- F. Conduct cleaning and disposal operation to comply with local ordinances and anti-pollution laws.
 - 1. Do not burn rubbish and waste materials on site.
 - 2. Do not dispose of volatile wastes such as mineral spirits, oil, or paint thinner in storm or sanitary drains.
- G. Use only those materials which will not create hazards to health or property and which will not damage surfaces.
- H. Use only those cleaning materials and methods recommended by manufacturer of surface materials to be cleaned.
- I. Provide on-site containers for collection of waste materials, debris and rubbish.
- J. Remove waste materials, debris and rubbish from the site periodically and dispose of at legal disposal areas off the construction site.

****** END OF SECTION ******

**SECTION 016000
PRODUCT REQUIREMENTS**

PART 1 – GENERAL

1.1 GENERAL PROVISIONS

Attention is directed to the CONTRACT and GENERAL CONDITIONS and all Sections within DIVISION 1 – GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 PRODUCTS

- A. Products include material, equipment, and systems.
- B. Comply with Specifications and referenced standards as minimum requirements.
- C. Components required to be supplied in quantity within a specification section shall be the same and shall be interchangeable.
- D. Do not use materials and equipment removed from existing structures, except as specifically required, or allowed, by the contract documents.

1.3 WORKMANSHIP

- A. Comply with industry standards except when more restrictive tolerances or specified requirements indicate more rigid standards or more precise workmanship.
- B. Perform work by persons qualified to produce workmanship of specified quality.
- C. Secure products in place with positive anchorage devices designed and sized to withstand stresses, vibration and racking.

1.4 MANUFACTURER'S INSTRUCTIONS

- A. When work is specified to comply with manufacturer's instructions, submit copies as specified in Section 01300, SUBMITTALS.
- B. Perform work in accordance with details of instructions and specified requirements.

1.5 TRANSPORTATION AND HANDLING

- A. Refer to CONTRACT and GENERAL CONDITIONS and Specifications

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

Sections for requirements pertaining to transportation and handling of materials and equipment.

- B. Transport products by methods to avoid product damage; deliver in undamaged condition in manufacturer's unopened containers or packaging, dry.
- C. Provide equipment and personnel to handle products by methods to prevent soiling or damage.
- D. Promptly inspect shipments to assure that products comply with requirements, that quantities are correct, and products are undamaged.

1.6 STORAGE AND PROTECTION

- A. Refer to CONTRACT and GENERAL CONDITIONS and Specifications Sections for requirements pertaining to storage and protection of materials and equipment.
- B. Store products in accordance with manufacturer's instructions, with seals and labels intact and legible. Store sensitive products in weathertight enclosures; maintain within temperature and humidity ranges required by manufacturer's instructions.
- C. For exterior storage of fabricated products, place on sloped supports above ground. Cover products subject to deterioration with impervious sheet covering; provide ventilation to avoid condensation.
- D. Store loose granular materials on solid surfaces in a well-drained area; prevent mixing with foreign matter.
- E. Arrange storage to provide access for inspection. Periodically inspect to assure that products are undamaged and are maintained under required conditions.

****** END OF SECTION ******

**SECTION 017000
CLOSEOUT PROCEDURES**

PART 1 – GENERAL

1.1 GENERAL PROVISIONS

Attention is directed to the CONTRACT and GENERAL CONDITIONS and all Sections within DIVISION 1 – GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 FINAL CLEANING

- A. Unless otherwise specified under the various Sections of the Specifications, the General Contractor shall perform final cleaning operations as herein specified prior to final inspection.
- B. Maintain project site free from accumulations of waste, debris, and rubbish caused by operation. At completion of work, remove waste materials, rubbish, caused by operation. At completion of work, remove waste materials, rubbish, tools, equipment, machinery and surplus materials, and clean all sight-exposed surfaces; leave project clean and ready for occupancy.
- C. Cleaning shall include all surfaces, interior and exterior in which the General Contractor has had access whether existing or new.
- D. Refer to Section of the Specifications for cleaning or specific products or work.
- E. Use only those materials which will not create hazards to health or property and which will not damage surfaces.
- F. Use only those cleaning materials and methods that are recommended by the manufacturer of surface material to be cleaned.
- G. Employ experienced workmen or professional cleaners for final cleaning operations.
- H. Remove grease, mastic, adhesives, dust, dirt, stains, labels, fingerprints, and other foreign materials from sight-exposed interior and exterior surfaces.
- J. Repair, patch and touch up marred surfaces to specified finish, to match adjacent surfaces.
- K. Polish glossy surfaces to a clear shine.

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

- L. Prior to final completion, or User Agency Use and Occupancy, the General Contractor shall conduct an inspection of sight-exposed interior and exterior surfaces, and all work areas, to verify that the entire work is clean.

1.3 RECORD DRAWINGS

- A. Record Drawings shall consist of **all** the contract drawings.
- B. The General Contractor and all Subcontractors shall be required to maintain one set of Record Drawings, as the work relates to their Sections of the Specifications, at the site.

1.4 GUARANTEES AND WARRANTIES

Submit to the Project Engineer all extended guarantees and warranties that have been specified in various, individual Sections of the Specifications.

****** END OF SECTION ******

**SECTION 024119
SELECTIVE DEMOLITION**

PART 1 – GENERAL

1.1 GENERAL PROVISIONS

Attention is directed to the CONTRACT and GENERAL CONDITIONS and all Sections within DIVISION 1 – GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 DESCRIPTION

- A. It is not the intent herein to describe all the items and work required to be removed under this Section. The General Contractor shall assure himself that all of the work to be removed, not otherwise specified herein or described under other Sections, but shown on the Drawings, shall be removed under this Section at no additional cost to the Commonwealth.
- B. The General Contractor shall also examine other Sections of these Specifications and familiarize himself with their provisions regarding the removal of existing items and work. He shall understand that all items and work not specifically mentioned to be removed by the requirements of other Sections of these Specifications shall be removed as part of the work under this Section.
- C. The scope of work consists of material and services to be furnished under this Section, and without limiting the generality thereof, includes labor, equipment and services required for the removal of existing work, special protection and all work incidental thereto as specified herein and as shown on the Drawings.

1.3 RELATED WORK SPECIFIED ELSEWHERE

- A. The following work is not included in this Section and is to be performed under the designated Sections:
 - 1. Movable items and items of User Agency's equipment in the areas of the existing building affected by the work under this Contract will be removed by the User Agency.
 - 2. SECTION 025000 – ASBESTOS ABATEMENT
 - 3. Cutting and core drilling for new electrical work will be performed by these respective trades.
 - 4. Disconnecting of existing services as required will be done by the

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

respective Mechanical and Electrical trades specified under Plumbing; Heating; Ventilating and Air Conditioning; and Electrical Work Sections, if applicable, otherwise General Contractor will be responsible for supplying trained individuals to complete the necessary work.

1.4 PERMITS AND CODES

- A. Work specified herein shall conform to the Drawings and Specifications and shall comply with all rules, regulations, laws and ordinances of the Commonwealth of Massachusetts.
- B. The General Contractor shall procure and pay for all permits and licenses required for the complete work specified or inferred under this Section.

1.5 SCHEDULING

- A. Before beginning the removal of work and demolition, the General Contractor shall consult jointly with the Facility and Project Engineer to determine the schedule of work, exact places, times and days during which the removal and demolition work may, or may not be carried on, and to determine further reasonable requirements, particularly in regards to noise prevention, dust prevention, weather protection, and safety precautions.
- B. No work shall be started in existing building without prior approval of the Facility. The General Contractor shall give the Facility adequate advance notice of his readiness to start such work in order that they may properly rearrange activities or evacuate the spaces to be affected.

1.6 EXAMINATION OF PREMISES

The Contractor will be held to have examined the premises before submitting proposals for the work and to have satisfied himself as to the existing conditions under which he will be obliged to operate or that will in any way affect the work under this Contract, also the character and amount of materials and debris to be removed. No allowances will be made in this connection for error or negligence of the Demolition Contractor.

1.7 USE OF PREMISES

- A. All apparatus, storage, and the operation of workmen in connection with activities under this Section shall be confined to limits of the Contract. Storage will not be permitted on the property without the approval of the Facility.
- B. All parking regulations shall be observed.

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

- C. All trucks carrying loose, dry material such as debris, broken concrete block, plaster, etc., shall be covered by tarpaulins to prevent blowing away or spillage of contents. All spillage of whatever nature shall be promptly taken up and removed.

1.8 PROTECTION

- A. The removal of all portions of the structure to be removed shall be done with utmost care, using tools and methods that will not transfer any heavy shocks to the remaining portions of the existing building. All possible care shall be taken to avoid vibration and other disturbances.
- B. All existing items directed by the Project Engineer to be retained as the User Agency's property or relocated as shown on the drawings or noted herein, shall be handled and removed with full consideration for their preservation. It is the full responsibility of the General Contractor to replace, without additional charge to the Commonwealth, all such items which are lost or damaged due to the removal operations or handling.
- C. When removing materials and making openings in walls, floors, etc., the General Contractor shall take all precautions and use whatever protective devices, shoring, guardrails, and the like as may be required to assure that the remaining and adjacent portions of the existing work which is to remain is substantially supported and/or not loaded beyond safe limits.
- D. Consult with the Program Manager regarding the electrical/mechanical equipment.

PART 2 – MATERIALS

2.1 DISPOSAL OF WORK REMOVED

- A. All non-salvageable refuse and debris which accumulate as a result of work under this Section shall be removed. No refuse or debris of any nature shall be allowed to accumulate to the detriment of the work.
- B. All existing items removed under this Section shall become the responsibility of the Demolition Contractor, and legally be disposed of off-site at his expense, unless such existing items to be removed are specifically noted on the drawings to be relocated or unless otherwise directed by the Project Engineer to be rendered to and become the property of the Commonwealth.
- C. Remove debris in covered containers on a route designated by the Facility.

PART 3 – EXECUTION

3.1 PREPARATION

Before starting the removal of work, the Contractor shall arrange for the disconnection of active utility services in the areas to be worked in. All work on existing utilities shall be accomplished by the respective subtrades or utility companies having jurisdiction.

3.2 REMOVAL OF EXISTING WORK

- A. Provide dust protection to contain dust and debris to the work area.
- B. Caution should be taken when removing all demolition material from the building to prevent damage to existing conditions to the property within and without the work area.

3.3 CLEAN-UP

At the completion of work, all rubbish, debris, waste, materials, and salvaged materials shall be removed from the site. All tools, scaffolds, apparatus and appliances used in connection with work under this Section shall be removed by the Contractor, and the premises shall be left in clean condition, ready for the alteration work as described under other Sections of these Specifications.

****** END OF SECTION ******

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

**SECTION 025000
ASBESTOS ABATEMENT**

PART 1 – GENERAL

1.01 GENERAL PROVISIONS

- A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all sections within DIVISION 1 – GENERAL REQUIREMENTS that are hereby made a part of this Section. Note also all Alternates and Addenda.
- B. For the purpose of this Section, the following definitions apply:
"Site" shall refer to the Haskell Building, located in Northampton, Massachusetts. *"Contractor"* shall refer to the Asbestos Abatement Contractor. *"Owner"* shall refer to Department of Mental Health. *"Consultant"* shall refer to EFI Global, Inc. *"ACM"* shall refer to *Asbestos-Containing Material*.
"ACWM" shall refer to *Asbestos-Containing Waste Material*.

1.02 RELATED REQUIREMENTS

- A. Examine the Floor Plan provided by the Owner and all other specification sections for requirements affecting the work of this Section whether or not such work is specifically mentioned in this Section.
- B. Coordinate work with that of all other trades affecting or affected by work of this Section. Cooperate with such trades to assure the steady progress of all work under the Contract.

1.03 DESCRIPTION OF WORK

A. PROJECT DESCRIPTION

The Contractor shall furnish all labor, materials, equipment, and services for the legal removal and disposal of all specified asbestos-containing materials, as outlined in the specifications.

- 1. The project involves the removal of specified areas of ACM from interior locations at the site building. The Contractor is responsible for proper removal and disposal of all ACM listed below in the Summary of Work Table:

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

Table 1: Summary of Work for Asbestos Abatement Haskell Building – 2nd Floor Corridors and Offices Northampton, Massachusetts		
Material Description	Material Location	Estimated Quantity
Remove and properly dispose of 9” x 9” gray floor tile in full negative pressure containment with attached 3-stage decontamination unit.	Rooms 247 & 265	270 SF
Remove and properly dispose of 9” x 9” gray with green streak floor tile in full negative pressure containment with attached 3-stage decontamination unit.	Rooms 228, 245, 246, 248, 264 & 2 nd Floor East Wing Corridor	3,700 SF
Remove and properly dispose of 9” x 9” brown replacement floor tile in full negative pressure containment with attached 3-stage decontamination unit.	Rooms 246 & 264	70 SF
Remove and properly dispose of 9” x 9” green with black speck floor tile in full negative pressure containment with attached 3-stage decontamination unit.	Room 256	570 SF

SF – square feet

1. Bidders are required to verify the locations and quantities of all materials prior to the bid deadline, including the dimensions and locations of areas requiring abatement as well as the types of materials to be abated. If further investigation time is required for the quantity verification, arrangements shall be made as needed. This estimation shall be performed prior to the submission of the bid. Bidders shall inform the Consultant and the Owner of any discrepancies between the quantities and types of materials specified herein and those verified to be present by the Bidder. If appropriate, an adjustment shall be made as to the types and/or quantities to be included in the Bid. If no discrepancies with the types and/or quantities of materials to be abated are brought to the attention of the Consultant and the Owner prior to the Bid due date, it will be understood that the Bidders are in agreement with the types and quantities of materials specified herein, and no change orders will be allowed for these materials.
2. The locations and quantities of the ACM and ACWM noted above are approximate only. The Contractor is responsible for identification, field verification, and removal of all ACM and ACWM specified above.
3. The Contractor is responsible for demolition to access, investigate, and remove all ACM and ACWMs specified in the Scope of Work Table. The Contractor shall include in the base bid all costs for demolition to access all ACM and ACWM identified herein.

B. GENERAL SCOPE OF WORK

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

The following is the General Scope of Work, at a minimum, required to be performed by the Contractor for asbestos abatement work in each of the work areas identified below. The Contractor shall adhere to the Scope of Work outlined below and depicted by the drawings as well as any additional requirements stated herein.

1. Work area preparation, including pre-cleaning, installation of critical barriers and polyethylene sheeting, construction of decontamination facilities, work area enclosures, sealing, isolation, and other activities as directed by the Consultant or the Owner.
2. Work area preparations for each location in accordance applicable sections of MassDLS 454 CMR 28.0 and MassDEP 310 CMR 7.15 regulations.
3. Full containment removal, installation and operation of HEPA filtration units sufficient to achieve a minimum of four to six air changes per hour in each containment (if full containment removal is utilized). The exact locations of HEPA filtration units, decontamination units, and other stationary equipment shall be coordinated with other contractors, Owner and the Consultant.
4. Removal and disposal of all specified ACM, ACWM, asbestos contaminated materials and non-asbestos containing materials as specified above.
5. Pre-cleaning of all asbestos-containing debris, as necessary, in all work areas prior to abatement.
6. Furnishing of all labor, materials, equipment, insurance, and services required for all work included in this specification.
7. Compliance with all applicable federal, state, and local regulations, as well as, all requirements set forth in these specifications.
8. Decontamination, teardown, and clean up following abatement activities.
9. Performance of any other work or activities required by this specification, applicable regulations, or as necessary to perform a complete job to the satisfaction of the Owner, and Consultant.
10. The Consultant reserves the right to collect samples of any suspect ACM and ACWM in order to verify that the asbestos has been satisfactorily removed by the Contractor in accordance with the Specifications.

C. SPECIFIC SCOPE OF WORK

The following Work shall be conducted for this project. Examine all Project Drawings, and specifications for full extent and location of work to be conducted.

1. General Building Areas
 - a. The Contractor is responsible for all hookups to existing water and electricity at the Site to conduct the required asbestos abatement activities. The Contractor is responsible for retaining licensed and qualified electricians and plumbers to perform electrical and water hookups as necessary to perform the asbestos abatement activities specified herein. The Contractor is responsible for

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

payment of all electrical permit and connection fees. The Contractor is responsible for the installation of temporary lighting in all work areas (if required), backflow protection, sanitary facilities, and shall include all costs to provide a licensed electrician to assess the facilities and provide generators, transformers and temporary electrical hookups as necessary. The Contractor shall supplement the existing electricity available at the site with generators as necessary throughout the project, due to temporary or permanent electrical shutdowns.

- b. Remove and dispose of ACM and ACWM flooring from areas which are to be disturbed as part of the project, as noted above. Coordinate this work with other contractors at the site, the Owner and the Consultant. Coordinate all system shutdowns with the Consultant and Owner in advance.

D. PROJECT SCHEDULE

The project shall begin as soon as the 10 business day notifications take effect and upon receipt of written authorization to proceed from the Owner. The Contractor is responsible to complete work in each building area as specified on the Project Drawings. Completion of work includes obtaining satisfactory air clearance, acceptable post-tear-down inspection of each work area and any required clean-up resulting from tear down activities.

1.04 SEQUENCE OF WORK

The following provisions shall apply for asbestos abatement work as identified by this section. The Contractor shall apply these provisions to all work areas throughout the buildings.

- A. The Contractor shall decontaminate, remove and properly dispose of all specified ACM and ACWM located throughout each identified work area.
- B. Prior to the commencement of the work, all stored items and general items in each area and other miscellaneous items in all work areas deemed to be non-contaminated, except as noted herein, shall be removed from each work area by the Contractor and left for disposal by others. All non-contaminated non-movable items in all work areas shall be covered with two (2) layers of 6-mil polyethylene sheeting and sealed with duct tape.
- C. A three-chambered decontamination unit shall be erected at the entrance to each work area. The three-chambered decontamination unit shall consist of a clean room, a shower room, and an equipment room.
- D. All critical barriers shall be sealed with two (2) layers of six-mil polyethylene sheeting and negative pressure established.
- E. The Contractor shall pre-clean all floor drains, and non-movable items of any asbestos debris present. Pre-cleaning shall include the use of wet misting, wet wiping and/or HEPA vacuuming of all affected surfaces.
- G. All work shall be performed in accordance with all federal, state, and local regulations governing asbestos abatement. The Contractor shall assume full responsibility and

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

liability for compliance with all applicable federal, state, and local regulations pertaining to work practices and engineering controls, hauling and disposal of asbestos waste, and protection of workers, visitors to the work site, and persons occupying areas adjacent to the work site.

- H. The scheduling and sequencing of the Work of this Contract shall be determined by the Owner.

1.05 WORK INCLUDED

The total scope of work shall not be based solely on the information provided in this specification. The Contractor is required to perform quantity take-offs and measurements of the amount of material to be removed using floor plans and on a site visit. Work shall be based on the Contractor's own quantity take-offs of the work required by examination of the drawings and site conditions.

1.06 SPECIAL CONSIDERATIONS

The Owner will pay for the first set of final clearance air sampling and analyses for each work area. In the event that these analyses do not pass the clearance criteria, all subsequent air sampling and analyses for the affected work areas that need to be rerun will be paid for by the Contractor. Phase Contrast Microscopy (PCM) shall be utilized for clearance of all areas of ACM was removed (for full containment removal). All additional monitoring and sampling costs will be automatically deducted from the Contractor's contract price until the area in question passes the clearance criteria established in this section.

1.07 SUBMITTALS

- A. Before preparations are allowed to begin, the Owner and Contractor shall submit the following to the Consultant for approval:
 - 1. Copies of all notifications, permits, applications, licenses, and like documents required by federal, state, or local regulations obtained or submitted in proper fashion;
 - 2. Copies of Contractor's DLS licenses for asbestos;
 - 3. A sketch of the proposed containment(s) that includes all entrances, HEPA exhausts and critical barriers;
 - 4. A proposed timetable for the complete job that shows the preparation, removal and disposal, clean up, testing, and teardown portions of the job for each work area. A critical path showing completion dates for each area shall be included;
 - 5. Proof of the abatement supervisor's MassDLS license and training, including the most recent refresher course completed;
 - 6. Proof of each asbestos abatement worker's MassDLS license and training, including the most recent refresher courses completed;

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

7. Written site-specific Respiratory Protection Program for employees throughout all phases of the job, including make, model and NIOSH approval numbers of respirators to be used on this specific job.
 8. Proof that the asbestos abatement supervisor and workers have been fit-tested within the past twelve months for using a negative-pressure respirator equipped with HEPA filter cartridges.
 9. Proof that the abatement supervisor and workers have been examined by a qualified physician within the past 12 months and are capable of wearing respiratory protection and are able to perform asbestos abatement work and other related activities.
 10. Proposed electrical safeguards to be implemented, including but not limited to location of transformers, GFCI outlets, lighting, and power panels necessary to safely perform the job, including a description of electrical hazards safety plan for common practices in the work area.
 11. Chain of Command of responsibility at work site including supervisors, foreman, and competent person, their names, and resumes.
 12. Proposed Emergency Plan and route of egress from work areas in case of fire or injury, including the name, directions/map and phone number of nearest medical assistance center.
 13. The name and address of the Contractor's personal air monitoring and testing laboratory including certification of Massachusetts DLS accreditation.
 14. Name, address, and ID number of the asbestos waste hauler, and proposed disposal site(s);
 15. Any other documentation that applies and is called for by this or other sections of the specifications.
 16. No work on the project will be allowed to begin until Owner and Consultant as listed herein approve the Pre-Job Submittals. Any delay caused by the Contractor's refusal to submit this documentation in a timely manner does not constitute a cause for change order or a time extension.
 17. Contractor's written site-specific Health and Safety Plan that includes Hazcom, Respiratory Protection, Lockout/Tagout Programs with site-specific written plans; and,
- B. Upon completion of the asbestos abatement work, the Contractor shall submit the following to the Consultant for approval:
1. All waste shipment records and landfill receipts detailing disposal of all asbestos and asbestos-containing waste materials generated by the work.
 2. All analytical results of personal asbestos air samples collected in accordance with OSHA regulations to verify that the 8-hour time weighted average (TWA) concentrations of asbestos fibers in the breathing zone of the workers has not exceeded the permissible exposure limit (PEL) of 0.1 f/cc.

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

1.08 TRAINING AND QUALIFICATIONS

A. Worker Training

All workers who work on this project shall be provided training, at a minimum, on the following topics:

1. The health hazards of asbestos including the nature of asbestos related diseases, routes of exposure, known dose-response relationships, the synergistic relationship between asbestos exposure and cigarette smoking, latency periods, and health basis for standards.
2. Personal protective equipment including the types and characteristics of respirator classes, limitations of respirators, proper selection, inspection, donning, use, maintenance and storage of respirators, field testing the face piece to face seal (positive and negative pressure fit tests), qualitative and quantitative fit testing procedures, variations between laboratory and field fit factors, factors that affect respirator fit, selection and use of disposable clothing, use and handling of washable clothing, non-skid shoes, gloves, eye protection, and hard hats.
3. Medical monitoring requirements for workers including required and recommended tests, reasons for medical monitoring and employee access to records.
4. Air monitoring procedures and requirements for workers including description of equipment and procedures, reasons for monitoring, types of samples and current standards with recommended changes.
5. Work practices for asbestos and hazardous materials abatement including purpose, proper construction and maintenance of airtight plastic barriers, job set-up of airlocks, posting of warning signs, engineering controls, electrical and ventilation system lockout, proper working techniques, waste clean-up, storage and disposal.
6. Personal hygiene including entry and exit procedures for the work area, use of showers and prohibition of eating, drinking, smoking, and chewing in the work area.
7. Special safety hazards that may be encountered including electrical hazards, air contaminants (CO, wetting agents, encapsulants), fire and explosion hazards, slippery surfaces, heat stress, and noise.
8. Workshops allowing both supervisory personnel and abatement workers the opportunity to observe and experience the construction of containment barriers and decontamination facilities.
9. Lockout/Tagout and Confined Space Entry procedures.

B. Site Supervisor Qualifications

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

1. The Contractor shall provide one Site Supervisor, whose responsibilities include coordination, safety, security, and execution of all phases of the asbestos abatement project. The Site Supervisor will not be used as an abatement worker and will be assigned full-time to the project.
2. The Site Supervisor shall be fully qualified and trained in all aspects of asbestos abatement practices and procedures. The asbestos training course will cover all topics listed above as well as training in contract specifications, liability insurance and bonding, legal considerations related to abatement, establishing respiratory protection medical surveillance programs, EPA and OSHA record-keeping programs, as well as any other topics requested by the Owner.
3. At least one licensed asbestos supervisor should be on site at all times who is certified in CPR and Emergency First Aid by an appropriate authority, as well as having received the required training under the OSHA Bloodborne Pathogen Standard.

1.09 REGULATORY SUBMITTALS

- A. The Contractor shall notify the following agencies in appropriate manner and place of impending work, and shall provide evidence of notifications at the pre-construction meeting:
 1. Massachusetts Dept. of Environmental Protection
1 Winter Street
Boston, Massachusetts 02108
(10 business days in advance)
 2. Massachusetts Division of Occupational Safety
Department of Labor Standards
1001 Watertown Street
West Newton, Massachusetts 02165
(10 business days in advance)
 3. Local Fire and Police Departments, Building Department, and other state or town agencies as required by law or ordinance.
- B. Permits
The Contractor shall be responsible for securing and paying for all necessary permits for asbestos and hazardous materials related work, including hauling, removal and disposal, building, and materials usage, or any other permits required to perform the specified work.
- C. Fees, Licenses, Patents, and Copyrights
 1. The Contractor shall pay all licensing fees, royalties, and other costs necessary for the use of any copyrighted or patented product, design, invention, or process in the performance of the job specified herein. The Contractor shall be solely responsible for costs, damages, or losses resulting from any infringement of these patent rights or copyrights.

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

2. The Contractor shall hold the Owner and the Consultant harmless from any costs, damages, and losses resulting from any infringement of these patent rights or copyrights.
3. If the Contract Specification requests the use of any product, design, invention, or process that requires a licensing fee or royalty fee for use in the performance of the job, the Contractor shall be responsible for the fee or royalty fee and shall disclose the existence of such rights.
4. The Contractor shall be responsible for costs of all licensing requirements, where applicable, and notification requirements and all other fees related to the Contractor's ability to perform the work in this section.

1.10 SAFETY CONSIDERATIONS

- A. This project is subject to compliance with Public Law 91-596, "Occupational Safety and Health Act of 1970" (OSHA), with respect to all Rules and Regulations pertaining to construction, including Volume 36, Numbers 75 and 105, of the Federal Register, as amended, and as published by the U.S. Department of Labor.
- B. In addition to any detailed requirements of the Specification, the Contractor shall at his own cost and expense comply with all laws, ordinances, rules and regulations of Federal, State, Regional and Local Authorities regarding handling and storage of asbestos, lead and other hazardous waste materials.
- C. All staging and scaffolding (if needed) shall be furnished and erected by the Contractor in accordance with all applicable requirements and be maintained in safe condition by him at no additional cost to the Owner.
- D. The Contractor is responsible for using safe procedures to avoid electrical hazards. When a hazard exists, work will be stopped and power will be shut off and checked before work begins again. All electrical panels and exposed wires within the work site shall be de-energized prior to the commencement of any wetting or removal operations. All extension cords and power tools used within the work area shall be attached to Ground Fault Circuit Interrupters (G.F.C.I.) in accordance with 1910.120 and the Contractor's Lockout/Tagout program.

1.11 SECURITY

- A. The Owner will provide specific access as required during the project to the Contractor and personnel assigned to the project. The access shall be determined by the Owner. The Contractor will be responsible for the security of the building involved in the abatement project. The Contractor shall maintain security in the building using appropriate secure barriers and locks. It will also be the Contractor's responsibility to allow only authorized personnel into each work area. Authorized personnel include licensed Contractor staff, the industrial hygienist, and all other personnel with the appropriate training, medical approval, respirator fit testing, and personal protective equipment.

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

- B. Any person entering or leaving the contained areas must sign the Contractor's bound logbook and enter the date and time. The logbook must be located immediately outside the entrance to the Decontamination Unit at all times, and be open for inspection by the Consultant.

1.12 REFERENCES

The following references are cited as applicable publications:

- A. Environmental Protection Agency
Asbestos Regulations (NESHAPS) Title 40 CFR Part 61, as currently amended.
Guidance for Controlling Friable Asbestos Containing Materials in Buildings, Final Rule and Notice.
- B. Occupational Safety and Health Administration
Title 29 CFR 1910.1001 (amended)
Title 29 CFR 1926.1101 (amended)
Title 29 CFR 1926.62 (amended)
- C. Commonwealth of Massachusetts
Department of Labor Standards
454 CMR 28.00, The Removal, Containment, Maintenance, or Encapsulation of Asbestos
- D. Commonwealth of Massachusetts
Department of Environmental Protection
310 CMR 7.15
- E. U.S. Department of Transportation Regulations
49 CFR Parts 172 and 173
- F. All regulations by these and other governing agencies in their most recent version are applicable. These specifications refer to many requirements found in these references, but in no way intend to cite or reiterate all provisions therein or elsewhere. It is the Contractor's responsibility to know, understand, and abide by all such regulations and common practices.
- G. Other provisions contained in these references may from time to time during the execution of this contract be enforced by the Owner at his own discretion.
- H. Toxic Substances and Control Act (TSCA) (40 CFR 761).
- I. Massachusetts Waste Disposal Regulations (310 CMR 7.15).
- J. Hazard Communication Standard (29 CFR 1926.59).
- K. Hazardous Waste Operations and Emergency Response (29 CFR 1910.120).
- L. National Contingency Plan (CERCLA, Section 105).
- M. Spill Prevention Control and Countermeasures Plan (40 CFR, Part 112).

PART 2 - PRODUCTS

2.01 MATERIALS AND EQUIPMENT

The Contractor shall provide new materials and new or used equipment in undamaged and serviceable condition. Only materials and equipment that are recognized as being suitable for the intended use, by compliance with appropriate standards, are to be used during the project.

A. Fire Extinguishers

The Contractor shall provide multi-purpose ABC minimum rating to A40BC fire extinguishers. The Contractor shall comply with the applicable recommendations of NFPA Standard 10 "Standard for Portable Fire Extinguishers." Fire extinguishers shall be located where they are most convenient and effective for their intended purpose but provide not less than one extinguisher inside each work area in the Equipment Room and one outside each work area in the Clean Room.

B. Construction Lumber

Construction lumber for critical barrier walls shall consist of nominal, fire-retardant, 2" x 4" framing, sixteen inches center to center.

C. Plastic Sheeting

The Contractor shall provide non-combustible, fire-retardant, 6-mil thick clear, frosted, or black plastic sheeting in the largest size possible to minimize seams in accordance with local fire department requirements. Spray plastic will not be allowed for use on this project.

D. Adhesive Materials

The Contractor shall provide duct tape in 2" or 3" widths, with an adhesive that is formulated to aggressively stick to plastic sheeting. The Contractor may also provide spray adhesive in aerosol cans that is specifically formulated to stick tenaciously to plastic sheeting.

E. Shower Assembly

1. The Contractor shall provide a leak tight shower enclosure with integrated drain pan fabricated from fiberglass or other durable waterproof material, approximately 3' x 3' square with minimum 6' high sides and back. The Contractor shall structurally support the unit as necessary for stability and equip it with a hose bib, mounted at approximately 4'-0" above drain pan.
2. The Contractor shall provide a factory made shower-head producing a spray of water that can be adjusted for spray size and intensity. The Contractor shall feed shower with water mixed from hot and cold supply lines, arranged so that control of water temperature, flow rate, and shutoff is from inside shower without outside aid.
4. The Contractor shall provide a totally submersible waterproof sump pump with an integral float switch. The unit shall be sized to pump two times the flow capacity of all showers or hoses supplying water to the sump, through the filters specified herein when they are loaded to the extent that replacement is required.

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

The unit shall be capable of pumping debris, sand, plaster or other materials washed off during decontamination procedures without damage to mechanism of pump. The Contractor shall adjust float switch so that a minimum of 3" remains between top of liquid and top of sump pan.

F. Negative Air Filtration System

The Contractor shall provide air-filtering equipment capable of filtering particles to 0.3 micrometers at 99.97% efficiency and of sufficient quantity and capacity to cause a complete air change within the work area at least once every 15 minutes. Such equipment shall exhaust the filtered air so as to maintain a negative pressure inside the work area. Air shall flow in through the Decontamination Unit and exhaust through the negative air filtration unit by means of flexible duct leading outside the work area, preferably outside of the building. Negative air filtration shall be in operation at all times.

G. HEPA Vacuum

The Contractor shall utilize high efficiency filter vacuums to filter particles of 0.3 micrometers or larger at 99.97% efficiency or greater. The Contractor shall obtain HEPA vacuum attachments, such as various size brushes, crevice tools, and angular tools to be used for varied application, and service the HEPA vacuum routinely to assure proper operation. Caution shall be used any time the vacuum is opened for HEPA filter replacement or debris removal. Operators shall wear protective clothing and respirators when using the HEPA vacuum. Vacuuming by conventional means is unacceptable.

H. Amended Water

For wetting prior to disturbance of asbestos-containing materials, the Contractor shall use an amended water solution. The Contractor shall provide water to which a commercial surfactant (i.e., not dish detergent) has been added. The Contractor shall use a mixture of surfactant and water, which results in wetting of the asbestos-containing material and retardation of fiber release during disturbance of the material, equal to or greater than that provided by the use of one ounce of a surfactant, consisting of 50% polyoxyethylene ester and 50% polyoxyethylene ether mixed with five gallons of water.

I. Disposal Bags

The Contractor shall provide appropriately labeled 6-mil thick leak tight plastic bags of sufficient size for application.

J. Water Service

All temporary water connections to the Owner's water system shall include back-flow protection. The Contractor shall provide heavy-duty abrasion-resistant hoses with a pressure rating greater than the maximum pressure of the water distribution system to provide water into the work area and to the Decontamination Unit. The Contractor shall provide a UL rated 40-gallon electric hot water heater to supply hot water for each Decontamination Unit shower.

K. Electrical Service

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

1. The Contractor shall provide temporary power service to the Decontamination Unit sub panel with minimum 60 amp, 2 pole circuit breaker or fused disconnect connected to the auxiliary power source. The sub panel and disconnect shall be sized and equipped to accommodate all electrical equipment required for completion of the work. The Contractor shall comply with applicable NEMA, NECA, and UL standards and governing regulations for materials and layout of temporary electric service.
2. The Contractor shall provide identification-warning signs of voltage differences at power outlets that are other than 110-120-volt power and provide polarized outlets for plug-in type outlets, to prevent insertion of 110-120 volt plugs into higher voltage outlets. Dry type transformers shall be provided where required to provide voltages necessary for work operations.
3. The Contractor shall provide receptacle outlets equipped with ground-fault circuit interrupters (GFCI), with reset button and pilot light, for plug-in connection of power tools and equipment. No electrically powered tools or equipment shall be operated without a Ground-Fault Interrupter. The Contractor shall provide the Consultant with documentation proving that the GFCI's are in proper working order.
4. The Contractor shall use only grounded extension cords. Use "hard-service" cords where exposed to abrasion and traffic. Single lengths of electric cord shall be used or waterproof connectors shall be used to connect separate lengths of electric cords, if single lengths will not reach areas of work.
5. The Contractor shall provide general service incandescent lamps of wattage required for adequate illumination (in accordance with OSHA 29 CFR 1910.56, "Illumination"). Lamps shall be equipped with guard cages or tempered glass enclosures where fixtures are exposed to breakage by construction operations. Exterior fixtures shall be provided where fixtures are exposed to the weather or moisture.

PART 3 - PROJECT EXECUTION

3.01 GENERAL CONSIDERATIONS

A. Approvals and Inspection

All temporary facilities, work procedures, equipment, materials, services, and agreements must strictly adhere to and meet these contract specifications along with EPA, OSHA, NIOSH, regulations and recommendations as well as any other federal, state, and local regulations. Where there exists overlap of these regulations, the most stringent one applies. All work performed by the Contractor is further subject to approval of the Consultant. Modifications to these isolations and sealing methods, procedures, and design may be considered if all elements of proper and safe procedures to prevent contamination and exposure can be demonstrated. Written modifications to these specifications must be made to the Consultant for review before they can be used for work on this project.

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

B. Damage and Repairs to The Work Site

Abatement and disposal shall be performed without damage to the building, including, but not limited to, structural members, ceilings, walls, pipes, duct work, light fixtures, etc. The Contractor shall provide protection of these items and materials as part of the work area preparation. The Contractor shall not perform any demolition activity that could result in the loss of integrity of any building or equipment-related structural member. Where asbestos abatement activity causes damage, the Contractor shall patch, repair, replace or otherwise restore same to its original condition at no additional cost to the Owner.

C. HVAC Systems

Wherever possible, shut down and lock out/tag out electric power to all work areas. Provide temporary power and lighting according to these specifications. Coordinate with the Consultant in advance prior to conducting shutdowns and lockouts. Whenever the work area cannot be completely de-energized, the Contractor will provide the Consultant with a plan for protecting workers and electrical equipment. Shut down and lock out all heating, cooling, and air conditioning system (HVAC) components that are within, supply, or pass through the work area. This will be done with the advice and counsel of the Consultant, but the Contractor is responsible to ensure all systems are shut down and it is impossible to re-energize until clearance is obtained.

1. Investigate the work area and agree on pre-abatement condition with the Owner.
2. Seal all intake and exhaust vents in the work area with tape and 2 layers of 6-mil polyethylene.
3. Seal any seams in system components that pass through the work area.
4. Remove all HVAC system filters and place in labeled, 6-mil polyethylene bags for staging and eventual disposal as asbestos-contaminated waste.

D. Barriers and Isolation Areas

1. The Contractor shall construct and maintain suitable critical barriers to separate work areas from spaces occupied by the Owner or other tradesmen. Critical barriers shall be of sufficient size and strength to prevent building occupants, the public, and others from entering the work areas.
2. Warning signs shall be posted on all critical barriers at the commencement of the work area preparation, as required in 1926.1101 of the Occupational Safety and Health Standards.
3. The signs shall display the proper legend in the lower panel, with letter sizes and styles of a visibility at least equal to that specified in OSHA Standard 1926.1101.

The signs will read as follows:

**DANGER
ASBESTOS
CANCER AND LUNG DISEASE HAZARD
AUTHORIZED PERSONNEL ONLY**

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

**RESPIRATOR AND PROTECTIVE CLOTHING
REQUIRED IN THIS AREA**

4. The signs shall be posted at the perimeters of asbestos removal, demolition or construction areas where the asbestos-containing material to be removed exists.
5. The Contractor shall maintain all temporary and critical barriers, facilities and controls as long as necessary for the safe and proper completion of the work. All containments shall consist of floors and walls covered with 2 layers of 6-mil poly sheeting, except in those instances where such floors are deemed impervious by the Consultant.
6. Any breaches in the containment will be corrected at the beginning of each shift and as necessary during the workday. Work will not be allowed to commence until all control systems are in place and operable.
7. No barriers shall be removed until the work areas are thoroughly cleaned, and all debris has been properly bagged and removed from work areas, and the air has passed final clearance tests, in accordance with provisions detailed herein.

3.02 ACM & ACWM LOCATION PREPARATION AND REMOVAL

A. Area Preparation

1. **PRIMARY BARRIERS:** Prior to the construction of each asbestos abatement area, all primary barriers shall be sealed with a minimum of one layer of 6-mil plastic sheeting and duct tape on plywood. Primary barriers consist of all windows, vents, closed and locked doors, and openings to adjacent spaces from the work area. Plywood shall be utilized to cover any doors, elevators, or other entrances to the work area(s) that may be accessible by unauthorized personnel.

B. Decontamination Unit and Procedures

1. It is the Contractor's responsibility to provide decontamination chambers consisting of a Clean Room, Shower Room, Equipment Room, and Equipment/Waste Decontamination Room for personnel and waste/equipment involved in asbestos abatement. Each of the four rooms shall be of sufficient size to accommodate authorized personnel. Shower shall be completely functional as described in 3.02 (B)(7).
2. Each room shall be separated from other rooms by a double flap of 6-mil polyethylene sheeting acting as an airlock. This shall be designed to minimize fiber migration and airflow between the decontamination unit rooms. A separate equipment and waste decontamination unit shall also be constructed. This can be adjacent to the personnel shower room.
3. The rooms shall be framed with 2" X 4" lumber, masked, sealed and attached to the entry/exit ways of asbestos/lead work areas.
4. The rooms together shall be referred to as the Decontamination Unit. A Decontamination Unit will be required for each separate containment area, if work is to be divided into sections.

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

5. The Equipment Room shall serve as a transfer room for decontamination procedures to occur in. This room shall be vacuumed and washed whenever necessary in order to prevent asbestos dust and debris accumulations or when required by the Consultant. Workers leaving the containment shall remove and dispose of disposable protective suits in the Equipment Room and proceed into the Shower Room.
6. The Shower Room shall contain an appropriate number of shower heads supplied with hot and cold water adjustable at the tap. Uncontaminated soap, shampoo, and towels shall be available at all times. The shower water shall be drained, collected, and filtered through a system with at least 5.0-micron particle size collection capability. A system containing a series of several filters with progressively smaller pore sizes shall be used to avoid rapid clogging of the filtration system by large particles. Filtered wastewater shall either be discharged in accordance with the applicable local codes or otherwise disposed of as asbestos waste. Contaminated filters shall be disposed of as asbestos waste.
7. The Clean Room shall store abatement workers' clean protective clothing and clean respirator equipment. Contaminated clothing, respirators, tools, equipment, or other materials shall not be allowed into the Clean Room or beyond. The Clean Room will serve as an access for personnel entering the work area, and for the donning of respiratory protection and protective clothing. The Contractor shall provide space in the Clean Room for the workers' personal clothing. This shall be in the form of lockable lockers.

C. HEPA Filtration

Adequate negative pressure shall be provided within the enclosure (where full containment removal is utilized) as specified below.

1. After asbestos work area is totally isolated, and prior to commencement of work, the Consultant will perform a visual inspection of the work area. This will consist of checking the integrity of barriers including smoke testing the containment if deemed necessary by the Consultant. This does not in any way relieve the Contractor's responsibilities to ensure the isolation of the work area. The volume of air within the contained work area shall be changed a minimum of four (4) times per hour. A pressure differential reading of -0.02 inches of water shall be maintained in the negative pressure work area relative to adjacent areas. A manometer with a strip chart recorder shall be used to show that the proper pressure differential is being maintained.
2. Equipment used for producing a negative pressure work area shall have a filtering device that is at least 99.97% efficient at a 0.3-micron pore size. Filters meeting these standards are referred to as High Efficiency Particulate Absolute (HEPA) filters. The HEPA filtration units shall be equipped with the following:
 - a. Magnehelic gauge to monitor the unit's air pressure difference across the filters and be able to interpret magnehelic readings to cubic feet per minute (CFM).

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

- b. An affixed label, clearly marked and conspicuous, showing the most recent installation date and hour reading of the primary internal HEPA filter.
 - c. A clock to record the unit's operation time.
 - d. Automatic shut off for filter failure or absence.
 - e. Audible alarm for unit shutdown.
 - f. Amber flashing warning light for filter loading.
 - g. The unit must be equipped with a safety system that prevents it from being operated with the HEPA filter in an improper orientation.
 - h. All flexible ducting, vent tubing, adapter plates and other equipment used for the passage of filtered air shall be undamaged, uncontaminated, and free of air leaks at all points.
- 3. Pre-filters shall be changed frequently during the abatement.
 - 4. All HEPA units shall exhaust to the outside of the building.
 - 5. Air movement shall flow uninterrupted from outside the work area through the Decontamination Unit into the work area. There shall be no other openings for air to enter the containment unless approved by the Consultant in writing.
 - 6. HEPA filtration units shall be placed as far as possible from the air intake to the containment to prevent short cycling of fresh air.
 - 7. This containment, along with the decontamination chamber, shall constitute the critical containment of the work area from the surrounding areas. All openings to this critical containment are to be sealed except where air must enter the work site due to the use of exhaust equipment.
 - 8. Unless approved by the Consultant, air shall enter the critical containment only through the Decontamination Unit. A pressure differential meter will be installed and maintained. If pressure differential drops below -0.02 inches of water, stop work until proper negative pressure is restored.
 - 9. Written modifications to these isolations and sealing methods, procedures, and design may be considered if all elements of proper and safe procedures to prevent contamination and exposure can be demonstrated.
 - 10. Written modifications to these specifications must be made to the Owner and Consultant for review before they can be used for work on this project.

D. ACM & ACWM Removal

- 1. Asbestos removal will not begin until the Owner and Consultant have given authorization to proceed. This authorization will be given after the removal area has passed a visual inspection by the Consultant based on the criteria presented herein. The Owner reserves the right to inspect the work area prior to start of abatement. The Owner also reserves the right to inspect the work area at any time and to order the Contractor to stop work.

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

2. All materials shall be sufficiently saturated/wetted to reduce fiber release so that the airborne fiber concentration does not exceed the established OSHA Permissible Exposure Limits (PEL's).
3. Dry removal will not be permitted at any time during this project.
4. All asbestos-containing material shall be carefully removed and placed into double 6-mil polyethylene bags or fiber drums for disposal. All bags, containers or wrapped materials transported out of the work area shall be labeled with preprinted labels required by Federal EPA, OSHA and the Department of Transportation regulations. The name of the waste generator (Owner) and the project location address shall also be placed on each bag/drum.
5. Fine cleaning of residual asbestos-containing material shall consist of carefully scraping or brushing the material from surfaces. The recommended method for brushing a substrate after gross removal has taken place is to use a nylon brush. Wetting of the substrate shall also occur while this brushing is performed, since the chance of airborne fiber generation during fine cleaning still exists.
6. Air testing will be performed continuously outside the asbestos work areas. If fiber concentrations exceed 0.010 fibers/cc, or background levels, work shall stop and the Contractor shall perform clean-up activities in the affected areas and check the integrity of all barriers.
7. Clean-up activities shall include but not be limited to wet-wiping and vacuuming surfaces with a HEPA equipped vacuum. Work may continue only after the source of contamination is identified, corrected, and proper cleaning activities are implemented.
8. Air testing will be performed by the Consultant on site in the affected areas. If the results of these air tests are not below 0.010 fibers/cc for PCM, the Contractor shall perform a thorough decontamination of the affected areas.
9. After brushing and scraping, surfaces shall be free of visible debris and fibers. A final wipe-down of the substrate with wet, lint-free cloths shall take place in order to ensure proper cleaning. All surfaces including floors, walls, ceilings, and suspended ceiling grid-work shall also be HEPA vacuumed clean.
10. If encapsulation is to be conducted, all visible asbestos-containing material is to be removed by the Contractor before encapsulation procedures are allowed to begin. The Consultant will conduct an inspection of the work area prior to giving approval to begin encapsulation of the work area. The removal substrate must be clean and bare, and the entire work area must be free and clear of any suspect material for the Contractor to pass this visual inspection and begin encapsulation.

E. Floor Coverings, Mastics and Floor Leveling Compounds

1. Asbestos-containing floor coverings and mastics requiring abatement are present within the Haskell Building Project.
2. The Asbestos Abatement Subcontractor shall remove all asbestos-containing

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

floor coverings, including but not limited to floor tile, mastic, floor sheeting, floor leveler, and multilayered floor coverings that are to be impacted by the renovation/addition. To the best of EFI's knowledge, substrates where ACM flooring materials are scheduled for removal include concrete. Removal shall include all layers to expose bare substrate.

3. The Asbestos Abatement Subcontractor shall eliminate all mastic remnants when positive. The Asbestos Abatement Subcontractor shall remove all materials or substrates if visible or microscopically detectable asbestos-containing mastic remains on these surfaces after abatement. The Asbestos Abatement Subcontractor shall also remove as asbestos any non-asbestos mastics which are asbestos contaminated or become asbestos contaminated during asbestos abatement operations in that location.

F. Removal of Critical Barriers

1. No critical barrier shall be taken down until the final visual inspection and final clearance air tests (where required) are found to be below 70 S/mm² by TEM or 0.010 fibers/cc by PCM.
2. After a successful final visual inspection, and a successful final air test, the Contractor shall conduct the post abatement takedown.
3. All polyethylene sheeting used in the construction of the Decontamination Unit and Containment Area shall be bagged and disposed of as asbestos contaminated waste.
4. Areas exposed during this process shall be examined for traces of suspect material.
5. If any is found, it will be picked up by HEPA vacuuming and wet cleaning. Based on the amount of suspect material found, the Consultant may request the use of misters in the surrounding area.
6. The Contractor will then implement the use of misters as a precautionary measure.

3.03 DISPOSAL OF ASBESTOS WASTE (ACWM)

- A. All waste removal procedures shall be conducted in accordance with local, state and federal regulations.
- B. The Contractor shall provide proof that disposal sites for all waste materials have current and valid permits to accept specific wastes at the time of the pre-construction meeting.
- C. Receipts shall be obtained by the Contractor from the disposal/recycling site(s), and submitted to the Consultant upon request for final payment.
- D. Warning labels having permanent, waterproof print and adhesive shall be affixed to all asbestos bags, trucks, drums (lids and sides), and other containers used to store and/or

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

transport asbestos-containing material. Labels must be conspicuous and legible and contain the following warning:

CONTAINS ASBESTOS FIBERS
AVOID CREATING DUST
CANCER AND LUNG DISEASE HAZARD

- E. The Contractor shall be responsible for all necessary precautions to prevent pollution by spilling during the performance of services and shall assume full responsibility for all Contractor caused spills, which shall be cleaned up at the Contractor's expense.
- F. Temporary storage of asbestos waste on-site (inside) will be determined by the Owner.

3.04 SCRAP METALS REMOVAL

- A. Precious, semi-precious, and scrap metals, including, but not limited to, copper, aluminum, silver, gold, brass, and steel shall not be cut and removed from the Site by the Abatement Contractor unless specifically required by the Asbestos Abatement provisions of these specifications and by written authorization from the Owner.

3.05 HOUSEKEEPING

- A. Throughout the work period, the Contractor shall maintain the building and site in a standard of cleanliness as specified throughout these specifications.
 - 1. Contaminated disposable clothing, respirator filters, and other debris shall be bagged and sealed at the end of each workday.
 - 2. All asbestos generated by either removal or repair shall be bagged immediately and not be allowed to be left exposed at the end of each workday.
 - 3. Respirators shall be thoroughly cleaned at the end of each workday and stored for the next day's use.
 - 4. The Contractor shall retain all stored items in an orderly arrangement allowing maximum access, not impeding traffic, and providing the required protection materials.
 - 5. The Contractor shall not allow the accumulation of scrap, debris, waste material, and other items not required for completion of the work.
 - 6. The Contractor shall provide adequate storage for all items awaiting removal from the job site, observing all requirements for fire protection and protection of the environment.
 - 7. Daily, and more often if necessary, the Contractor shall inspect the work areas and adjoining spaces, and pick up all scrap, debris, and waste material. Remove all such items to the place designated for their storage.
 - 8. The Contractor shall maintain the site in a neat and orderly condition at all times.

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

3.06 QUALITY CONTROL

- A. The Owner has retained the Consultant, to provide project administration, monitoring of Contractor work practices and performance, inspection of the work sites, bulk fiber identification, and air sampling and analysis throughout the asbestos and hazardous materials abatement project.
- B. Many references to Owner will in fact be managed by the Consultant in lieu of the Owner, at the Owner's request, and the Contractor is required to regard the requests and interpretations of the Consultant as having full force unless expressly informed otherwise by the Owner.
- C. Air Monitoring
 - 1. The air clearance acceptance criteria for this project is <0.010 fibers per cubic centimeter of air (f/cc) by Phase Contrast Microscopy (PCM) using the NIOSH 7400 Method.
 - 2. Background (pre-testing) air may be taken to represent conditions before the Contractor starts masking and sealing operations.
 - 3. During removal, area samples will be collected by the Consultant outside major openings in the containment: in the clean room, at other critical points outside the work areas, just outside the clean room, inside the contained work sites, and at HEPA exhaust locations. Final clearance air samples will be collected inside each removal area after acceptance of visual inspection.
 - 4. NOTE: Encapsulation on all surfaces (including floor) must be dry prior to final air sampling.
 - 5. A sufficient number of samples to reliably characterize the work place air quality will be taken. Air will be agitated by means of a small leaf blower prior to the test, and kept agitated by means of a small electric fan. The results of all samples must comply with the regulations set forth in this specification. Failure to meet the specified criteria will require the Contractor to re-clean the designated work site and then the Consultant to repeat the final air clearance testing. All repeat air testing shall be the Contractor's financial responsibility. Cleaning and testing will be repeated until the specified criteria are met.
- D. Work Review
 - 1. The Consultant and the Owner will review the Contractor's work practices prior to the start of, and during all asbestos related work, and will report any specification violations to the Contractor. If the Contractor fails to correct deficiencies in a timely manner, the Contractor will be notified in writing, and work may be stopped.
 - 2. The Consultant will review the containment structure and negative air conditions before work begins and after the Contractor Site Supervisor has given approval. Outside containment airborne fiber concentrations must not exceed 0.010 fibers/cc or pre-abatement levels, whichever is greater.

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

3. If concentrations exceed this level, then work must be stopped, conditions reviewed as to the probable cause, and then corrected. A description of procedures regarding fiber concentrations greater than 0.010 fibers/cc outside the containment can be found above.
4. The Consultant will keep a daily log of the Contractor's work practices and will make these daily logs a part of the final project documents.

3.07 PERSONAL PROTECTION

A. Respirators and Protective Clothing

1. Protective Clothing
 - a. Personal protection, in the form of disposable Tyvek suits, and NIOSH approved respirators, are required for mechanics, Contractor supervision, Owner, Consultant, and visitors at the work site during the set-up, removal, and cleaning operations.
 - b. The Contractor shall provide all this protective equipment for workers, Owner, Consultant, and authorized personnel to access this work site.
 - c. Each worker shall be supplied with a minimum of two complete disposable uniforms every day.
 - d. Removal workers shall not be limited to two uniforms, and the Contractor will be required to supply additional uniforms as is necessary. Under no circumstances will anyone entering the removal area be allowed to reuse a contaminated uniform.
 - e. Work clothes shall consist of disposable full body suits, head covers, gloves, footwear, and eye protection. Street clothes are forbidden in the work area at all times, even under protective suits.
2. Respiratory Protection
 - a. The Contractor shall supply workers and supervisory personnel with NIOSH approved protective respirators and HEPA filters.
 - b. Appropriate respirator selection shall be determined by the daily personal samples being taken and strictly follow the guidelines set forth in the OSHA respiratory program 29 CFR 1910.134 and the Massachusetts DLS Regulations 453 CMR 6.00. The respirators shall be sanitized and maintained according to the manufacturer's specifications. Appropriate respirators shall be selected using the information provided in OSHA Title 29 CFR Part 1910.1926 Final Rules. This determination has been made for this project. Disposable respirators shall not be considered acceptable in any circumstance.
 - c. The Contractor will maintain on site a sufficient supply of disposable HEPA filters to allow workers and supervisory personnel to change contaminated filters at least three (3) times daily. The Contractor is

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

solely responsible for means and methods used and for compliance with applicable regulations.

- d. Respirators shall be individually assigned to removal workers for their exclusive use.
 - e. All respiratory protection shall be provided to workers in accordance with the written submitted respiratory protection program, which includes all items in OSHA 29 CFR 1910.134 (b) (1-11). A copy of this program shall be kept at the work site, and shall be posted in the Clean Room of the Decontamination Unit.
 - f. Workers must perform negative and positive pressure fit tests each time a respirator is put on, whenever the respirator design permits.
 - g. Workers shall be given a qualitative fit test in accordance with procedures detailed in the OSHA 29 CFR 1910.1025, Appendix D, Qualitative Fit Test Protocols, for all respirators to be used on this abatement project. An appropriately administered quantitative fit test may be substituted for the qualitative fit test.
 - h. Upon leaving the active work area, the pre-filter shall be discarded, cartridges removed, and respirators cleaned in disinfectant solution and clean water rinse. Clean respirators shall be stored in plastic bags when not in use. The Contractor shall inspect respirators daily for broken, missing, or damaged parts.
3. Personal Sampling
- a. The Contractor shall provide daily personal sampling to check personal asbestos exposure levels for the purpose of establishing respiratory protection needs.
 - b. Samples shall be taken for the duration of the work shift or for eight hours, whichever is less.
 - c. Personal samples need not be taken every day after the first day if working conditions remain consistent but must be taken every time there is a change in the removal operation, either in terms of the location or the type of work, or during any changes in personnel. Sampling will be to determine eight-hour Time Weighted Averages (TWA). The Contractor is responsible for personal sampling as outlined in OSHA Standard 1926.1101.
 - d. Sampling personnel shall be proficient in the taking of asbestos air samples as prescribed by NIOSH 7400, and must be supervised by an individual who has completed the NIOSH 582, or equivalent, training course.
 - e. Asbestos air sampling results shall be available for posting at the job site in written form no more than twenty-four (24) hours after the completion of a sampling cycle. The document shall list each sample's result, sampling time and date, individual monitored, flow rate,

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

sampling duration, microscope field area, number of fibers per fields counted, cassette size, and analyst's name and company. Air sample analysis results will be reported in fibers per cubic centimeter.

*******END OF SECTION*******

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

**SECTION 096813
TILE CARPETING**

PART 1 – GENERAL

1.1 GENERAL CONDITIONS

- A. Attention is directed to the printed form of the proposal, Section I, of these Specifications entitled “Summary of the Work” listed in the table of contents which are hereby made a part of this Section of the Specifications.
- B. Equality of materials or articles other than those named or described in this Section will be determined in accordance with the provisions of Section I, “Summary of the Work”, Sub-section 1.12 Reference Standards. Paragraph A.

1.2 SCOPE OF WORK

- A. Work of this section consists of furnishing all labor, materials, equipment, and services, unless noted otherwise, necessary to complete the carpet flooring work indicated, and without limiting the generality thereof includes:
 - 1. Direct glue-down carpet squares, including all accessories to complete the work as indicated on the drawings. Note: an additional five per cent attic stock shall be included in the allotted material
 - 2. Supply and install 4” vinyl .080” or 1/8” cove base trim as manufactured by Mannington Burke Wall Base or equal.
 - 3. Preparation and cleaning of subfloors as per manufacturer’s specifications and as indicated within this section and Specification Section
- B. Reference to Drawings: Work to be done under this section is shown on Drawing A1. **Note: Contractor shall be responsible for verifying all square footage quantities for proposed project.**

1.3 QUALITY ASSURANCE

- A. Installer Qualifications: Use skilled mechanics who are thoroughly trained and experienced in the necessary crafts and who are completely familiar with the specified requirements and methods needed for proper installation of the work.

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

- B. Requirements of Regulatory Agencies: Conform to the requirements of Section 904 of the Massachusetts State Building Code.
1. **Fire rating tests:** Carpeting shall meet or exceed ASTM E648 Floor Radiant Panel Test) requirements with carpeting withstanding a test exposure of 0.45 watts per sq. cm. or greater for corridors and exit ways, and a minimum of 0.22 watts per square cm. for other areas.

1,4 SUBMITTALS

- A. **Shop Drawings:** Submit layout drawings indicating direction of carpet squares as recommended by the manufacturer.

Layout shall conform to the following:

1. Each style of Mannington Commercial carpet will have a recommended layout or method for installation that will be specific to that style. Each style will have recommended layouts which help maximize seam appearance. A small mock-up of the recommended layout and tile direction shall be completed before installation for evaluation by owner.
- B. **Samples:** Submit the following samples:
1. Minimum 24 inch by 24-inch squares of selected samples of each of the manufacturer's standard colors for each carpet type being considered.
 2. Accessories, each type, size, and finish.
 3. Manufacturer's full color range of 4" vinyl cove base trim strips.
- C. **Maintenance Data:** Prior to final acceptance of carpet installations, the carpet contractor shall deliver to the owner two printed copies of the carpet manufacturer's detailed recommendations for the care, cleaning and repair of the types of carpets installed under this contract.
- D. **Certificates:** Submit copies of certification by independent testing laboratory attesting that carpet materials satisfy the minimum requirements specified when tested in accordance with ASTM E648.
- E. **Registration Numbers:** All carpet shall be registered with the manufacturer. Registration numbers shall be removed from carpet in the presence of the Commonwealth's Project Representative, when carpet is delivered, and submitted to him.

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

1.5 PRODUCT DELIVERY, STORAGE AND HANDLING

- A. The carpet installer shall be responsible for the scheduling, receiving, and placement of goods from the manufacturer.
- B. Deliver carpet to job site in manufacturer’s original mill wrappings with each roll clearly marked as to size, dye-lot and materials.
- C. Store carpet under cover in well ventilated areas as soon as delivered.
- D. Protect carpet from soiling, moisture and damage during transit, storage and installation.

1.6 WARRANTIES

- A. Wear – Limited Lifetime Wear and Backing Guaranty
- B. Limited 15 Year XGUARD® Stain Resistant Warranty
- C. Limited 15 Year ColorSafe® Bleach Resistant Warranty

PART 2 - PRODUCTS

2.1 CARPETING

- A. Carpet unless noted otherwise on plans shall be equal to **Seeds (Modular) – Automata Collection** as manufactured by Mannington Commercial Carpet,

Characteristics	Requirements
Face Fiber	Antron® Lumena™ Type 6,6 Nylon
Construction	Textured Patterned Loop
Dye Method	Solution
Gauge	5/64 (50.39 per 10 cm)
Stitches Per Inch	10.17 (40.04 per 10 cm)
Density	7,807 (290.09 kg/m ²)
Pile Thickness	0.083” (2.11 mm)
Weight	18oz/yd ² (610 g/m ²)
Backing Type	Infinity® 2 Modular
Size	18” x 36” (45.72 x 91.44 cm)
Colors	10
Adhesive	Infinity 2 Adhesive
Electrostatic Propensity (AATCC 134)	Less than 3.0 kV

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

Flooring Radiant Panel (ASTM E648)	Passes – Class 1, ≥ 0.45 watts/cm ²
Smoke Density (ASTM E662)	Passes - ≤ 450
Secondary backing	Polymeric vinyl compound
Methenamine Pill Test (ASTM D2859)	Passes
NSF/ANSI 140 Certification	Infinity® 2 Modular - Gold
Recycled Content	Contains Recycled Content
Indoor Air Quality	CRI Green Label Plus Certified
Commercial Warranties	Wear – Limited Lifetime Wear and Backing Guaranty Limited 15 Year XGUARD® Stain Resistant Warranty Limited 15 Year ColorSafe® Bleach Resistant Warranty

- D. Adhesive shall be as recommended by the carpet manufacturer.
- E. **Installation:**
1. Carpet shall be installed over properly prepared substrate flooring using direct glue down application. Adhesive shall be as recommended by the carpet manufacturer. Roll carpet with 75 – 100 lb. roller to insure proper contact.
 2. Carpet tiles shall be installed as per an approved layout recommended by Mannington Commercial for the particular floor tile that has been selected.
 3. Mixing of dye lots will be strictly prohibited in open areas so that the continuity of the installation will not be affected. If different dye lots need to be introduced, it should only happen in natural break areas where changes would be the least noticeable.
 4. Install metal edge strips or other approved material at all exposed edges of installed carpet. Ensure that strips are properly secured to the floor.
 5. Any concrete floors shall be checked for porosity, if water is absorbed rapidly it will need to be sealed, as per manufacturer’s specifications, with Mannington’s Universal Primer or equal.
 6. Installer must be familiar with manufacturer’s guidelines for installation to ensure that all carpeting types are properly installed.
- F. All usable pieces of carpet not necessary to complete the work shall be left at the job site and placed in an orderly manner where directed.

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

2.2 ACCESSORIES

- A. **General:** Installation and material shall conform to the quality, function, and substance of the products listed below. The Project Engineer will be the sole judge of the quality of materials to be used on the project.

- B. **Adhesives:**
 - 1. Infinity 2 Adhesive high-solids ultra-premium acrylic pressure sensitive adhesive for porous and non-porous sub floors. For additional information pertaining to this product refer to Mannington Commercial adhesive specification. .

- B. **Edge Reducing Strips:** Where carpet transitions to hard surface flooring, the edge should be finished with an appropriate molding. Acceptable reducers are square nose, end molding, end cap, baby threshold, universal edge, or carpet reducer. Metal, vinyl, wood, rubber, or laminate reducers are all acceptable, final selection to be made by project engineer and site director.

- C. **Miscellaneous Materials:** Provide all other materials and accessories required for a complete installation. For any excess wet adhesive that needs to be removed form the face of the carpet use a clean, soapy, damp, cloth immediately. Dried adhesive can be removed with denatured alcohol or adhesive solvent.

PART 3 - EXECUTION

3.1 DEMOLITION

- A. During demolition care must be taken not to remove or damage any existing floor tile which shall remain installed and new carpeting will be installed over it. Refer to Specification Section 025000 – Asbestos Abatement for information pertaining to floors being abated and how surfaces should be prepared before carpet installation.

3.2 PREPARATION

- A. Examine substrates to receive carpeting and verify that they are in satisfactory condition for proper execution of the work of this section.

- B. Notify Project Engineer, in writing, of any conditions preventing satisfactory installation of carpet. Do not proceed until such defects or

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

conditions have been corrected. Proceeding with installation shall indicate acceptance of job conditions.

- C. Substrates shall be completely dry and broom clean prior to carpeting.

3.3 INSTALLATION

- A. **Underlayment:** Subfloor must be smooth, firm, flat, clean, dry, free from defects, and fit for purpose. A suitable smoothing compound should be used to ensure that no irregularities show through to the surface of the finished floor. In all cases, the subfloor must meet the moisture and pH requirements before installation.
- B. **Primer:** Mannington's Universal Primer, an acrylic latex solution made to neutralize excess alkali and to prevent over absorption of adhesive to ensure a better bond shall be applied before the adhesive application. Gypsum topped or patched areas
- C. **Adhesive:** Spread Mannington Infinity 2 Adhesive', as recommended by the carpet manufacturer, evenly using a 1/16-inch x 1/32-inch x 1/32-inch U-notched trowel allowing adhesive to set up for application. Infinity 2 is a high-solids ultra-premium acrylic pressure sensitive adhesive for use with Mannington's backed carpet over porous and non-porous sub floors. After spreading the Infinity 2 Adhesive, allow adhesive to dry, no adhesive transfer to your finger. The working time will vary with the temperature, humidity, and porosity of the subfloor.
 - 1. **Clean-Up:** Wet adhesive should be immediately removed from tools and surfaces with a clean, soapy damp cloth. Dried adhesives can be removed with denatured alcohol or adhesive solvent.
- D. **Carpet:**
 - 1. Lay carpet with seams and direction as indicated on the approved shop drawings.
 - 2. Lay carpet with weave straight, true and geometrically aligned with room axis. Wavy installations will not be accepted and shall be removed.
 - 3. Roll carpet areas with a 75 lb. to 100 lb. carpet roller to ensure proper contact of carpet to substrate and to remove any and all bubbles or buckles.
 - 4. Refer to manufacturer's instructions for any additional recommendations pertaining to the installation of the carpet.
 - 5. Where carpet meets raised tile or other finishes, take special care to provide flush surfaces between the two materials. Secure raw carpet edges in place with vinyl carpet edge protector. Install protectors with double application of contact adhesive.

**FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA**

E. Seaming:

1. Follow any special seaming instructions per carpet manufacturer depending upon which of the products is being installed.

3.4 CLEAN-UP AND PROTECTION

- A. Before final acceptance of work, remove all rubbish, wrapping paper, and other debris from job site. Clean carpet of all spots, remove loose threads, and vacuum so that installation is left in perfect condition.
- B. All excess carpet squares not necessary to complete the work shall be left on the job site and placed in an orderly manner where directed by the owner for future repairs.
- C. After installation, in areas requiring further work by other trades, the carpet installer shall protect all carpeting with a layer of non-staining reinforced heavy building paper with all edges lapped not less than 6 inches and sealed with non-staining adhesive.
- D. Protect the carpet installation from heavy traffic for the first 24 hours.

****** END OF SECTION ******

FLOORING ABATEMENT AND REPLACEMENT HASKELL BUILDING
ONE PRINCE AND WEST STREET NORTHAMPTON, MA

ATTACHMENT A

ASBESTOS FLOORING
SURVEY

January 17, 2023

Paul Truax, P.E.
Director, Engineering & Fire Maintenance
Department of Mental Health
167 Lyman Street
Westborough, Massachusetts 01581

RE: **Pre-Renovation Asbestos Flooring Survey**
Haskell Building
1 Prince Street
Northampton, Massachusetts, 01060
EFI Project No.: 014.05200

Dear Paul:

Pursuant to your request, EFI Global, Inc. (EFI) performed a pre-renovation asbestos flooring survey at the Haskell Building, located at 1 Prince Street in Northampton, MA (Site). The asbestos survey was conducted on the second floor east and west wing corridors, rooms 227, 228, 245, 246, 247, 248, 256, 263, 264, and 265 (Project Area). The site visit and asbestos testing were conducted on January 6, 2023, by Massachusetts Department of Labor Standards (MassDLS) licensed asbestos inspectors Robert Thomson (License AI-0314315) of EFI.

SURVEY PROCEDURES

Samples of suspect ACMs identified during the survey were collected and submitted under chain of custody protocol to Asbestos Identification Laboratory (AIL) of Woburn, Massachusetts, a State-licensed laboratory. AIL is accredited by the National Voluntary Laboratory Accreditation Program (NVLAP) for bulk asbestos fiber analysis which is administered by the National Institute of Standards and Testing (NIST). The samples were analyzed using polarized light microscopy (PLM) with dispersion staining via EPA's "Method for the Determination of Asbestos in Bulk Building Materials" (EPA/600/R-93/116). Asbestos concentrations for the samples were determined by visual area estimation. Commonwealth of Massachusetts Department of Environmental Protection (MassDEP) asbestos regulations define an ACM as any material containing greater than or equal to one percent asbestos.

SURVEY RESULTS

The following suspect ACMs sampled by EFI were reported by AIL as containing greater than or equal to one percent asbestos, the MassDEP classification as ACM:

- 9" x 9" gray floor tile Rooms 247 and 265 (approximately 270 square feet)
- 9" x 9" gray with green streak floor tile Rooms 228, 245, 246, 248, 264, and 2nd floor east wing corridor (approximately 3,700 square feet)

- 9" x 9" brown replacement floor tile rooms 246 and 264 (approximately 70 square feet)
- 9" x 9" green with black speck floor tile room 256 (approximately 570 square feet)

9' x 9" floor tile in present beneath carpet in rooms 256, 228, and 2nd floor east corridor. Visible 9" x 9" floor tile appeared to be in good condition.

The following suspect ACMs sampled by EFI were reported by AIL as containing no detectable concentration of asbestos:

- Black mastic associated with 9' x 9' floor tile
- Plaster wall finish and base coat
- Wall base molding and associated adhesive
- Adhesive associated with carpet squares
- Black mastic beneath carpet squares
- Carpet adhesive on terrazzo flooring
- Carpet adhesive

A copy of the laboratory report prepared by AIL and photographs of the building materials sampled by EFI are attached.

CONCLUSIONS AND RECOMMENDATIONS

The 9" x 9" floor tiles were reported by AIL as ACM's. Since carpet and floor tile cannot be feasibly separated at the time of removal, EFI recommends that all carpet with 9" x 9" floor tiles present beneath be removed and managed as an ACM.

EFI recommends that the asbestos-containing materials present throughout the Project Area be removed and properly disposed of by a State licensed asbestos abatement contractor, in accordance with MassDEP and MassDLS asbestos regulations. Third party air monitoring must be performed during and/or at the completion of abatement activities for re-occupancy of the Project Area by cleaning crews, construction trades, and residents. EFI is available to assist with abatement management, contractor oversight, and air monitoring as required by applicable state and federal asbestos regulations.

If suspect ACMs other than the above-referenced materials are identified during renovation activities, EFI recommends that they be sampled by a MassDLS licensed asbestos inspector and analyzed by a MassDLS licensed asbestos analytical laboratory.

LIMITATIONS

EFI's survey was limited to those portions of the Project Area accessible by reasonable and ordinary means. EFI performed limited destructive testing and investigation of flooring materials to identify suspect ACMs within the facility. EFI's inspection did not include an evaluation of building areas and materials other than those referenced in this report.

EFI is pleased to provide environmental consulting services to the Department of Mental Health. If you have any questions regarding the contents of this report, or are in need of additional information, please do not hesitate to contact either of the undersigned at 800-659-1202. Thank you for the opportunity to serve your environmental needs.

Sincerely,
EFI Global, Inc.



Robert Thomson
Project Manager




Richard Murphy
Senior Project Manager

Attachments:
Attachment A - Photographs
Attachment B – Laboratory Analytical Report

ATTACHMENT A

PHOTOGRAPHS



Door to Room 265



ACM 9" x 9" gray floor tile and associated black mastic



Wall base molding and associated adhesive



Plaster wall



Door to Room 264



ACM 9"x 9' Gray with green streak floor tile and ACM brown replacement tile



Door to Room 246



Typical glazed block wall



Door to Room 263



Carpet with black mastic beneath



Black mastic beneath carpet



Door to Room 245



ACM 9" x 9" gray with green streak floor tile



Door to Room 227



Terrazzo floor beneath carpet



Door to 2nd Floor Small Conference Room



Carpet with ACM 9" x 9" green with black speck floor tile and black mastic



ACM 9" x 9" Green with black dot floor tile beneath carpet



Door to Room 247



Carpet with ACM 9" x 9" gray floor tile beneath



ACM 9" x 9" gray floor tile beneath carpet



Wall base molding and associated adhesive



Plaster walls



Door to Room 248




ACM 9" x 9" gray with green streak floor tile



Door to Room 228



ACM 9" x 9" gray with green streak floor tile beneath carpet



Carpet in hallway with ACM 9" x 9" floor tile beneath



ACM 9" x 9" floor tile beneath carpet in hallway



Terrazzo flooring beneath carpet in hallway

ATTACHMENT B

LABORATORY ANALYTICAL REPORT



Asbestos Identification Laboratory.

165 New Boston St., Ste 227
Woburn, MA 01801
781-932-9600

Web: www.asbestosidentificationlab.com Email:
mikemanning@asbestosidentificationlab.com



Batch: 90367

Robert Thomson
EFI Global, Inc
155 West Street
Suite 6
Wilmington, MA 01887

Project Information
014.05200
*DMH - Haskell Bldg.,
1 Prince St.,
Northampton,
MA*

*Method: BULK PLM ANALYSIS,
EPA/600/R-93/116*

Dear Robert Thomson,

Asbestos Identification Laboratory has completed the analysis of the samples from your office for the above referenced project. The Analysis Method is BULK PLM ANALYSIS, EPA/600/R-93/116. The information and analysis contained in this report have been generated using the EPA /600/R-93/116 Method for the Determination of Asbestos in Bulk Building Materials. Materials or products that contain more than 1% of any kind or combination of asbestos are considered an asbestos containing building material as determined by the EPA. This Polarized Light Microscope (PLM) technique may be performed either by visual estimation or point counting. Point counting provides a determination of the area percentage of asbestos in a sample. If the asbestos is estimated to be less than 10% by visual estimation of friable material, the determination may be repeated using the point counting technique. The results of the point counting supersede visual PLM results. Results in this report only relate to the items tested. This report may not be used by the customer to claim product endorsement by NVLAP or any other U.S. Government Agency.

Laboratory results represent the analysis of samples as submitted by the customer. Information regarding sample location, description, area, volume, etc., was provided by the customer. Asbestos Identification Laboratory is not responsible for sample collection activities or analytical method limitations. Unless notified in writing to return samples, Asbestos Identification Laboratory discards customer samples after 30 days. Samples containing subsamples or layers will be analyzed separately when applicable. Reports are kept at Asbestos Identification Laboratory for three years. This report shall not be reproduced, except in full, without the written consent of Asbestos Identification Laboratory.

- NVLAP Lab Code: 200919-0
- Massachusetts Certification License: AA000208
- State of Connecticut, Department of Public Health Approved Environmental Laboratory Registration Number: PH-0142
- State of Maine, Department of Environmental Protection Asbestos Analytical Laboratory License Number: LB-0078(Bulk) LA-0087(Air)
- State of Rhode Island and Providence Plantations. Department of Health Certification: AAL-121
- State of Vermont, Department of Health Environmental Health License AL934461

Thank you Robert Thomson for your business.

Michael Manning
Owner/Director

FieldID LabID	Material	Location	Color	Non-Asbestos %	Asbestos %
01A 993057	9x9 Gray Floor Tile	Rm 265	gray	Non-Fibrous 98	Detected Chrysotile 2
01B 993058	9x9 Gray Floor Tile	Rm 247			Not Analyzed
02A 993059	Black Mastic Assoc. with 9x9 Gray Floor Tile	Rm 247	black	Non-Fibrous 100	None Detected
02B 993060	Black Mastic Assoc. with 9x9 Gray Floor Tile	Rm 247	black	Non-Fibrous 100	None Detected
03A 993061	Plaster Wall Base Coat	Rm 265	gray	Non-Fibrous 100	None Detected
03B 993062	Plaster Wall Base Coat	Rm 265	gray	Non-Fibrous 100	None Detected
03C 993063	Plaster Wall Base Coat	Rm 247	gray	Non-Fibrous 100	None Detected
04A 993064	Plaster Wall Finish Coat	Rm 265	white	Non-Fibrous 100	None Detected
04B 993065	Plaster Wall Finish Coat	Rm 265	white	Non-Fibrous 100	None Detected
04C 993066	Plaster Wall Finish Coat	Rm 247	white	Non-Fibrous 100	None Detected
05A 993067	Wall Base Molding	Rm 265	black	Non-Fibrous 100	None Detected
05B 993068	Wall Base Molding	Rm 247	black	Non-Fibrous 100	None Detected
06A 993069	Adhesive on Wall Base	Rm 265	tan	Non-Fibrous 100	None Detected
06B 993070	Adhesive on Wall Base	Rm 247	tan	Non-Fibrous 100	None Detected
07A 993071	9x9 Gray with Green Streak Floor Tile	Rm 246	gray	Non-Fibrous 98	Detected Chrysotile 2
07B 993072	9x9 Gray with Green Streak Floor Tile	2nd Floor East Corridor			Not Analyzed

Sampled: January 06, 2023 Received: January 09, 2023 Analyzed: January 10, 2023

Thursday 12 January 2023

Analyzed by:



Batch: 90367

FieldID LabID	Material	Location	Color	Non-Asbestos %	Asbestos %
07C 993073	9x9 Gray with Green Streak Floor Tile	Rm 228			Not Analyzed
08A 993074	Black Mastic Assoc. with 9x9 Gray with Green Streak Floor Tile	Rm 246	black	Non-Fibrous 100	None Detected
08B 993075	Black Mastic Assoc. with 9x9 Gray with Green Streak Floor Tile	2nd Floor East Corridor	black	Non-Fibrous 100	None Detected
08C 993076	Black Mastic Assoc. with 9x9 Gray with Green Streak Floor Tile	Rm 228	black	Non-Fibrous 100	None Detected
09A 993077	9x9 Brown Replacement Floor Tile	Rm 246	brown	Non-Fibrous 98	Detected Chrysotile 2
09B 993078	9x9 Brown Replacement Floor Tile	Rm 264			Not Analyzed
10A 993079	Black Mastic Assoc. with 9x9 Brown Replacement Floor Tile	Rm 246	black	Non-Fibrous 100	None Detected
10B 993080	Black Mastic Assoc. with 9x9 Brown Replacement Floor Tile	Rm 264	multi	Non-Fibrous 100	None Detected
11A 993081	Adhesive on Carpet Squares	Rm 265	multi	Non-Fibrous 100	None Detected
11B 993082	Adhesive on Carpet Squares	Rm 265	multi	Non-Fibrous 100	None Detected
12A 993083	Black Mastic Beneath Carpet Squares	Rm 265	black	Non-Fibrous 100	None Detected
12B 993084	Black Mastic Beneath Carpet Squares	Rm 265	multi	Non-Fibrous 100	None Detected
13A 993085	Carpet Adhesive on Terrazzo	Conf. Rm 227	tan	Synthetic 5 Non-Fibrous 95	None Detected
13B 993086	Carpet Adhesive on Terrazzo	2nd Floor West Corridor	tan	Non-Fibrous 100	None Detected
14A 993087	9x9 Green Black Speck Floor Tile	Small Conf. Rm 256	green	Non-Fibrous 97	Detected Chrysotile 3
14B 993088	9x9 Green Black Speck Floor Tile	Small Conf. Rm 256			Not Analyzed

Sampled: January 06, 2023 Received: January 09, 2023 Analyzed: January 10, 2023

Thursday 12 January 2023

Analyzed by:



Batch: 90367

FieldID LabID	Material	Location	Color	Non-Asbestos %	Asbestos %
15A 993089	Black Mastic Assoc. with 9x9 Green Black Speck Floor Tile	Small Conf. Rm 256	black	Non-Fibrous 100	None Detected
15B 993090	Black Mastic Assoc. with 9x9 Green Black Speck Floor Tile	Small Conf. Rm 256	black	Non-Fibrous 100	None Detected
16A 993091	Yellow Carpet Adhesive	East Corridor	tan	Non-Fibrous 100	None Detected
16B 993092	Yellow Carpet Adhesive	East Corridor	tan	Non-Fibrous 100	None Detected

Sampled: January 06, 2023 **Received:** January 09, 2023 **Analyzed:** January 10, 2023

Thursday 12 January 2023

Analyzed by: 

Batch: 90367



BOSTON NORTH

155 West Street | Suite 6 | Wilmington, MA 01887 | PHONE 978.688.3736 | FAX 978.688.5494 | FREE 800.659.1202

BULK SAMPLE CHAIN OF CUSTODY FORM

Report to (Inspector Name):	Robert Thomson	Bill To:	Accounts Payable
Company:	EFI Global, Inc.	Address:	Same
Address:	155 West Street	City, State, Zip:	Same
	Suite 6	Telephone:	800-659-1202
City, State, Zip:	Wilmington, MA 01887	Email:	US-EFIGlobal-BostonEnviroPC@efiglobal.com
Inspector Cell:	603-395-0335		

Project Information

Project No./ Description:	014,05200 DMH, Haskell Bldg 1 Prince St. Northampton, MA
Email Report to:	Robert.thomson@efiglobal.com / Rich.murphy@efiglobal.com
Alternate:	

Requested Turnaround Time:

<input type="checkbox"/> RUSH (6hr)	<input type="checkbox"/> 1 day (24hr)	<input type="checkbox"/> 2 day (48hr)	<input checked="" type="checkbox"/> 3 day (72hr)	<input type="checkbox"/> 5 day
-------------------------------------	---------------------------------------	---------------------------------------	--	--------------------------------

Media and Methodology

Type of Analysis:	PLM Asbestos	Check for Positive Stop:	<input checked="" type="checkbox"/>
Notes:		Date Collected:	1/6/23

Sample ID	Type of Material	Location
01A	9x9 Gray floor tile	Rm 265
01B	" "	Rm 247
02A	Black mastic above with 9x9 gray floor tile	" "
02B	" "	Rm 247
03A	Plaster wall base coat	Rm 265
03B	" "	" "
03C	" "	Rm 247
04A	Plaster wall finish coat	Rm 265
04B	" "	" "
04C	" "	Rm 247

Total Number of Samples Submitted: 36

Samplers Name: Robert Thomson Samplers Signature: [Signature]


Relinquished By (Client): [Signature] 1/6/23 Date: _____ Time: _____

Received By (Lab): 1/9/23 JAY MORGIN Date: _____ Time: _____

Sample ID	Type of Material	Location
05A	wall base molding	Rm 265
05B	" "	Rm 247 "
06A	Adhesive on wall base	Rm 265
06B	" "	Rm 247
07A	9x9 Gray with Green Streak floor tile	Rm 246
07B	" "	2nd floor East Corridor
07C	" "	Rm 228
08A	Black mastic, assoc with 9x9 Gray with Green Streak Floor tile	Rm 246
08B	" "	2nd floor East Corridor
08C	" "	Rm 228
09A	9x9 Brown Replacement floor tile	Rm 246
09B	" "	Rm 264
10A	Black mastic assoc with 9x9 Brown Replacement floor tile	Rm 246
10B	" "	Rm 264
11A	Adhesive on carpet squares	Rm 265
11B	" "	" "
12A	Black mastic Beneath carpet squares	" "
12B	" "	" "
13A	carpet Adhesive on Terrazzo	Conf Rm 227
13B	" "	2nd floor west corridor
14A	9x9 Green Black Speck floor tile	small Conf Rm 256
14B	" "	" "
15A	Black mastic assoc with 9x9 Green Black Speck floor tile	" "
15B	" "	" "
16A/6x	Yellow carpet adhesive	East Corridor
16B/6x8	" "	" "

1/9/23 JAY MOREHEAD

ROOM NO.	FINISH	DATE	WALL	CEILING	FLOOR	REMARKS
205	STAINLESS	GLT	GLT	GLT	GLT	
206	STAINLESS	GLT	GLT	GLT	GLT	
207	STAINLESS	GLT	GLT	GLT	GLT	
208	STAINLESS	GLT	GLT	GLT	GLT	
209	STAINLESS	GLT	GLT	GLT	GLT	
210	STAINLESS	GLT	GLT	GLT	GLT	
211	STAINLESS	GLT	GLT	GLT	GLT	
212	STAINLESS	GLT	GLT	GLT	GLT	
213	STAINLESS	GLT	GLT	GLT	GLT	
214	STAINLESS	GLT	GLT	GLT	GLT	
215	STAINLESS	GLT	GLT	GLT	GLT	
216	STAINLESS	GLT	GLT	GLT	GLT	
217	STAINLESS	GLT	GLT	GLT	GLT	
218	STAINLESS	GLT	GLT	GLT	GLT	
219	STAINLESS	GLT	GLT	GLT	GLT	
220	STAINLESS	GLT	GLT	GLT	GLT	
221	STAINLESS	GLT	GLT	GLT	GLT	
222	STAINLESS	GLT	GLT	GLT	GLT	
223	STAINLESS	GLT	GLT	GLT	GLT	
224	STAINLESS	GLT	GLT	GLT	GLT	
225	STAINLESS	GLT	GLT	GLT	GLT	
226	STAINLESS	GLT	GLT	GLT	GLT	
227	STAINLESS	GLT	GLT	GLT	GLT	
228	STAINLESS	GLT	GLT	GLT	GLT	
229	STAINLESS	GLT	GLT	GLT	GLT	
230	STAINLESS	GLT	GLT	GLT	GLT	
231	STAINLESS	GLT	GLT	GLT	GLT	
232	STAINLESS	GLT	GLT	GLT	GLT	
233	STAINLESS	GLT	GLT	GLT	GLT	
234	STAINLESS	GLT	GLT	GLT	GLT	
235	STAINLESS	GLT	GLT	GLT	GLT	
236	STAINLESS	GLT	GLT	GLT	GLT	
237	STAINLESS	GLT	GLT	GLT	GLT	
238	STAINLESS	GLT	GLT	GLT	GLT	
239	STAINLESS	GLT	GLT	GLT	GLT	
240	STAINLESS	GLT	GLT	GLT	GLT	
241	STAINLESS	GLT	GLT	GLT	GLT	
242	STAINLESS	GLT	GLT	GLT	GLT	
243	STAINLESS	GLT	GLT	GLT	GLT	
244	STAINLESS	GLT	GLT	GLT	GLT	
245	STAINLESS	GLT	GLT	GLT	GLT	
246	STAINLESS	GLT	GLT	GLT	GLT	
247	STAINLESS	GLT	GLT	GLT	GLT	
248	STAINLESS	GLT	GLT	GLT	GLT	
249	STAINLESS	GLT	GLT	GLT	GLT	
250	STAINLESS	GLT	GLT	GLT	GLT	
251	STAINLESS	GLT	GLT	GLT	GLT	
252	STAINLESS	GLT	GLT	GLT	GLT	
253	STAINLESS	GLT	GLT	GLT	GLT	
254	STAINLESS	GLT	GLT	GLT	GLT	
255	STAINLESS	GLT	GLT	GLT	GLT	
256	STAINLESS	GLT	GLT	GLT	GLT	
257	STAINLESS	GLT	GLT	GLT	GLT	



ROOM NO.	FINISH	DATE	WALL	CEILING	FLOOR	REMARKS
205	STAINLESS	GLT	GLT	GLT	GLT	
206	STAINLESS	GLT	GLT	GLT	GLT	
207	STAINLESS	GLT	GLT	GLT	GLT	
208	STAINLESS	GLT	GLT	GLT	GLT	
209	STAINLESS	GLT	GLT	GLT	GLT	
210	STAINLESS	GLT	GLT	GLT	GLT	
211	STAINLESS	GLT	GLT	GLT	GLT	
212	STAINLESS	GLT	GLT	GLT	GLT	
213	STAINLESS	GLT	GLT	GLT	GLT	
214	STAINLESS	GLT	GLT	GLT	GLT	
215	STAINLESS	GLT	GLT	GLT	GLT	
216	STAINLESS	GLT	GLT	GLT	GLT	
217	STAINLESS	GLT	GLT	GLT	GLT	
218	STAINLESS	GLT	GLT	GLT	GLT	
219	STAINLESS	GLT	GLT	GLT	GLT	
220	STAINLESS	GLT	GLT	GLT	GLT	
221	STAINLESS	GLT	GLT	GLT	GLT	
222	STAINLESS	GLT	GLT	GLT	GLT	
223	STAINLESS	GLT	GLT	GLT	GLT	
224	STAINLESS	GLT	GLT	GLT	GLT	
225	STAINLESS	GLT	GLT	GLT	GLT	
226	STAINLESS	GLT	GLT	GLT	GLT	
227	STAINLESS	GLT	GLT	GLT	GLT	
228	STAINLESS	GLT	GLT	GLT	GLT	
229	STAINLESS	GLT	GLT	GLT	GLT	
230	STAINLESS	GLT	GLT	GLT	GLT	
231	STAINLESS	GLT	GLT	GLT	GLT	
232	STAINLESS	GLT	GLT	GLT	GLT	
233	STAINLESS	GLT	GLT	GLT	GLT	
234	STAINLESS	GLT	GLT	GLT	GLT	
235	STAINLESS	GLT	GLT	GLT	GLT	
236	STAINLESS	GLT	GLT	GLT	GLT	
237	STAINLESS	GLT	GLT	GLT	GLT	
238	STAINLESS	GLT	GLT	GLT	GLT	
239	STAINLESS	GLT	GLT	GLT	GLT	
240	STAINLESS	GLT	GLT	GLT	GLT	
241	STAINLESS	GLT	GLT	GLT	GLT	
242	STAINLESS	GLT	GLT	GLT	GLT	
243	STAINLESS	GLT	GLT	GLT	GLT	
244	STAINLESS	GLT	GLT	GLT	GLT	
245	STAINLESS	GLT	GLT	GLT	GLT	
246	STAINLESS	GLT	GLT	GLT	GLT	
247	STAINLESS	GLT	GLT	GLT	GLT	
248	STAINLESS	GLT	GLT	GLT	GLT	
249	STAINLESS	GLT	GLT	GLT	GLT	
250	STAINLESS	GLT	GLT	GLT	GLT	
251	STAINLESS	GLT	GLT	GLT	GLT	
252	STAINLESS	GLT	GLT	GLT	GLT	
253	STAINLESS	GLT	GLT	GLT	GLT	
254	STAINLESS	GLT	GLT	GLT	GLT	
255	STAINLESS	GLT	GLT	GLT	GLT	
256	STAINLESS	GLT	GLT	GLT	GLT	
257	STAINLESS	GLT	GLT	GLT	GLT	



PROJECT M-718
NORTHAMPTON STATE HOSPITAL
THE COMMONWEALTH OF MASSACHUSETTS
DIVISION OF BUILDING CONSTRUCTION
DEPARTMENT OF MENTAL HEALTH

PERLEY F. GILBERT ASSOCIATES, INC.
ARCHITECTS AND ENGINEERS
LOWELL, MASS.

SCALE: 1/8" = 1'-0"
DATE: 10/10/66

NO. REVISIONS
DATE

SECOND FLOOR PLAN A3

DEDS. SHOWN NOT IN CONTRACT

FIN. 2ND FLOOR
EL. 112.50

KEY PLAN