

GENERAL NOTES

1) THE CONTRACTOR SHALL INSTALL THE NEW POSTS & BEAM AND SHALL PROVIDE TEMPORARY SUPPORT FOR THE EXISTING 2ND FLOOR JOISTS, PRIOR TO DEMOLITION OF THE EXISTING PARTITION WALL SCHEDULED TO BE REMOVED.

2) THE CONTRACTOR SHALL DESIGN, FURNISH, AND INSTALL THE TEMPORARY

2ND FLOOR SUPPORT JOIST.

3. JACK THE EXISTING FLOOR JOISTS 15 HIGHER THAN FINAL ELEVATION PRIOR TO INSTALLING THE NEW BEAM. THE PROPOSED BEAM SHALL BE INSTALLED SO THAT THE BOTTOM ELEV. OF THE FLOOR JOISTS IN THE FINAL POSITION IS THE SAME AS THE PRESENT FLOOR JOIST ELEVATION.

4) THE CONTRACTOR SHALL USE MAXIMUM CARE NOT TO DAMAGE THE EXISTING PORTION OF THE STRUCTURE SCHEDULE TO BE RETAINED.


5. THE PROPOSED POST SHALL CONSISTS OF 35x7" PARALLAM (PSL) WITH 1.8E AND Foll = 2500 PSI.

6. THE PROPOSED BEAM SHALL CONSISTS OF (3)-13 x16" MICROLLAM (LVL) WITH 1.9E AND Fb = 2600 PSI.

7) THE CONTRACTOR IS RESPONSIBLE FOR BRACING THE 2ND FLOOR DURING THE CONSTRUCTION PHASE. THE CONTRACTOR SHALL DETERMINE AND ESTABLISH, BY FIELD MEASUREMENT, THE ACTUAL DIMENSIONS AND DETAILS NECESSARY TO COMPLETE THE WORK AS SHOWN ON THE PLAN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE ACCURACY AND ADEQUACY OF SAID MEASUREMENTS, AND SHALL NOT ORDER ANY MATERIALS OR COMMENCE WITH ANY WORK UNTIL THE FULL EXTENT OF THE PROPOSED WORK HAS BEEN DISCUSSED WITH AND APPROVED BY THE OWNER/OWNER REPRESENTATIVE.

8. THE CONTRACTOR SHALL REMOVE THE TEMPORARY SHORING ONLY AFTER THE PROPOSED MODIFICATIONS HAS BEEN COMPLETED.

9. THE DIMENSIONS SHOWN ON THESE DRAWINGS ARE TAKEN FROM FIELD MEASUREMENTS AND ARE NOT GUARANTEED.



SHT. 3 of 3

TITLE SECTIONS AND GENERAL NOTES

LOCATION

PROP. 2nd FLOOR SUPPORT BEAM 80 NAHANT STREET, LYNN, MA

ENGINEERING, INC. CONSULTING ENGINEERS 99 Washington Street, Suite 215 Melrose, MA 02176 (781) 662-4690 CHECKED BY: DATE: PROJ. NO.:

2/26/18 18.104A(1)

DQ

AS NOTED