# National Grid Distributed Generation MA Webinar

# <u>Complex</u> Interconnection Process Review

April 17th, 2025

# **Disclaimer:**

This presentation has been prepared solely as an aid to discussions between National Grid and interested stakeholders and should not be used for any other purposes. This presentation contains high-level, general information (not project specific) which may not be applicable in all circumstances. National Grid makes no guarantees of completeness, accuracy, or usefulness of this information, or warranties of any kind whatsoever, express or implied. National Grid assumes no responsibility or liability for any errors or omissions in the content. Nothing contained in this presentation shall constitute legal or business advice or counsel.

No party is authorized to modify this presentation.

The presentation is being recorded.

The information in this presentation could be affected by future revisions to the Standards for Interconnection of Distributed Generation, M.P.D.U. No. 1579 (Tariff), or by open docket D.P.U. 19-55.

# Agenda

01	Welcome & Opening Remarks - Will Kern
	Safety Message
02	Concrel Communications & EV25 Successor Will Korn
UZ	General Communications & F125 Successes – Will Kenn
	Standard Interconnection Process Review
03	Screening - Anish Ganta, Jorge Jorge (JJ) and Claudia Cobani
04	Standard/Complex - Jess Kosinski
05	Fulfillment of ISO-NE's I.3.9 Requirements (Includes ASO Study Process) - Jess Kosinski
06	Post Connection Support – Alex Bellavia
07	Portal Moment – Kara Nail
08	Flexible Connections Programs - Arnaldo Arnal
09	Q&A - Will Kern

Note: As used in the following slides, reference to "National Grid" or the "Company" means Massachusetts Electric Company and Nantucket Electric Company, as applicable, when the context is the distribution system and/or distribution interconnection requirements, and shall mean New England Power Company when the context is the transmission system and/or transmission system requirements.

#### **National Grid**

01

# Safety Message

Will Kern

## **Checking for Ticks**

Tickborne diseases are on the rise, particularly in the spring, summer and early fall when ticks are most active, according to the Centers for Disease Control and Prevention.

# Steps to protect against ticks. Follow these whether you work outside, enjoy your yard or spend time on a national forest or grassland. You should:

•Avoid areas with high grass and leaf litter and walk in the center of trails when hiking.

•Use repellent that contains 20 percent or more DEET, picaridin, or IR3535 on exposed skin for protection that lasts several hours.

•Use products that contain permethrin to treat clothing and gear, such as boots, pants, socks and tents or look for clothing pre-treated with permethrin.

•Treat dogs for ticks. Dogs are very susceptible to tick bites and to some tickborne diseases. They may also bring ticks into your home. Tick collars, sprays, shampoos, or monthly "top spot" medications help protect against ticks.

•Bathe or shower as soon as possible after coming indoors to wash off and more easily find crawling ticks before they bite you.

•Conduct a full-body tick check using a hand-held or full-length mirror to view all parts of your body upon returning from tick-infested areas. Parents should help children check thoroughly for ticks. Remove any ticks right away.

•Tumble dry clothes in a dryer on high heat for 10 minutes to kill ticks on dry clothing after you come indoors. If the clothes are damp, additional time may be needed.



02

General Communications & FY25 Successes

Will Kern

# **General Communications**

- Simplified Interconnection Process Webinar is scheduled to take place July 2025
- CEI Open House May 15th 2025
- Former Webinars are posted to our 'Stakeholder Meetings Updates Page'
- Transfer of Ownership
  - Outages
  - Reconciliation/Cost Sharing Payouts
  - Record Keeping
  - Interconnections Documents Website
- Schedule Z / Community Solar
  - opportunity to make changes increased to 6x per year
- Apr'24 Mar'25: Interconnected 13,742 applications totaling to 197.68 MWs
  - Complex 1,816 apps totaling 113.25 MWs
    - Solar –
    - Other -
  - Simplified 11,926 apps totaling 84.43 MWs
    - Solar –
    - Other –

03

# Screening Review Process

Jorge Jorge (JJ), Anish Ganta & Claudia Cobani

# **Pre - Applications**

•Required for all cases 250 kW or greater, optional for cases less than 250 kW (Tariff Section 3.2)

Project Size	Pre-Application Report Fee
< 250 kW	\$100
250 kW – 500 kW	\$250
> 500 kW	\$750

•Pre-application requirements include, but not limited to: Proposed site location, system size, generation type (Solar, Wind, Hydro, CHP, Diesel, Energy Storage, etc.) and an uploaded screenshot using any web mapping platform (Google Maps, Bing Maps, Assessors Maps)

•Pre-application reports are completed by the Company within 10 business days (BD)

•Pre-application report includes, but not limited to: feeder/circuit information, substation name, phase(s), if the area is in a network or non-network area, potential system constraints, application checklist, the connected & pending aggregate distributed generation (DG) on the feeder(s) and if a project will fall in an area that has an ongoing Affected System Operator (ASO) or Group Study

### Pre – Application Report

#### \*Report is a sample and for illustrative purposes only\*

#### nationalgrid

Massachussetts	Applicant:	123456 National Grid					
Pre-Application	Pre-Application Re	quest Date:	Preparation Date:	7/7/20			
Report	Prepared by:	Jorge Jorge	5 	Revision # (if any):	0		

I. Executive Summary:

A. <u>Interconnection Applications</u>: The Applicant (noted above), has submitted a request for a Pre-Application Report (Report) for the interconnection of Appendix and a state of the proposed location(s) noted below) to the National Grid (Company) Electric Power Sy.

B. <u>Pre-Application Process</u>: The proposed location was reviewed (as per the Standards for Interconnecting Distributed Generation referenced below) to: (1) determine the characteristics of the existing Company EPS near the proposed location(s), (2) identify the aggregate amount of other proposed and existing generation capacity connected to the nearby Company EPS, and (3) identify other potential system constraints critical times that may impact the proposed generation system(s).

C. <u>Further Inquiries:</u> All additional questions and comments related to this report should be directed to National Grid's Distributed Generatis Services email account: Distributed.Generation@nationalgrid.com.

#### II. Proposed Location Information:

The proposed location information provided in the table below is based on the information provided by the Applicant (i.e. Interconnecting Customer) in the Exhibit B - Pre-Application Report Form, which has been attached to this Report.

Table of Proposed Location Information			Proposed kW(AC	):	2,500 kW	Phase	
Proposed Energy S	Source:	Solar	Existing Account	(if applicable):	100	N/A	
Street Address:	93	9 Southbridge Str	eet	X-Street:		N/A	
City:	Wore	ester	State:	MA	Zip Code:	01610	
Likely Process:	Stand	lard	GPS (North):	N/A	GPS (West):	N/A	_

#### III. The Company's Electric Power System (EPS):

A. As required by the Standards for Interconnecting Distributed Generation (referenced below), the Company must identify feeders within ¼ 1 of the proposed interconnection site. Since many locations may not have any adequate feeders within ¼ mile, the Company may elect to provide information for the nearest adequate feeder(s) to the proposed location.

rable of information	ion for ivearest reeder				
Feeder Number:	01-HT17		Radial or Network?:	Radial	
Hosting Capacity:	Available		Feeder Rating:		
Substation:	Cambridge St.		Voltage at Substation:		
Substation 3V0:	Not In Service	1	Substation Transformer Rating:	- MVA	
Voltage (near locat	ion): 23 kV		Phase (near location):	3 <b>Φ</b>	
Distance to three-p	hase (if not within 1/4 mile of propose	ed location):		0 ft	
Distance to Substa	tion: 4,260 ft		Feeder Peak Load:	- MVA	
DG on Feeder:	0 kW	Pending DG:	0 kW Existing DG:	0 kW	
	Included in total above:	Pending PV:	0 kW Existing PV:	0 kW	
		Pending non-PV:	0 kW		
		Non-PV Type:	N/A		
Table of Informat	ion for Second Nearest Feeder (if a	railable)		5	
Feeder Number:	01-8W2		Radial or Network?:	Radial	
Hosting Capacity:	Available		Feeder Rating:	527 A	
Substation:			-		
	Vernon Hill		Voltage at Substation:	13.8 kV	
Substation 3V0:	Vernon Hill In Service-Cost Sharing Required		Voltage at Substation: Substation Transformer Rating:	13.8 kV 40 MVA	
Substation 3V0: Voltage (near locat	Vernon Hill In Service-Cost Sharing Required ion): 13.8 kV		Voltage at Substation: Substation Transformer Rating: Phase (near location):	13.8 kV 40 MVA 3 Φ	
Substation 3V0: Voltage (near locat Distance to three-p	Vernon Hill In Service-Cost Sharing Required ion): 13.8 kV hase (if not within 1/4 mile of propos	ed location):	Voltage at Substation: Substation Transformer Rating: Phase (near location):	13.8 kV 40 MVA 3 Φ 150 ft	
Substation 3V0: Voltage (near locat Distance to three-p Distance to Substa	Vernon Hill In Service-Cost Sharing Required ion): 13.8 kV hase (if not within 1/4 mile of propos- tion: 10,230 ft	ed location):	Voltage at Substation: Substation Transformer Rating: Phase (near location): Feeder Peak Load:	13.8 kV 40 MVA 3 Φ 150 ft 7.9 MVA	
Substation 3V0: Voltage (near locat Distance to three-p Distance to Substa DG on Feeder:	Vernon fill In Service-Cost Sharing Required ion): hase (if not within 1/4 mile of propos ion: 10,230 ft 2,748 kW	ed location): Pending DG:	Voltage at Substation: Substation Transformer Rating: Phase (near location): Feeder Peak Load: 21 kW Existing DG:	13.8 kV 40 MVA 3 Φ 150 ft 7.9 MVA 2.727 kW	
Substation 3V0: Voltage (near locat Distance to three-p Distance to Substa DG on Feeder:	Vernon Fill In Service-Cost Sharing Required ion): 13.8 kV included for twithin 1/4 mile of proport 10,230 ft 2,748 kW Included in total above:	ed location): Pending DG: Pending PV:	Voltage at Substation: Substation Transformer Rating: Phase (near location): Feeder Peak Load: 21 kW Existing DG: 21 kW Existing PI'	13.8 kV 40 MVA 3 Φ 150 ft 7.9 MVA 2,727 kW 2,698 kW	
Substation 3V0: Voltage (near locat Distance to three-p Distance to Substa DG on Feeder:	Vernon Fhil In Service-Cost Sharing Required ion): hon: 10,230 ft 10,230 ft 10,230 ft 10,248 kW Included in total above:	ed location): Pending DG: Pending PV: Pending non-PV:	Voltage at Substation: Substation Transformer Rating: Phase (near location): Feeder Peak Load: 21 kW Existing DG: 21 kW Existing PV:	13.8 kV 40 MVA 3 Φ 150 ft 7.9 MVA 2,727 kW 2,698 kW	

#### B. Other Known System Constraints:

 Recent changes in the Massachusetts net metering rules may have further restrictions regarding the size of a distributed generation system that can be offered Net Metering Services on any one single parcel of land. Refer to the Massachussetts Depart. of Energy & Environmental Affinis / Dept of Public Utilities (D.P.U.) homepage:

http://www.mass.gov/ea/grants-ind-tech-assistance/upical-assistance/apencies-and-divisions/dpu/ Massachussetts Dept. of Energy & Environmental Affairs / Dept. of Public Utilities (D.P.U.) - Net Metering Homepage: http://www.mass.gov/ea/energy-utilities-clean-tech/electric-power/net-metering/net-metering.html Massachussetts Dept. of Public Utilities (D.P.U.) - Net Metering Frequently Asked Questions and Answers: NOTE: See section VI. Design and Development of Net Metering Facilities / Question #46.: "What is the maximum capacity of a net metering facility?"

http://www.mass.gov/eea/grants-and-tech-assistance/guidance-technical-assistance/agencies-and-divisions/dpu/net-metering-faqs.html

2. A conceptual grade cost estimate of the required system modifications will be determined during the System Impact Study (SIS). The cost for line extensions / re-conductioning of rabits/ feders can approach or exceed \$500,000 mile depending on the keyl of complexity. State and Federal taxes apply to payments for system modifications, including feeder line extensions. The Point of Interconnection, circuit characteristics, and/or other projects may afflect feasibility of installing the proposed generation capacity on this circuit at the proposed location. Also, the available distributed generation capacity is open to other project proponent tumbes and until a complete application is received.

3. Additional system constraints particular to the proposed location (if applicable):

	Thank you for your interest in interconnecting to National Grid's Electric Power System. We look forward to working with you to progress your application through the interconnection process. Please review the following conditions as they may impact your overall processing time and associated costs.	
	Due to the high volume of existing and proposed DG interconnections, this project's location falls within an area that is currently undergoing study by an Affected System Operator (ASO), which analyzes the potential impacts of a DG project to non-distribution assets. As such, in accordance with MDPU 1320, should this application proceed to impact study, it will immediately be placed on hold pending the results of the ASO study. In addition, because system modifications are anticipated to be in excess of \$1 Million; study timeframes will be by mutual agreement in accordance with MDPU 1320.	Ongoing ASO Notes
	Prior study of the Barre feeder, which is near the proposed Facility, has shown significant interconnection challenges. Be advised that interconnection in this area may require substantial system modifications, impacting the Customer's desired project schedule and budget. Further National Grid engineering review will be required to determine the most viable method of interconnection.	Challening Interconnection Notes
j	Barre is 13.8Kv Grd'd Wye/ effectively grounded.	
	As the proposed Facility is equal to or greater than SMW please be advised that significant distribution and transmission system upgrades may be required that may result in a longer project schedule and higher costs than a smaller project. In addition to the Distribution System Impact Study (DSIS) be required. This will require that the DSIS be placed on hold at the point that the Distribution System interconnection solution is identified. Once that point is reached in the DSIS a high level non-binding cost estimate and timeline will be provided to the Interconnecting Customer and they may determine if they with to proceed or not at that point. Link to the ISO Tariff for Section 1.3.9 https://www.iso-ne.com/participaler/ule-procedures/tariff	DSIS/TSIS Notes
	Based on the information provided in the Applicant's Exhibit B - Pre-Application Report Form and the other information identified in this report, the Company expects that if an application is submitted at the proposed location, the application will ultimately need to be processed in the Standard process track. If the applicant submits a complete application and leatest to proceed directly to the Standard process, the application will proceed directly to the Impact or Group Study process once an initial review is completed. The applicant may still submit an Expedited application, and in which case upon receipt of a completed application the Company will perform a Screening Review (and if necessary Supplemental Review) to determine if an Impact or Group Study is required.	Process Track Notes
	Group Study Hold: Proot to completion of Screening for your Application/Case, the company began the process of performing necessary engineering studies to determine the coope of required modifications to the electric distribution system in this area in order to provide the requested interconnection. In performing such studies, it has been determined that the interconnection will also impact the electric transmission system and will require substantial review and study by the Affected System Operators (including, but not limited to, New England Power Company and ISO-NE) to determine a safe and reliable interconnection solution. Your Case/Application had not completed Screening prior to determination of the scope of this study, and as such, your Application/Case with Massachusetts Electric Company will remain On Hold until the conclusion of the review of the Affected System Operators. Please review the information on this link to determine the potential impact of a group study on this project https://ngus.force.com/servlet/servlet.FileDownload/file=0156700000FLq3	Group Study Notes

# **Application Checklist**

							C12754C 04502 6				
Requirement	WOPU LISS/APUCISIO	250-18-180-18	100xW and iDone		Templete Cumments	The RCC line of demonstration (subtraner us, whiley equipment)	047540 GANNA	Required	Required		
Rodal Nast same maximum to	E8 794C/E8 7940			04			fgya-i			Regired	
His the Application Peerson processes?	WTO VIEW REFER TO	Repired	Repired	Replied		interrupting Device (recover, snearer, Aux, etc.) shell be shown, including make, model, voltage and current rating	63875407.5	Aspirel	Required	Include	
	COLUMN STORE AS					Generic El should be shown if customer has AC Coupled BEES and		Returns for Doctors	Security for Damage		
Die beiten schengen eine er beiten heber		Required	Repired	Required		would like to limit the output				Required for Durings	
					or real million of the base						functing with most livery include 74, 744 OH 747 settings on
Technical Details Section							1				the result a series of the the series of the or a
the substrate of a Man and American Review Room						Relaying for interrupting Davies (Including Value and Model, voltage	and the second second				they island them prives away from utility if so trip the main. If
grade greed in: (and periodic regions result and, and heat access of a resident radius as an read-		Repired	Repired	hepitel		and current rating of device) proves the phone (Also - 500kW can out to use hid PTR and tune instead of recurrent rates)	EXEMPTING TALE - TALES EXEMPTING TALE - TALES EXEMPTING TALE - TALES	10.	Required	Include	they do not then trip the generator treaster. Autoring machines without an investor with require a spec these reas/22( in their
Confirm that the Peopler 1 line has the Nasier listed in the pre-						week general managing some (5, 20,800/0 mc)	087540 Tele 7 4 55 2 4				they protection activity and any device that can appen in Instances the utility and the prevention. If rational paternines
application if one exists. If no facilier is written, and the nearest 3- phase feator to the site using SC.		Report.	Report	Reputed							they will not expertiplement type of study when is then
The waterup and system size must be consistent with the remainder of		hearing	Repired	hequies							and said
Application.							647940733				
Spature		Aspirat	Repired	Paquint		Treature: Cutore 3x3 reay & estimations: Center	087969-013	N/A	Required	Required	
The lightern size		Repired	Repired	Regired		21.7 rate state state into an experimental Pho-	CONTRACTOR OF				
Does the Address of Techts metch what is found on the one the and		Neturel	Petrini	Petrel		wyewye	08796074.4	n/A	Required	terijet	
deventing unit type information must be cearly shown, showing at relevant of reliant that match information shows on the coar sheet.		Annine	Realized	Ren.int		SC Power Supply for Resping (including fail-self-contract) prover pa	Contract in a local division of the local di				
include theil type for rotating			-		Syndronout, Houbler, Turbine, Huener, Aue Cel, Hyers or Tailwe	stown including utility restaration settings	68756013.2	N/A	Required	Required	
dise line						All real a role laying satisfy a real to set for 14 hours			-		
	MPDU 2020 Banket C					Wark Service Breaker or Funde Doctomedt (Poetweld Curtomer Ged)	EDETTIC DATE: A	N/A	Required	Required	
Central PT Dark and sampling	ENTER 1721	selves.	adhan .	abra .		Automatic support Marcal Response Victoria and an United					
box the extrem metch the portal and the application?		Anguinet	Repired	Pequint		operated, visite treat when operand, while inclusive in oper position,	0879627.4				
increasing of any local data and increasing the state	CETHOLOGICA					Accession by The West ( Mound in Press)	10875607.4	N/A	Required	Repired	
Agridan of colors an data and in parameter party of	EXTING Beloit 4	Repired	Repired	Repired		They must include the sublety/Current/Make/Mader of the sublid	ECETTAD GANGE A		÷	1 C	
	rgun 2				Desents and Prime nover	unies it is cutom made					
	CETRODADE4						6879627.2				
person alle serverne and anonal and a pre-	Feunit	refract	repres	who are		Utility Revenue Meter should be shown	08756072	Required	Tenjine .	Required	
	CETHCTD						CETHO Smith 4				
proved measures resortions and a use fermatic for otherware	EXTING 1.0			and a second			08796(7.6.12.3				
an excise and a lease of note is not accord	CETSC DATE: 4	10A		abre .		USINg Rectaur shown (P> 1000HW) should be shown any 500HW P	EXEMPTION 11.12.3		Ten int	Service .	Participation of the second seco
	Figm 2				Next impelance: Forn the sut sheet for madeling purposes	sultane spolar 55 PR is pair of sultane relusion reay	CETNO BANK 4 8.4				- Provide and a second s
	CETNC10										
water Templete wing of the investor and miss patients should be	DEDICTA3					USity Docered Means Alows	CETNO GAIR 4 L 4	Required	Required	Regired	
HOW, DO NOT TAKE TO THE POWERT WE WIND THE PT LETTING	08750743	Aspirel	Required	Required Finvener asset OrP	Some ratesing mechinic are setting an inverter, all		6587560116				Only if the rotating angles is patient an investor is this reacted.
W 21,56,31 C/L WENGS DE HILM 2000WW TO MAKING PTK.	CETSIC BADDA				untrained employing and an over the second prover the second	Internet 20 Protective Device Defining (Bath Primery and December, Restaurier, Mate, Setting)	CETHOTA CETHOTA	Required	Required	Required Triverter Salved CvP	Generally there will be a redundant protective device over 720
	Form?				a considered "survives"		687560-Fg/H462				-
steraweding Tendomer						Dire plan from the site actives match the sorted and the exclusion is it is tot.					
-stinding Configuration (N.A. Publik surred)	G8796(13.3					huppint		Aspured	Required	Required	
fatings vice, primary votage, secondary votage	DETRICTION OF A	Aspire	Required	hepite		Are the property lines shown? Any essense to lower 40%, Rel tread, weithinkey, put lend etc.	K087540.5.5.8 K087540.5.5.5.8	Aspuired	Repired	Repired	
utilitating in the second second second	CETOC DADC4					Gerdine direction hardly shown	087903113	Required	Peoplet	Repired	
Offective Drounding (not required <500x8)						The same to prove with some tax	0879(3113	Anning	Ten int	and the second se	
specie handed and so concludes our as provid							087903113	and and a second s		- alberta	
LA supported to supported technic with a pounded							087963113	and the second s	and a second		
press ava						at news (perty and culture rearies) about	02503111	retines	naines.	hebres	
2. It is yespecticle connected primary winding with a fully incurated restriction of the						(terrature)	0875023113	Required	Required	Required	
accordary winding to have a data connection. The inclusion neutral is						interrupting Device(i)	087963113	Neguined	Required	Nepind	
entation providers for the solition of a provering reactor or						contine deviation (e.g. generator discovered) (24.7 scattalise.	6475463.5.5.8	Required	Regime	Repired .	
is the event the Bosenito, I considering in the period of the Doubleski.	0879673435					Paint of Common Coupling (POC)	087967113	Assures	Peoples	Regime	
of the second se	087907321	NB.	Required	hequine			0879071113				
1.4 sysponed to syspone cheating with an applied	CETHO Bright					coulted free source researce are belonge up?	02303111	rational	- adures	repres	
provide						Guiding and proposed access result() including at a minimum, result				adv.es	
tentres. A 2 sets simply allefar all a singly life musical tentemer.						material, and dimensions at least 20 to confirm Company personnel					
actual and a second second second						and equipment actes requirements are not. The access road must be assisted to company equipment, equipment for requirement as	C8790C1113	Required	Regired		
aul serves inclusion						located on private property (e.g. connot have recises; load					
to a sind count house and also also also readed age a						man(units and a tase)					
granding treatment.					The culture is propose a grounding transformer, the bill	Autointe autour, Nacco, page, and autour particip	087963113	Annuired	Tenuine .	Repires	
y y elevisiones buelling electronistic elevisiones					N of Seen roberghos priors and Cale St. prior		002502113			too int	
with a primary size grounding transformer.					Shown, I're reun'e grounding reactur 's wed, the proposed size	derentor scalar	087901113	Aegured	Required		
Service antenna refer in desar	0896711	and and	animi			bining arrives	0875403.5.5	Aspired	Required	animate and a second	
and	04750111			Reputed							

# **Standard Interconnection Application**

### **Interconnection Application**

- Required for all projects
- Requires all items on application review checklist to be filled out and submitted
- Application reviews are completed within 10BD



### **Application Requirements**

- All submissions require a completed application form, application fee, Billing account number, system size, equipment assets, account location, site plan, line diagram, site control documentation tech sheet(s) and legal information document
- Larger projects could require additional forms such as: De-Rating Letters, Anti Islanding Forms, UL 1741SB Certificate, Load Rejection Overvoltage Letter. Projects with storage also require the Energy Storage Narrative and Energy Storage Checklist
- All required documents are detailed in the app review checklist

## **Commonly Missed Items Leading To Application Review Holds**

- Document Discrepancies
- Billing Account Number
- Construction Work Request Number

### Line Diagram Omissions:

- Inverter & interrupting device nameplate rating, relay settings, make, model, voltage and current rating
- Internal DG protective settings with redundant relay settings for inverters (Table 7.6.11.1-1, ESB 756)
- Missing Electrical Engineering PE Stamp
- Aggregate AC KW/KVA Ratings of entire proposed system

- •UL 1741SB Certificate
- Anti-Islanding Forms
- •De-Rating Letter

#### Site Plan Omissions:

- Point of Common Coupling (PCC)
- Company pole number nearest to the proposed PCC
- Access road notes that include road material, and dimensions of at least 20' wide for necessary clearance requirements
- All equipment will be required to be grouped and will need to be approved by National Grid metering department before installation.

# **Application Review Guidelines**

### •Electric Service Bulletin (ESB) 756D

•National Grid will not provide transformers larger than 300kVA or when primary metering is least cost to serve option

•All commercial meters and disconnects need to be grouped together

•Existing metering located on a pad mounted transformer will be required to be relocated when applying for new stand-alone DG systems

•New MA SMART meter installations require disconnecting means on both the line and load side of the meter

•MA SMART systems over 500KW must be co-located with an energy storage system (ESS) that meets the requirements for an energy storage adder pursuant to 225CMR 20.06(1)(e). AC coupled projects require individual meters for the solar, ESS & a utility meter ahead of the entire system

•All final metering locations will be determined by the metering department and will be based upon existing service configuration

•All Expedited cases that need further study will need all the documentation required for Standard projects

• Final disconnect and meter locations should not be installed until National Grid has approved the location on site with the electrician

National Grid | April Standard Interconnection Webinar | April 17, 2025

# Screening

- Screening is **required** for Expedited and Standard projects
- Expedited projects require a screening review to be completed within 25 BD
- Standard projects require an initial review to be completed within 20 BD

## **Screening Checkpoints:**

- Is the proposed PCC on a radial/Network System?
- Is the facility using UL1741 SB Listed equipment?
- Is the service configuration screen met?
- Substation back-feed screen met?
- If any of the screening checkpoints fail, National Grid may require further study before providing an Interconnection Service Agreement (ISA)
- Most proposed projects larger than 25KW on a 4KV Feeder and any projects on a network or non-effectively grounded system will require further study

# **Potential System Constraints That Lead To Further Study**

- Ongoing Area Studies or Group Studies
- Challenging Feeders
- Hosting Capacity
- Feeder Reconfiguration
- Ungrounded Feeders, Non-Effectively Grounded Feeders and HT Lines
- Planned Substation Work
- Feeder Saturation

# Screening Memo \*Report is a sample and for illustrative purposes only\*

Screening Memo Prepared by: Jorge Jorge		Revision Number: 0.0 Preparation Date: 10/17/2022	2	natio	onalgrid
Interconnecting Customer:	Nationa	l Grid	Application(s):	Const. WR(s):	
1000.00	kW(AC) Proposed Inverter Base	ed Interconnection Project	Case:XXXXXX	XXXXXXXXX	Droiget 9
250.00	kW(AC) Proposed Battery Base	d Interconnection Project			Project &
0.00	kW(DC) Proposed Battery Base	ed Interconnection Project			Site
0.00	kW(AC) Existing Inverter Based	Interconnection Project			Information
1250.00	Aggregate kW(AC) of Proposed	and Existing Inverter Based	Interconnection Dr	niecte	
Droject Address:	Aggregate KW(AC) of Proposed	Southbridge Street Worceste	MA 01610	Jecis	
Project Address.		Southeringe Street, Wordeste	I MA, 01010		
Executive Summ:     A. The Interconnecting described herein to The application Due to the comple This cost must be returned within 15 in 55 business day Company will infor impact study.	arv: g Customer has submitted an ap the National Grid (Company) E M.D.P.U. 1468 & National Grid requires further study sity of your application, a study fi paid in full before National Grid i business days of its issuance to s. An additional 5 business day m the Interconnecting Customer	oplication for the interconnect lectric Power System (EPS). s Electric Service Bulletin (ES based on the results of this e estimate will be establishen nitiates the impact study. The the Interconnecting Custome maybe required if substantia about incremental study time	tion of the generatin Reviewed as outlin SB) 756 Appendix C review. d by our engineerin e study agreement n er. The impact study I modifications are re e after the Company	ig system ed in: g team. nust be signed and will be completed required. The commences the	Study Required Or Not Required DSIS Cost Estimate If Progressing To Impact Study
I. The Company's E     A. Table of Informat     Feeder Number:     Feeder Rating (A):     Substation Name:     Substation Transfe     Substation Transfe     Feeder Phase & V     Voltage (kV):     Phase:     B. Is the existing se     C. Interconneted an     The following desc     Note that the follow     available informati     Total Interco     Total Interco	clectric Power System (EPS):         ion for Nearest Feeder         01-8W         527         Vernon Hill         ormer Number:       T2         ormer Rating (MVA)       40         foltage at/near Site of Proposed is         13.8 kV         3Φ         rvice equipment compatible with a site of proposed is         with site interconnected and in-         wing values are provided for information at the time of writing of this reported DG on the Subject Ferencested DG on the Subject Ferencested and and here	Radial or Network?     Feeder Voltage at Sul     Distance to Substation     Peak Feeder Load (es     12 months):  DG:     Feeder extension or u     serve the site?  ith the proposed generating process DG on the subject fe mational purposes, based or port, and are not binding. eder:     7114 eder:     369	bostation (kV): h (Circuit Feet): stimated for past pgrade required to g system? Metering Type: beder, as of the time h the current status kVA kVA kVA	Radial 13.8 kV ~10,230' 7.9 No Yes Primary of this report. of the feeder and	Proposed Feeder & Substation Information
Total Interc Total DG Exce The combined inte substation transfor required.	onnected and In-Process DG o Subject Substation Transfo eds Substation Transformer R rconnected and in-process DG, mer. As a result, it is not expect	on the 13013 rmer: No including this application, doe ed at this time that a substati	kVA ss not exceed the ra on transformer repla	ating of the acement will be	

## **Screening Memo**

\*Report is a sample and for illustrative purposes only\*

Screening Memo Prepared by: Jorge Jorge Revision Number: 0.0 Preparation Date: 10/17/2022

## national**grid**

#### D. Additional Interconnection Details The Interconnecting Customer (IC) has proposed to install a 3 $\Phi$ generating Facility. Customer has proposed to interconnect onto customer owned pad mounted transformer with (See below)kVA rating. Actual point of interconnection to be determined. Please, refer to NGRID EPS diagram for the location of the nearest three-phase feeder. Final interconnection determination to be made during the Study. System modifications may be required. Project Configuration Notes: New MA SMART Stand Alone PV System that is proposing 3PH 13.8KV Primary Interconnection. Utility & Site Equipment Site configuration includes interconnection behind new proposed utility loadbreak, recloser and primary meter. Layout Notes System equipment proposal includes: New system disconnect loadbreak, pad mounted recloser, one 1500 KVA 13.8KV To 600V Transformer and Four Yaskawa PV Inverters. Interconnecting customer must ensure that all service equipment will be suitable for the existing service General Site characteristics and confirm equipment locations are approved before any installations. Requirement All PV Meters and disconnects are required to be grouped with any existing metering. NGrid Metering Notes department will approve of any taps or tap boxes and final location of all equipment. Please note if your project intends to be over 1 MW, a PSCAD model and PSCAD Model Review payment will Additional be required. Additionally, if you project intends to be 5 MW or above, a PSSE model and PSSE Model Review Information For payment will be required \* Possible For further detail; Please refer to the 'Updated Model Requirements & ASO Initiation Timeline' document Requirements provided here: https://gridforce.my.salesforce.com/servlet/servlet.FileDownload?file=0156T00000GJcFN. Moving Forward Screening Notes: This application will be diverted to the Group Study process as project is proposing interconnection in an area with an open group study window. Group Study will encompass multiple applications and study the surrounding infrastructure and will determine: - System Grounding Requirements (if required) - System Relaying Requirements (if required) System Modifications (if required) Screening Feeder 01-8W2 has hosting capacity **Review Notes** Vernon Hill Substation 3V0 Is In Service This interconnection application has failed the risk of islanding screen This interconnection application has passed the substation feedback screen Any required construction costs will be developed during the conclusion of the Study Review This application is proposing to interconnect in the Worcester Study Area where there is an ongoing group study. This project will be placed on hold until the conclusion of the Group Study, where it could possibly be included in a new pending group study that will commence once the current group study concludes.

## **Screening Memo**

\*Report is a sample and for illustrative purposes only\*

Screening Memo Prepared by: Jorge Jorge Revision Number: 0.0 Preparation Date: 10/17/2022

## nationalgrid

#### III. The Description of Interconnecting Customer's Facility:

The proposed design of the generating Facility described herein is subject to change based on the requirements identified by National Grid prior to the execution of the Interconnection Service Agreement.

A. Description of G The proposed 12:	enerating Facility 50kW system consis	ts of:	UL1741 certifi	ed equipment		Proposed
Quantity	Manufacturer	Model	Generator Type	kWAC Nameplate	Phase/VAC	Conoratin
4	Yaskawa	Solectria XGI 1500-250-600	PV Inverter	250 KW/KVA	3PH/600V	Equipmen

Refer to the attached line diagram for system configuration and protection equipment details.

NOTE: UL 1741 SA certified equipment is required for interconnection/ during Commissioning - listing TBD. \*IC must ensure that the max. output power of the proposed system is limited to 1250kW AC PV - as proposed (1000kW AC PV + 0kWh DC coupled + 250kW AC coupled Battery Storage System) \*The system design capacity of the proposed system MUST not exceed nameplate rating as proposed. \*Note: "The Company reserves the right to disconnect the Facility if the output exceeds the nameplate rating".

B. Point of Common Coupling (PCC)

The point of common coupling (PCC) for this interconnection application will be the

Point where the customer-owned primary conductors connect to the company-owned conductors on the 'load' side of the primary metering. This interconnection project will be capable of exporting power beyond the PCC onto the Company's Electric Power System (EPS)

#### C. Corrections to Proposed Design

The proposed design documentation does not require corrections before the next step in the process. Refer to the attached Customer Documentation Checklist for comments on the proposed design documentation. Further design changes may be identified during the study (if applicable).

#### IV. Requirements:

#### A. General Requirements

- 1. In addition to any specific requirements identified herein, the Interconnecting Customer is required to comply with all applicable requirements described in the Interconnection Tariff & National Grid's Electric Service Bulletin 750 Series.
- 2. The Customer shall provide documentation from the inverter manufacturer for the islanding detection method to be used by the inverter(s). The documentation shall be sufficient to determine whether the islanding detection method is active (perturbing the utility system and looking for a response), or passive (monitoring grid parameters without perturbing the system), and describe how the islanding detection method functions, including what parameters (i.e. phase, frequency, VARs,) are perturbed and monitored.
- The Company recommends installing surge arrestors on the Customer side of the Point of Common Coupling for the protection of Customer-owned equipment during possible overvoltage conditions.
- 4. The information provided herein is a non-binding report of existing National Grid electrical facilities in the area of your proposed project. This report shall not be used to infer the ability to interconnect any project to any of the existing National Grid facilities. That determination can only be made following National Grid completing the applicable review process as outlined in the Tariff.

# **Screening Memo**

\*Report is a sample and for illustrative purposes only\*

Screening Memo Prepared by: Jorge Jorge Revision Number: 0.0 Preparation Date: 10/17/2022





# Standard/Complex

Jess Kosinski

# **Interconnection Process Steps**

- Pre-Application
- Application
  - Standard
- Engineering Review
  - Distribution System Impact Study/Detailed Study/Group Study
    - ASO Study by Affected System Operator (If Applicable)
- Interconnection Service Agreement (includes interconnection terms and conditions, including System Modifications and associated costs)
- Design
- Pre-Construction Requirements
- National Grid Construction
- Witness Test and Completion Documents/Photos
- Meter Installation
- Register Assets
- Authorization to Interconnect

https://ngus.force.com/s/article/MA-Complex-Standard-Application-Process

#### National Grid | April Standard Interconnection Webinar | April 17, 2025



## Standard Review Path for Independent Application (non Group Study)

	Standard
Eligible Facilities	Any DG
Acknowledge Receipt of Application	3 business days
Review Application for Completeness	10 business days
Complete Standard Process Initial Review	20 business days
Send Impact Study Agreement / Invoice	5 business days
Study Agreement Execution and Payment	15 business days
Complete Impact Study	55 – 60 business days, or by mutual agreement depending on complexity
Complete Detailed Study (if needed)	30-60 business days, or by mutual agreement depending on complexity
Send Executable Agreement (ISA)	15 business days
Total Maximum Days	<ul><li>135 business days, 160 business days (if began as Expedited),</li><li>200 business days or more (if Standard Complex)</li></ul>
Construction Schedule	Varied
Witness Test	10 business days from the National Grid's approval of test procedures or by mutual agreement

# **Group Study Timeline**

Timing*	Step Description
up to 40BD	Group Window
20BD	Scoping Meeting
10BD	Group members notify the Company as to whether they wish to proceed; non- response=withdrawal
2BD	Company provides notice to remaining Group members for opt-in to Extended Group Study
5BD	Group to provide Extended Group Study Consent Form with unanimous consent; non-response=no Extended Group Study
15BD	Company issues Group Study Agreements
15BD	Group members to each execute Group Study agreement and submit payment of fees. Group Study will not commence until full payment received from all members
100BD	<b>100BD:</b> Group study timeframe if the area contains equal to or less than 3 applications with an aggregate Nameplate Capacity of equal to or less than 10 MW and estimated aggregate System Modifications less than \$1.5M. Study timeframe may be longer if the Group elects the Extended Group Study.
OR	<b>125BD:</b> Group study timeframe if the area contains equal to or less than 5 applications with an
125BD	aggregate Nameplate Capacity of equal to or less than 25 MW and estimated aggregate System Modifications less than \$1.5M. Study timeframe may be longer if the Group elects the
OR	Extended Group Study.
160BD	<b>160BD:</b> Group Study timeframe if the area contains over 5 applications, over 25 MW of cumulative Nameplate Capacity, or any Group Study with estimated aggregate System Modifications \$1.5M or more. Study timeframe may be longer if the Group elects the Extended Group Study.

\*Denotes time after previous step completed, and is exclusive of any holds or ASO study requirements

# **Timeline Cont..**

Timing	Step Description					
~ 40-60BD**	Preliminary Assessment: high level Impact and associated thresholds					
***	Group study potential hold pending developer decision and/or change submission					
ASO Stu	ASO Study Assessment – <b>Study Hold</b> – ISO-NE Determines if ASO Study Required					
Balance Distribu	tion Analysis – DSIS reports delivered inclusive of document revisions required to proceed to ISA					
15BD	Customers to identify intent to proceed to ISA and address document deficiencies					
15BD – 35BD****	ISA draft/delivery					
20BD	Customers to sign and return ISA					
Ti	Timelines follow those in the Interconnection Tariff M.D.P.U. 1468					

\*\* Not a tariff requirement. This is approximate timing of when Company expects to identify high level impacts and associated thresholds. This milestone could vary based on study duration.

\*\*\* Please refer to change process in the Group study provisions, without limitation Tariff Section 3.4.1.j).

\*\*\*\* In accordance with Group Study timeframes in Tariff Section 3.4.1.i).

# Group Study Summary

Group Study Language: Link to DPU File Room

- Each Group member is encouraged to review the Group Study provisions (Tariff Section 3.4.1.) to understand the full scope of the process and requirements for the Group Study process.
- National Grid will provide visibility and communication in accordance with the Tariff
- Group members are responsible to understand individual responsibilities and process tasks that require Group consensus



April Standard Interconnection Webinar | April 17, 2025

# Group Study References

- Group Study Website Link was updated: https://gridforce.my.site.com/s/article/MA-Distribution-Group-Study-Documents
- Monthly Group Study Status Report can be found on our <u>MA Distribution Group</u> <u>Study Documents</u> website
  - The purpose of this report is to provide status updates for each on-going Group Study, inclusive of ASO Study statuses and more visibility of expected timelines for certain milestones.
  - You can also find Group Study Forms, past meetings, resources, links, and CIP schedules within the Group Study Website
- A Group Study Status Map can be found here: https://systemdataportal.nationalgrid.com/MA/



# **ESS** Timelines

- The Screening Memo will indicate that a distribution system Impact Study (DSIS) is required. If the ESS will be charging from the grid, the customers will be asked in the Screening Memo if they want to be studied in scheduled AND unscheduled operating modes under a mutually agreed upon timeframe of 95BD. If the study is to be performed based on a single mode of operation then the study will follow the typical 55BD tariff path
- For projects reviewed under the 95BD timeframe, a preliminary assessment will be provided around the 35BD
  - The preliminary assessment will provide information regarding available system capacity and estimated distribution System Modifications that are required under multiple operating scenarios for ESS projects
- Following the delivery of the preliminary assessment the project will be placed on a 10BD hold awaiting a response on how the customer wishes to proceed
  - Any design updates submitted by the customer beyond those necessary to reflect alignment with the decided path forward will be subject to the National Grid's policy on significant and moderate changes
  - Any design updates submitted beyond the 10BD time frame will be subject to National Grid's policy on significant and moderate changes
  - If no response is received, the project will progress as unscheduled at full nameplate
  - If document revisions are required, they will be requested at this point in the process as well
- DSIS proceeds in accordance with normal planning processes and engineering analyses, based on confirmed or updated operating methodology provided by the customer in the above step

National Grid | April Standard Interconnection Webinar | April 17, 2025

Common Errors at Study/ISA Stage		
1	Legal Information Document needs to be completely filled out with all required information	
2	The One Line diagram is required to have an electrical engineer PE Stamp	
3	If a project includes ESS, ensure application reflects this equipment	
4	Make sure storage charging/discharging capability is noted on the One Line	
5	When case status is "Conditional Approval - Delivered - Pending Customer Decision", don't hit the "finalize submission" button unless you have uploaded the signed ISA.	

Common Errors in Completion Documents		
1	<ul> <li>Commissioning Test should consist of at least the following:</li> <li>Two (2) second shutdown when disconnect open test.</li> <li>Five (5) minutes before restart when disconnect is closed test.</li> <li>Confirm system matches As-built (include most recent revision date of as built provided).</li> <li>List the inverter relay frequency</li> <li>There are separate commissioning memos for SA vs SB rated inverters</li> </ul>	
2	<ul> <li>Pictures:</li> <li>Meter picture should show permanent plaque (visible at eye level) that includes a warning about generator installed.</li> <li>If the AC utility disconnect switch is not grouped with and adjacent to the utility revenue meter, then a permanent plaque (visible at eye level) that clearly identifies the location of the AC utility disconnect is required.</li> </ul>	
3	<ul> <li>Qualifying Facility Documents:</li> <li>Schedule A (P-Rate) required for all QF projects.</li> <li>W9 (Only for projects &gt;60kW)</li> <li>ACH (Only for projects &gt;60kW)</li> <li>Supplier Enrollment Form (Only for projects &gt;60kW)</li> <li>Asset Registration (Only for projects &gt;60kW)</li> </ul>	
4	<ul><li>As Built:</li><li>Must be PE stamped (Electrical) and signed/ dated by person that performed the commissioning test.</li></ul>	
5	<ul> <li>Evidence of Insurance:</li> <li>This is required for Expedited and Standard projects except for eligible Class I Net Metering facilities (see Tariff 11.1 (a) (iv) and (b)). Refer to the ISA and Tariff for insurance requirements</li> </ul>	

# **Standard Review Path Reminders**

- DSIS, Detailed Study (if required), and Group Study (if required) will determine the electrical impact on the National Grid's distribution electric power system (EPS) with the required system modifications and associated cost.
- All projects greater than 1 MW will require ISO-NE I.3.9 Submission for ISO-NE approval regardless of whether an ASO Study is required. This submission will take place within the DSIS. Once submitted, the DSIS will be placed on an ASO hold until the ISO-NE provides approval and/or the ASO study (if required) is complete.
- If substation modifications are required, National Grid has 60BD for study. If estimated construction cost are greater than \$1M, study timeline could be by mutual agreement. Notified at 20BD review.
- ISA will have the estimated construction timeline and is provided after study is complete. If Detailed Study is required, the customer may request an early ISA, which will not have a construction timeline.
- Under the Tariff, 1st ISA payment (sometimes referred to as CIAC) is due within 60BD and CIACs do not have a cure period. Failure to make timely payments will result in application withdrawal.
- Design begins after 1<sup>st</sup> CIAC payment.
- Easements, permitting, Right of Way (R.O.W.), etc. begin after design and are required to move into construction.

# **Metering Reminder**

- No equipment (adapters) between the meter and the socket or in a meter socket
- Meter sockets are not allowed to be used as junction boxes
- Projects greater than 60 kW in MA require interval metering (wireless or phone line)
- Make sure test meter is removed from generation meter socket
- A 4G wireless signal test on a Verizon network is required in order to provide wireless metering
- Phone lines must be dedicated and terminated at the meter location. Line must be 100% copper. Fiber lines will not communicate properly.
- These meters are long lead time items and prep time can be 10-12 weeks, so it is important to work through this with your job owner well in advance of when you intend to seek Authority to Interconnect.
- Wireless test form: <u>https://ngus.force.com/s/article/MA-Interconnection-Documents</u>

National Grid | April Standard Interconnection Webinar | April 17, 2025

# **Witness Test & Completion Document Reminders**

- Most recent checklists on nCAP: <u>https://ngus.force.com/s/article/MA-Interconnection-Documents</u>
- Documents can be approved in advance, but all must be provided before review can begin.
- For any specific questions, please reach out to your account manager.
- Witness Test Checklist
  - Include pictures of nameplates.
  - All checklist requirements must be approved and both National Grid and customer construction (including municipal approval) must be completed prior to scheduling a Witness Test.
- Compliance Document Checklist
  - Asset registration is required as part of compliance documents.
  - National Grid applies for asset registration on behalf of the customer; typically takes 5-10 BD.
  - All incentive projects (e.g., Qualifying Facility / Net Metering) >60kW require asset registration with ISO <u>before</u> ATI is granted because we cannot backdate payments.
  - Behind-the-meter Class II/III Net Metering and Demand Response systems are exempt from being registered as a Settlement Only Generator with ISO.
  - If AC ESS Standalone system is generating power to the EPS, it needs to be registered separately with ISO.

# **Document Revision & Restudy Reminders**

- A Change Request form will need to be completed and submitted in addition to any documents supporting the change (one lines, site plan, etc.). Form can be found on the Interconnections Documents website <u>https://gridforce.my.site.com/s/article/MA-Interconnection-Documents</u>
- Whenever new one lines or site plans are submitted, all changes (including text changes) should be clouded, and the revision block (including the rev # and dates) should be updated
- One lines and site plans need to have the PE stamp, as per ESB 756.
- If making changes after study has been finalized, the customer needs to inform National Grid of changes via Change Request button on the portal & provide revised documents to determine if restudy would be necessary. Restudy will have associated study costs and timelines.
- Restudies can cause impacts to project costs & timelines, even if the scope of work doesn't change. Please refer to the moderate/significant change guidance prior to submitting your change. <u>https://ngus.force.com/servlet/servlet.FileDownload?file=0156T00000FLhJr</u>
- If an ISA has already been executed, National Grid's design/construction process may be put on hold (as determined by the Company) for the duration of the restudy and until an ISA amendment has been fully executed. Re-evaluation of the construction schedule may be necessary and will be determined during the restudy.



## **Important Target Dates for**

## Interconnecting Customer Requesting EOY Interconnection

By October 1st	Submit the following documentation:
	<ul> <li>Witness Testing Documents - (including but not limited to) proposed Witness Procedure, Energization Plan, all other applicable witness test documentation as outlined in the Witness Test Checklist that can be found here: https://gridforce.my.site.com/s/article/MA-Interconnection-Documents</li> </ul>
	Witness Test Checklist updated as of 08/12/2024
	Wireless Meter Test form OR Meter Phone Number (as applicable)
By November 15th	1. Complete distributed generation facility construction
	2. Submit all outstanding documentation
	All Completion Documentation must be submitted prior to National Grid for review

Meeting these target dates does not guarantee EOY interconnection for your facility, however it does give National Grid a better opportunity to meet your request. These target dates have been established based on the Company's experience with delays to EOY processing including:

- Necessary engineering review of initial plans and documentation as well as multiple subsequent reviews and communications with Interconnecting Customer as necessary to achieve the Interconnecting Customer's compliance with the requirements
- Queueing and resource allocation for both witness testing scheduling and meter installations
- Fewer processing days due to state holidays and weather conditions (when they result in force majeure)

• Required registration with the ISO-NE that must be processed prior to ATI and Interconnecting Customer delay in starting the registration process in a timely manner.

The Interconnecting Customer's planning and cooperation is essential to this process. Please keep in mind that Authorization to Interconnect will not be issued until the Interconnecting Customer has satisfied all interconnection requirements (including, without limitation, the wiring inspection, all Compliance Documentation, the Witness Test, and ISO-NE Registration) and the required meter is installed.

Additional information and resources to assist you in this process can be found at <u>https://ngus.force.com/s/article/Submitting-</u> <u>Witness-Test-Documents</u>. If you have any questions, please contact the CEI job owner assigned to your project. 05

# Fulfillment of ISO-NE's I.3.9 Requirements (Includes ASO Study Process)

Jess Kosinski
### **Overview**

### **PSCAD / PSSE Model Requirement:**

To assist the Company in complying with ISO-NE modeling requirements; PSCAD models and model review payment are required for all systems over 1 MW, and PSSE models and model review payment are required for all systems 5 MW and above, regardless of ASO Study requirements.

### **ISO-NE I.3.9 Approval Requirement:**

All proposed projects > 1MW are required to receive ISO-NE I.3.9 approval of either a Generator Notification Form (GNF), or a Proposed Plan Application (PPA). An ASO Study may be needed prior to meeting this requirement.

# **Process for Providing Approved PSCAD/PSSE Models**

### **1. Initial Model Request:**

- Model and Model Review Fee will be formally requested from the Customer when their Interconnection Application's screening is complete. Customers will be invoiced in full for the model review. Models will not be reviewed until payment has been received.
  - Costs cover 3 attempts for each discrete model submission. Fundamental design or equipment changes, including inverter changes, would be considered a new model, and thus charged accordingly. If there are still model deficiencies identified after the third review, the Customer will need to submit additional payment for further model review.

### 2. Initial Model & Payment Submission:

 Required Models and Model Review Payment are *expected* to be initially submitted within 30 BD of the initial request. It is very unlikely a model will be considered working/approved after an initial submission, so submitting the required models and payment as soon as possible will ensure there is enough time for multiple rounds of revised model submissions and additional engineering reviews before the Model Approval Due Date.

### 3. Model Approval Due Date:

- The Model Approval due date will be determined upon the start of the Impact Study or Group Study. *Please note this is the date the model must be approved, not submitted for the first time.* The Model Approval due date also aligns with when the individual project or Group Study is expected to go on hold for ASO Determination because ASO Determination cannot be made without the required approved models.
  - Failure to provide an approved model by the Model Approval Due Date will result in the project being subject to withdrawal from the interconnection queue and must reapply if they wish to proceed.

# **Process for Receiving ISO-NE I.3.9 Approval**

- All proposed projects > 1MW are required to receive ISO-NE I.3.9 approval of either a Generator Notification Form (GNF), or a Proposed Plan Application (PPA).
- Prior to receiving that approval, ISO-NE must determine if any proposed project that is greater than 1 MW, but less than 5 MW requires an ASO Study. All projects 5 MW or greater automatically require a Comprehensive ASO Study.
- In the event an ASO Study is required, the ASO Study must complete prior to receiving ISO-NE I.3.9 approval. ISO-NE ASO Study Determinations are made on a monthly basis.

### When to Request ISO-NE's ASO Study Determination

In order to receive ISO-NE's ASO Study Determination, a project or Group Study must have confirmed transmission injection points, and all required models must be approved. A project's DSIS will be placed on hold for ASO purposes when transmission injection points are identified via engineering.

Study Type	Targeted ASO Study Determination Timeline (& Targeted Model Approval Due Date)
100 BD Group Study	65 BD
125 BD Group Study	80 BD
160 BD Group Study	105 BD
55 BD Individual System Impact Study	35 BD

Customers with models outstanding or models that are not fully approved by the date transmission injection points are identified will be subject to withdrawal from the interconnection queue and must reapply if they wish to proceed.

Once ISO-NE's ASO Study Determination has been made for a project, the Customer will be notified via the Company of that determination and next steps.

### ISO-NE Determines an ASO Study is <u>NOT</u> Required

If ISO-NE determines that no ASO Study is required, the project will be presented, as a Generator Notification Form (GNF), at the next monthly NEPOOL RC meeting for I.3.9 approval. About 1-3 weeks following the meeting, a formal ISO-NE i.3.9 approval letter is received by the Company.

If the project is not part of a Distribution Group Study, the DSIS can resume once the ISO-NE I.3.9 approval letter has been received by the Company.

If the project is part of a Distribution Group Study, the Distribution Group Study will remain on hold until the Company has received a formal ISO-NE I.3.9 approval letter for ALL >1MW applications in the Group Study.



### ISO-NE Determines an ASO Study *is* Required

If ISO-NE determines a project requires an ASO Study, then an ASO Study will be required prior to the project receiving ISO-NE I.3.9 Approval. The Customer will be informed of this determination and next steps.

Remember; projects that are 5 MW or greater *automatically* require a Comprehensive ASO Study.

### Pre-ASO Study Commencement

Prior to an ASO Study being able to commence, all other ongoing ASO Studies and/or FERC Studies within the same electrical area must be complete. Once there are no ongoing ASO Studies or FERC Studies taking place within the same electrical area, ASO Study commencement preparation can begin. These pre-commencement steps typically take about 30-60 BD. This includes:

- 1. Finalizing ASO Group (if more than one >1MW project within the same electrical area)
- 2. Finalizing Scope with ISO-NE
- 3. Finalizing ASO study costs
- 4. ASO Study Invoicing (15 BD to make payment from invoicing date)

Once all ASO Study payments have been received, then the ASO Study can officially commence.

### **ASO Study In-Progress**

- Once the ASO Study has officially commenced; expected completion timelines are based on the level of ASO Study being performed.
  - Non-Comprehensive ASO Study: 1-4 months to complete
  - Limited Comprehensive ASO Study: 4-6 months to complete
  - Full Comprehensive ASO Study (level III): 6-12 months to complete
- Comprehensive ASO Study updates are published monthly on the <u>MA ASO Updates</u> knowledge page, via the <u>1.E.9 Stakeholder Monthly ASO Update</u> report.

### 1.E.9 Stakeholder Monthly ASO Update

- 1.E.9 Stakeholder Monthly ASO Update 04/01/2025
- 1.E.9 Stakeholder Monthly ASO Update 03/03/2025
- 1.E.9 Stakeholder Monthly ASO Update 02/03/2025
- 1.E.9 Stakeholder Monthly ASO Update 01/02/2025

### **Completion of an ASO Study**

Upon ASO Study completion, projects included will be presented, as a Proposed Plan Application (PPA) *(for Comprehensive ASO Studies)* or GNF *(for Non-Comprehensive ASO Studies)*, at the next monthly NEPOOL RC meeting for I.3.9 approval. About 1-3 weeks following the meeting, a formal ISO-NE I.3.9 approval letter is received by the Company.

If the project is not part of a Distribution Group Study, the DSIS can resume once the ISO-NE I.3.9 approval letter has been received by the Company.

If the project is part of a Distribution Group Study, the Distribution Group Study will remain on hold until the Company has received a formal ISO-NE I.3.9 approval letter for ALL >1MW applications in the Group Study.



# Project Changes after ISO-NE I.3.9 Approval Letter is Received

# Certain project changes made after an ISO-NE I.3.9 Approval Letter has been received would trigger the following:

Project Change (not limited to)	Trigger
Inverter Changes	New PSCAD / PSSE Model (including review costs)
PV / CHP / BESS (including kWh) Size Increases	Revised ISO-NE ASO Study Determination &
	Revised GNF or PPA Submission
PV / CHP / BESS (including kWh) Size Decreases	Revised GNF or PPA Submission
Addition or Removal of a DC or AC Coupled BESS	Revised ISO-NE ASO Study Determination (only if increasing total max export) &
	Revised GNF or PPA Submission
Site Address Change	Revised GNF or PPA Submission
Transmission Injection Point Change	Revised ISO-NE ASO Study Determination &
	Revised GNF or PPA Submission
Withdrawal	Withdrawal of GNF or PPA

# **ASO References, Reports, Resources**

### MA ASO Updates Page

- I.E.4 Stakeholder Bi-Monthly Report
- I.E.6/E.7 Notices of Potential ASO Study and Bi-Weekly Update
- I.E.9 Stakeholder Monthly ASO Update

### MA Interconnection Documents Page

- Model Review Requirements & ASO Initiation Timeline
- Guidelines: PSCAD and PSSE Models
- ASO Impact Screen

### MA Distribution Group Study Documents Page

Monthly Group Study Status Report (includes ASO information)

### National Grid – MA System Data Portal

• Group Study Map (includes ASO information)

### MA Standard DG Process Steps

 Pre-ISA Process Map: Flow of a 55BD or 95BD DSIS to ISA delivery and initial payment of system modifications (includes ISO-NE's I.3.9 requirements for >1MW applicants, which may include an ASO Study) 06

Post Connection & Incentive Program Support

**Alex Bellavia** 

nationalgrid

# **Connected Customer Requests**

### Who can submit Connected Customer request?

Any party that is a stakeholder (such as billing customer or system owner) can submit a connected customer request. Please note that information or changes to the system will not be honored without proper authorization from the billing customer and/or system owner.

### What type of requests should be submitted?

#### **DG Billing Inquiries**

- Why haven't I received my bill?
- Why am I getting multiple bills?
- I don't see my incentive credits

#### **Credit Allocation Inquiries**

- How do I change my allocations?
- I don't know my meter number?
- Why haven't the transfers gone out?
- Can I get a transfer history?

#### **Transfer of Ownership**

• Follow the steps outlined in the knowledge page

#### **Power Quality / High Voltage**

- We are seeing constant spikes in our data
- Our generation is not matching your generation
- Our project is tripping off-line several times a week

#### **Credit Allocation Change Requests**

#### **Other Post Interconnection Inquiry**

- I need to update my mailing address
- I would like to add this to my billing portal
- I would like to expand my system what are the steps?

#### System Terminated / Decommissioned

# How to submit a DG Inquiry

# Go to: https://gridforce.my.site.com/s



### **Customer Application Portal (nCAP)**



\*\* To find proposed and connected distributed generation on a specific feeder, put the district and feeder number in the search bar, select the feeder, click on the "related" tab and select view all in feeder list for a feeder-specific report.

CASES INFRASTRUCTURE

# Where to find allocation change forms

# Go to: https://gridforce.my.site.com/s



# **Customer Application Portal (nCAP)**



# Where to find allocation change forms (pt 2)

#### ♠ APPLICATIONS HELP

### **Distributed Generation Post Interconnection**

For additional guidance on navigation, registration and more, please visit our Help Page or Submit Inquiry/ Contact Us





APPLICATIONS HELP

#### **Distributed Generation Post Interconnection**

For additional guidance on navigation, registration and more, please visit our Help Page or Submit Inquiry/ Contact Us

How to Submit a Post Interconnection Inquiry/Request



#### How to Submit a Post Interconnection Inquiry/Request

Guidance on how to submit a distributed generation post interconnection inquiry or request through the Post Interconnection Inquiry form

#### **Massachusetts DG Billing Inquiry**

Knowledge and helpful links for all distributed generation billing inquiries, including meter readings, data analysis, and first bill walk throughs. Billing inquiries will assist in understanding and answering any issue you may have with your distributed generation bill.

#### **Massachusetts Transfer of Ownership**

Knowledge of how to submit a transfer of ownership for a distributed generation project. Transfer of ownership payment information should be submitted through this request. Required documentation for specific incentive programs, types of projects, and definitions of roles are explained to provide additional guidance.

#### Massachusetts Credit Allocation Change Request or Inquiry

Knowledge and helpful links on credit allocation change requests, including access and guidance on which documents need to be submitted based on the project's incentive program.

#### **Massachusetts Other Post Interconnection Inquiry**

If your inquiry does not fall into the pre-defined topics, submit your inquiry using Other Post Interconnection Inquiry topic.

# **Credit Allocation Change Information**

- National Grid allows up to 6 credit allocation change requests per year, in addition to accepting "removal" and "swap" forms (where a single account number is removed or replaced, with no further changes to other allocation accounts or percentages on the form) as needed.
- Under both the SMART Provision (MDPU 1574) and Net Metering Provision (MDPU 1578), National Grid will carry forward any remaining credit balance on a customer account, except for Alternative On-bill Credit (AOBC) customers in SMART and Cap Exempt Facilities Serving On-site Load (CEFSOL) customers in Net Metering, who will have the option to cash-out excess balances each fiscal year. Carrying forward of credit balances applies to both host customers and recipients.
- If a recipient account closes before bill credits generated during a billing period are allocated to it, the allocated percentage will remain on the host customer's account.

# **Credit Allocation Change Forms**

### Net Metering – Complex and/or MA SMART + Net Metering

Please submit the <u>Schedule Z</u> form and the <u>Schedule Z Excel</u> \*Please fill in only blanks on Excel document, do not alter the excel sheet in any way.

Net Metering – Account Removals/Swaps (no change to % of credit allocations) Please submit the <u>Account Removal</u> form Please submit the <u>Swap</u> form

If you are closing your account and would like National Grid to apply your balance of bill credits to another account, you may use a One-Time Transfer form. Request must be from the customer (host or recipient) closing account.

- To transfer to a single account please use the One Time Transfer Form
- To transfer to multiple accounts please use the <u>One Time Transfer Form for Multiple</u> <u>Accounts</u>

\*\* Credits can only be transferred within the originating accounts load zone.

\*\*\*Accumulated credits on a satellite account are only allowed to be transferred when the satellite account is in a final status.

\*\*\*\*National Grid is otherwise not permitting OTTs for Net Metering customers

### MA SMART – ALTERNATIVE ON-BILL CREDIT

Please submit the <u>AOBC</u> (Alternative On-bill Credit) form

# **Portal Post-connection & Regulatory Resource Hubs**

### https://gridforce.my.site.com/s/article/MA-BUSINESS-Net-Metering

https://gridforce.my.site.com/s/article/SMART-Solar-Massachusetts-Renewable-Target-Program#Documents

https://gridforce.my.site.com/s/article/Massachusetts-Incentive-Document

# **Important Reminders for Interconnected Customers**

Outage notifications for DG Facilities require updated emergency contact information. Please be sure to notify National Grid **if** or **as** your emergency contact information changes!



### My Business Account is available for commercial customer billing. Access My Business Account <u>here</u>

Our <u>Solar hub</u> is now live - read about everything solar and view sample bills per project type

# **Physical Changes to Connected Projects**

- Customers seeking to make changes to Connected Projects should submit a DG Inquiry Case via the <u>Contact Us</u> button in the Portal.
- The Case will be reviewed and routed to an Account Manager who will guide you through what is needed based on the changes or upgrades you are requesting.
- Management of the ask will take place in the Portal either on the original Case or a new one that will be created by the Account Manager.
- Only non-Significant Changes can be handled this way. Significant changes will require a new Application.
  - Example of a non-Significant Change: inverter updates/replacements at the end of their warranty period or natural life cycle
  - Example of a Significant Change: Adding batteries to a connected solar project
  - If unsure if the change is Significant, submit the DG Inquiry Case and NG will advise
- Age of projects and nature of the ask will drive cost and timeline
  - A study or review from engineering may be required
  - A Witness Test may need to be performed

Do not make changes to Connected Projects without informing National Grid. Alterations that invalidate the ISA may force a project to be disconnected until corrections are made.

07

# **Portal Moment**

Kara Nail

nationalgrid

# **Portal Registration**

### https://gridforce.my.site.com/s/homepage

To start the registration process, click the Login button

national <b>grid</b>	Distributed Generation Switch to Electric Connections Switch to Electric Vehicle		
	Search	SEARCH	LOGIN
	HELP		

# **Customer Application Portal (nCAP)**

### **Portal Registration**



### **Portal Registration – New Company**

* New Company/Existing Company		
New Company		* *
* Company Name	* Phone	
* Company Email	* Contact Email	
you@example.com	you@example.com	
* Operating Region	Mailing Address	
LI	* Street	
MA		
NYC		li li
RI	*City	
UNY	·	
Billing Address	* State/Province	
* Street		
	* Zip/Postal Code	
	4	
* C'L.	* Country	

# **Portal Registration – Existing Company**

APPLICATIONS HELP	APPLICATIONS HELP
* New Company/Existing Company Existing Company Existing Company Enter company owner email Cancel I'm not a robot	First Name

### **Company Admin Responsibilities**

# **Customer Application Portal (nCAP)**



# **Invite a new Portal user**

# To add a user, click the upper right-side button "Create New Contact"

User Profil	le Manageme	nt			← Back + Create New Contact
Last Name	First Name	Email	Username	Active	
Doe	Jon	jond@email.com	ng_jond@email.com		Activate
Doe	Jane	janed@email.com	ng_janed@email.com		Activate
East	Sarah	sarahe@email.com	ng_sarahe@email.com	~	Remove User
Rowe	Jake	jaker@emailcom	cap_jaker@email.com	$\checkmark$	Remove User

### **Invite a new Portal user**

A new screen will pop up, allowing user to place the information of the new user in the appropriate places:

Once that has been completed, click "Create".

The invitee will receive an invite to complete the Portal registration.

	Username	Active
mail.com		
	Create New Contact	<b>C</b>
	First Name *	× R
		R
	Last Name *	R
	Email *	V R
	Confirm Email *	
	Cancel	

# **Portal Registration – Existing Company**

New users with an Existing Company can also register without having an invite.

♠ APPLICATIONS HELP
* New Company/Existing Company Existing Company Existing Company Enter company owner email Cancel
l'm not a robot

# **Portal Registration – Existing Company**

APPLICATIONS HELP	
First Name	
Last Name	
Company Name	
* Email	
you@example.com	
* Password	
* Confirm Password	
Cancel	
	Register

# **Approve a new Portal user**

# When a new Portal user registers without an invite, the Company Admin will need to click the Approve button.

User Profil	le Manageme	ent			← Back + Create New Contact
Last Name	First Name	Email	Username	Active	
Doe	Jon	jond@email.com	ng_jond@email.com	~	Remove User
Doe	Jane	janed@email.com	ng_janed@email.com	~	Remove User Approve
East	Sarah	sarahe@email.com	ng_sarahe@email.com	~	Remove User
Rowe	Jake	jaker@emailcom	cap_jaker@email.com	1	Remove User

### **Remove a Portal user**

### To remove/deactivate a user, locate that user on the User Profile Management Page and click "Remove User"

User Profil	e Manageme	nt			← Back + Create New Contact
Last Name	First Name	Email	Username	Active	
Doe	Jon	jond@email.com	ng_jond@email.com	Remove User	
Doe	Jane	janed@email.com	ng_janed@email.com	Remove User	Approve
East	Sarah	sarahe@email.com	ng_sarahe@email.com	Remove User	
Rowe	Jake	jaker@emailcom	cap_jaker@email.com	Remove User	

### Activate a new Portal user

### To reactivate a user, locate that user on the User Profile Management Page and click "Activate"

User Profil	e Manageme	ent				← Back	+ Create New Contact
Last Name	First Name	Email	Username	Active			
Doe	Jon	jond@email.com	ng_jond@email.com	~	Remove User		
Doe	Jane	janed@email.com	ng_janed@email.com	~	Remove User	Approve	
East	Sarah	sarahe@email.com	ng_sarahe@email.com	~	Remove User		
Rowe	Jake	jaker@emailcom	cap_jaker@email.com	$\checkmark$			Activate

# Standard DG Process Steps: Click Here

#### Standard DG Process Steps

This knowledge page is to provide resources and guidance specifically for MA Standard DG applicants in the queue that have submitted an application and will follow the Independent Distribution System Impact Study (DSIS) path.

() Apr 10, 2025 DG Documentation

#### ARTICLE BODY

### MA Standard DG Process Steps

#### from Application to Interconnection

The process documents below will provide guidance on action items for each nCap Portal (Salesforce) case status from the point that a customer application is submitted up to when the project interconnects. *Please note:* If your project is following the <u>Distribution Group Study process path</u>, please refer to the MA Distribution Group Study Process Steps page (coming soon) for step by step documents and process map.

#### **Process Maps**

 Pre-ISA Process Map (PDF): Flow of a 55BD or 95BD DSIS to ISA delivery and initial payment of system modifications (includes ISO-NE's I.3.9 requirements for >1MW applicants, which may include an ASO Study)
Post-ISA Process Map (PDF): Flow of process steps from once Design is initiated to when the project interconnects (coming soon)

#### **Process Step Documents per Case Status**

1. Application - Draft / Submitted / In Review (Webpage): Customer Application submitted

2. Screening - Complete - Pending Customer Decision (PDF): NE Complex Customer Decision Form and initial PSCD/PSSE Model request for >1MW projects

3. Study - Draft [Includes Study - Submitted] (PDF): DSIS Agreement and Invoice [Includes Customer Signature and Payment]

4. Study - In Progress - Start Study (PDF): DSIS Commencement

5. Study - In Progress - Initial Review (PDF): Initial Review updates provided. (may include status 'Study - Hold - Study Hold' if document revisions are requested)

6. Study - Hold - ASO Hold: Only needed if max export of proposed system or proposed aggregate system is > 1 MW, because ISO-NE I.3.9 approval is required and an ASO Study may be required prior to receiving that approval. Once the ASO Hold is lifted, the application case status will be placed back into the status Study - In Progress - Initial Review, and the DSIS will resume.

7. Study - In Progress - QC and Review: Draft DSIS Under Internal Review (5 BD). No PDF needed since there is no Customer action items at this status.

8. Study - In Progress - Draft Ready (PDF): Draft DSIS Report Provided. (may include status 'Study - Hold -Study Hold' if document revisions are requested)

9. Study - Complete - Sent to Customer (PDF): Final DSIS Report Provided

#### **Other Potential Case Statuses:**

1. Study - Hold - Study Hold: For holds not related to the Initial Review / Preliminary Assessment, or when the Draft DSIS Report is provided.

2. Pending Withdraw: A project can be placed in this status for various reasons; such as customer noncompliance or customer initiated withdrawal.

3. Study - Restudy: When a project that has already completed it's initial Distribution System Impact Study, but is now undergoing a Re-Study due to project changes.

#### **Resource Links:**

- MA Interconnection Documents
- ASO Study Updates
- MA DG Stakeholder Meeting Information
- Massachusetts Typical System Modifications and Estimated Costs for DG Interconnection
- MA Distribution Group Studies

#### **National Grid**



# Flexible Connections Programs

**Arnaldo Arnal** 

nationalgrid

# **Flexible Connections - Introduction**

# Through a Flexible Connection, customers can interconnect quicker and reduce expensive system upgrades






## **Value Proposition for Flex Connect**

Benefits	Flex C. Customer	The Commonwealth	The Electric Power System
Faster Interconnection times			
Lower System upgrade Costs			
Increased Network utilization			
Increase overall grid visibility and control			
Facilitated renewable generation growth			
Improve Customer experience for developers			
Increase energy realization toward the Commonwealth's clean energy goals			

**Note:** Currently the queue for the Flex Connect Pilot is filled, we are planning to have a full offering by Q1 2026





## Please submit questions using the Q&A link provided in the Microsoft Teams meeting chat.

We will do our best to address your question during this time. Q&A's will also be formally documented and uploaded to our website.



## **Appendix: Summary of Resources, Documents & Links**

Distributed Generation Website: https://ngus.force.com/s/ma-home

Interconnection Process Resources: https://ngus.force.com/s/ma-process

MA Dist. Group Studies: https://gridforce.my.site.com/s/article/MA-Distribution-Group-Study-Documents

**ISO – NE's Interconnection Process**: <u>https://www.iso-ne.com/static-assets/documents/rules\_proceds/isone\_plan/pp05\_1/pp5\_1.pdf</u>

National Grid's list of active and pending FERC feeders: <u>https://ngus.force.com/s/?tabset-651ee=2&Infrastructure\_c-filterId=00B0W000006uAI3UAM</u>

MA DG Stakeholder Meeting Information: https://ngus.force.com/s/article/MA-DG-Stakeholder-Meeting-Information

ASO Updates: <u>https://ngus.force.com/s/article/MA-ASO-Updates</u>

Hosting Capacity Maps: https://systemdataportal.nationalgrid.com/MA/

**Storage Assistance -** <u>https://ngus.force.com/s/article/Storage-Assistance</u>

**DPU Interim Guidance for ESS -**

https://ngus.force.com/s/article/How-to-Add-Energy-Storage-to-an-In-Progress-Application-in-Massachusetts

## Sample One Line Diagrams SMART Program-

https://ngus.force.com/servlet/servlet.FileDownload?file=0150W00000ET8dj

Interconnection Documents- https://ngus.force.com/s/article/MA-Interconnection-Documents

Typical System Modifications and Estimated Costs for DG Interconnection- <u>https://ngus.force.com/s/article/System-Modifications-for-DG-Interconnection</u>

National Grid | April Standard Interconnection Webinar | April 17, 2025

nationalgrid