



## AYER DISTRICT COURT HVAC SYSTEM EVALUATION SUMMARY

Visited February 4, 2021. While on site, inspected the air handling units located in the mechanical rooms and toured the facility to determine if the spaces generally matched usage noted on the architectural plans. The Ayer District Courthouse was converted to a courthouse in 1970. According to staff, the building was a town school prior to being used as a courthouse. The building is approximately 32,000 square feet in size. Four air handling units (AHU) provide ventilation air to the building.

### 1.0 Airflow Rate per Person (Reduced Occupancy)

| <i>Courtroom</i> | <i>Total People</i> | <i>Total Air</i>            |                                  | <i>Outdoor Air</i>           |                                  |
|------------------|---------------------|-----------------------------|----------------------------------|------------------------------|----------------------------------|
|                  |                     | <i>Supply Airflow (CFM)</i> | <i>Airflow Rate (CFM/Person)</i> | <i>Outside Airflow (CFM)</i> | <i>Airflow Rate (CFM/Person)</i> |
| Jury Pool Room   | 6                   | 1,500                       | 250                              | 167                          | 28                               |
| Courtroom #1     | 22                  | 4,000                       | 182                              | 1,500                        | 68                               |
| Courtroom #2     | 14                  | 2,200                       | 157                              | 244                          | 17                               |

### 2.0 Recommendations

| <b>Section</b> | <b>Recommendation/Finding</b>  | <b>Action</b> |
|----------------|--|---------------|
| <b>2.1</b>     | <b>Filtration Efficiency</b>   |               |
| RF-1           | Replace filters with a MERV 13 filter  | Complete      |
| RF-3           | Install a differential pressure sensor (switch) across the filter banks            | In progress   |
| RF-3a          | Connect the pressure sensor to the BMS system and/or a local alarm                 | In progress   |
| <b>2.2</b>     | <b>Testing and Balancing</b>   |               |
| RTB-1          | Test and rebalance air handling unit supply air and minimum outside air flow rates | Complete      |
| RTB-4          | Test and balance air inlets and outlets  | Complete      |
| RTB-5          | Test and balance all air inlets and outlets  | Complete      |
| <b>2.3</b>     | <b>Equipment Maintenance and Upgrades</b>  |               |
| RE-1           | Test existing air handling system dampers and actuators for proper operation       | Complete      |
| RE-2           | Clean air handler coils and drain pans   | Complete      |
| RE-3           | Confirm the existing freeze stat is working correctly on each air handling unit    | In progress   |
| RE-4           | Test the existing air handler control valves and actuators for proper operation    | Complete      |
| <b>2.4</b>     | <b>Control System</b>  |               |
| RC-1           | Implement a pre-occupancy flush sequence   | In progress   |

**2.5 Additional Filtration and Air Cleaning**

---

|              |   |          |
|--------------|---|----------|
| <b>RFC-1</b> | Install portable HEPA filters -- <i>if courthouse is to operate at a high occupancy (i.e. 50% or greater), install portable HEPA filters in high traffic areas.</i> | Complete |
|--------------|---|----------|

---

**2.6 Humidity Control**

---

|  |   |          |
|--|---|----------|
|  | No actionable items listed – continuous monitoring for seasonal changes | On-going |
|--|---|----------|

---

**2.7 Other Recommendations**

---

|              |                                       |  |
|--------------|---------------------------------------|--|
| <b>2.7.1</b> | Add ventilation to all occupied areas | Deferred – included in 5 year Capital Plan |
|--------------|---------------------------------------|--|

---

|              |   |  |
|--------------|---|--|
| <b>2.7.2</b> | Upgrade controls and building management system (BMS) | Deferred – included in 5 year Capital Plan |
|--------------|---|--|

---

|              |                                   |          |
|--------------|-----------------------------------|----------|
| <b>2.7.3</b> | Inspect reheat coils and controls | Complete |
|--------------|-----------------------------------|----------|

---

|              |  |  |
|--------------|--|--|
| <b>2.7.4</b> | Replace air handling units and fan coils | Deferred – included in 5 year Capital Plan |
|--------------|--|--|

---



**Ayer District Court  
Ayer, MA**

**HVAC SYSTEM  
EVALUATIONS  
COVID-19**

Office of Court Management

June 22, 2021

# Section 1

## Existing Conditions & Site Observations

Tighe & Bond visited the Ayer District Courthouse on February 4, 2021. While on site we inspected the air handling equipment located in the mechanical rooms and toured the facility to determine if the spaces generally matched usages noted on the architectural plans.

### Site Visit Attendees:

- *Office of Court Management:*
  - Randen Davis, Courthouse Facilities Staff
  - Raymond Nardone, Courthouse Facilities Staff
  - Bob Caughlin, Courthouse Facilities Staff
  
- *Tighe & Bond*
  - Sean Pringle, PE, Mechanical Engineer
  - Tim Bill, Staff Mechanical Engineer

### **1.1 Existing Ventilation System**

The Ayer District Courthouse was converted to a courthouse in 1970. According to staff, the building was a town school prior to being used as a courthouse. The building is approximately 32,000 square feet in size. Four air handling units (AHU) provide ventilation air to the building. The AHU's appear to be from the 1970 renovation and are in poor condition. Note that we were not able to inspect the dampers and coils where they were located in the ductwork.

AC-2 and AC-3 contain 2" MERV 8 filters, a chilled water cooling coil, and a supply fan. A dedicated return fan operates in conjunction with each air handling unit. AC-2 also contains a hot water coil. AC-3 does not have a hot water coil within the unit. However, duct mounted reheat coils in the supply ductwork serve each zone in the building. Each unit has return, outdoor, and relief air dampers, operated by pneumatic actuators. The outdoor air and relief dampers for AC-2, which serves Courtroom 1, were fully closed at the time of the visit. AC-3 serves the second floor.

AC-1 is a 100 percent outdoor air unit. The unit contains an outdoor air damper, 2" MERV 8 filters, a hot water coil, chilled water coil, and a supply fan. AC-1 serves the interior areas in the first floor.

HV-4 is also a 100 percent outdoor air unit. The unit contains an outdoor air damper, 2" MERV 8 filters, a hot water coil, and a supply fan. There is also a cooling coil in the downstream ductwork. HV-4 serves the lockup areas in the basement. HV-4 supplies fresh air to the corridors surrounding the holding cells. Air is exhausted through registers located in each cell.

There are 16 fan coils units serving perimeter private and open offices on the first floor. The fan coils have hot/chilled water coils and MERV 8 filters. The units are in fair condition. There are no outdoor air openings for any of these units. As a result, while these areas receive the benefit of air filtration, there is no ventilation. These areas do have operable windows.

Similarly, there is no ventilation in the first floor lobby and corridors, outside the main courtroom. There are concealed fan coils that condition this space and provide filtration, but they do not provide outdoor air.

Much of the basement, aside from the lockup area, is unventilated. Most of the basement is comprised of a large open area that has been divided with office partitions for use as a community room, maintenance offices, and a break room.

At the time of the visit, all exhaust fans serving restrooms and holding areas were operating.

A 2.7 million BTU/h hot water boiler provides hot water to air handlers, unit ventilators, duct heating coils, and radiators. A split 70 ton air cooled chiller located in the mechanical room provides chilled water to all air handlers.

Table 1 summarizes the air handling units’ designed airflow rates, the MERV rating of the installed filters, and the condition.

**TABLE 1**  
Existing Air Handling Units

| <b>Unit</b> | <b>Original Design Airflow (CFM)</b> | <b>Original Design Min. O.A. (CFM)</b> | <b>Pre/Final Filters</b> | <b>Condition</b> |
|-------------|--------------------------------------|--|--------------------------|------------------|
| AC-1        | 1,210                                | 1,210                                  | 2" MERV 8                | Poor             |
| AC-2        | 4,000                                | 1,500                                  | MERV 6 Roll Filter       | Poor             |
| AC-3        | 13,510                               | 1,500                                  | MERV 6 Roll Filter       | Poor             |
| HV-4        | 960                                  | 960                                    | 2" MERV 8                | Poor             |



Photo 1 – Typical Air Handler

## **1.2 Existing Control System**

A pneumatic system controls most of the existing HVAC air handling equipment. It is an old, obsolete system and appears to be original. There is an extremely limited Schneider SmartStruxure building management system (BMS) that enables AC's 1-3 based on a schedule, monitors supply air and space temperatures, and controls the chiller, boiler, and pumps. There is no economizer control, control of outdoor air dampers, or control of supply air or reheat temperatures through the BMS.

According to staff, AC-3 has issues with freeze stat trips during cold weather, generally when it is below 20 °F outside. Because of this, the unit is set to turn on at 10:30 am each day during the winter and has to be reset several times a day.

## Section 2

# Recommendations

Below is a list of recommendations that we propose for the Ayer District Courthouse. Please refer to the "Master Recommendation List" for further explanation and requirements of the stated recommendations.

As noted in Section 1 above, several offices and the lobby on the first floor, and much of the basement is currently unventilated. Building areas without adequate ventilation and filtration significantly increase the risk of spreading viruses like COVID-19, especially areas with high occupant density and where people occupy the same space for relatively long periods of time. Consider significantly reducing occupancy or relocating occupants to other areas with adequate ventilation.

### 2.1 Filtration Efficiency Recommendations

We recommend the following measures be implemented for the existing air handling units:

**RF-1:** *Replace filters with MERV-13 filters.*

We recommend replacing the MERV 8 filters in AC-1 and HV-4 with MERV 13 filters.

Air handlers AC-2 and AC-3 contain roll filters and do not have traditional filter racks. To our knowledge, MERV 13 roll filters are not available. We recommend investigating if filter racks can be installed within the air handling units in place of the filter roll system. If this is not feasible, we recommend keeping the roll filters in place and installing MERV 13 filters in the supply air ductwork downstream of the unit.

The TAB Contractor and/or Engineer shall verify that the AHU's can accommodate MERV-13 filters per Appendix A in the overview of recommendations report.

**RF-3:** *Install a differential pressure sensor with a display across the filter bank.*

**RF-3a:** *Connect the pressure sensor to the BMS system and/or a local alarm.*

If there are no controllers with available I/O in the vicinity of the AHU's, provide a local alarm.

### 2.2 Testing & Balancing Recommendations

The air handling units are approximately 50 years old and it is unknown to Tighe & Bond when the last time the units were tested and balanced. Also, the code requirements to determine the outside air flow rates that were used to design the original system may be different than the 2015 International Mechanical Code (IMC) and current ASHRAE Standard 62.1 requirements.

We recommend the following testing and balancing measures be implemented:

**RTB-1:** *Test and balance air handling unit supply air and minimum outside air flow rates.*

We recommend testing and balancing the outdoor air flow rates for all air handling units to the recommended minimum O.A. rates listed in Table 2.

**TABLE 2**  
Recommended Air Handler O.A. Flow Rates

| <b>Unit</b> | <b>Original Supply Airflow (CFM)</b> | <b>Original Design Min. O.A. (CFM)</b> | <b>Current Code Min. O.A. Requirements (CFM)</b> | <b>Recommended Minimum O.A. (CFM)</b> |
|-------------|--------------------------------------|--|--|---------------------------------------|
| AC-1        | 1,210                                | 1,210                                  | 160  | 1,210                                 |
| AC-2        | 4,000                                | 1,500                                  | 770  | 1,500                                 |
| AC-3        | 13,510                               | 1,500                                  | 1,450  | 1,500                                 |
| HV-4        | 960                                  | 960                                    | 350  | 960                                   |

Note: Although the ASHRAE Position Document on Infectious Aerosols recommends using the latest published standards and codes as a baseline for minimum ventilation, the mechanical code in effect at the time the HVAC systems were designed and constructed is what governs the required outdoor air flowrate for the HVAC equipment, if there have been no additions, renovations, alterations or changes in occupancy to the building. The 2015 International Mechanical Code does not prevent the continued use of existing systems.

During the pandemic, we recommend maintaining the outdoor airflows at the original designed values as they exceed the code minimums calculated by Tighe & Bond. Supplying more outdoor than required by code will provide better indoor air quality.

The average airflow rate per person is shown below in Table 3. These values are based on the original full design supply airflow rate and the recommended outdoor airflow rates shown in Table 2. The airflow rate per person assumes a diversity factor of 70%, meaning the maximum number of occupants assumed to be in all zones at all times equates to 70% of the code required occupancy. Note that areas without ventilation are not included in the calculated averages.

**TABLE 3**  
Average Airflow Rate per Person

|                               | <b>All spaces</b> | <b>Courtrooms</b> | <b>Non-Courtroom Spaces</b> |
|-------------------------------|-------------------|-------------------|-----------------------------|
| Total Occupancy (People)      | 224               | 127               | 97                          |
| Total Supply Air (CFM/Person) | 88                | 50                | 140                         |
| Outdoor Air (CFM/Person)      | 23                | 14                | 35                          |

The airflow rate per person for each Courtroom and the Jury Pool Room is shown below in Table 4. These values are based on full occupancy without taking diversity into account, the original full design supply airflow rate, and the recommended outdoor airflow rate. The airflow rate per person assumes the full supply airflow is being delivered to the room.

**TABLE 4**  
Airflow Rate per Person (Full Occupancy)

|  | <b>Total Air</b> | <b>Outdoor Air</b> |
|--|------------------|--------------------|
| Ayer District Courthouse HVAC System Evaluation COVID-19 |                  | 2-2                |



| <b>Courtroom</b> | <b>Total People</b> | <b>Supply Airflow (CFM)</b> | <b>Airflow Rate (CFM/Person)</b> | <b>Outside Airflow (CFM)</b> | <b>Airflow Rate (CFM/Person)</b> |
|------------------|---------------------|-----------------------------|----------------------------------|------------------------------|----------------------------------|
| Jury Pool Room   | 30                  | 1,500                       | 50                               | 167                          | 6                                |
| Courtroom #1     | 105                 | 4,000                       | 38                               | 1,500                        | 14                               |
| Courtroom #2     | 77                  | 2,200                       | 29                               | 244                          | 3                                |

Note: Courtroom occupant density is based on 70 people/1,000 square feet, per the 2015 International Mechanical Code

The airflow rate per person for each Courtroom and the Jury Pool Room, based on a reduced occupancy schedule determined by the Office of Court Management, is shown below in Table 4a. The airflow rate per person assumes the full supply airflow is being delivered to the room.

**TABLE 4a**

Airflow Rate per Person (Reduced Occupancy)

| <b>Courtroom</b> | <b>Total People</b> | <b>Total Air</b>            |                                  | <b>Outdoor Air</b>           |                                  |
|------------------|---------------------|-----------------------------|----------------------------------|------------------------------|----------------------------------|
|                  |                     | <b>Supply Airflow (CFM)</b> | <b>Airflow Rate (CFM/Person)</b> | <b>Outside Airflow (CFM)</b> | <b>Airflow Rate (CFM/Person)</b> |
| Jury Pool Room   | 6                   | 1,500                       | 250                              | 167                          | 28                               |
| Courtroom #1     | 22                  | 4,000                       | 182                              | 1,500                        | 68                               |
| Courtroom #2     | 14                  | 2,200                       | 157                              | 244                          | 17                               |

Note: If occupancy is further reduced, the airflow rate per person will increase, assuming full airflow is being delivered to the space.

**RTB-4:** *Test and balance air inlets and outlets.*

If specific areas within the Courthouse experience regular cooling and heating comfort complaints this may be an indication of a lack of airflow to the space. We recommend testing and balancing the air inlets and outlets serving those spaces to the designed values. Prior to rebalancing the building, we recommend verifying the boiler and chilled water plants are maintaining the correct supply water temperature. Incorrect supply water temperature may be contributing to the temperature control complaints instead of a lack of airflow.

**RTB-5:** *Test and balance all air handler chilled and hot water coils.*

Testing and balancing the air handler hot and chilled water coils will help ensure the coils are receiving the proper water flow rates. Due to the age of the coils, the coils may not perform as required to properly temper the supply air. Coils become fouled over time, which degrades the performance.

## 2.3 Equipment Maintenance & Upgrades

We recommend the following equipment maintenance and upgrades:

**RE-1:** *Test existing air handling system dampers and actuators for proper operation.*

Replace dampers and actuators that are not functioning properly. As noted in Section 1, the outdoor and relief air dampers were closed on AC-2, indicating a possible pneumatic control issue.

**RE-2:** *Clean air handler coils and drain pans.*

**RE-3:** *Confirm the existing freeze stat is working correctly on each air handling unit.*

According to staff, AC-3 has had ongoing freeze stat issues. Confirm the Freeze stat is correctly adjusted and set to the correct temperature. Test the operation of all freeze stats.

**RE-4:** *Test the existing air handler control valves and actuators for proper operation.*

## **2.4 Control System Recommendations**

We recommend the following for the control system:

**RC-1:** *Implement a pre and post-occupancy flush sequence.*

While the existing BMS is limited, it does appear to have a scheduling function that would allow extended occupancy periods to be set.

## **2.5 Additional Filtration and Air Cleaning**

We recommend the installation of the following air cleaning devices:

**RFC-1:** *Install portable HEPA filters.*

If the Courthouse is to operate at a high capacity (i.e. 50% occupancy or greater), we recommend installing portable HEPA filters in high traffic areas, such as entrance lobbies. They should also be considered for Courtrooms, depending on the occupancy of the room and how much noise is generated from the filters. The noise levels will vary depending on the manufacturer.

## **2.6 Humidity Control**

Several AHU's originally contained humidifiers in the supply ductwork. According to staff, they have not been operational for some time. Before replacing these units, we recommend determining if humidification can safely be used in the building. The feasibility of using active humidification is determined by the building envelope. Buildings that were not designed to operate with active humidification can potentially be damaged due to a lack of a vapor barrier, adequate insulation, and air tightness.

Duct mounted humidifiers must be engineered, integrated into the building control system, tested, and commissioned. They are available in many configurations but require substantial maintenance and additional controls. They also run the risk of adversely affecting IAQ from growing microorganisms, or leaking water through poorly sealed ductwork damaging insulation and ceilings. Portable humidifiers are easier to install and require less maintenance, but still have the potential to damage the building envelope.

While active humidification is not recommended as a whole building solution due to high installation costs, operational costs, potential to damage the building envelope and adversely affect poor IAQ, it may be warranted as a temporary solution in some areas.

## **2.7 Other Recommendations**

### **2.7.1 Add Ventilation to All Occupied Areas**

Several occupied areas in the basement and the first floor do not have any mechanical ventilation. Consider adding mechanical ventilation to serve these areas. Consider the use of an energy recovery ventilator (ERV) or a small dedicated outdoor air system (DOAS) to provide tempered outdoor air directly to the spaces. Further system analysis and improvements are required to execute this recommendation.

### **2.7.2 Upgrade Controls and Building Management System**

We recommend replacing the pneumatic control system with electronic actuators and sensors, and upgrading the building management system to control and monitor all HVAC equipment, including space temperatures, reheat controls, AHU controls, and fan coil controls. Pneumatic air systems are antiquated and do not offer the same benefits as a BMS. A BMS can monitor the position of electronic valves, trend valve position data, and report alarms. Pneumatic actuators also tend to leak air, may result in poor control of the HVAC equipment, cause the air compressor to run more frequently and increase energy usage.

If the existing pneumatic system can cycle damper and valve actuators and position the valves and dampers in their correct position repeatedly, then immediate replacement is not necessary. If the system cannot cycle the actuators to correct damper or valve positions, this may cause too little or too much outdoor air flow and water flow through the units, affecting the quantity of ventilation air and heating and cooling capacity of the coils.

This recommendation is primarily an energy saving and maintenance measure and does not affect the indoor air quality of the building, although it would make some of the recommended measures easier to implement.

If possible, installing a BMS should be implemented at the same time as measure 2.7.1 and 2.7.4 as a single project.

### **2.7.3 Inspect Reheat Coils and Controls**

If specific area experience temperature complaints, the reheat coils may be clogged or there may be a control issue with the pneumatic control valve. For these areas, we recommend adjusting the thermostats and verifying that the supply air temperature changes in response to the thermostat setpoint. Consider cleaning the reheat coils. Any reheat coils not providing the required temperature control should be repaired or replaced.

### **2.7.4 Replace Air Handling Units and Fan Coils**

We recommend replacing all air handling units and fan coils within the next three years. The units are approximately 50 years old and are beyond their expected life span of 30 to 40 years. This recommendation does not affect the indoor air quality of the building, assuming the existing air handling units can deliver the proper quantity of supply and

outdoor air and temper the air adequately. Consider converting the existing duct systems to VAV by replacing the reheat coils with VAV boxes with reheat to improve temperature and humidity control.

## Section 3 Testing & Balancing Results

Milharmer Associates, Inc. visited the Ayer District Courthouse on May 11, 2021 to test the airflow rates of the air handling units and the exhaust fans. A summary of the tested airflow rates versus the design airflow rates are shown below in Tables 5 and 6. The full testing and balancing report is attached.

**TABLE 5**  
Air Handler Testing & Balancing Results

| Unit | Design                         |                                   |                      | Actual                   |                       |                      |
|------|--------------------------------|-----------------------------------|----------------------|--------------------------|-----------------------|----------------------|
|      | Total Supply Fan Airflow (CFM) | Recommended Outdoor Airflow (CFM) | Return Airflow (CFM) | Supply Fan Airflow (CFM) | Outdoor Airflow (CFM) | Return Airflow (CFM) |
| AC-1 | 1,220                          | 1,220                             | N/A                  | 1,340                    | 1,340                 | N/A                  |
| AC-2 | 4,000                          | 1,500                             | 4,000                | 2,080                    | 1,311                 | 769                  |
| AC-3 | 13,520                         | 1,500                             | 13,520               | 12,240                   | 1,629                 | 10,611               |
| HV-4 | 960                            | 960                               | 0                    | 202                      | 202                   | 0                    |

**TABLE 6**  
Exhaust Fan Testing & Balancing Results

| Unit | Serving          | Design Return/Exhaust Airflow (CFM) | Actual Return/Exhaust Airflow (CFM) |
|------|------------------|-------------------------------------|-------------------------------------|
| EF-4 | Bathrooms        | 1,180                               | 1,375                               |
| EF-5 | Bathrooms        | 800                                 | 628                                 |
| EF-6 | Basement Toilets | 960                                 | 870                                 |

Typical balancing tolerances for air systems is  $\pm 10\%$  of the design airflow.

In reviewing the airflow report data, the following should be noted:

1. AC-1 and 3 are performing within the acceptable airflow range.
2. The AC-2 supply airflow is performing at approximately 50% of the design airflow. The Milharmer report notes that a sheave change is required to increase the airflow. However, changing the sheaves with the existing 3HP motor would only allow the airflow to be increased to approximately 65% of design. We recommend investigating the unit further to determine the cause of the issue.
3. HV-4 is operating at 20% of the design value. We recommend investigating the unit further to determine the cause of the issue. The technician indicated the low

- airflow may have been a result of dirty coils. These should be cleaned prior to any retest, including the duct mounted coils.
4. The technician noted that a new belt is needed in AC-1 as the existing belt is worn.
  5. Toilet exhaust fan EF-5 is not performing within acceptable range. We recommend investigating the cause of the low airflow. If no obvious obstructions or balancing issues are found, larger capacity fan should be selected by an engineer.
  6. The building appears to be negatively pressurized overall, operating at a deficit of approximately 2,000 CFM over the entire building. Generally, buildings should be positively pressurized to limit drafts and moisture infiltration. The current pressurization appears consistent with the original design airflows. We recommend that an engineer review the airflow throughout the building and develop a revised airflow plan. Note that while there may be long term building envelope, energy use, environmental air quality, and comfort impacts as a result of negative pressurization, this issue does not directly affect short term IAQ or ventilation rates.

## **Disclaimer**

Tighe and Bond cannot in anyway guarantee the effectiveness of the proposed recommendations to reduce the presence or transmission of viral infection. Our scope of work is intended to inform the Office of Court Management on recommendations for best practices based on the guidelines published by ASHRAE and the CDC. Please note that these recommendations are measures that may help reduce the risk of airborne exposure to COVID-19 but cannot eliminate the exposure or the threat of the virus. Implementing the proposed recommendations will not guarantee the safety of building occupants. Tighe & Bond will not be held responsible should building occupants contract the virus. The Office of Court Management should refer to other guidelines, published by the CDC and other governing entities, such as social distancing, wearing face masks, cleaning and disinfecting surfaces, etc. to help reduce the risk of exposure of COVID-19 to building occupants.

**MILHARMER ASSOCIATES, INC.**

534 New State Highway, Route 44, Suite 3

Raynham, MA 02767

Tel.: 508-823-8500; Facsimile: 508-823-8600



## TEST AND BALANCE REPORT

**Project:** **Ayer District Court**  
Ayer, MA

**Project No.:** **21-209**

**Project Date:** **5/11/2021**

**MECHANICAL CONTRACTOR**

*Tighe & Bond*



3384

*A N.E.B.B. Certified Company*

**Project:** Ayer District Court

**Address:** Ayer, MA

**Date:** 5/11/2021

**Project No.**

21-209

## CERTIFICATION


*Submitted & Certified by:*

**Milharmer Associates, Inc.**

*Certification No.:* **3384**

*Certification Expiration Date:* **3-31-23**

The data presented in this Report is a record of system measurements and final adjustments that have been obtained in accordance with the current edition of the ***N.E.B.B. Procedural Standards for Testing, Adjusting and Balancing of Environmental Systems***. Any variances from design quantities which exceed N.E.B.B. tolerances, are noted in the Test-Adjust-Balance Report Project Summary.



N.E.B.B. Qualified TAB Supervisor Name: **Scott F. Miller**

N.E.B.B. Qualified TAB Supervisor Signature: \_\_\_\_\_







# Certification

**SCOTT F. MILLER**

**HAS MET ALL REQUIREMENTS FOR NEBB CERTIFIED PROFESSIONAL  
STATUS IN THE FOLLOWING DISCIPLINE**

***Testing, Adjusting and Balancing of Environmental Systems***

This Certificate, as well as individual affiliation with a NEBB Certified Firm and associated NEBB Certification Stamp are REQUIRED to provide a NEBB Certified Report. Participation in the NEBB Quality Assurance Program requires the Certificant be affiliated with a NEBB Certified Firm

**CP-23541**

NEBB Certification Number

**March 31, 2023**

Expiration Date

NEBB President

NEBB President-Elect



# Firm Certification

**MILHARMER ASSOCIATES, INC.**

**HAS MET ALL REQUIREMENTS FOR NEBB CERTIFIED  
STATUS IN THE FOLLOWING DISCIPLINE**

**Testing, Adjusting and Balancing of Environmental Systems**



3384

NEBB Certification Number

March 31, 2023

Expiration Date

NEBB President

NEBB President-Elect

**Project:** Ayer District Court

**Address:** Ayer, MA

**Date:** 5/11/2021

**Project No.**

21-209

***TABLE OF CONTENTS***

**SECTION 1**

**TAB Qualifications**

- A. N.E.B.B. Certification
- B. N.E.B.B. Company Certificate
- C. N.E.B.B. Supervisor Certificate
- D. Instrument Sheet
- E. Symbol Sheet

**SECTION 2**

**TAB Building Systems**

**Project:** Ayer District Court  
**Address:** Ayer, MA  
**Date:** 5/11/2021

**Project No.** 21-209

### INSTRUMENT SHEET

The following is a list of Instruments owned and operated by Milharmer Associates, Inc. and used on this project.

| <b>Instrument ID Number</b> | <b>Instrument</b>          | <b>Calibration Date</b> | <b>Calibration Due Date</b> |
|-----------------------------|----------------------------|-------------------------|-----------------------------|
| 1                           | ADM-870 Digital Multimeter | 8-20-20                 | 8-20-21                     |
| 2                           | Shortridge Flow Hood       | 8-20-20                 | 8-20-21                     |
| 3                           | Ampmeter                   | 8-20-20                 | 8-20-21                     |
| 4                           | Tachometer                 | 8-20-20                 | 8-20-21                     |
| 5                           | Airflow Anemometer         | 8-20-20                 | 8-20-21                     |
| 6                           | Digital Thermometers       | 8-20-20                 | 8-20-21                     |
|                             |                            |                         |                             |
| 7                           | Shortridge Water Meter     | 8-20-20                 | 8-20-21                     |
|                             |                            |                         |                             |
| 8                           | Sound Meter                | 8-20-20                 | 8-20-21                     |
|                             |                            |                         |                             |
| 9                           | Vibration Meter            | 8-20-20                 | 8-20-21                     |

Please Note: Instruments are tested annually at the M.A.I. Lab. and sent back to the factory if deviation exceeds manufacturing tolerance.

Technician:

## SYMBOL SHEET

|             |                            |             |                                 |
|-------------|----------------------------|-------------|---------------------------------|
| AHU         | Air Handling Unit          | HEATER O.L. | Thermal Overload                |
| AC or ACU   | Air Conditioner Unit       |             | Protection For Motors           |
| ACCU        | Air Cooled Condensing Unit |             | Located at Starter Motor        |
| ADJ P.D.    | Adjusted Pitch Diameter    |             |                                 |
| AMP         | Amperage                   | HEPA        | High Efficiency Particulate     |
| AVG         | Average                    |             | Arrestance                      |
| A.D.        | Air Density                | HOA         | Hand/Off/Auto Switch            |
|             |                            | H.P.        | Horsepower                      |
| B.H.P.      | Brake Horsepower           | HPS         | High Pressure Steam             |
|             |                            | HRC         | Heat (Recovery or Recliam) Coil |
| CFM         | Cubic Feet Per Minute      | HVAC        | Heating, Ventilation and        |
| CH          | Chiller                    |             | Air Conditioning                |
| CHWR        | Chilled Water Return       | HWR         | Hot Water Return or             |
| CHW or CHWS | Chilled Water Supply       |             | Heating Water Return            |
| CT          | Cooling Tower              | HWS         | Hot Water Supply or             |
| CWR         | Condenser Water Return     |             | Heating Water Supply            |
| CW or CWS   | Condenser Water Supply     | HX          | Heat Exchanger                  |
| DB          | Dry Bulb                   | I.D.        | Inside Diameter                 |
| D.D.        | Direct Drive               |             |                                 |
| DIA         | Diameter                   | LAT         | Leaving Air Temperature         |
|             |                            | L.D.        | Linear Supply Diffuser          |
| EAT         | Entering Air Temperature   | LPS         | Low Pressure Steam              |
| EDC         | Electric Duct Coil         | L.T.        | Light Troffer                   |
| EDH         | Electric Duct Heater       | LWT         | Leaving Water Temperature       |
| EF          | Exhaust Fan                |             |                                 |
| EMS         | Energy Mgt System          | MAU/MUA     | Make Up Air Unit                |
| EWT         | Entering Water Temperature | MBH         | 1,000 BTU's per Hour            |
| FCU         | Fan Coil Unit              | N.A.        | Not Accessible                  |
| FH          | Fume Hood                  | N/A         | Not Applicable                  |
| F.L.A.      | Full Load Amperage         | N.I.        | Not Installed                   |
| FPB         | Fan Powered Box            | N.L.        | Not Listed                      |
| FPM         | Feet Per Minute            |             |                                 |
| FT. HD.     | Feet of Head               |             |                                 |
| GPM         | Gallons Per Minute         |             |                                 |

## SYMBOL SHEET CONTINUED

|             |  |            |   |
|-------------|--|------------|---|
| O.D.        | Outside Diameter   | TAB        | Testing, Adjusting, and Balancing   |
| OA Min      | Outside Air Minimum                                      | TSP        | Total Static Pressure   |
| OAT         | Outside Air Total  | TP         | Thermally Protected   |
| PF          | Power Factor   | UH         | Unit Heater   |
| PHC         | Preheat Coil   |            |   |
| PH          | Phase(s)   | V          | Volts   |
| PSI         | Pounds Per Square Inch                                   | VAV        | Variable Air Volume   |
| P.T.        | Pitot Traverse   | VD         | Volume Damper   |
|             |  | VFD        | Variable Frequency Drive  |
| RA          | Return Air   | VP         | Velocity Pressure   |
| RF          | Return Air Fan   |            |   |
| R.G.        | Return Grille  | W          | Watts   |
| RHC         | Reheat Coil  | WB         | Wet Bulb  |
| RPM         | Revolutions per Minute                                   | W.D.       | Water Density   |
|             |  | W.G.       | Water Gauge   |
| SA          | Supply Air   |            |   |
| SAT         | Supply Air Temperature                                   | F          | Degrees Fahrenheit  |
| S.D.        | Supply Diffuser  |            |   |
| SEF         | Smoke Exhaust Fan  | $\Delta P$ | Differential (Delta) Pressure or<br>Pressure Drop                             |
| SF (AIR)    | Supply Fan   |            |   |
| S.F.(Elect) | Service Factors  |            |   |
| SHC         | Steam Heating Coil                                       | $\Delta T$ | Differential (Delta) Temperature,<br>Net Temperature                          |
| S.P. "W.C." | Static Pressure<br>Measured in Inches of<br>Water Column | #          | Decrease or Increase<br>PSI or Pounds Per Square Inch<br>Decrease or Increase |

**Project:** Ayer District Court  
**Address:** Ayer, MA  
**Date:** 1/0/1900

**Project No.** 21-209

## REPORT SUMMARY

The following is the report for the Ayer District Court. A survey was performed on AC-1 thru 3, HV-1 and the toilet exhaust fans with the following comments:

1. Chilled water was not running during testing.
2. AC-1 - Unit needs a new belt.
3. AC-2 - The unit is operating at 52% of design airflow and would require a sheave change to increase airflow to design.
4. Toilet exhaust fans have been tested and some are below design with no adjustment as they are direct drive fans.

**Project:** Ayer District Court  
**Address:** Ayer, MA  
**Date:** 1/0/1900

**Project No.** 21-209

### REPORT SUMMARY

#### AIR HANDLING UNITS

| UNIT | SUPPLY     | RETURN     | OUTSIDE AIR |
|------|------------|------------|-------------|
| AC-1 | 1,340 CFM  | NA         | 1,340 CFM   |
| AC-2 | 2,080 CFM  | 769 CFM    | 1,311 CFM   |
| AC-3 | 12,240 CFM | 10,611 CFM | 1,629 CFM   |
| HV-1 | 202 CFM    | NA         | 202 CFM     |



**Project:** Ayer District Court  
**Address:** Ayer, MA  
**Date:** 5/11/2021 **Project No.** 21-209

**FAN DATA SHEET**

|                    | FAN NO. AC-1         |           | FAN NO. EX-1         |           |
|--------------------|----------------------|-----------|----------------------|-----------|
| Serves / Location: | Judges Lobby 1st fl. | Mech. Rm. | Judges Lobby 1st fl. | Mech. Rm. |
| Manufacturer:      | McQuay               |           | Barry Blower Co.     |           |
| Model Number:      | No Tag               |           | No Tag               |           |
| Size:              | No Tag               |           | No Tag               |           |
| Serial Number:     | No Tag               |           | 21105                |           |

| MOTOR             | DESIGN | TESTED      | DESIGN | TESTED |
|-------------------|--------|-------------|--------|--------|
| Manufacturer:     | NL     | BALDOR      | NL     | G.E.   |
| Frame Number:     | NL     | 143T        | NL     | 48Y    |
| Horsepower:       | 1      | 1           | NL     | 1/3    |
| Brake Horsepower: | NL     | 0.83        | NL     | NA     |
| Safety Factor:    | NL     | 1.15        | NL     | 1.35   |
| Volts/Phase:      | 208/3  | 208         | 115    | NA     |
| Motor Amperage:   | 4      | 3.3/3.3/3.1 | 6.6    | NA     |
| Motor RPM:        | 1725   | 1725        | 1725   | 1725   |
| Speeds:           | NL     | 1           | NL     | NA     |
| Heater Size:      | NL     | NA          | NL     | NA     |
| Heater Amps.:     | NL     | NA          | NL     | NA     |

| FAN                  | DESIGN | TESTED | DESIGN | TESTED |
|----------------------|--------|--------|--------|--------|
| Supply Air CFM:      | 1220   | 1340   |        |        |
| Return Air CFM:      |        |        |        |        |
| Exhaust Air CFM:     |        |        | 1220   | 1129   |
| Outside Air CFM:     | 1220   | 1340   |        |        |
| Suction Pressure:    | NL     | 1.39   | NL     | -0.49  |
| Discharge Pressure:  | NL     | 0.02   | NL     | 0.31   |
| Fan Static Pressure: | NL     | 1.41   | NL     | 0.8    |
| External Pressure:   | NL     | NA     | NL     | NA     |

| RPM                 | DESIGN | TESTED  | DESIGN | TESTED   |
|---------------------|--------|---------|--------|----------|
| Fan RPM:            | NL     | NA      | NL     | NA       |
| Motor Drive:        | NL     | 1VP40   | NL     | VP25     |
| Motor Size/Bore:    | NL     | 7/8"    | NL     | 1/2"     |
| Fan Drive:          | NL     | AK35    | NL     | AK38     |
| Fan Size/Bore:      | NL     | 1"      | NL     | 1"       |
| Belt Size / Number: | NL     | 4L420/1 | NL     | 4L290H/1 |
| Shafts C-C:         | NL     | 15"     | NL     | 9"       |
| Turns Open:         | NL     | 2       | NL     | 0        |

Comments:

Project: Ayer District Court


Address: Ayer, MA

Date: 5/11/2021

Project No.

21-209

### STATIC PRESSURE PROFILE



Project: Ayer District Court  
 Address: Ayer, MA  
 Date: 5/11/2021

Project No. 21-209

**TRAVERSE DATA**

SYSTEM: AC-1 TRVERSE NUMBER : T1  
 TRVERSE LOCATION: MECH ROOM

DUCT SIZE (ROUND) \_\_\_\_\_ " DIAMETER Sq Ft = 0.00  
 DUCT SIZE (RECT.) 22 " WIDTH x 12 " DEPTH Sq Ft = 1.83

AIR DENSITY DATA

STATIC PRESS @ CL: 0.29 InWg. DESIGN CFM = 1220  
 DUCT AIR TEMP : 70 Deg F ACTUAL CFM = 1340  
 BAROMETRIC PRESS : 29.92 In Hg. SCFM= 1342

AIR DENSITY RATIO CORRECTION = 1.00  
 SCFM CORRECTION FACTOR 1.00  
 ACTUAL DENSITY 0.075

| TEST HOLE | 1   | 2   | 3   | 4   | 5 | 6 | 7 |
|-----------|-----|-----|-----|-----|---|---|---|
| A         | 717 | 708 | 722 | 675 |   |   |   |
| B         | 706 | 729 | 783 | 754 |   |   |   |
| C         | 758 | 753 | 755 | 714 |   |   |   |
| D         |     |     |     |     |   |   |   |
| E         |     |     |     |     |   |   |   |
| F         |     |     |     |     |   |   |   |
| G         |     |     |     |     |   |   |   |
| H         |     |     |     |     |   |   |   |
| I         |     |     |     |     |   |   |   |

NO. OF READINGS = 12 AVERAGE FPM = 731

|   |  |  |  |  |  |  |  |
|---|--|--|--|--|--|--|--|
| J |  |  |  |  |  |  |  |
| K |  |  |  |  |  |  |  |
| L |  |  |  |  |  |  |  |
| M |  |  |  |  |  |  |  |
| N |  |  |  |  |  |  |  |
| O |  |  |  |  |  |  |  |
| P |  |  |  |  |  |  |  |
| Q |  |  |  |  |  |  |  |
| R |  |  |  |  |  |  |  |

TECHNICIAN: Brian Murphy

**Project:** Ayer District Court

**Address:** Ayer, MA

**Date:** 5/11/2021

**Project No.**

21-209

**TRAVERSE DATA**

**SYSTEM:** EX-1

**TRAVERSE NUMBER :** T1

**TRAVERSE LOCATION:** MECH ROOM

**DUCT SIZE (ROUND)**

" DIAMETER

Sq Ft =

0.00

**DUCT SIZE (RECT.)**

24

" WIDTH x 8 " DEPTH

Sq Ft =

1.33

**AIR DENSITY DATA**

**STATIC PRESS @ CL:**

0.35

InWg.

**DESIGN CFM =**

1220

**DUCT AIR TEMP :**

70

Deg F

**ACTUAL CFM =**

1129

**BAROMETRIC PRESS :**

29.92

In Hg.

**SCFM=**

1131

**AIR DENSITY RATIO CORRECTION =** 1.00

**SCFM CORRECTION FACTOR** 1.00

**ACTUAL DENSITY** 0.075

**TEST HOLE**

1

2

3

4

5

6

7

A  
B  
C  
D  
E  
F  
G  
H  
I

|     |     |     |     |     |  |  |
|-----|-----|-----|-----|-----|--|--|
| 888 | 893 | 833 | 837 | 799 |  |  |
| 867 | 841 | 855 | 900 | 844 |  |  |
| 773 | 811 | 898 | 882 | 781 |  |  |
|     |     |     |     |     |  |  |
|     |     |     |     |     |  |  |
|     |     |     |     |     |  |  |
|     |     |     |     |     |  |  |
|     |     |     |     |     |  |  |
|     |     |     |     |     |  |  |

**NO. OF READINGS =**

15

**AVERAGE FPM =**

847

J  
K  
L  
M  
N  
O  
P  
Q  
R

|  |  |  |  |  |  |  |
|--|--|--|--|--|--|--|
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |

**TECHNICIAN:**

Brian Murphy

**Project:** Ayer District Court  
**Address:** Ayer, MA  
**Date:** 5/11/2021 **Project No.** 21-209

**FAN DATA SHEET**

|                    | FAN NO. AC-2   |           | FAN NO. RA-2     |           |
|--------------------|----------------|-----------|------------------|-----------|
| Serves / Location: | Main Court Rm. | Mech. Rm. | Main Court Rm.   | Mech. Rm. |
| Manufacturer:      | McQuay         |           | Barry Blower Co. |           |
| Model Number:      | No Tag         |           | NL               |           |
| Size:              | No Tag         |           | NL               |           |
| Serial Number:     | No Tag         |           | 21106            |           |

| MOTOR             | DESIGN | TESTED      | DESIGN | TESTED |
|-------------------|--------|-------------|--------|--------|
| Manufacturer:     | NL     | DAYTON      | NL     | DAYTON |
| Frame Number:     | NL     | 182T        | NL     | NA     |
| Horsepower:       | NL     | 3           | NL     | 1/2    |
| Brake Horsepower: | NL     | 1.64        | NL     | NA     |
| Safety Factor:    | NL     | 1.15        | NL     | 1.25   |
| Volts/Phase:      | 208/3  | 208         | 208/3  | NA     |
| Motor Amperage:   | 9.7    | 5.2/5.3/5.1 | 4.4    | NA     |
| Motor RPM:        | 1755   | 1755        | 1725   | NA     |
| Speeds:           | NL     | 1           | NL     | 1      |
| Heater Size:      | NL     | NA          | NL     | NA     |
| Heater Amps.:     | NL     | NA          | NL     | NA     |

| FAN                  | DESIGN | TESTED | DESIGN | TESTED |
|----------------------|--------|--------|--------|--------|
| Supply Air CFM:      | 4000   | 2080   |        |        |
| Return Air CFM:      |        |        |        |        |
| Exhaust Air CFM:     |        |        | 4000   | 2386   |
| Outside Air CFM:     | 1500   | 1311   |        |        |
| Suction Pressure:    | NL     | 1.45   | NL     | 0.19   |
| Discharge Pressure:  | NL     | 0.1    | NL     | 0.5    |
| Fan Static Pressure: | 0.75   | 1.55   | NL     | 0.69   |
| External Pressure:   | NL     | NA     | NL     | NA     |

| RPM                 | DESIGN | TESTED | DESIGN | TESTED   |
|---------------------|--------|--------|--------|----------|
| Fan RPM:            | NL     | 1039   | NL     | NA       |
| Motor Drive:        | NL     | 1VP52  | NL     | VP40     |
| Motor Size/Bore:    | NL     | 1 1/8" | NL     | 5/8      |
| Fan Drive:          | NL     | BK90   | NL     | AK104    |
| Fan Size/Bore:      | NL     | 1 3/8" | NL     | 1 1/2"   |
| Belt Size / Number: | NL     | B77/1  | NL     | 4L540H/1 |
| Shafts C-C:         | NL     | 29"    | NL     | 16"      |
| Turns Open:         | NL     | 1 1/2  | NL     | 1        |

Comments:

Project: Ayer District Court


Address: Ayer, MA

Date: 5/11/2021

Project No.

21-209

### STATIC PRESSURE PROFILE



**Project:** Ayer District Court

**Address:** Ayer, MA

**Date:** 5/11/2021

**Project No.**

21-209

**TRAVERSE DATA**

SYSTEM: AC-2  
Zone 1

TRAVERSE NUMBER : T1  
TRAVERSE LOCATION: MECH ROOM

DUCT SIZE (ROUND) \_\_\_\_\_ " DIAMETER Sq Ft = 0.00  
DUCT SIZE (RECT.) 24 " WIDTH x 16 " DEPTH Sq Ft = 2.67

**AIR DENSITY DATA**

STATIC PRESS @ CL: 0.04 InWg. DESIGN CFM = NA  
DUCT AIR TEMP : 70 Deg F ACTUAL CFM = 1206  
BAROMETRIC PRESS : 29.92 In Hg. SCFM= 1206

AIR DENSITY RATIO CORRECTION = 1.00  
SCFM CORRECTION FACTOR 1.00  
ACTUAL DENSITY 0.075

| TEST HOLE | 1   | 2   | 3   | 4   | 5 | 6 | 7 |
|-----------|-----|-----|-----|-----|---|---|---|
| A         | 617 | 474 | 279 | 160 |   |   |   |
| B         | 587 | 495 | 266 | 315 |   |   |   |
| C         | 624 | 468 | 468 | 458 |   |   |   |
| D         | 590 | 526 | 455 | 452 |   |   |   |
| E         |     |     |     |     |   |   |   |
| F         |     |     |     |     |   |   |   |
| G         |     |     |     |     |   |   |   |
| H         |     |     |     |     |   |   |   |
| I         |     |     |     |     |   |   |   |

NO. OF READINGS = 16 AVERAGE FPM = 452

|   |  |  |  |  |  |  |  |
|---|--|--|--|--|--|--|--|
| J |  |  |  |  |  |  |  |
| K |  |  |  |  |  |  |  |
| L |  |  |  |  |  |  |  |
| M |  |  |  |  |  |  |  |
| N |  |  |  |  |  |  |  |
| O |  |  |  |  |  |  |  |
| P |  |  |  |  |  |  |  |
| Q |  |  |  |  |  |  |  |
| R |  |  |  |  |  |  |  |

TECHNICIAN: Brian Murphy

**Project:** Ayer District Court

**Address:** Ayer, MA

**Date:** 5/11/2021

**Project No.**

21-209

**TRAVERSE DATA**

**SYSTEM:** AC-2  
Zone 2

**TRAVERSE NUMBER :** T2  
**TRAVERSE LOCATION:** MECH ROOM

DUCT SIZE (ROUND) \_\_\_\_\_ " DIAMETER Sq Ft =   
DUCT SIZE (RECT.) 24 " WIDTH x 16 " DEPTH Sq Ft =

**AIR DENSITY DATA**

STATIC PRESS @ CL:  InWg. DESIGN CFM =   
DUCT AIR TEMP :  Deg F ACTUAL CFM =   
BAROMETRIC PRESS :  In Hg. SCFM=

AIR DENSITY RATIO CORRECTION = 1.00  
SCFM CORRECTION FACTOR 1.00  
ACTUAL DENSITY 0.075

| TEST HOLE | 1   | 2   | 3   | 4   | 5 | 6 | 7 |
|-----------|-----|-----|-----|-----|---|---|---|
| A         | 339 | 331 | 311 | 258 |   |   |   |
| B         | 348 | 377 | 347 | 323 |   |   |   |
| C         | 304 | 397 | 351 | 299 |   |   |   |
| D         | 259 | 353 | 347 | 297 |   |   |   |
| E         |     |     |     |     |   |   |   |
| F         |     |     |     |     |   |   |   |
| G         |     |     |     |     |   |   |   |
| H         |     |     |     |     |   |   |   |
| I         |     |     |     |     |   |   |   |

NO. OF READINGS = 16 AVERAGE FPM = 328

|   |  |  |  |  |  |  |  |
|---|--|--|--|--|--|--|--|
| J |  |  |  |  |  |  |  |
| K |  |  |  |  |  |  |  |
| L |  |  |  |  |  |  |  |
| M |  |  |  |  |  |  |  |
| N |  |  |  |  |  |  |  |
| O |  |  |  |  |  |  |  |
| P |  |  |  |  |  |  |  |
| Q |  |  |  |  |  |  |  |
| R |  |  |  |  |  |  |  |

TECHNICIAN: Brian Murphy



Project: Ayer District Court

Address: Ayer, MA

Date: 5/11/2021

Project No.

21-209

TRAVERSE DATA

SYSTEM: RA-2

TRAVERSE NUMBER : T1

TRAVERSE LOCATION: MECH ROOM

DUCT SIZE (ROUND)

" DIAMETER

Sq Ft =

0.00

DUCT SIZE (RECT.)

30

" WIDTH x 18 " DEPTH

Sq Ft =

3.75

AIR DENSITY DATA

STATIC PRESS @ CL:

0.5

InWg.

DESIGN CFM =

4000

DUCT AIR TEMP :

70

Deg F

ACTUAL CFM =

2386

BAROMETRIC PRESS :

29.92

In Hg.

SCFM=

2391

AIR DENSITY RATIO CORRECTION = 1.00

SCFM CORRECTION FACTOR 1.00

ACTUAL DENSITY 0.075

TEST HOLE

1

2

3

4

5

6

7

A  
B  
C  
D  
E  
F  
G  
H  
I

|     |     |     |  |  |  |  |
|-----|-----|-----|--|--|--|--|
| 614 | 641 | 604 |  |  |  |  |
| 624 | 668 | 633 |  |  |  |  |
| 667 | 592 | 707 |  |  |  |  |
| 673 | 602 | 715 |  |  |  |  |
| 636 | 555 | 614 |  |  |  |  |
|     |     |     |  |  |  |  |
|     |     |     |  |  |  |  |
|     |     |     |  |  |  |  |
|     |     |     |  |  |  |  |

NO. OF READINGS =

15

AVERAGE FPM =

636

J  
K  
L  
M  
N  
O  
P  
Q  
R

|  |  |  |  |  |  |  |
|--|--|--|--|--|--|--|
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |

TECHNICIAN:

Brian Murphy

**Project:** Ayer District Court

**Address:** Ayer, MA

**Date:** 5/11/2021

**Project No.**

21-209

**TRAVERSE DATA**

**SYSTEM:** RA-2

**TRAVERSE NUMBER :** T2

Return to AC-2

**TRAVERSE LOCATION:** MECH ROOM

**DUCT SIZE (ROUND)**

" **DIAMETER**

Sq Ft =

0.00

**DUCT SIZE (RECT.)**

30

" **WIDTH** x 18 " **DEPTH**

Sq Ft =

3.75

**AIR DENSITY DATA**

**STATIC PRESS @ CL:**

0.5

InWg.

**DESIGN CFM =**

NL

**DUCT AIR TEMP :**

70

Deg F

**ACTUAL CFM =**

795

**BAROMETRIC PRESS :**

29.92

In Hg.

**SCFM=**

796

**AIR DENSITY RATIO CORRECTION =** 1.00

**SCFM CORRECTION FACTOR** 1.00

**ACTUAL DENSITY** 0.075

**TEST HOLE**

1

2

3

4

5

6

7

A

168

135

125

B

210

101

130

C

267

151

156

D

318

222

268

E

369

284

274

F

G

H

I

**NO. OF READINGS =**

15

**AVERAGE FPM =**

212

J

K

L

M

N

O

P

Q

R

**TECHNICIAN:**

Brian Murphy

**Project:** Ayer District Court  
**Address:** Ayer, MA  
**Date:** 5/11/2021

**Project No.** 21-209

**FAN DATA SHEET**

|                      | FAN NO. AC-3   |                | FAN NO. RA-3     |             |
|----------------------|----------------|----------------|------------------|-------------|
| Serves / Location:   | Top Floor      | Mech. Rm.      | Top Floor        | Mech. Rm.   |
| Manufacturer:        | McQuay         |                | Barry Blower Co. |             |
| Model Number:        | TS-228H        |                | 402-SWSI         |             |
| Size:                | NA             |                | NL               |             |
| Serial Number:       | 0.0.82155H-090 |                | 70-1022          |             |
| MOTOR                | DESIGN         | TESTED         | DESIGN           | TESTED      |
| Manufacturer:        | NL             | DAYTON         | NL               | LINCOLN     |
| Frame Number:        | NL             | 213T           | NL               | 182T        |
| Horsepower:          | NL             | 7.5            | NL               | 3           |
| Brake Horsepower:    | NL             | 4.6            | NL               | 2.8         |
| Safety Factor:       | NL             | 1.15           | NL               | NA          |
| Volts/Phase:         | 208/3          | 208            | 208/3            | 208         |
| Motor Amperage:      | 22.5           | 13.4/13.9/13.9 | 10.8             | 9.8/9.9/9.9 |
| Motor RPM:           | 1740           | 1740           | 1755             | 1755        |
| Speeds:              | NL             | 1              | NL               | 1           |
| Heater Size:         | NL             | NA             | NL               | NA          |
| Heater Amps.:        | NL             | NA             | NL               | NA          |
| FAN                  | DESIGN         | TESTED         | DESIGN           | TESTED      |
| Supply Air CFM:      | 13520          | 12240          |                  |             |
| Return Air CFM:      |                |                |                  |             |
| Exhaust Air CFM:     |                |                | 13520            | 13362       |
| Outside Air CFM:     | 1500           | 1629           |                  |             |
| Suction Pressure:    | NL             | 0.62           | NL               | 0.6         |
| Discharge Pressure:  | NL             | 0.56           | NL               | 0.02        |
| Fan Static Pressure: | 0.85           | 1.18           | NL               | 0.62        |
| External Pressure:   | NL             | NA             | NL               | NA          |
| RPM                  | DESIGN         | TESTED         | DESIGN           | TESTED      |
| Fan RPM:             | NL             | NA             | NL               | 562         |
| Motor Drive:         | NL             | 1VP60          | NL               | 2VP58       |
| Motor Size/Bore:     | NL             | 1 3/8"         | NL               | 1 1/8"      |
| Fan Drive:           | NL             | 2B1460         | NL               | 2TB184      |
| Fan Size/Bore:       | NL             | 2 1/4"         | NL               | 2 1/4"      |
| Belt Size / Number:  | NL             | B85/2          | NL               | A128/2      |
| Shafts C-C:          | NL             | 28 1/2"        | NL               | 45 1/2"     |
| Turns Open:          | NL             | 2              | NL               | 1           |

Comments:

Project: Ayer District Court


Address: Ayer, MA

Date: 5/11/2021

Project No.

21-209

### STATIC PRESSURE PROFILE



**Project:** Ayer District Court

**Address:** Ayer, MA

**Date:** 5/11/2021

**Project No.**

21-209

**TRAVERSE DATA**

**SYSTEM:** AC-3  
Supply

**TRAVERSE NUMBER :** T1  
**TRAVERSE LOCATION:** MECH ROOM

DUCT SIZE (ROUND) \_\_\_\_\_ " DIAMETER Sq Ft = 0.00  
DUCT SIZE (RECT.) 60 " WIDTH x 24 " DEPTH Sq Ft = 10.00

**AIR DENSITY DATA**

STATIC PRESS @ CL: 0.53 InWg. DESIGN CFM = 13520  
DUCT AIR TEMP : 70 Deg F ACTUAL CFM = 12240  
BAROMETRIC PRESS : 29.92 In Hg. SCFM= 12262

AIR DENSITY RATIO CORRECTION = 1.00  
SCFM CORRECTION FACTOR 1.00  
ACTUAL DENSITY 0.075

| TEST HOLE | 1    | 2    | 3    | 4    | 5    | 6    | 7 |
|-----------|------|------|------|------|------|------|---|
| A         | 1271 | 1307 | 1440 | 1307 | 1356 | 1186 |   |
| B         | 1355 | 1339 | 1258 | 1367 | 1321 | 1283 |   |
| C         | 1272 | 967  | 935  | 1151 | 1262 | 1318 |   |
| D         | 1362 | 983  | 980  | 847  | 1214 | 1294 |   |
| E         |      |      |      |      |      |      |   |
| F         |      |      |      |      |      |      |   |
| G         |      |      |      |      |      |      |   |
| H         |      |      |      |      |      |      |   |
| I         |      |      |      |      |      |      |   |

NO. OF READINGS = 24 AVERAGE FPM = 1224

|   |  |  |  |  |  |  |  |
|---|--|--|--|--|--|--|--|
| J |  |  |  |  |  |  |  |
| K |  |  |  |  |  |  |  |
| L |  |  |  |  |  |  |  |
| M |  |  |  |  |  |  |  |
| N |  |  |  |  |  |  |  |
| O |  |  |  |  |  |  |  |
| P |  |  |  |  |  |  |  |
| Q |  |  |  |  |  |  |  |
| R |  |  |  |  |  |  |  |

**TECHNICIAN:** Brian Murphy

**Project:** Ayer District Court

**Address:** Ayer, MA

**Date:** 5/11/2021

**Project No.**

21-209

**TRAVERSE DATA**

SYSTEM: RA-3

TRAVERSE NUMBER : T1

TRAVERSE LOCATION: MECH ROOM

DUCT SIZE (ROUND)

" DIAMETER

Sq Ft =

0.00

DUCT SIZE (RECT.)

60

" WIDTH x 24 " DEPTH

Sq Ft =

10.00

**AIR DENSITY DATA**

STATIC PRESS @ CL:

0.02

InWg.

DESIGN CFM =

13520

DUCT AIR TEMP :

70

Deg F

ACTUAL CFM =

13362

BAROMETRIC PRESS :

29.92

In Hg.

SCFM=

13370

AIR DENSITY RATIO CORRECTION = 1.00

SCFM CORRECTION FACTOR 1.00

ACTUAL DENSITY 0.075

TEST HOLE

1 2 3 4 5 6 7

A  
B  
C  
D  
E  
F  
G  
H  
I

|      |      |      |      |      |  |  |
|------|------|------|------|------|--|--|
| 1313 | 1330 | 1437 | 1329 | 1337 |  |  |
| 1366 | 1423 | 1400 | 1331 | 1301 |  |  |
| 1331 | 1443 | 1314 | 1213 | 1242 |  |  |
| 1418 | 1371 | 1400 | 1226 | 1198 |  |  |
|      |      |      |      |      |  |  |
|      |      |      |      |      |  |  |
|      |      |      |      |      |  |  |
|      |      |      |      |      |  |  |
|      |      |      |      |      |  |  |

NO. OF READINGS =

20

AVERAGE FPM =

1336

J  
K  
L  
M  
N  
O  
P  
Q  
R

|  |  |  |  |  |  |  |
|--|--|--|--|--|--|--|
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |

TECHNICIAN:

Brian Murphy

Project: Ayer District Court

Address: Ayer, MA

Date: 5/11/2021

Project No.

21-209

TRAVERSE DATA

SYSTEM: RA-3

TRAVERSE NUMBER : T2

Return to AC-3

TRAVERSE LOCATION: MECH ROOM

DUCT SIZE (ROUND)

" DIAMETER

Sq Ft =

0.00

DUCT SIZE (RECT.)

32

" WIDTH x 44 " DEPTH

Sq Ft =

9.78

AIR DENSITY DATA

STATIC PRESS @ CL:

0.11

InWg.

DESIGN CFM =

NL

DUCT AIR TEMP :

70

Deg F

ACTUAL CFM =

10221

BAROMETRIC PRESS :

29.92

In Hg.

SCFM=

10230

AIR DENSITY RATIO CORRECTION = 1.00

SCFM CORRECTION FACTOR 1.00

ACTUAL DENSITY 0.075

TEST HOLE

1

2

3

4

5

6

7

A

960

1036

1228

1100

B

927

644

915

1299

C

621

636

710

1182

D

659

802

631

1300

E

956

1148

1194

1441

F

1265

1389

1526

1520

G

H

I

NO. OF READINGS =

24

AVERAGE FPM =

1045

J

K

L

M

N

O

P

Q

R

TECHNICIAN:

Brian Murphy

**Project:** Ayer District Court  
**Address:** Ayer, MA  
**Date:** 5/11/2021 **Project No.** 21-209

**FAN DATA SHEET**

|                    |                     |                |
|--------------------|---------------------|----------------|
|                    | <b>FAN NO. HV-1</b> | <b>FAN NO.</b> |
| Serves / Location: | Holding Rooms       | Basement Mech. |
| Manufacturer:      | McQuay              |                |
| Model Number:      | No Tag              |                |
| Size:              | No Tag              |                |
| Serial Number:     | No Tag              |                |

| <b>MOTOR</b>      | <b>DESIGN</b> | <b>TESTED</b> | <b>DESIGN</b> | <b>TESTED</b> |
|-------------------|---------------|---------------|---------------|---------------|
| Manufacturer:     | NL            | GE MOTORS     |               |               |
| Frame Number:     | NL            | 56            |               |               |
| Horsepower:       | NL            | 1             |               |               |
| Brake Horsepower: | NL            | NA            |               |               |
| Safety Factor:    | NL            | 1.15          |               |               |
| Volts/Phase:      | 208/3         | NA            |               |               |
| Motor Amperage:   | 3.4           | NA            |               |               |
| Motor RPM:        | 1725          | NA            |               |               |
| Speeds:           | NL            | NA            |               |               |
| Heater Size:      | NL            | NA            |               |               |
| Heater Amps.:     | NL            | NA            |               |               |

| <b>FAN</b>           | <b>DESIGN</b> | <b>TESTED</b> | <b>DESIGN</b> | <b>TESTED</b> |
|----------------------|---------------|---------------|---------------|---------------|
| Supply Air CFM:      | 960           | 202 *1        |               |               |
| Return Air CFM:      |               |               |               |               |
| Exhaust Air CFM:     |               |               |               |               |
| Outside Air CFM:     | 960           | 202           |               |               |
| Suction Pressure:    |               |               |               |               |
| Discharge Pressure:  |               |               |               |               |
| Fan Static Pressure: |               |               |               |               |
| External Pressure:   |               |               |               |               |

| <b>RPM</b>          | <b>DESIGN</b> | <b>TESTED</b> | <b>DESIGN</b> | <b>TESTED</b> |
|---------------------|---------------|---------------|---------------|---------------|
| Fan RPM:            | NL            | 1380          |               |               |
| Motor Drive:        | NL            | 1VP40         |               |               |
| Motor Size/Bore:    | NL            | 5/8"          |               |               |
| Fan Drive:          | NL            | A52           |               |               |
| Fan Size/Bore:      | NL            | 1"            |               |               |
| Belt Size / Number: | NL            | 4L420/1       |               |               |
| Shafts C-C:         | NL            | 15"           |               |               |
| Turns Open:         | NL            | 3             |               |               |

**Comments:** \*1 Possible dirty coils resulting in low airflows.



**Project:** Ayer District Court  
**Address:** Ayer, MA  
**Date:** 5/11/2021 **Project No.** 21-209

**FAN DATA SHEET**

|                    | <b>FAN NO. RF-4</b> |      | <b>FAN NO. RF-5</b> |      |
|--------------------|---------------------|------|---------------------|------|
| Serves / Location: | Toilets (SE)        | Roof | Toilets (NW)        | Roof |
| Manufacturer:      | EMERSON CLIMATE     |      | No Tag              |      |
| Model Number:      | 5BDD15D8            |      | No Tag              |      |
| Size:              | NL                  |      | No Tag              |      |
| Serial Number:     | NL                  |      | No Tag              |      |

| <b>MOTOR</b>      | <b>DESIGN</b> | <b>TESTED</b> | <b>DESIGN</b> | <b>TESTED</b> |
|-------------------|---------------|---------------|---------------|---------------|
| Manufacturer:     | NL            | EMERSON       | NL            | No Tag        |
| Frame Number:     | NL            | NL            | NL            | No Tag        |
| Horsepower:       | NL            | 1/2           | NL            | No Tag        |
| Brake Horsepower: | NL            | NA            | NL            | No Tag        |
| Safety Factor:    | NL            | 1             | NL            | No Tag        |
| Volts/Phase:      | 115           | NA            | No Tag        | NA            |
| Motor Amperage:   | 8.4           | NA            | No Tag        | NA            |
| Motor RPM:        | 1725          | 1725          | No Tag        | NA            |
| Speeds:           | NL            | NA            | NL            | NA            |
| Heater Size:      | NL            | NA            | NL            | NA            |
| Heater Amps.:     | NL            | NA            | NL            | NA            |

| <b>FAN</b>           | <b>DESIGN</b> | <b>TESTED</b> | <b>DESIGN</b> | <b>TESTED</b> |
|----------------------|---------------|---------------|---------------|---------------|
| Supply Air CFM:      |               |               |               |               |
| Return Air CFM:      |               |               |               |               |
| Exhaust Air CFM:     | 1180          | 1375          | 800           | 628           |
| Outside Air CFM:     |               |               |               |               |
| Suction Pressure:    |               |               |               |               |
| Discharge Pressure:  |               |               |               |               |
| Fan Static Pressure: |               |               |               |               |
| External Pressure:   |               |               |               |               |

| <b>RPM</b>          | <b>DESIGN</b> | <b>TESTED</b> | <b>DESIGN</b> | <b>TESTED</b> |
|---------------------|---------------|---------------|---------------|---------------|
| Fan RPM:            | NL            | 1380          | NL            | DIRECT DRIVE  |
| Motor Drive:        | NL            | 1VL40         | NL            | DIRECT DRIVE  |
| Motor Size/Bore:    | NL            | 1/2           | NL            | DIRECT DRIVE  |
| Fan Drive:          | NL            | A50           | NL            | DIRECT DRIVE  |
| Fan Size/Bore:      | NL            | 7/8"          | NL            | DIRECT DRIVE  |
| Belt Size / Number: | NL            | 4L240/1       | NL            | DIRECT DRIVE  |
| Shafts C-C:         | NL            | 5 1/2         | NL            | DIRECT DRIVE  |
| Turns Open:         | NL            | CLOSED        | NL            | DIRECT DRIVE  |

Comments:





**Project:** Ayer District Court  
**Address:** Ayer, MA  
**Date:** 5/11/2021 **Project No.** 21-209

**FAN DATA SHEET**

|                    |                     |                |
|--------------------|---------------------|----------------|
|                    | <b>FAN NO.</b> RF-6 | <b>FAN NO.</b> |
| Serves / Location: | Toilets Basement    | Roof           |
| Manufacturer:      | No Tag              |                |
| Model Number:      | No Tag              |                |
| Size:              | No Tag              |                |
| Serial Number:     | No Tag              |                |

| <b>MOTOR</b>      | <b>DESIGN</b> | <b>TESTED</b> | <b>DESIGN</b> | <b>TESTED</b> |
|-------------------|---------------|---------------|---------------|---------------|
| Manufacturer:     | NL            | No Tag        |               |               |
| Frame Number:     | NL            | No Tag        |               |               |
| Horsepower:       | NL            | No Tag        |               |               |
| Brake Horsepower: | NL            | No Tag        |               |               |
| Safety Factor:    | NL            | No Tag        |               |               |
| Volts/Phase:      | No Tag        | NA            |               |               |
| Motor Amperage:   | No Tag        | NA            |               |               |
| Motor RPM:        | No Tag        | NA            |               |               |
| Speeds:           | NL            | NA            |               |               |
| Heater Size:      | NL            | NA            |               |               |
| Heater Amps.:     | NL            | NA            |               |               |

| <b>FAN</b>           | <b>DESIGN</b> | <b>TESTED</b> | <b>DESIGN</b> | <b>TESTED</b> |
|----------------------|---------------|---------------|---------------|---------------|
| Supply Air CFM:      |               |               |               |               |
| Return Air CFM:      |               |               |               |               |
| Exhaust Air CFM:     | 960           | 870           |               |               |
| Outside Air CFM:     |               |               |               |               |
| Suction Pressure:    |               |               |               |               |
| Discharge Pressure:  |               |               |               |               |
| Fan Static Pressure: |               |               |               |               |
| External Pressure:   |               |               |               |               |

| <b>RPM</b>          | <b>DESIGN</b> | <b>TESTED</b> | <b>DESIGN</b> | <b>TESTED</b> |
|---------------------|---------------|---------------|---------------|---------------|
| Fan RPM:            | NL            | DIRECT DRIVE  |               |               |
| Motor Drive:        | NL            | DIRECT DRIVE  |               |               |
| Motor Size/Bore:    | NL            | DIRECT DRIVE  |               |               |
| Fan Drive:          | NL            | DIRECT DRIVE  |               |               |
| Fan Size/Bore:      | NL            | DIRECT DRIVE  |               |               |
| Belt Size / Number: | NL            | DIRECT DRIVE  |               |               |
| Shafts C-C:         | NL            | DIRECT DRIVE  |               |               |
| Turns Open:         | NL            | DIRECT DRIVE  |               |               |

Comments:

**Project:** Ayer District Court

**Address:** Ayer, MA

**Date:** 5/11/2021

**Project No.**

21-209

**TRAVERSE DATA**

**SYSTEM:** RF-6

**TRAVERSE NUMBER :** T1

**TRAVERSE LOCATION:** Basement Mech

**DUCT SIZE (ROUND)**

" DIAMETER

Sq Ft =

0.00

**DUCT SIZE (RECT.)**

20

" WIDTH x 10 " DEPTH

Sq Ft =

1.39

**AIR DENSITY DATA**

**STATIC PRESS @ CL:**

0.18

InWg.

**DESIGN CFM =**

960

**DUCT AIR TEMP :**

70

Deg F

**ACTUAL CFM =**

870

**BAROMETRIC PRESS :**

29.92

In Hg.

**SCFM=**

871

**AIR DENSITY RATIO CORRECTION =** 1.00

**SCFM CORRECTION FACTOR** 1.00

**ACTUAL DENSITY** 0.075

**TEST HOLE**

1

2

3

4

5

6

7

A  
B  
C  
D  
E  
F  
G  
H  
I

|     |     |     |     |  |  |  |
|-----|-----|-----|-----|--|--|--|
| 573 | 560 | 607 | 556 |  |  |  |
| 681 | 673 | 669 | 619 |  |  |  |
| 631 | 675 | 654 | 623 |  |  |  |
|     |     |     |     |  |  |  |
|     |     |     |     |  |  |  |
|     |     |     |     |  |  |  |
|     |     |     |     |  |  |  |
|     |     |     |     |  |  |  |
|     |     |     |     |  |  |  |

**NO. OF READINGS =**

12

**AVERAGE FPM =**

627

J  
K  
L  
M  
N  
O  
P  
Q  
R

|  |  |  |  |  |  |  |
|--|--|--|--|--|--|--|
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |

**TECHNICIAN:**

Brian Murphy