



CAPE COD CANAL TRANSPORTATION STUDY



Prepared by:



ACKNOWLEDGEMENTS

The preparation of this report has been financed in part through MassDOT's Statewide Planning and Research (SPR) Program agreement with the Federal Highway Administration of the United States Department of Transportation. The views and opinions of the authors and agencies expressed herein do not necessarily state or reflect those of the United States Department of Transportation.

TEAM



MassDOT Office of Transportation Planning

Ten Park Plaza, Room 4160
Boston, MA 02116

David Mohler, Executive Director
Ethan Britland, Project Manager



Stantec

226 Causeway Street, Boston, MA 02114
(617) 523-8103

Contact:

Michael Paiewonsky, AICP – Associate / Project Manager
Frederick Moseley, P.E., Principal / Senior Traffic Engineer

TrafInfo Communications

10 Tower Park, Suite 301
Woburn, MA 01801
781-710-5380

Contact:

Sudhir Murthy, P.E., PTOE
President

FXM Associates

53 County Road
Mattapoissett, MA 02739
508-758-2238

Contact:

Francis X. Mahady, Principal

Harriman

19 Kingston Street, 4th Floor
Boston, MA 02111
617-426-5050

Contact:

Steven Cecil, AIA, ASLA

Normandeau Associates Inc.

25 Nashua Road
Bedford, NH 03110
603-472-5191

Contact:

Tory Fletcher

HMMH

77 S. Bedford Street #120
Burlington, MA 01803
781-229-0707

Contact:

Chris Menge, Senior Vice
President

Archeological and Historical Services (AHS)

569 Middle Turnpike
P.O. Box 543
Storrs, CT 06268
860-429-2142

Contact:

Mary (Meg) Harper, M.A., RPA,
President

CONTENTS

EXECUTIVE SUMMARY

A Familiar Story: Aging Infrastructure and Increased Travel	
Demands	1
The Study Area	3
Report and Study Process Overview	4
Step 1: Define the Study Goals, Objectives, and Evaluation	
Criteria	5
Goals.....	5
Objectives	5
Evaluation Criteria	6
Step 2: Review & Evaluate Existing and Future Conditions ...	7
Natural Environmental Resources.....	7
Social Environmental Resources	8
Existing Transportation Network.....	10
Pedestrian Facilities	13
Bicycle Facilities.....	13
Bus Service	14
Rail Service.....	14
Ferry Service.....	14
Airline Service.....	15
Park & Ride Lots	15
Traffic Conditions	15
Issues, Constraints, and Opportunities.....	21
Step 3: Develop a Range of Design Alternatives	21
Local Intersection Alternatives	22
Gateway Intersection Alternatives	25
Multimodal Transportation Alternatives.....	35
Bicycle and Pedestrian Alternatives.....	35
Step 4: Analyze Design Alternatives Based on Evaluation	
Criteria	36
Regional Travel Analysis Modeling	37
Economic Analysis	39
Step 5: Provide Recommendations to Meet Study Goals and Objectives.....	47
Gateway Intersection Improvements.....	47
Multimodal Transportation Improvements.....	48
Roadway Improvements	48
Bicycle and Pedestrian Improvements.....	51
Multimodal Transportation Center.....	51
Next Steps	54
MassDOT Highway Design Process	54
Project Delivery Methods	55
Environmental Considerations	56
Implementation Summary	57

INTRODUCTION AND STUDY FRAMEWORK

1.1	Introduction	1-1
1.1.1	Cape Cod Canal Bridges	1-4
1.2	Study Context	1-5
1.3	Study Area	1-6
1.4	Goals and Objectives	1-7
1.4.1	Goals	1-7
1.4.2	Objectives	1-8
1.5	Evaluation Criteria	1-8
1.6	Public Involvement Plan	1-8
1.6.1	Working Group	1-11
1.6.2	Working Group/Public Meetings	1-12
1.6.3	Outreach to Environmental Resource Agencies	1-12
1.6.4	Outreach to Tribes	1-13
1.6.5	Project Website.....	1-13

EXISTING ENVIRONMENTAL AND TRAFFIC CONDITIONS

2.1	Existing Environmental Conditions	2-1
2.1.1	Wetland, Floodplain, and Surface Waterbodies	2-2
2.1.2	Aquifers and Public Water Supply Wells.....	2-3
2.1.3	Fisheries and Shellfish Growing Areas	2-4
2.1.6	Rare, Threatened, and Endangered Species	2-6
2.1.7	Areas of Critical Environmental Concern.....	2-8
2.1.8	Oil and Hazardous Materials Sites	2-8
2.1.9	Upper Cape Water Supply Reserve	2-10
2.1.4	Cultural, Historical, and Archaeological Resources	2-12
2.1.5	Protected Open Space	2-15
2.1.6	Utilities.....	2-16
2.1.7	Environmental Justice Populations.....	2-17
2.1.8	MEMA Evacuation Zones	2-19
2.2	Land Use and Development	2-19
2.2.1	Land Uses within the Study Area.....	2-19
2.2.2	Joint Base Cape Cod	2-21
2.2.3	Belmont Circle and Bourne Rotary.....	2-22
2.3	Socio-Economic Conditions	2-24
2.3.1	Population	2-24
2.3.2	Housing Units	2-26
2.3.3	Median Household Income	2-27
2.3.4	Employment	2-28
2.3.5	Journey to Work	2-30
2.4	Public Health Conditions	2-32
2.5	Transportation Conditions	2-34
2.5.1	Major Highways in the Study Area	2-34
2.5.2	Local Roadways/Highways and Principal Intersections in the Study Area	2-36

2.5.3	Traffic Counting Methods.....	2-41
2.5.4	BlueTOAD™ Origin–Destination Study	2-43
2.5.5	Transportation Analysis Methodology	2-44
2.5.6	Existing Average Daily Traffic and Peak–Hour Traffic Volumes.....	2-47
2.5.7	Existing (2014) Turning Movements.....	2-51
2.5.8	Existing (2014) Peak–Hour Levels of Service	2-55
2.5.9	Origin–Destination Analysis Findings	2-62
2.5.10	Existing Traffic Conditions at Belmont Circle and Bourne Rotary	2-62
2.5.11	Crashes.....	2-66
2.6	Multimodal Transportation	2-68
2.6.1	Pedestrian Facilities.....	2-68
2.6.2	Bicycle Facilities	2-71
2.6.3	Transit Services.....	2-72
2.6.4	Bus Service.....	2-74
2.6.5	Rail	2-80
2.6.6	Ferry Service	2-81
2.6.7	Airline Service	2-84
2.6.8	Intelligent Transportation Systems	2-85
2.6.9	Park & Ride Lots.....	2-85
2.6.10	Rest Areas.....	2-86
2.7	Summary of Existing Conditions.....	2-86
2.8	Issues, Constraints, and Opportunities	2-90

FUTURE NO-BUILD TRANSPORTATION CONDITIONS

3.1	Introduction.....	3-1
3.2	Factors Affecting Future Transportation Conditions ..	3-2
3.3	Transportation	3-3
3.3.1	Regional Travel Demand Modeling.....	3-3
3.3.2	Planned Transportation Improvements.....	3-4
3.3.3	Cape Cod Commission Regional Transportation Plan.....	3-4
3.3.4	Future (2040) No-Build Average Daily Traffic Volumes and Peak-Period Traffic Volumes	3-5
3.3.5	Turning Movement Counts	3-8
3.3.6	Future (2040) No-Build Levels of Service	3-12
3.3.7	Traffic Operations at Belmont Circle and Bourne Rotary.....	3-20
3.4	Problem Intersections	3-22
3.5	Summary of Future No-Build Traffic Conditions.....	3-25

ALTERNATIVES DEVELOPMENT AND ANALYSIS

4.1 Design Approach and Assumptions	4-2
4.2 Alternatives Development and Analysis	4-3
4.2.1 Traffic Analysis – Measures of Effectiveness	4-4
4.2.2 Conceptual Cost Estimate Methodology	4-5
4.3 Roadway Improvement Alternatives Analysis.....	4-5
4.3.1 Working Group Transportation Improvement Submissions	4-6
4.4 Local Intersection Improvements.....	4-7
4.4.1 Scenic Highway/Meetinghouse Lane at Canal Road/ State Road.....	4-7
4.4.2 Sandwich Road at Bourne Rotary Connector	4-10
4.4.3 Route 6A (Sandwich Road) at Cranberry Highway.	4-14
4.4.4 Route 130 (Forestdale Road) at Cotuit Road	4-16
4.5 Screening-Level Analysis	4-21
4.5.1 Public-Private Partnership Alternatives.....	4-22
4.6 Gateway Intersection Improvements	4-26
4.6.1 Route 6 Exit 1C Relocation	4-26
4.6.2 Route 6 Additional Eastbound Travel Lane	4-38
4.6.3 Belmont Circle and Bourne Rotary – Introduction	4-40
4.6.4 Belmont Circle	4-41
4.6.5 Bourne Rotary	4-51
4.6.4 Bourne Rotary Interchange	4-62
4.7 Bourne and Sagamore Bridge Replacement or Rehabilitation.....	4-65
4.7.1 Bourne and Sagamore Bridges – Potential Replacement Design Features	4-65
4.8 Regional Transportation Analysis Modeling.....	4-68
4.9 Travel Demand Model – Case Analysis.....	4-71
4.9.1 Case 1	4-71
4.9.2 Case 1A	4-75
4.9.3 Case 1B	4-78
4.9.4 Case 2	4-82
4.9.5 Case 2B	4-85
4.9.6 Case 3	4-88
4.9.7 Case 3A	4-91
4.9.8 Overall Findings of Transportation Demand Modeling Analysis	4-96
4.10 Additional Study Analysis	4-102
4.10.1 Air Quality Evaluation	4-102
4.10.2 Preliminary Noise Evaluation.....	4-105
4.10.3 Economic Analysis	4-106
4.11 Summary of Conceptual Cost EstimatesSUMMARY OF CONCEPTUAL COST ESTIMATES	4-112
4.12 Summary of Potential Environmental, Community, and Property Impacts	4-113
4.13 Multimodal Improvements	4-114

4.13.1 Bicycle/Pedestrian Facility Improvements.....	4-114
4.13.1 Multimodal Transportation Center.....	4-120

STUDY RECOMMENDATIONS

5.1 Evaluation Criteria.....	5-2
5.2 Evaluation Methodology.....	5-2
5.3 Multimodal Transportation Improvement Recommendations	5-5
5.3.1 Bicycle and Pedestrian Improvements	5-5
5.3.2 Multimodal Improvements	5-6
5.4 Roadway Improvements	5-6
5.4.1 Local Intersection Improvements	5-7
5.4.2 Gateway Intersection Improvements	5-9
5.5 Implementation.....	5-14
5.5.1 MassDOT Project Development and Design Process	5-14
5.5.2 Project Delivery Methods.....	5-19
5.5.3 Environmental Considerations	5-20
5.5.4 Climate Change Considerations	5-21
5.5.5 Implementation Summary	5-22

EXHIBITS

EXECUTIVE SUMMARY

Exhibit ES-1	Study Area / Focus Area	3
Exhibit ES-2	Wetlands and 100-Year Floodplain Areas.....	6
Exhibit ES-3	Rare, Threatened, and Endangered Species	7
Exhibit ES-4	Protected Open Space	9
Exhibit ES-5	Major Roadways in the Study Area	11
Exhibit ES-6	Routing of Traffic Between Highway Corridors	17
Exhibit ES-7	Problem Intersections in the Study Area	20
Exhibit ES-8	Local Intersection Improvement Locations	23
Exhibit ES-9	Local Intersection Improvements	24
Exhibit ES-10	Potential Gateway Intersection Improvements	25
Exhibit ES-11	Relocation of Route 6 Exit 1C	26
Exhibit ES-12	Route 6 Eastbound Travel Lane	27
Exhibit ES-13	Scenic Highway Westbound to Route 25 Westbound Ramp	30
Exhibit ES-14	Alternatives Evaluated – Belmont Circle	30
Exhibit ES-15	Alternatives Evaluated – Bourne Rotary	32
Exhibit ES-16	Bourne Rotary Interchange	33

Exhibit ES-17	Potential Cross Section of Replacement Canal Bridges.....	35
Exhibit ES-18	Components of Seven Travel Demand Analysis Cases	38
Exhibit ES-19	Average Non-Summer and Summer Delay – Belmont Circle and Bourne Rotary	40
Exhibit ES-20	Average Non-Summer and Summer Delay – Sagamore Bridge Approaches	40
Exhibit ES-21	Annual Vehicle Hours Savings compared to No-Build	42
Exhibit ES-22	Evaluation Matrix – Definition of Benefit and Impact Ratings	45
Exhibit ES-23	Evaluation Matrix – Comparison of Travel Analysis Model Cases.....	46
Exhibit ES-24	Recommended Gateway Intersection Improvements – Case 3A	48
Exhibit ES-25	Recommended Local Intersection Improvements	50
Exhibit ES-26	Enhanced Bicycle-Pedestrian Access at Sagamore Bridge	52
Exhibit ES-27	Enhanced Bicycle-Pedestrian Access at Bourne Bridge	53

INTRODUCTION AND STUDY FRAMEWORK

Exhibit 1-1	Cape Cod, Massachusetts	1-3
Exhibit 1-2	Study Area/Focus Area.....	1-7

EXISTING ENVIRONMENTAL AND TRAFFIC CONDITIONS

Exhibit 2-1	Wetlands and Surface Waterbodies	2-2
Exhibit 2-2	FEMA Floodplains	2-3
Exhibit 2-3	Aquifers and Public Water Supply Wells	2-4
Exhibit 2-4	Fisheries and Shellfish Growing Areas	2-5
Exhibit 2-5	Rare, Threatened, and Endangered Species.....	2-7
Exhibit 2-6	Areas of Critical Environmental Concern	2-7
Exhibit 2-7	Oil and Hazardous Materials Sites	2-9
Exhibit 2-8	Upper Cape Water Reserve	2-11
Exhibit 2-9	Historic Districts and Individual Historic Properties.....	2-12
Exhibit 2-10	Protected Open Space	2-15
Exhibit 2-11	Utilities	2-16
Exhibit 2-12	Environmental Justice Populations	2-17
Exhibit 2-13	MEMA Hurricane Evacuation Zones	2-18
Exhibit 2-14	Land Uses in the Study Area.....	2-20

Exhibit 2-15	Existing Land Uses and Environmental Resources – Belmont Circle	2-22
Exhibit 2-16	Existing Land Uses and Environmental Resources – Bourne Rotary	2-23
Exhibit 2-17	Major Roadways in the Study Area.....	2-34
Exhibit 2-18	Location of Automatic Traffic Recorders and Turning Movement Counts	2-41
Exhibit 2-19	Seasonal Traffic Volumes Differences on Canal Bridges.....	2-42
Exhibit 2-20	Location of BlueTOAD™ Units.....	2-44
Exhibit 2-21	Existing Non-Summer Average Daily and Peak Hour Traffic Volumes (AM/PM/Saturday)	2-47
Exhibit 2-22	Existing Summer Average Daily and Peak Hour Traffic Volumes (AM/PM/Saturday)	2-48
Exhibit 2-23	Existing Non-Summer AM Turning Movements.....	2-52
Exhibit 2-24	Existing Non-Summer Weekday PM Turning Movements.....	2-52
Exhibit 2-26	Existing Non-Summer Saturday Turning Movements.....	2-53
Exhibit 2-25	Existing Summer Weekday AM Turning Movements.....	2-53
Exhibit 2-27	Existing Summer Weekday PM Turning Movements.....	2-54
Exhibit 2-28	Existing Summer Saturday Turning Movements.....	2-54
Exhibit 2-29	Existing Non-Summer Levels of Service – AM/PM/Saturday Peak Hour (Freeway)	2-58
Exhibit 2-30	Existing Summer Levels of Service – AM/PM/Saturday Peak Hour (Freeway)	2-58
Exhibit 2-32	Existing Non-Summer Weekday PM Levels of Service (Intersections).....	2-59
Exhibit 2-31	Existing Non-Summer Weekday AM Levels of Service (Intersections).....	2-59
Exhibit 2-34	Existing Non-Summer Saturday Levels of Service (Intersections)	2-60
Exhibit 2-33	Existing Summer Weekday AM Levels of Service (Intersections)	2-60
Exhibit 2-35	Existing Summer Weekday PM Levels of Service (Intersections)	2-61
Exhibit 2-36	Existing Summer Saturday Levels of Service (Intersections)	2-61
Exhibit 2-37	Routing of Traffic Between Highway Corridors	2-63
Exhibit 2-38	Belmont Circle and Bourne Rotary Queue Lengths.....	2-65
Exhibit 2-39	Crashes in the Study Area	2-66
Exhibit 2-40	Pedestrian Facilities in the Focus Area	2-69

Exhibit 2-41	Pedestrian/Bicycle Travel Desire Routes over the Canal Bridges.....	2-71
Exhibit 2-42	Gaps in Pedestrian/Bicycle Connections to Canal Bike Path.....	2-72
Exhibit 2-43	Bicycle Facilities and Bus Routes in the Study Area	2-73
Exhibit 2-44	Cape Cod Regional Transit Authority (CCRTA) Annual Ridership	2-77
Exhibit 2-45	Cape Cod Regional Transit Authority (CCRTA) Fixed Route Ridership.....	2-78
Exhibit 2-46	Rest Area and Park & Ride Lots in Study Area	2-85

FUTURE NO-BUILD TRANSPORTATION CONDITIONS

Exhibit 3-1	Visitors as a Percent of Traffic on Cape Cod Canal Bridges CTPS Method	3-2
Exhibit 3-2	Future (2040) Non-Summer Average Daily and Peak Period Traffic Volumes (AM/PM/Saturday)	3-7
Exhibit 3-3	Future (2040) Summer Average Daily and Peak Period Traffic Volumes (AM/PM/Saturday)	3-7
Exhibit 3-4	Future (2040) Non-Summer Weekday AM Turning Movements.....	3-9
Exhibit 3-5	Future (2040) Non-Summer Weekday PM Turning Movements.....	3-10
Exhibit 3-6	Future (2040) Non-Summer Saturday Turning Movements.....	3-10
Exhibit 3-7	Future (2040) Summer Weekday AM Turning Movements.....	3-11
Exhibit 3-8	Future (2040) Summer Weekday PM Turning Movements.....	3-11
Exhibit 3-9	Future (2040) Summer Saturday Turning Movements.....	3-12
Exhibit 3-10	Future (2040) No-Build Non-Summer Levels of Service - AM/PM/Saturday (Freeway)	3-15
Exhibit 3-11	Future (2040) No-Build Summer Levels of Service - AM/PM/Saturday (Freeway)	3-15
Exhibit 3-12	Future (2040) No-Build Non-Summer Weekday AM Levels of Service (Intersections)	3-16
Exhibit 3-13	Future (2040) Non-Build Non-Summer Weekday PM Levels of Service (Intersections)	3-16
Exhibit 3-15	Future (2040) No-Build Non-Summer Saturday Levels of Service (Intersections)	3-17
Exhibit 3-14	Future (2040) No-Build Summer Weekday AM Levels of Service (Intersections)	3-17

Exhibit 3-16	Future (2040) No-Build Summer Weekday PM Levels of Service (Intersections)	3-18
Exhibit 3-17	Future (2040) No-Build Summer Saturday Levels of Service (Intersections)	3-18
Exhibit 3-18	Belmont Circle and Bourne Rotary - Future (2040) No-Build Queue Lengths	3-22
Exhibit 3-19	Problem Intersections in the Study Area	3-23
Exhibit 3-20	Photos of Problem Intersections	3-24

ALTERNATIVES DEVELOPMENT AND ANALYSIS

Exhibit 4-1	Scenic Highway/Meetinghouse Lane at Canal Road/State Road	4-7
Exhibit 4-2	Existing Conditions - Sandwich Road at Bourne Rotary Connector	4-10
Exhibit 4-3	Sandwich Road at Bourne Rotary Connector ...	4-12
Exhibit 4-4	Existing Conditions - Route 6A (Sandwich Road) at Cranberry Highway	4-14
Exhibit 4-5	Route 6A (Sandwich Road) at Cranberry Highway	4-16
Exhibit 4-6	Existing Conditions - Route 130 at Cotuit Road	4-18
Exhibit 4-7	Route 130 at Cotuit Road	4-20
Exhibit 4-8	Public-Private Partnership Design Alternatives	4-23
Exhibit 4-9	Route 25 to Route 6 Connector (Mid-Canal Bridge) - Environmental Impact	4-24
Exhibit 4-10	Route 25 to Route 3 Connector - Environmental Impact	4-24
Exhibit 4-11	Existing Conditions - Route 6 Exit 1C	4-27
Exhibit 4-12	Adjacent Land Uses - Route 6 Between Exit 1C and Exit 2 (Route 130)	4-28
Exhibit 4-13	Route 6 Exit 1C Relocation	4-31
Exhibit 4-14	Route 6 Exit 1C Ramp	4-31
Exhibit 4-15	Route 6 Exit 1C - Route 6A Intersection Alternatives	4-32
Exhibit 4-16	Route 6 Exit 1C at Route 6A/Route 130 Intersection - Suggested Alternative	4-37
Exhibit 4-17	Route 6 - Additional Eastbound Travel Lane and Westbound Auxiliary Lane	4-39
Exhibit 4-18	Belmont Circle - Existing Conditions	4-42
Exhibit 4-19	Suggested Improvements - Scenic Highway Westbound to Route 25 Westbound Ramp	4-43
Exhibit 4-20	Alternatives Evaluated - Belmont Circle	4-45
Exhibit 4-21	Belmont Circle - Suggested Alternative	4-50
Exhibit 4-22	Bourne Rotary - Existing Conditions	4-52
Exhibit 4-23	Alternatives Evaluated - Bourne Rotary	4-52

Exhibit 4-24	Bourne Rotary - Suggested Alternative	4-62
Exhibit 4-25	Bourne Rotary Interchange	4-63
Exhibit 4-27	Potential Cross Section - Bourne and Sagamore Bridge Replacements	4-67
Exhibit 4-26	Potential Alignment - Bourne and Sagamore Bridge Replacement	4-67
Exhibit 4-28	Location of Components of Travel Demand Model Cases	4-70
Exhibit 4-29	Case 1- Maximum Queue and Average Delay, Belmont Circle and Bourne Rotary	4-71
Exhibit 4-30	Case 1 - Maximum Queues and Average Delay, Sagamore Bridge Approaches	4-74
Exhibit 4-31	Case 1A - Maximum Queue and Average Delay, Belmont Circle and Bourne Rotary	4-77
Exhibit 4-32	Case 1B - Maximum Queue and Average Delay, Belmont Circle and Bourne Rotary	4-79
Exhibit 4-33	Case 2 - Maximum Queue and Average Delay, Belmont Circle and Bourne Rotary	4-82
Exhibit 4-34	Case 2B - Maximum Queue and Average Delay, Belmont Circle and Bourne Rotary	4-87
Exhibit 4-35	Case 3- Maximum Queue and Average Delay, Belmont Circle and Bourne Rotary	4-90
Exhibit 4-36	Case 3A - Maximum Queue and Average Delay, Belmont Circle and Bourne Rotary	4-92
Exhibit 4-37	Case 3A - Maximum Queue and Average Delay, Sagamore Bridge Approaches	4-94
Exhibit 4-38	Average Non-Summer Weekday and Summer Saturday Peak Period Delay, Belmont Circle and Bourne Rotary.....	4-98
Exhibit 4-39	Average Non-Summer Weekday and Summer Saturday Peak Period Delay, Sagamore Bridge Approaches.....	4-99
Exhibit 4-40	Preliminary Noise Analysis	4-105
Exhibit 4-41	Annual Vehicle Hours Savings (2040 Weekday AM/ PM Peak Periods)	4-108
Exhibit 4-42	Annual Vehicle Hours Savings (2040 Summer Saturday Peak Period)	4-109
Exhibit 4-43	Annual Vehicle Hour Savings (2040 All Trips).....	4-109
Exhibit 4-44	Annual Vehicle Hour Savings Compared to Annualized Costs.....	4-111
Exhibit 4-45	New Bicycle/Pedestrians Connections to Cape Cod Canal Bike Trail	4-115
Exhibit 4-46	Bicycle/Pedestrian Connections at Sagamore Bridge	4-118
Exhibit 4-47	Bicycle/Pedestrian Connections at Bourne Bridge	4-119
Exhibit 4-48	Park & Ride Lot, Route 6 Exit 2 (Route 130)	4-121

STUDY RECOMMENDATIONS

Exhibit 5-1	Alternatives Evaluation Matrix – Definition of Benefit and Impact Ratings.....	5-3
Exhibit 5-2	Evaluation Matrix – Comparison of Travel Analysis Model Cases.....	5-4
Exhibit 5-3	Recommended Local Intersection Equipment Improvements	5-7
Exhibit 5-4	Alternatives Evaluation Matrix – Definition of Benefit and Impact Ratings.....	5-8
Exhibit 5-5	Components of Case 3A – Recommended Gateway Intersection Improvements.....	5-10

TABLES

EXECUTIVE SUMMARY

Table ES-1	Historical Population Change in Barnstable County	10
Table ES-2	Growth in Average Daily Traffic (ADT) at Key Locations 2014 – 2040	18
Table ES-3	Future (2040) Year-Round Problem Intersections.....	21
Table ES-4	Components of Seven Travel Demand Analysis Cases	38
Table ES-5	Summary of Case Analysis for Queues, Delay, and LOS at Belmont Circle and Bourne Rotary.....	41
Table ES-6	Summary of Conceptual Cost Estimate by Location (\$ million)	43
Table ES-7	Summary of Conceptual Cost Estimate by Travel Model Case (\$ million).....	43
Table ES-8	Potential Environmental Impact by Location	44
Table ES-9	Potential Community and Property Impact by Location	44
Table ES-10	Components of Case 3A – Recommended Gateway Intersection Improvements	47
Table ES-11	Recommended Multimodal Transportation Improvements	49

INTRODUCTION AND STUDY FRAMEWORK

Table 1-1	Transportation Improvement Evaluation Criteria ..	1-9
Table 1-2	Invited Members of the Study Working Group.....	1-11
Table 1-3	Public Involvement Meetings.....	1-12

EXISTING ENVIRONMENTAL AND TRAFFIC CONDITIONS

Table 2-1	Historic Status of Resources Inventoried by the Massachusetts Historic Commission	2-14
Table 2-2	Historical Population Change in Barnstable County	2-24
Table 2-3	Change in Age Cohorts 2000–2017, Barnstable County	2-25
Table 2-4	Housing Units (2005–2015), Barnstable, Dukes, and Nantucket Counties and the Commonwealth of Massachusetts	2-26
Table 2-5	Median Household Income, 2017	2-27
Table 2-6	Per Capita Income, 2017	2-27
Table 2-7	Monthly 2017 Labor Force and Unemployment Data, Barnstable County	2-28
Table 2-8	Labor Force and Unemployment Data by Municipality, August 2017 Cape Cod and the Islands	2-29
Table 2-9	Mode of Commuter Transportation to Work in Barnstable County (2010–2017)	2-30
Table 2-10	Barnstable County Labor Force Commuting Off-Cape to Work (2010)	2-31
Table 2-11	Mortality and Hospitalization Rates in Barnstable County	2-32
Table 2-12	Population with Sad, Blue, or Depressed Feelings	2-32
Table 2-13	Population with Health Risk Factors in Barnstable County	2-33
Table 2-14	Suicide Rate in Barnstable County	2-33
Table 2-15	Level of Service (LOS) Criteria ¹	2-45
Table 2-16	Existing Average Daily Traffic Volumes and Peak Hour Traffic Volumes	2-49
Table 2-17	Comparison of Non-Summer and Summer Daily Traffic Volumes	2-51
Table 2-18	Existing Levels of Service for Freeway Sections	2-55
Table 2-19	Existing Levels of Service at Selected Intersections	2-57
Table 2-20	Belmont Circle - Existing (2014) Queue Lengths and Average Delay	2-64
Table 2-21	Bourne Rotary - Existing (2014) Queue Lengths and Average Delay	2-64
Table 2-22	Crashes in Study Area, 2012–2014	2-67
Table 2-23	Pedestrian and Bicycle Counts at Select Intersections	2-70
Table 2-24	Steamship Authority Ferry Ridership	2-82
Table 2-25	Steamship Authority Ridership - Monthly Trends 2014 to 2015	2-83

FUTURE NO-BUILD TRANSPORTATION CONDITIONS

Table 3-1	Future (2040) No-Build Average Daily Traffic and Peak Hour Traffic Volumes.....	3-5
Table 3-2	Growth in Average Daily Traffic (ADT) at Key Locations 2014 - 2040	3-9
Table 3-3	Future (2040) No-Build Levels of Service for Freeway Sections.....	3-13
Table 3-4	Future (2040) No-Build Levels of Service at Select Intersections.....	3-14
Table 3-5	Belmont Circle - Comparison of Existing (2014) and Future (2040) No-Build Queue Lengths and Average Delay.....	3-21
Table 3-6	Bourne Rotary - Comparison of Existing (2014) and Future (2040) No-Build Queue Lengths and Average Delay	3-21
Table 3-7	Growth in Average Daily Traffic (ADT) at Key Locations 2014 - 2040	3-23

ALTERNATIVES DEVELOPMENT AND ANALYSIS

Table 4-1	Future (2040) Year-Round Problem Intersections	4-4
Table 4-2	Working Group Submissions	4-6
Table 4-3	Traffic Operations - Scenic Hwy/Meetinghouse Lane at Canal Road/State Road	4-9
Table 4-4	Traffic Operations - Sandwich Road at Bourne Rotary Connector	4-13
Table 4-5	Traffic Operations - Route 6A (Sandwich Road) at Cranberry Highway	4-17
Table 4-6	Traffic Operations - Route 130 at Cotuit Road	4-19
Table 4-7	Route 25 to Route 6 Connector (Mid-Canal Bridge) - Environmental Impact	4-25
Table 4-8	Route 25 to Route 6 Connector - Environmental Impact	4-25
Table 4-9	Traffic Operations - Route 3 / Route 6 Approaches to Sagamore Bridge	4-30
Table 4-10	Traffic Operations - Existing and Future No-Build Conditions, Route 6A at Route 130	4-33
Table 4-11	Traffic Operations - Exit 1C Ramp at Route 6A/Route. 130, Two Signalized Intersection Alternative	4-34
Table 4-12	Exit 1C Ramp at Route 6A and Route 130, Roundabout Alternatives.....	4-35

Table 4-13	Potential Environmental Impact – Exit 1C Ramp at Route 6 and Route 130	4-36
Table 4-14	Relocation of Route 6 Exit 1C, Conceptual Cost Estimate.....	4-37
Table 4-15	Route 6 Eastbound Travel Lane – Conceptual Cost Estimate by Build Year	4-40
Table 4-16	Scenic Highway to Route 25 WB Ramp – Traffic Operations at Belmont Circle.....	4-44
Table 4-17	Scenic Highway to Route 25 WB Ramp – Conceptual Cost Estimate	4-44
Table 4-18	Belmont Circle Reconstruction, Traffic Operations – Comparison of Alternatives	4-47
Table 4-19	Belmont Circle – Comparison of Alternatives, Maximum Queue Length.....	4-48
Table 4-20	Belmont Circle Reconstruction – Environmental Impact by Alternative	4-49
Table 4-21	Belmont Circle Reconstruction – Conceptual Cost Estimate.....	4-50
Table 4-22	Bourne Rotary, Traffic Operations – Comparison of Alternatives, Veterans Way at Trowbridge Road	4-55
Table 4-23	Bourne Rotary, Traffic Operations – Comparison of Alternatives, Veterans Way at Old Sandwich Road	4-56
Table 4-24	Bourne Rotary, Traffic Operations – Comparison of Alternatives, Sandwich Road at Bourne Rotary Connector.....	4-57
Table 4-25	Bourne Rotary – Comparison of Alternatives, Maximum Queues Length	4-58
Table 4-26	Bourne Rotary – Environmental Impact by Alternative	4-61
Table 4-27	Bourne Rotary Reconstruction – Conceptual Cost Estimates	4-61
Table 4-28	Traffic Operations – Bourne Rotary Interchange	4-64
Table 4-29	Bourne Rotary Interchange – Potential Property or Environmental Impact.....	4-64
Table 4-30	Bourne Rotary Interchange – Conceptual Cost Estimate by Build Year	4-65
Table 4-31	Components of the Seven Travel Analysis Cases	4-69
Table 4-32	Case 1 – Future (2040) Traffic Operations, Belmont Circle and Bourne Rotary	4-73
Table 4-33	Case 1 Traffic Operations, Sagamore Bridge Approaches.....	4-74
Table 4-34	Case 1A – Future (2040) Traffic Operations, Belmont Circle and Bourne Rotary	4-76
Table 4-35	Case 1B – Future (2040) Traffic Operations, Belmont Circle and Bourne Rotary	4-80

Table 4-36	Case 2 – Future (2040) Traffic Operations, Belmont Circle and Bourne Rotary	4-83
Table 4-37	Case 2B – Future (2040) Traffic Operations, Belmont Circle and Bourne Rotary	4-86
Table 4-38	Case 3 – Future (2040) Traffic Operations, Belmont Circle and Bourne Rotary	4-89
Table 4-39	Case 3A – Future (2040) Traffic Operations, Belmont Circle and Bourne Rotary	4-93
Table 4-40	Case 3A – Future (2040) Traffic Operations, Sagamore Bridge Approaches	4-94
Table 4-41	Summary of Case Analysis for Queues, Delay, and LOS at Belmont Circle and Bourne Rotary	4-97
Table 4-42	Summary of Conceptual Cost Estimate by Location	4-112
Table 4-43	Summary of Conceptual Cost Estimate by Case	4-112
Table 4-44	Potential Environmental, Community, and Property Impact by Location	4-113
Table 4-45	Potential Environmental, Community, and Property Impact by Case	4-114
Table 4-46	Route 6 Exit 2 Park and Ride Lot – Conceptual Cost Estimate by Build Year	4-121

STUDY RECOMMENDATIONS

Table 5-1	Components of Case 3A – Recommended Gateway Intersection Improvements	5-9
Table 5-2	Recommended Multimodal Transportation Improvements	5-13