9th Edition Stretch Code Modeling Analysis

2000 sq.ft. 3 BR Family Townhome with Natural Gas Heat Worcester, MA





HERS Index	
Target	55
Example Base	58
Example Stretch	50

Incremental Costs and Benefits to Meet Stretch Code 0.26% of Total Construction Cost⁴

mple Stretch 50	COSTS		BENEFITS	NET	
	Adjustments + HERS Rater Fee		Utility Rebates ¹	Cost Compared to Base Code	
BUILDER	-\$2,411		+\$1,332	-\$1,079	
HOMEBUYER	Change to Downpayment ³	Change to Annual Mortgage Payment ³	Estimated Reduced Energy Cost per Year ²	Year 1 Cash Flow	Year 2+ Cash Flow
	-\$108	-\$86	+\$138	-\$56	+\$52

- 1 Incentives are determined using the Pay For Savings calculator. Savings compared to MA reference home. PFS Incentive = \$0.50 * kWh savings + \$50 * MMBtu savings + \$4000 * 0.xx percent savings (single family home)
- 2 Energy costs are based on \$0.25/kWh, \$1.21/therm, \$2.90/gal propane, \$2.88/gal oil. Savings are compared with Base Code home.
- 3 30-year mortgage assumes 10% down payment at 4% APR.
- 4 NAHB New Contractor Built Median Cost Per Square Foot in North East US (2017) \$161.53



9th Edition Stretch Code Modeling Analysis 2000 sq.ft. 3 BR Family Townhome with Natural Gas Heat Worcester, MA





Breakdown of Incremental Construction Costs to Meet Stretch Code

FEATURE	Base Code	Stretch Code	Construction Cost
HERS RATING	58	50	\$500
WINDOWS (U- VALUE/SHGC)	.30/.30 .27/.30		\$500
HEATING	95% gas furnace	96% gas furnace	\$295
COOLING	13 SEER	15 SEER	\$392
DHW	0.62 EF 40 Gallon tank Gas	0.96 EF Tankless Gas	\$724
DUCT LEAKAGE TO OUTSIDE	4 CFM25 / 100 CFA	2 CFM25 / 100 CFA	\$0
HIGH EFFICACY LIGHTING	100% LED	No change required	\$0
AIR INFILTRATION	3.0 ACH50	No change required	\$0
FOUNDATION	Unconditioned, uninsulated basement	No change required	\$0
FLOOR	R38 fiberglass Grade 1	No change required	\$0
WALLS	R21 fiberglass Grade 1	No change required	\$0
CEILING – FLAT	R-50 blown in cellulose	No change required	\$0
TOTAL			\$2,411



