

## NORFOLK COUNTY SUPERIOR COURT HVAC SYSTEM EVALUATION SUMMARY

Visited September 22, 2020. While on site, inspected the air handling equipment located in the mechanical rooms and on the roof, and toured the facility to determine if the spaces generally matched usages noted on the plans. The Norfolk County Superior Courthouse is a National Historic Landmark at 650 High Street in Dedham, Massachusetts.

The building has granite walls, with two above-grade stories and an occupied basement. There are two large attic spaces and a central dome that contain many duct risers that are no longer active or functional.

#### 1.0 Airflow Rate per Person (Reduced Occupancy)

		Total Air		Outdo	or Air
Courtroom	Total People	Supply Airflow (CFM)	Airflow Rate (CFM/Person)	Outside Airflow (CFM)	Airflow Rate (CFM/Person)
Grand Jury	16	1,200 75 510		510	32
Jury Pool	23	Unknown	-	Unknown	
Courtroom 3	16	Unknown	-	Unknown	-
Courtroom 8	12	Unknown	-	Unknown	-
Courtroom 10	20	Unknown	-	Unknown	-
Courtroom 20	24	Unknown	-	Unknown	-
Courtroom 25	23	Unknown	-	Unknown	-
Main Courtroom	76	Unknown	-	Unknown	-

#### 2.0 Recommendations

Section	Recommendation/Finding	Action
2.1	Filtration Efficiency	
RF-1	Replace filters with a MERV-13 filter.	Complete
RE-3	Install a differential pressure sensor across the filter bank.	N/A
2.2	Testing and Balancing	
RTB-1	Test and rebalance air handling unit supply air and minimum outside air flow rates	N/A
RTB-3	Increase outside air flow rate beyond minimum under non-peak conditions.	N/A
2.3	Equipment Maintenance and Upgrades	
RE-2	Clean air handler coils.	N/A
2.4	Control System	
RC-1	Implement a pre and post-occupancy flush sequence	N/A
RC-2	Install controls required to introduce outside air beyond the minimum requirements.	N/A
<b>1</b>   P a g e	6 / 2 5 / 2 0 2 1	

2.5	Additional Filtration and Air Cleaning	
RFC-1	Install portable HEPA filters – if courthouse is to operate at a high occupancy (i.e. 50-75% or greater), install portable HEPA filters in high traffic areas.	In-progress
2.6	Humidity Control	
	Installing portable humidifiers and dehumidifiers is not recommended unless high-risk employees are present	On-going
2.7	Other Recommendations	
2.7.1	Run Ventilation Fans Continuously During Occupied Hours	On-going
2.7.2	Repair and Recommission Energy Recovery Ventilators	N/A
2.7.3	Refurbish or Replace Ventilation Systems	In-progress
2.7.4	Repair or Replace Toilet Exhaust Fans and Controls	In-progress
2.7.5	Install a Building Management System	Deferred – included in 5 year Capital Plan



Norfolk County Superior Court Dedham, MA

## HVAC SYSTEM EVALUATIONS COVID-19

Office of Court Management

February 1, 2021

# Tighe&Bond

100% Recyclable 🚺

## Section 1 Existing Conditions & Site Observations

Tighe & Bond visited the Norfolk County Superior Court on September 22, 2020. While on site we inspected the air handling equipment located in the mechanical rooms and on the roof, and toured the facility to determine if the spaces generally matched usages noted on the plans.

Site Visit Attendees:

- Office of Court Management:
  - Mike Mullen, Scott Arneil, and Mike Ostman
- Tighe & Bond
  - Todd Holland, PE, Senior Mechanical Engineer
  - Timothy Bill, PE, Project Mechanical Engineer

### **1.1 Existing Ventilation System**

The Norfolk County Courthouse is a National Historic Landmark at 650 High Street in Dedham, Massachusetts. The building has granite walls, with two above-grade stories and an occupied basement. There are two large attic spaces and a central dome that contain many duct risers that are no longer active or functional.

The Registry of Deeds is located directly across the street, also of granite construction, and has two above-grade stories and a basement.

The mechanical plans and other documentation available to us were minimal. Most of our observations and recommendations are based on the walk through and subsequent discussion with facilities personnel.

### **Courthouse:**

Most spaces in the courthouse have steam perimeter convection heat and wall-mounted mini-split systems for cooling. There are no active central air or mechanical ventilation systems.

The windows have operable sashes and are in good condition. Most of the larger interior spaces have transom windows over the doors.

There are many small toilet rooms in the courthouse with dedicated exhaust fans, some of which are not in working condition. The exhaust fans are either separately switched or switched with the lights.

A project in 2002 to improve indoor air quality (IAQ) installed two energy recovery units (ERUs) to exhaust air from and supply outdoor air (OA) to occupied non-mechanical areas in the basement. Each of these systems provides approximately 1,500 cfm, has a 5-kW electric heater, 2" MERV-8 filters, and total energy wheel that recovers heat and humidity

Norfolk County Superior Court HVAC System Evaluation – COVID 19 from outgoing exhaust air. Each unit has a 4-ton cooling coil with split condensing units outside on grade. According to staff, the cooling coils are no longer functional, and the ERUs are no longer used.

The antiquated ventilation systems serving many rooms on the first and second floors consists of a pair of wall-mounted cast iron grilles, one low and one high, with a damper in the high grille with chain pulls marked "open" and "shut". In most rooms there is a third grille mounted to the side, part way up the wall. Some of these provide passive ventilation, as evidenced by dust collecting on the grille face. At least one of the three grilles has a duct that extends to the attic space, where the original ducts were capped with goosenecks and bird screens. The attic space is ventilated by louvers on the gable ends, covered by plenum boxes with manual control dampers. The goosenecks have all been removed and abandoned, leaving the ducts open to the attic space. Most of these ducts have been used to run electrical conduit, network cable, piping, or condensate piping from the mini-split systems.

This ventilation system, likely original to the 1825 building, has been abandoned and compromised for decades, and it would take a very substantial effort to understand and refurbish, or to replace with a new system.

Table 1 summarizes the heat recovery units' designed airflow rates, the MERV rating of the installed filters, and the condition, based on a review of design documentation, nameplate data, and visual inspection.

#### TABLE 1

Design Design Unit Airflow Min. O.A. Condition Filters (CFM) (CFM) Non-ERU-1 1,500 1,500 2", MERV-8 functional Non-ERU-2 2", MERV-8 1,450 1,450 functional

Existing Air Handling Units in Courthouse

### **Registry:**

Most spaces in the Registry of Deeds have steam perimeter radiation and wall-mounted mini-split systems for cooling.

There are several older ducted heating and ventilating systems with steam coils. These are abandoned in place, and there is no opportunity for refurbishing or recommissioning them. Some toilet rooms have local exhaust fans, but not all of them.

There are four air handlers in the building. One system serves the Engineering area (east wing) in the basement, is a cooling-only system, and has no outdoor air supply.

A rooftop unit (RTU) with electric DX cooling and gas heat serves the 1975 Probate Court addition. It was not running at the time of the visit, likely because space temperature was satisfied. This constant volume unit has a fixed outdoor air intake. It is a replacement for the original 5-ton Mammoth unit that had 20-kW electric heat.

Two 10-ton air handlers in an attic mechanical space serve the main records hall, and these were not running because space temperatures were satisfied. These constant volume units have fixed outdoor air volumes via 12" round ducts with dampers. Air-cooled condensing units are mounted on the adjacent roof of the Probate Court addition.

Code requires for ventilation to be provided during the periods that the room or space is occupied. The fans in these units should operate continuously during occupied hours, and not set to "auto" which turns the fans off when cooling or heating is not active.

Table 2 summarizes the air handling units' designed airflow rates, the MERV rating of the installed filters, and the condition, based on a review of design documentation, nameplate data, and visual inspection.

Existing Air Handling Units in Registry								
Unit	Design Airflow (CFM)	Design Min. O.A. (CFM)	Filters	Condition				
Engineering	2,000	0	1″, MERV unknown	Good				
RTU	1,900	Unknown	2", MERV-8	Good				
AHU-1	4,000	Unknown	2", MERV-8	Good				
AHU-2	4,000	Unknown	2", MERV-8	Good				

#### TABLE 2

### **1.2 Existing Control System**

There is no central Building Management System (BMS) or centralized controls in either building. Honeywell T7300A programmable thermostats are used as seven-day programmable timeclocks to start and stop several of the systems.

## Section 2 Recommendations

Below is a list of recommendations that we propose for the Norfolk County Superior Court . Please refer to the "Master Recommendation List" for further explanation and requirements of the stated recommendations.

### 2.1 Filtration Efficiency Recommendations

We recommend the following measures be implemented the existing air handling units in both buildings:

**RF-1:** Replace filters with a MERV-13 filter.

TAB Contractor and/or Engineer shall verify that the rooftop unit and air handlers can accommodate MERV-13 filters.

**RF-3:** Install a differential pressure sensor across the filter bank.

### 2.2 Testing & Balancing Recommendations

The RTU serving the Probate Court was installed in 2016, and the AHUs serving the Records Hall were installed in 2012. It is unknown to Tighe & Bond if the units were tested and balanced, or the actual rates of the fixed outdoor air flows.

The ASHRAE climatic data for outdoor air conditions in Norwood state a summer design condition of 90.6°F/73.5°F DB/WB and a winter condition of 3.1°F. We recommend the following measures be implemented:

**RTB-1:** Test and rebalance air handling unit supply, return, and minimum outside air flow rates.

We recommend rebalancing the air handler outside airflow rates to the values shown in Tables 3 and 4. The units' cooling capacities should be able to provide adequate leaving air conditions similar to the original design under peak outdoor air conditions, assuming the cooling coils are clean and their performance has not degraded significantly over time.

TABLE 3           Courthouse - Recommended Air Handler OA Flow Rates								
Unit	Supply Airflow (CFM)	Design Min. OA (CFM)	2015 IMC Min. OA Requirements (CFM)	Recommended Minimum OA (CFM)				
ERU-1	1,500	1,500	296	1,500				
ERU-2	1,450	1,450	184	1,450				

Note: Although the ASHRAE Position Document on Infectious Aerosols recommends using the latest published standards and codes as a baseline for minimum ventilation, the mechanical code in effect at the time the HVAC systems were designed and constructed is what governs the required outdoor air flowrate for the HVAC equipment, if there have been no additions, renovations, alterations or changes in occupancy to the building. The 2015 International Mechanical Code does not prevent the continued use of existing systems.

#### TABLE 4

Registry - Recommended Air Handler OA Flow Rates

Unit	Supply Design Airflow Min. OA (CFM) (CFM)		2015 IMC Min. OA Requirements (CFM)	Recommended Minimum OA (CFM)		
Engineering	2,000	Unknown	170	340		
RTU	1,900	Unknown	510	510		
AHU-1	4,000	Unknown	480	800		
AHU-2	4,000	Unknown	480	800		

Note: Although the ASHRAE Position Document on Infectious Aerosols recommends using the latest published standards and codes as a baseline for minimum ventilation, the mechanical code in effect at the time the HVAC systems were designed and constructed is what governs the required outdoor air flowrate for the HVAC equipment, if there have been no additions, renovations, alterations or changes in occupancy to the building. The 2015 International Mechanical Code does not prevent the continued use of existing systems.

The recommended OA volume above code levels will serve as makeup air for toilet exhaust.

The unit serving Engineering is cooling-only, and will need a source of heat for winter operation to temper the air. This can be done by adding an electric resistance coil (approximately 5 kW), or by replacing the condensing unit with a heat pump unit, along with the appropriate controls, refrigerant piping, and accessories.

Although the AHUs serving the Records Hall do not have heat, the high ceilings and high capacity of the steam perimeter radiation should easily handle the heating load. Facilities personnel indicated that the space is usually too warm.

The airflow rate per person is shown below in Tables 5 and 6. These values are based on the recommended outdoor airflow and the original design supply airflow rates shown in Tables 3 and 4 above.

#### TABLE 5

Courthouse Basement - Airflow Rate per Person								
	Average for		Non-Courtroom					
	all spaces	Courtrooms	Spaces					
	(CFM/Person)	(CFM/Person)	(CFM/Person)					
Total Supply Air	0-48	N/A	0-60					
Outdoor Air	0-48	N/A	0-60					

The airflow rate per person for each Courtroom and the Jury Pool Room is shown below in Table 6. These values are based on full occupancy without taking diversity into account, the original full design supply airflow rate, and the recommended outdoor airflow rate. The airflow rate per person assumes the full supply airflow is being delivered to the room. Note that the Grand Jury and Jury Pool Rooms are located in the Registry Building.

#### TABLE 6

Airflow Rate per Person (Full Occupancy)

		Total Air		Out	door Air
Courtroom	Total People	Supply Airflow (CFM)	Airflow Rate (CFM/Person)	Outside Airflow (CFM)	Airflow Rate (CFM/Person)
Grand Jury	29	1,200	42	510	18
Jury Pool Room	36	Unknown	-	Unknown	-
Courtroom 3	93	Unknown	-	Unknown	-
Courtroom 8	41	Unknown	-	Unknown	-
Courtroom 10	109	Unknown	-	Unknown	-
Courtroom 20	56	Unknown	-	Unknown	-
Courtroom 25	78	Unknown	-	Unknown	-
Main Courtroom	181	Unknown	-	Unknown	-

The airflow rate per person for each Courtroom and the Jury Pool Room, based on a reduced occupancy schedule determined by the Office of Court Management, is shown below in Table 6a. The airflow rate per person assumes the full supply airflow is being delivered to the room. At times when the supply airflow is reduced due to the space temperature being satisfied, the airflow rate per person will also be reduced. **TABLE 6a** 

#### Airflow Rate per Person (Reduced Occupancy) Total Air **Outdoor Air** Outside Supply Total Airflow Airflow Rate Airflow Airflow Rate (CFM) (CFM) (CFM/Person) Courtroom People (CFM/Person) Grand Jury 75 16 1,200 510 32 23 Unknown Jury Pool Room Unknown Courtroom 3 16 Unknown Unknown Courtroom 8 12 Unknown Unknown Courtroom 10 20 Unknown Unknown Courtroom 20 24 Unknown Unknown Courtroom 25 23 Unknown Unknown Main Courtroom 76 Unknown Unknown

Note: If occupancy is further reduced, the airflow rate per person will increase, assuming full airflow is being delivered to the space.

**RTB-3**: *Increase outside air flow rate beyond minimum under non-peak conditions.* We recommend increasing the outdoor air flow rate per Table 3. We do not believe this would run the risk of high humidity in summer or cold temperatures in winter, based on our calculation of discharge air temperatures.

### 2.3 Equipment Maintenance & Upgrades

We recommend the following equipment maintenance and upgrades for the units in both buildings:

**RE-2:** Clean air handler coils and drain pans.

### 2.4 Control System

The Norfolk County Superior Court buildings have local control systems with limited functionality. We recommend the following control system strategies be implemented into the existing control systems:

Run supply fans continuously during occupied hours to provide mechanical ventilation, per Section 2.7, Other Recommendations.

**RC-1:** Implement a pre-occupancy flush sequence.

**RC-2:** Install controls required to introduce outside air beyond the minimum requirements.

### 2.5 Additional Filtration and Air Cleaning

We recommend the installation of the following air cleaning devices:

Norfolk County Superior Court HVAC System Evaluation – COVID 19 **RFC-1:** Install portable HEPA filters.

If the Courthouse is to operate at a high capacity (i.e. 50%-75% occupancy or greater), we recommend installing portable HEPA filters in high traffic areas, such as entrance lobbies, and occupied spaces that do not have mechanical ventilation systems. They should be considered for courtrooms, jury rooms, offices, and the holding cells. Noise levels will be a concern in the courtrooms, and will vary depending on the manufacturer, size of the unit, and whether it can be run at low or medium speed.

### 2.6 Humidity Control

Installing portable humidifiers and dehumidifiers is not recommended unless there are high risk employees who cannot work remotely and are required to be in the courthouse.

### 2.7 Other Recommendations

#### 2.7.1 Run Ventilation Fans Continuously During Occupied Hours

The systems that provide ventilation air to the Registry were not operating during our visit, presumably because the weather was mild, occupancy was low, and space temperatures were satisfied. We strongly recommend running the supply fans continuously during occupied hours to provide mechanical ventilation, as code requires. Further system analysis and improvements are required to execute this recommendation.

### 2.7.2 Repair and Recommission Energy Recovery Ventilators

The non-operational ERUs serving the courthouse basement areas should be repaired, refurbished, cleaned, and recommissioned. The DX coils and/or condensing units should be repaired or replaced as required. If these units are replaced, heat pumps should be considered to provide heat with much greater efficiency than the existing electric resistance coils, which could remain as backup.

#### 2.7.3 Refurbish or Replace Ventilation Systems

The decommissioned and abandoned courthouse ventilation systems should be refurbished, enhanced, and recommissioned. It is possible that the existing grilles and duct risers could be reused, with the attic space housing direct outdoor air systems (DOAS) with heat recovery for efficiency and MERV-13 filters for IAQ.

This effort would start with understanding how the original systems were designed and operated, and would then require a substantial and invasive construction project. The existing ducts would have to be cleared of electrical, data, telephone, plumbing, and other utilities that have been routed through them over the decades. The ducts would also need to be cleaned and sealed. These utilities would have to be rerouted elsewhere or new duct systems would have to be installed. Due to the constraints of the existing building construction, adding new ductwork may be difficult. New ducts may need to be run to ensure adequate ventilation effectiveness, so that inlets and outlets are not too close together.

#### 2.7.4 Repair or Replace Toilet Exhaust Fans and Controls

All of the toilet rooms in both buildings should have dedicated working exhaust fans, properly sized, with suitable controls. Toilet exhaust fans should be sized at 70 cfm per fixture in heavy use areas, such as those with public access. They can be sized at 50 cfm for single-person occupancy if they are run continuously during occupied hours. If toilet exhaust fans are controlled with the lights, we recommend using a switch with auxiliary contacts for the fan and a time delay, to run the fan for an interval, 10 minutes for example, after the lights are shut off.

If new ventilation systems are considered for the Courthouse, it would be ideal if toilet exhaust was routed through the heat recovery systems. However, because of the number and location of small toilet rooms, it may not be practical to route all toilet exhaust to a few central locations.

#### 2.7.5 Install a Building Management System

We recommend installing a BMS to schedule, control, and monitor equipment. The local control systems are antiquated and do not offer the same benefits as a BMS.

A BMS for each building could also be used to control and schedule other pieces of equipment such as boilers and mini-split systems. If it is desired to control only the air handling systems, less complex programmable controllers that are web-accessible may be able to provide the benefits of a BMS at a lower cost.

## Section 3 Testing & Balancing Results

On November 10, 2020 Milharmer Associates, Inc. visited the Norfolk County Superior Court to test the airflow rates of the air handling units. The Office of Court Management's Automatic Temperature Controls (ATC) Contractor was also on site to assist in the balancing process. A summary of the tested airflow rates versus the design airflow rates are shown below in Table 7. Their full testing and balancing report is attached.

#### TABLE 7

Air Handler Testing & Balancing Results (Courthouse)

		Design	Actual				
Unit	Total Supply Fan Recommended Airflow Outdoor (CFM) Airflow (CFM)		Exhaust Fan Airflow (CFM)	Supply Fan Airflow (CFM)	Outdoor Airflow (CFM)	Exhaust Fan Airflow (CFM)	
ERU-1	1,500	1,500	1,500	1,599	1,599	1,623	
ERU-2	1,500	1,500	1,500	1,384	1,384	1,505	

Both energy recovery units are operating with acceptable airflow ranges for both the supply and exhaust fans. According to the TAB report, these units have adequate capacity to increase the efficiency of the air filters, as the motors are approximately 62% loaded. It should be noted that the cooling coils for these units are no longer functional, and the ERUs are no longer used.

#### TABLE 8

Air Handler Testing & Balancing Results (Registry of Deeds)

		Design	Actual					
Unit	Total Supply Fan Airflow (CFM)	Recommended Outdoor Airflow (CFM)	Return Recommended Fan Outdoor Airflow Airflow (CFM) (CFM)		Outdoor Airflow (CFM)	Return Fan Airflow (CFM)		
RTU	1,900	510	1,390	1,108	413	695		
AHU-1	4,000	800	3,200	3,761	255	3,506		
AHU-2	4,000	800	3,200	3,955	234	3,721		

The rooftop unit serving the Probate Court is operating at only a fraction of the design supply airflow. The outdoor air (OA) flow rate is below the 2015 IMC minimum requirements and recommended minimum in Table 4. These airflow shortfalls are significant, more than 40% on supply and about 20% for OA. Not only does that affect ventilation rates, it likely adversely affects the performance and reliability of the cooling and heating equipment from short cycling.

Both air handlers serving the Records Hall are operating with acceptable airflow ranges for both the supply and return fans. However, OA flow rates are significantly below the 2015 IMC minimum requirements and recommended minimums in Table 4. The TAB report states that the OA could be increased slightly because the OA dampers were not 100% open during the test.

According to the TAB report, these units have adequate capacity to increase the efficiency of the air filters, as the motors are approximately 72% loaded.

The Engineering air handling unit was not tested since it does not provide any outdoor air.

### Disclaimer

Tighe and Bond cannot in anyway guarantee the effectiveness of the proposed recommendations to reduce the presence or transmission of viral infection. Our scope of work is intended to inform the Office of Court Management on recommendations for best practices based on the guidelines published by ASHRAE and the CDC. Please note that these recommendations are measures that may help reduce the risk of airborne exposure to COVID-19 but cannot eliminate the exposure or the threat of the virus. Implementing the proposed recommendations will not guarantee the safety of building occupants. Tighe & Bond will not be held responsible should building occupants contract the virus. The Office of Court Management should refer to other guidelines, published by the CDC and other governing entities, such as social distancing, wearing face masks, cleaning and disinfecting surfaces, etc. to help reduce the risk of exposure of COVID-19 to building occupants.

J:\M\M1671 Comm. of MA Court system\011 - COVID-19 Courthouse Evaluations\Report\_Evaluation\Draft Reports\Norfolk Court and Registry\Norfolk Courthouse and Registry Summary.docx

MILHARMER ASSOCIATES, INC.
534 New State Highway, Route 44, Suite 3
Raynham, MA 02767

Tel.: 508-823-8500; Facsimile: 508-823-8600



## **TEST AND BALANCE REPORT**

Project:

### **Norfolk Superior Court House**

650 High St Dedham, MA

Project No.:

20-549

Project Date: 11/10/2020

**MECHANICAL CONTRACTOR** 

Tighe & Bond



A N.E.B.B. Certified Company



FOR THE NEBB BOARD OF DIRECTORS Testing, Adjusting and Balancing of Environmental Systems A-ALCC gyfury Schoole NEBB President-Elect **NEBB** President HAS MET ALL REQUIREMENTS FOR NEBB CERTIFICATION IN THE FOLLOWING DISCIPLINE Milharmer Associates, Inc. THIS IS TO CERTIFY THAT Certification **NEBB** Certification Number March 31, 2021 **Expiration Date** 3384

n Board sional	0Y	EMENTS FOR L STATUS IN	rvíronmental Systems	Firm and associated NEBB Certification ation in the NEBB Quality Assurance NEBB Certified Firm.	Ruchard Fant	V NEBB Certification Board Chairman	lymenia device	NEBB Certification Director	tion Board Policy Manual governs use of this certificate.
NEBB Certification NEBB Certified Profession	Scott F. Miller	HAS MET ALL THE NEBB REQUIREN NEBB CERTIFIED PROFESSIONAL	Testing, Adjusting and Balancing of Env	This Certificate, as well as individual affiliation with a NEBB Certified Firm Stamp are REQUIRED to provide a NEBB Certified Report. Participatio Program requires the Certificant be affiliated with a NEB	March 31, 2021	Expiration Date	23541	NEBB Certificant Number	The NEBB Certification Board retains sole ownership of all certificates. The NEBB Certification l

Project: Address: Date:	Norfolk Superior Co 650 High St Dedha 11/10/2020	ourt House m, MA <b>Project No.</b>	20-549
	TABLE OF CO	NTENTS	
SECTION 1	TAE A. 1 B. 1 C. 1 D. 1 E. 5	B Qualifications N.E.B.B. Certification N.E.B.B. Company Certificate N.E.B.B. Supervisor Certificate nstrument Sheet Symbol Sheet	
SECTION 2	2 <b>TAE</b>	3 Building Systems	

	Norfolk Superior Court House		
Address:	650 High St Dedham, MA		
Date:	11/10/2020	Project No.	20-549
	INSTRUM	MENT SHEET	
The following is	s a list of Instruments owned and operated by	Milharmer Associates. Inc. and used	lon
this project.			
Instrument	Instrument	Calibration	Calibration
Instrument ID Number	Instrument	Calibration Date	Calibration Due Date
Instrument ID Number 1	Instrument ADM-870 Digital Multimeter	Calibration Date 8-20-20	Calibration Due Date 8-20-21
Instrument ID Number 1 2	Instrument ADM-870 Digital Multimeter Shortridge Flow Hood	Calibration           Date           8-20-20           8-20-20	Calibration Due Date 8-20-21 8-20-21
Instrument ID Number 1 2 3	Instrument ADM-870 Digital Multimeter Shortridge Flow Hood Ampmeter	Calibration           Date           8-20-20           8-20-20           8-20-20	Calibration Due Date 8-20-21 8-20-21 8-20-21
Instrument ID Number 1 2 3 4	Instrument ADM-870 Digital Multimeter Shortridge Flow Hood Ampmeter Tachometer	Calibration           Date           8-20-20           8-20-20           8-20-20           8-20-20           8-20-20           8-20-20	Calibration Due Date 8-20-21 8-20-21 8-20-21 8-20-21
Instrument ID Number 1 2 3 4 5	Instrument         ADM-870 Digital Multimeter         Shortridge Flow Hood         Ampmeter         Tachometer         Airflow Anemometer	Calibration           Date           8-20-20           8-20-20           8-20-20           8-20-20           8-20-20           8-20-20           8-20-20           8-20-20	Calibration Due Date 8-20-21 8-20-21 8-20-21 8-20-21 8-20-21 8-20-21
Instrument ID Number 1 2 3 4 5 5 6	Instrument ADM-870 Digital Multimeter Shortridge Flow Hood Ampmeter Tachometer Airflow Anemometer Digital Thermometers	Calibration           Date           8-20-20           8-20-20           8-20-20           8-20-20           8-20-20           8-20-20           8-20-20           8-20-20           8-20-20           8-20-20           8-20-20	Calibration Due Date 8-20-21 8-20-21 8-20-21 8-20-21 8-20-21 8-20-21 8-20-21
Instrument ID Number 1 2 3 4 5 6	InstrumentADM-870 Digital MultimeterShortridge Flow HoodAmpmeterTachometerAirflow AnemometerDigital Thermometers	Calibration           Date           8-20-20           8-20-20           8-20-20           8-20-20           8-20-20           8-20-20           8-20-20           8-20-20           8-20-20           8-20-20           8-20-20	Calibration Due Date 8-20-21 8-20-21 8-20-21 8-20-21 8-20-21 8-20-21 8-20-21
Instrument ID Number 1 2 3 4 5 6 6 7	Instrument ADM-870 Digital Multimeter Shortridge Flow Hood Ampmeter Tachometer Airflow Anemometer Digital Thermometers Shortridge Water Meter	Calibration         Date         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20	Calibration Due Date 8-20-21 8-20-21 8-20-21 8-20-21 8-20-21 8-20-21 8-20-21
Instrument ID Number 1 2 3 4 5 6 7	Instrument ADM-870 Digital Multimeter Shortridge Flow Hood Ampmeter Tachometer Airflow Anemometer Digital Thermometers Shortridge Water Meter	Calibration         Date         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20	Calibration Due Date 8-20-21 8-20-21 8-20-21 8-20-21 8-20-21 8-20-21 8-20-21 8-20-21
Instrument ID Number 1 2 3 4 5 6 6 7 7 8	Instrument ADM-870 Digital Multimeter Shortridge Flow Hood Ampmeter Tachometer Airflow Anemometer Digital Thermometers Shortridge Water Meter Sound Meter	Calibration         Date         0       8-20-20         8-20-20       8-20-20         8-20-20       8-20-20         8-20-20       8-20-20         8-20-20       8-20-20         8-20-20       8-20-20         8-20-20       8-20-20         8-20-20       8-20-20         8-20-20       8-20-20         8-20-20       8-20-20         8-20-20       8-20-20         8-20-20       8-20-20	Calibration Due Date 8-20-21 8-20-21 8-20-21 8-20-21 8-20-21 8-20-21 8-20-21 8-20-21
Instrument ID Number 1 2 3 4 5 6 7 7 8	Instrument ADM-870 Digital Multimeter Shortridge Flow Hood Ampmeter Tachometer Airflow Anemometer Digital Thermometers Shortridge Water Meter Sound Meter	Calibration         Date         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20         8-20-20	Calibration Due Date 8-20-21 8-20-21 8-20-21 8-20-21 8-20-21 8-20-21 8-20-21 8-20-21

Please Note: Instruments are tested annually at the M.A.I. Lab. and sent back to the factory if deviation exceeds manufacturing tolerance.

Technician:

### SYMBOL SHEET

AHU	Air Handling Unit	HEATER O.L.	Thermal Overload
AC or ACU	Air Conditioner Unit		Protection For Motors
ACCU	Air Cooled Condensing Unit		Located at Starter Motor
ADJ P.D.	Adjusted Pitch Diameter		
AMP	Amperage	HEPA	High Efficiency Particulate
AVG	Average		Arrestance
A.D.	Air Density	HOA	Hand/Off/Auto Switch
		H.P.	Horsepower
B.H.P.	Brake Horsepower	HPS	High Pressure Steam
		HRC	Heat (Recovery or Recliam) Coil
CFM	Cubic Feet Per Minute	HVAC	Heating, Ventilation and
СН	Chiller		Air Conditioning
CHWR	Chilled Water Return	HWR	Hot Water Return or
CHW or CHWS	Chilled Water Supply		Heating Water Return
СТ	Cooling Tower	HWS	Hot Water Supply or
CWR	Condenser Water Return		Heating Water Supply
CW or CWS	Condenser Water Supply	HX	Heat Exchanger
DB	Dry Bulb	I.D.	Inside Diameter
D.D.	Direct Drive		
DIA	Diameter	LAT	Leaving Air Temperature
		L.D.	Linear Supply Diffuser
EAT	Entering Air Temperature	LPS	Low Pressure Steam
EDC	Electric Duct Coil	L.T.	Light Troffer
EDH	Electric Duct Heater	LWT	Leaving Water Temperature
EF	Exhaust Fan		6
EMS	Energy Mgt System	MAU/MUA	Make Up Air Unit
EWT	Entering Water Temperature	MBH	1,000 BTU's per Hour
FCU	Fan Coil Unit	N.A.	Not Accessible
FH	Fume Hood	N/A	Not Applicable
F.L.A.	Full Load Amperage	N.I.	Not Installed
FPB	Fan Powered Box	N.L.	Not Listed
FPM	Feet Per Minute		
	Feet of Head		
FT. HD.			

### SYMBOL SHEET CONTINUED

O.D.	Outside Diameter	TAB	Testing, Adjusting, and Balancing
OA Min	Outside Air Minimum	TSP	Total Static Pressure
OAT	Outside Air Total	TP	Thermally Protected
PF	Power Factor	UH	Unit Heater
РНС	Preheat Coil		
PH	Phase(s)	V	Volts
PSI	Pounds Per Square Inch	VAV	Variable Air Volume
P.T.	Pitot Traverse	VD	Volume Damper
		VFD	Variable Frequency Drive
RA	Return Air	VP	Velocity Pressure
RF	Return Air Fan		
R.G.	Return Grille	W	Watts
RHC	Reheat Coil	WB	Wet Bulb
RPM	Revolutions per Minute	W.D.	Water Density
	-	W.G.	Water Guage
SA	Supply Air		-
SAT	Supply Air Temperature	F	Degrees Fahrenheit
S.D.	Supply Diffuser		-
SEF	Smoke Exhaust Fan	$\Delta P$	Differential (Delta) Pressure or
SF (AIR)	Supply Fan		Pressure Drop
S.F.(Elect)	Service Factors		-
SHC	Steam Heating Coil	$\Delta T$	Differential (Delta) Temperature,
S.P. "W.C."	Static Pressure		Net Temperature
	Measured in Inches of		Decrease or Increase
	Water Column	#	PSI or Pounds Per Square Inch
			Decrease or Increase

Project:	Norfolk Superior Court House		
Address:	650 High St Dedham MA		
Date:	11/10/2020	Project No.	20-549
2 4101	11110/2020		20 0 10
	REPORT S	UMMARY	
	The ventilation for Norfolk Superior Courthouse	e is provided by two Energy Recove	ſy
	Units both of which are operating at design air	low. The units have available	
	capacity to increase Outside Air or Exhaust Air	tiows if required. There is also	
	sufficient capacity to increase the filter efficience	cy on both units.	

#### Project No.

20-549

### **REPORT SUMMARY**

ERU's

UNIT	SUPPLY	EXHAUST	OUTSIDE AIR
ERU-1	1,599 CFM	1,623 CFM	1,599 CFM
ERU-2	1,384 CFM	1,505 CFM	1,384 CFM

Project:	Norfolk Su	perior Court House			
Address:	650 High S	St Dedham, MA			
Date:	11/10/2020	0		Project No.	20-549
		E.	AN DATA SHEET	-	
		FAN NO.	ERU-1(SUPPLY)	FAN NO. E	RU-1(EXHAUST)
Serves / Locat	tion:	Bsmt & 1st FI / Mecl	n Rm	Bsmt & 1st FI / Mech	Rm
Manufacturer:		Greenheck		Greenheck	
Model Numbe	r:	ERV-361S-15-A-ES		ERV-361S-15-A-ES	
Size:		NL		NL	
Serial Number	r:	03D17306		03D17306	
Μ	OTOR	DESIGN	TESTED	DESIGN	TESTED
Manufacturer:		NL	Marathon	NL	Marathon
Frame Numbe	er:	NL	56H-70	NL	56H-70
Horsepower:		1 1/2	1 1/2	1	1 1/2
Brake Horsep	ower:	NL	NA	NL	NA
Safety Factor:		NL	1.15	NL	1.15
Volts/Phase:		208/3	200	208/3	200
Motor Ampera	ige:	5.7	3.6	5.7	3.5
Motor RPM:		1725	1744	1725	1742
Speeds:		1	1	1	1
Heater Size:		NL	EA	NL	EA
Heater Amps.	:	NL	Set @ 6.0	NL	Set @ 6.0
	FAN	DESIGN	TESTED	DESIGN	TESTED
Supply Air CF	M:	1500	1599		
Return Air CF	M:				
Exhaust Air Cl	FM:			1500	1623
Outside Air CF	FM:	1500	1599		
Suction Press	ure:	NL	-1.53	NL	-1.46
Discharge Pre	essure:	NL	0.63	NL	0.34
Fan Static Pre	essure:	NL	2.16	NL	1.8
External Press	sure:	NL	NA	NL	NA
I	RPM	DESIGN	TESTED	DESIGN	TESTED
Fan RPM:		NL	NA	NL	NA
Motor Drive:		NL	1VL40	NL	1VL40
Motor Size/Bo	re:	NL	5/8	NL	5/8
Fan Drive:		NL	AK39	NL	AK39
Fan Size/Bore	):	NL	3/4	NL	3/4
Belt Size / Nur	mber:	NL	A40 / 1	NL	A40 / 1
Shafts C-C:		NL	15 1/2"	NL	15 1/2"
Turns Open:		NL	1	NL	1
Comments:					



Project:	Norfolk Superior (	Court House					
Address: 6	650 High St Dedh	am, MA					
Date:	11/10/2020				Project No.	20-	549
		-	TRAVERSE	DATA			
SYSTEM: ERU-	1 Supply			TRAVERS	E NUMBER :	T-1	
				TRAVERS	E LOCATION:	OSA	
DUCT SIZE (RC	UND)		" DIAMETER	R		Sa Ft =	0.00
DUCT SIZE (RE	CT.)	20	" WIDTH x	17	DEPTH	Sq Ft =	2.36
AIR DENSITY D	ΔΤΔ						
STATIC PRESS	@ CL:	-0.05 ln'	Wa.		DESIGN	CFM =	NL
DUCT AIR TEM	P :	70 De	eg F		ACTUAL	CFM =	1598
BAROMETRIC F	PRESS :	29.92 ln	Hg.		S	CFM=	1599
AIR DENSITY R	ATIO CORRECT	ION =	1 00				
SCFM CORREC	TION FACTOR		1.00				
ACTUAL DENSI	ТҮ		0.075				
TEST HOLE	1	2	3	4	5	6	7
А	601	724	677	488			
В	686	687	657	591			
С	776	826	521	569			
D	696	860	730	603			
Е	552	860	835	601			
F							
G							
н							
I							
NO. OF READIN	IGS =	20	AVERAGE F	PM =	677		
J							
к							
L							
М							
N							
0							
Р							
Q							
R							
TECHNICIAN:	Greg Miller		-				

Project:	Norfolk Superior (	Court House					
Address:	650 High St Dedh	am, MA					
Date:	11/10/2020				Project No.	20-5	549
			<b>TRAVERSE</b>	DATA			
SYSTEM:	ERU-1 Exhaust			TRAVERSE	NUMBER :	T-1	
				TRAVERSE	LOCATION:	Exhaust	
DUCT SIZE (RC	) UND)		" DIAMETER	2		Sa Ft =	0.00
DUCT SIZE (RE	CT.)	22	" WIDTH x	. 14 "	DEPTH	Sa Ft =	2.14
		Actual Size is	24 X 16 with	1" insulation		- 1	
AIR DENSITY D	ATA						
STATIC PRESS	@ CL:	-0.04 In	Ng.		DESIGN	CFM =	NL
	P :	70 De	eg⊢		ACTUAL		1622
BAROMETRICT	PRESS :	29.92 In	Hg.		S	CFM=	1623
AIR DENSITY R	ATIO CORRECT	ION =	1.00				
SCFM CORREC	CTION FACTOR		1.00				
ACTUAL DENS	ITY		0.075				
TEST HOLE	1	2	3	4	5	6	7
А	562	829	928	628			
В	762	868	964	747			
С	817	944	886	751			
D	810	919	739	655			
E	727	719	482	429			
F							
G							
н							
NO. OF READIN	NGS =	20	AVERAGE F	PM =	758		
J							
к							
L							
М							
N							
0							
Р							
Q							
R							
TECHNICIAN:	Greg Miller						

Project:	Norfolk Sup	erior Court House			
Address:	650 High St	: Dedham, MA			
Date:	11/10/2020			Project No.	20-549
		F	AN DATA SHEET	-	
		FAN NO.	ERU-2(SUPPLY)	FAN NO. E	RU-2(EXHAUST)
Serves / Loca	tion:	Bsmt & Upper flrs / F	File rm Mech	Bsmt & Upper flrs / F	ile rm Mech
Manufacturer:		Greenheck		Greenheck	
Model Numbe	r:	ERV-361S-15-A-ES		ERV-361S-15-A-ES	
Size:		NL		NL	
Serial Number	r:	03D17307		03D17307	
М	OTOR	DESIGN	TESTED	DESIGN	TESTED
Manufacturer:		NL	Marathon	NL	Marathon
Frame Numbe	er:	NL	NA	NL	56
Horsepower:		1 1/2	1 1/2	1	1
Brake Horsep	ower:	NL	NA	NL	NA
Safety Factor:		NL	1.15	NL	1.15
Volts/Phase:		208/3	200	208/3	200
Motor Ampera	ige:	5.7	3.3	4	2.9
Motor RPM:		1725	1752	1725	1733
Speeds:		1	1	1	1
Heater Size:		NL	EA	NL	EA
Heater Amps.	:	NL	Set @ 6.0	NL	Set @ 5
	FAN	DESIGN	TESTED	DESIGN	TESTED
Supply Air CF	M:	1450	1384		
Return Air CF	M:				
Exhaust Air C	FM:			1450	1505
Outside Air Cl	FM:	1450	1384		
Suction Press	ure:	NL	-1.53	NL	-1.34
Discharge Pre	essure:	NL	0.49	NL	0.48
Fan Static Pre	essure:	NL	2.02	NL	1.82
External Press	sure:	NL	NA	NL	NA
	RPM	DESIGN	TESTED	DESIGN	TESTED
Fan RPM:		NL	NA	NL	NA
Motor Drive:		NL	1VL40	NL	1VL34
Motor Size/Bo	re:	NL	5/8	NL	5/8
Fan Drive:		NL	AK39	NL	AK32
Fan Size/Bore	):	NL	3/4	NL	3/4
Belt Size / Nu	mber:	NL	A40 / 1	NL	A38 / 1
Shafts C-C:		NL	15 1/2"	NL	15 1/4"
Turns Open:		NL	1	NL	1
Commonto					

Comments:



Project: N	lorfolk Superior (	Court House					
Address: 6	50 High St Dedh	am, MA			Droject No	20.5	10
Date:	1/10/2020				Project No.	20-5	949
		-	TRAVERSE	DATA			
SYSTEM: E	RU-1 Supply			TRAVERSE	NUMBER :	T-1	
				TRAVERSE	ELOCATION:	OSA	
DUCT SIZE (ROI			" DIAMETER	,		Sa Ft =	0.00
DUCT SIZE (REC	CT.)	24	" WIDTH x	10 "	DEPTH	Sq Ft =	1.67
, , , , , , , , , , , , , , , , , , ,	,					·	
AIR DENSITY DA	ATA	l					
STATIC PRESS	@ CL:	-0.44 ln	Wg.		DESIGN	CFM =	NL 1005
		70 De	eg F Ha		ACTUAL		1385
BAROMETRIC P	KE33 .	29.92	пg.		50		1304
AIR DENSITY RA	ATIO CORRECT	ION =	1.00				
SCFM CORREC	TION FACTOR		1.00				
ACTUAL DENSI	ΓY		0.075				
TEST HOLE	1	2	3	4	5	6	7
А	267	127	194	173			
В	1221	878	798	529			
С	1474	1167	1053	1258			
D	834	1169	1092	1059			
E							
F							
G							
Н							
I							
NO. OF READIN	GS =	16	AVERAGE FF	PM =	831		
J							
К							
L							
М							
N							
0					4		
Р					_		
Q							
R							
TECHNICIAN:	Greg Miller						

Project:	Norfolk Superior C	Court House					
Address:	650 High St Dedh	am, MA					
Date:	11/10/2020				Project No.	20-5	549
		7	<b>TRAVERSE</b>	DATA			
SYSTEM:	ERU-2 Exhaust			TRAVERSE	NUMBER :	T-1	
				TRAVERSE	LOCATION:	Exhaust	
DUCT SIZE (RC	) DUND)		" DIAMETER	R		Sa Ft =	0.00
DUCT SIZE (RE	CT.)	16	" WIDTH x	16 "	DEPTH	Sq Ft =	1.78
	· · · · · · · · · · · · · · · · · · ·	Actual Size is	3 18X18 with 1	" insulation			
AIR DENSITY D	ATA				5501011	0-14	
STATIC PRESS	5 @ CL:	-0.48 In	Wg.		DESIGN	CFM =	NL
		70 De	eg ⊦		ACTUAL	CFM =	1506
BAROMETRIC	PRESS :	29.92 In	Hg.		50	JFIM=	1505
AIR DENSITY R	ATIO CORRECT	ION =	1.00				
SCFM CORREC	CTION FACTOR		1.00				
ACTUAL DENS	ITY		0.075				
TEST HOLE	1	2	3	4	5	6	7
А	870	973	876	608			
В	978	948	998	744			
С	1009	974	916	736			
D	969	951	743	655			
E	843	907	602	643			
F							
G							
н							
I							
NO. OF READIN	NGS =	20	AVERAGE FI	PM =	847		
J							
к							
L							
М							
N							
0							
Р							
Q							
R							
TECHNICIAN:	Greg Miller						

MILHARMER ASSOCIATES, INC.
534 New State Highway, Route 44, Suite 3
Raynham, MA 02767

Tel.: 508-823-8500; Facsimile: 508-823-8600



## **TEST AND BALANCE REPORT**

Project:

### **Norfolk County Registry of Deeds**

649 High Street Dedham, MA

Project No.:

20-549

Project Date:

1/4/2021

**MECHANICAL CONTRACTOR** 

TIGHE & Bond



A N.E.B.B. Certified Company

Project:	Norfolk Coun	ty Registry of Deeds				
Address:	649 High Stre	eet Dedham, MA				
Date:	1/4/2021		Project No.		20-549	
		CE	RTIFICATION			
		Subm Milharı	itted & Certified by: ner Associates,	Inc.		
Certification No	o.: <b>3384</b>			Certification	Expiration Date: 3-31-2	21
The data pr have been obta <b>Testing, Adju</b> exceed N.E.B.I	esented in this ained in accorda <i>sting and Bala</i> B. tolerances, a	Report is a record of sy ance with the current ec <i>ncing of Environment</i> re noted in the Test-Ad	stem measurements lition of the <i>N.E.B.B.</i> <i>al Systems.</i> Any va just-Balance Report	and final adju <b>Procedural S</b> ariances from o Project Summ	stments that Standards for design quantities which ary.	
N.E.B.B. Quali	fied TAB Super	visor Name: Scott F. M	filler			
NEBB Quali	fied TAB Super	visor Signature				
<u>.</u>			NEBB			

FOR THE NEBB BOARD OF DIRECTORS Testing, Adjusting and Balancing of Environmental Systems A-ALCC gyfury Schoole NEBB President-Elect **NEBB** President HAS MET ALL REQUIREMENTS FOR NEBB CERTIFICATION IN THE FOLLOWING DISCIPLINE Milharmer Associates, Inc. THIS IS TO CERTIFY THAT Certification **NEBB** Certification Number March 31, 2021 **Expiration Date** 3384

n Board sional	0Y	EMENTS FOR L STATUS IN	rvíronmental Systems	Firm and associated NEBB Certification ation in the NEBB Quality Assurance NEBB Certified Firm.	Ruchard Fant	V NEBB Certification Board Chairman	lymenia device	NEBB Certification Director	tion Board Policy Manual governs use of this certificate.
NEBB Certification NEBB Certified Profession	Scott F. Miller	HAS MET ALL THE NEBB REQUIREN NEBB CERTIFIED PROFESSIONAL	Testing, Adjusting and Balancing of Env	This Certificate, as well as individual affiliation with a NEBB Certified Firm Stamp are REQUIRED to provide a NEBB Certified Report. Participatio Program requires the Certificant be affiliated with a NEB	March 31, 2021	Expiration Date	23541	NEBB Certificant Number	The NEBB Certification Board retains sole ownership of all certificates. The NEBB Certification l

Project: Address: Date:	Norfolk County Re 649 High Street De 1/4/2021	gistry of Deeds edham, MA <b>Project No.</b>	20-549
	TABLE OF CO	NTENTS	
SECTION 1	<b>TAI</b> A. B. C. D. E.	B Qualifications N.E.B.B. Certification N.E.B.B. Company Certificate N.E.B.B. Supervisor Certificate Instrument Sheet Symbol Sheet	
SECTION 2		3 Building Systems	

Project:	Norfolk County Registry of Deeds		
Address:	649 High Street Dedham, MA		
Date:	1/4/2021	Project No.	20-549
	INSTRUME	INT SHEET	
The following is this project.	a list of Instruments owned and operated by M	ilharmer Associates, Inc. and used o	on
Instrument	Instrument	Calibration	Calibration
ID Number		Date	Due Date
1	ADM-870 Digital Multimeter	8-20-20	8-20-21
2	Shortridge Flow Hood	8-20-20	8-20-21
3	Ampmeter	8-20-20	8-20-21
4	Tachometer	8-20-20	8-20-21
5	Airflow Anemometer	8-20-20	8-20-21
6	Digital Thermometers	8-20-20	8-20-21
7	Shortridge Water Meter	8-20-20	8-20-21
8	Sound Meter	8-20-20	8-20-21
9	Vibration Meter	8-20-20	8-20-21

Please Note: Instruments are tested annually at the M.A.I. Lab. and sent back to the factory if deviation exceeds manufacturing tolerance.

Technician:

### SYMBOL SHEET

AHU	Air Handling Unit	HEATER O.L.	Thermal Overload
AC or ACU	Air Conditioner Unit		Protection For Motors
ACCU	Air Cooled Condensing Unit		Located at Starter Motor
ADJ P.D.	Adjusted Pitch Diameter		
AMP	Amperage	HEPA	High Efficiency Particulate
AVG	Average		Arrestance
A.D.	Air Density	HOA	Hand/Off/Auto Switch
		H.P.	Horsepower
B.H.P.	Brake Horsepower	HPS	High Pressure Steam
		HRC	Heat (Recovery or Recliam) Coil
CFM	Cubic Feet Per Minute	HVAC	Heating, Ventilation and
СН	Chiller		Air Conditioning
CHWR	Chilled Water Return	HWR	Hot Water Return or
CHW or CHWS	Chilled Water Supply		Heating Water Return
СТ	Cooling Tower	HWS	Hot Water Supply or
CWR	Condenser Water Return		Heating Water Supply
CW or CWS	Condenser Water Supply	HX	Heat Exchanger
DB	Dry Bulb	I.D.	Inside Diameter
D.D.	Direct Drive		
DIA	Diameter	LAT	Leaving Air Temperature
		L.D.	Linear Supply Diffuser
EAT	Entering Air Temperature	LPS	Low Pressure Steam
EDC	Electric Duct Coil	L.T.	Light Troffer
EDH	Electric Duct Heater	LWT	Leaving Water Temperature
EF	Exhaust Fan		<i>C I</i>
EMS	Energy Mgt System	MAU/MUA	Make Up Air Unit
EWT	Entering Water Temperature	MBH	1,000 BTU's per Hour
FCU	Fan Coil Unit	N.A.	Not Accessible
FH	Fume Hood	N/A	Not Applicable
F.L.A.	Full Load Amperage	N.I.	Not Installed
FPB	Fan Powered Box	N.L.	Not Listed
FPM	Feet Per Minute		
	Feet of Head		
FT. HD.			

### SYMBOL SHEET CONTINUED

O.D.	Outside Diameter	TAB	Testing, Adjusting, and Balancing
OA Min	Outside Air Minimum	TSP	Total Static Pressure
OAT	Outside Air Total	TP	Thermally Protected
PF	Power Factor	UH	Unit Heater
РНС	Preheat Coil		
PH	Phase(s)	V	Volts
PSI	Pounds Per Square Inch	VAV	Variable Air Volume
P.T.	Pitot Traverse	VD	Volume Damper
		VFD	Variable Frequency Drive
RA	Return Air	VP	Velocity Pressure
RF	Return Air Fan		
R.G.	Return Grille	W	Watts
RHC	Reheat Coil	WB	Wet Bulb
RPM	Revolutions per Minute	W.D.	Water Density
	-	W.G.	Water Guage
SA	Supply Air		-
SAT	Supply Air Temperature	F	Degrees Fahrenheit
S.D.	Supply Diffuser		-
SEF	Smoke Exhaust Fan	$\Delta P$	Differential (Delta) Pressure or
SF (AIR)	Supply Fan		Pressure Drop
S.F.(Elect)	Service Factors		-
SHC	Steam Heating Coil	$\Delta T$	Differential (Delta) Temperature,
S.P. "W.C."	Static Pressure		Net Temperature
	Measured in Inches of		Decrease or Increase
	Water Column	#	PSI or Pounds Per Square Inch
			Decrease or Increase

Project:	Norfolk County Registry of Deeds		
Address:	649 High Street Dedham, MA		
Date:	1/4/2021	Project No.	20-549
	REPORT SU	IMMARY	
	The ventilation for the Norfolk County Registry of	f Deeds is provided by two small	
	Air Handling Units Located in the Mezzanine of t	the building. The units bring in a	
	continuous minimum amount of outside air to the	e building. The minimum outside air	
	could be slightly increased as the outside air da	mpers were not 100% open at the	
	time of testing. The units have sufficient capacity	y to increase the filter efficiency.	

Project:	Norfolk Co	unty Registry of Deed	S		
Address:	649 High S	treet Dedham, MA		Brainat No	20 540
Date:	1/4/2021			Project No.	20-349
		F/	AN DATA SHEET		
		FAN I	NO. RTU-1	FAN	I NO.
Serves / Locat	tion:	Probation Annex / R	.oof		
Manufacturer:					
	<u>r:</u>				
Size. Serial Numbe	r.	1600125/11			
		DESIGN	TESTED	DESIGN	TESTED
Manufacturer:			Selectech		
Frame Numbe			56		
Horsepower	<u></u>		1		
Brake Horsep	ower.		0.75		
Safety Factor:			1.15		
Volts/Phase:		208/1	200		
Motor Ampera	ade:	6.9	5.2		
Motor RPM:	.90	NL	Direct Drive		
Speeds:		ECM	High		
Heater Size:		NL	CB		1
Heater Amps.		NL	СВ		
	FAN	DESIGN	TESTED	DESIGN	TESTED
Supply Air CF	M:	Not Listed	1108		
Return Air CF	M:		695		
Exhaust Air C	FM:				
Outside Air CF	- <u>-</u> M:	Not Listed	413		
Suction Press	ure:	NL	-0.68		
Discharge Pre	essure:	NL	0.56		
Fan Static Pre	ssure:	NL	1.24		
External Press	sure:	NL	NA		
'	RPM	DESIGN	TESTED	DESIGN	TESTED
Fan RPM:		NL	Direct Drive		
Motor Drive:		NL	Direct Drive		
Motor Size/Bo	ore:	NL	Direct Drive		
Fan Drive:		NL	Direct Drive		
Fan Size/Bore	»:	NL	Direct Drive		
Belt Size / Nur	mber:	NL	Direct Drive		
Shafts C-C:		NL	Direct Drive		
Turns Open:		NL	Direct Drive		
Comments:			!	<b>!</b>	-

Project:	Norfolk County I	Registry of De	eeds				
Address: 6	649 High Street	Dedham, MA	N N				
Date:	11/10/2020				Project No.	20-5	49
			AIR DISTR	IBUTION			
SYSTEM: I	RTU-1			l			
SUPPLY	K		RETURN		EX	HAUSI	
				DESIGN	TEST	DESIGN	TESTED
	NUMBER	SIZE	FACTOR	FT/MIN	FT/MIN	CFM	CFM
Probation Annex	1	12x12	F.H.	NA	NA	NL	190
Probation Annex	2	12x12	F.H.	NA	NA	NL	233
Probation Annex	3	12x12	F.H.	NA	NA	NL	71
Probation Annex	4	12x12	F.H.	NA	NA	NL	100
Probation Annex	5	12x12	F.H.	NA	NA	NL	280
Probation Annex	6	12x12	F.H.	NA	NA	NL	234
	-						
	4		<b> </b>	ļ	<b> </b>		
					<b> </b>		
	-				+		
	-						
	1				<u>∤</u>		
Comments:	•				TOTALS:	NL	1108

Project: N	orfolk Superior	Court House	e				
Address: 65	50 High St Ded	ham, MA					
<b>Date:</b> 11	1/10/2020				Project No.	20-5	49
			AIR DISTR	BUTION			
SYSTEM: R	TU-1						
SUPPLY			RETURN X		EX	HAUST	
ROOM OR	UNIT	UNIT	AREAxK	DESIGN	TEST	DESIGN	TESTED
LOCATION	NUMBER	SIZE	FACTOR	FT/MIN	FT/MIN	CFM	CFM
Probation Annex	1	12x12	F.H.	NA	NA	NL	795
Comments:					TOTALS:	NL	795

Project:	Norfolk C	ounty Registry of Deed	S		
Address:	649 High	Street Dedham, MA			
Date:	1/4/2021			Project No.	20-549
		F	AN DATA SHEET	-	
		FAN M	IO. AHU-1	FANI	NO. AHU-2
Serves / Locat	tion:	Main Records / Mez	zanine	Main Records / Mezz	anine
Manufacturer:		Trane		Trane	
Model Numbe	r:	TWE120E300AB		TWE120E300AB	
Size:		NL		NL	
Serial Number		12083KAPBA		12102MSSBA	
M	OTOR	DESIGN	TESTED	DESIGN	TESTED
Manufacturer:		NL	Marathon	NL	Marathon
Frame Numbe	er:	NL	145T	NL	145T
Horsepower:		NL	2	NL	2
Brake Horsepo	ower:	NL	1.4	NL	1.45
Safety Factor:		NL	1.15	NL	1.15
Volts/Phase:		208/3	200	208/3	200
Motor Ampera	ge:	6.2	4.3	6.2	4.7
Motor RPM:		1725	1733	1725	1740
Speeds:		1	1	1	1
Heater Size:		NL	СВ	NL	СВ
Heater Amps.:		NL	СВ	NL	СВ
	FAN	DESIGN	TESTED	DESIGN	TESTED
Supply Air CF	M:	NL	3761	NL	3955
Return Air CFI	M:	NL	3506	NL	3721
Exhaust Air Cl	FM:				
Outside Air CF	FM:	NL	255	NL	234
Suction Press	ure:	NL	-0.77	NL	-0.74
Discharge Pre	ssure:	NL	0.26	NL	0.12
Fan Static Pre	ssure:	NL	1.03	NL	0.86
External Press	sure:	NL	-0.26	NL	-0.24
	RPM	DESIGN	TESTED	DESIGN	TESTED
Fan RPM:		NL	NA	NL	NA
Motor Drive:		NL	1VL40	NL	1VL40
Motor Size/Bo	re:	NL	7/8"	NL	7/8"
Fan Drive:		NL	AK79	NL	AK79
Fan Size/Bore	:	NL	1"	NL	1"
Belt Size / Nur	mber:	NL	A50 / 1	NL	A50 / 1
Shafts C-C:		NL	17"	NL	17"
Turns Open:		NL	2	NL	2
Comments:					

Project: N	Norfolk County Re	egistry of Deed	ds					
Address: 6	49 High Street D	edham, MA						
Date: 1	/4/2021				Project No.	<b>.</b> 20-549		
TRAVERSE DATA								
SYSTEM: AHU-1 TRAVERSE NUMBER : T-1								
		TRAVERSE	LOCATION:	RETURN				
DUCT SIZE (ROUND)			" DIAMETER	2		Sa Ft =	0.00	
DUCT SIZE (RECT.)		34	" WIDTH x	18 "	DEPTH	Sq Ft =	4.25	
``````````````````````````````````````	,	Actual is 36X	20 with 1" Ins	ulation		•		
AIR DENSITY D	ATA							
STATIC PRESS	@ CL:	-0.15 ln\	Ng.	DESIGN CFM = N			NL	
		70 De	eg F	ACTUAL CFM =			3506	
BAROME I RIC P	RESS :	29.92 In	Hg.	SCFM= 3507			3507	
AIR DENSITY R	ATIO CORRECT	ION =	1.00					
SCFM CORREC	TION FACTOR		1.00					
ACTUAL DENSI	ΓY		0.075					
TEST HOLE	1	2	3	4	5	6	7	
А	378	462	646	617	801	796		
В	353	682	754	765	813	906		
С	693	660	1084	819	826	1087		
D	1036	942	1176	1149	946	1094		
E	780	1229	1161	916		353		
F								
G								
Н								
1								
NO. OF READINGS =		29	AVERAGE FI	PM =	825			
J								
К								
L								
Μ								
N								
0								
Р								
Q								
R								
TECHNICIAN:	Greg Miller							

Project:	Norfolk County Re	egistry of Dee	ds						
Address:	649 High Street Dedham, MA								
Date:	1/4/2021				Project No.	549			
TRAVERSE DATA									
SYSTEM: AHU-1 TRAVERSE NUMBER : T-1									
				TRAVER	SE LOCATION:	OSA			
DUCT SIZE (ROUND)			" DIAMETER			Sq Ft =	0.55		
DUCT SIZE (RECT.)			" WIDTH x"		" DEPTH	Sq Ft =	0.00		
AIR DENSITY D	ATA								
STATIC PRESS	@ CL:	-0.07 InWg.			DESIGN	CFM =	NL		
DUCT AIR TEM	P :	70 De	eg F		ACTUAL CFM =		255		
BAROMETRIC PRESS :		29.92 In Hg.			S	CFM=	255		
AIR DENSITY R	ATIO CORRECT	ION =	1.00						
SCFM CORREC	TION FACTOR		1.00						
ACTUAL DENSITY			0.075						
TEST HOLE	1	2	3	4	5	6	7		
А	511	434							
В	454	376							
С	424	583							
D	480	473							
Е									
F									
G									
н									
I									
NO. OF READIN	IGS =	8	AVERAGE FI	PM =	467				
J									
К									
L									
Μ									
N									
0									
Р									
Q									
R									
TECHNICIAN:	Greg Miller								

Project:	Norfolk County Re	egistry of Deed	ds					
Address: 6	649 High Street D							
Date: 1	/4/2021				<b>Project No.</b> 20-549			
TRAVERSE DATA								
SYSTEM: AHU-2 TRAVERSE NUMBER : T-1								
				TRAVERSE	LOCATION:	RETURN		
DUCT SIZE (ROUND)			DIAMETER	R		Sq Ft =	0.00	
DUCT SIZE (RECT.)		34	" WIDTH x	18 DEPTH Sq Ft =4.2			4.25	
		Actual is 36X	20 with 1" Ins	ulation				
					<b>DEGION</b>	0-14		
STATIC PRESS	@ CL:	-0.18 In\ 70 D -	Wg.		DESIGN CFM =			
		70 De	eg ⊢ ⊌∝		ACTUAL CFM = 372			
BAROMETRICF	RESS:	29.92 in	⊢g.		50	JE IVI=	3721	
AIR DENSITY R	ATIO CORRECT	ION =	1.00					
SCFM CORREC	TION FACTOR		1.00					
ACTUAL DENSI	TY		0.075					
TEST HOLE	1	2	3	4	5	6	7	
А	515	564	505	607	588	889		
В	763	1052	945	848	705	1143		
С	1309	1315	1178	902	838	1385		
D	1324	1344	1252	1115	780	1445		
E	608	421	288	344	777	515		
F								
G								
н								
I								
NO. OF READINGS =		30	AVERAGE FI	PM =	875			
J								
К								
L								
Μ								
N								
0								
Р								
Q								
R								
TECHNICIAN:	Greg Miller							

Project: N	orfolk County Re	egistry of Dee	ds					
Address: 6	49 High Street D	edham, MA						
<b>Date:</b> 1,	1/4/2021				Project No.	20-5	49	
TRAVERSE DATA								
SYSTEM: AHU-2 TRAVERSE NUMBER : T-2								
				TRAVERSE	LOCATION:	OSA		
			" DIAMETER			Sa Ft =	0.55	
DUCT SIZE (REC	СТ.)		" WIDTH x		" DEPTH Sq Ft = 0.00			
						-		
AIR DENSITY DA	ATA					~-··		
STATIC PRESS	@ CL:	-0.06 In	Wg.		DESIGN	CFM =	NL	
		70 De	eg F Ha		ACTUAL CFM =		234	
BAILOWIE FILIC F	NL00.	29.92	rig.			JI IVI-	234	
AIR DENSITY RA	TIO CORRECT	ION =	1.00					
SCFM CORREC	FION FACTOR		1.00					
ACTUAL DENSIT	Υ		0.075					
TEST HOLE	1	2	3	4	5	6	7	
А	491	382						
В	451	350						
С	370	503						
D	406	483						
E								
F								
G								
н								
I								
NO. OF READIN	GS =	8	AVERAGE FI	PM =	430			
J								
К								
L								
М								
N								
0								
Р								
Q								
R								
TECHNICIAN:	Greg Miller							