


MYSTIC RIVER WATERSHED MAILLET CONSERVATION AREA READING, MASSACHUSETTS MAY 2021







SITE SCALE 1" =1000'

Sheet List Table				
Sheet Number	Sheet Title			
1	COVER SHEET			
2	CONSTRUCTION NOTES			
3	EXISTING CONDITIONS			
4	ESC & SITE PREPARATION PLAN			
5	LAYOUT PLAN			
6	GRADING AND DRAINAGE PLAN (1)			
7	GRADING AND DRAINAGE PLAN (2)			
8	PLANTING KEY PLAN			
9	TREE PLANTING AND SEEDING PLAN			
10	TREE PLANTING AND SEEDING PLAN			
11	PLANTING DETAIL PLAN (1)			
12	PLANTING DETAIL PLAN (2)			
13	DETAILS 1			
14	DETAILS 2			
15	PLANTING DETAILS			

GENERAL NOTES:

1. THIS PLAN SET IS FOR PERMITTING ONLY AND NOT FOR CONSTRUCTION. LOT: ADDRESS: 0 WILLOW STREET ZONING DISTRICT: SINGLE FAMILY 19

0 WILLOW STREET ZONING DISTRICT: SINGLE FAMILY 15


MYSTIC RIVER WATERSHED MAILLET CONSERVATION AREA READING, MASSACHUSETTS

Town of Reading 16 Lowell Street

Reading, MA 01867 (781) 942-9082

Horsley Witten Group, Inc. Sustainable Environmental Solutions www.horsleywitten.com

Headquarters 112 Water Street, 6th Floor 55 Dorrance Street, Suite 200 90 Route 6A Sandwich, MA 02563 (401) 272-1717 voice (857) 263-8193 voice (508) 833-6600 voice (617) 574-4799 fax (401) 439-8368 fax



PERMITTING SET ONLY NOT FOR CONSTRUCTION

GENERAL CONSTRUCTION NOTES

- ALL SITE WORK TO COMPLETE THIS PROJECT AS INDICATED ON THE DRAWINGS AND IN THE SPECIFICATIONS IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR.
- IMMEDIATELY CONTACT AND COORDINATE WITH THE ENGINEER AND OWNER IF ANY DEVIATION OR ALTERATION OF THE WORK PROPOSED ON THESE DRAWINGS IS REQUIRED
- UTILIZE ALL PRECAUTIONS AND MEASURES TO ENSURE THE SAFETY OF THE PUBLIC, ALL PERSONNEL AND PROPERTY DURING CONSTRUCTION IN ACCORDANCE WITH OSHA STANDARDS, INCLUDING THE INSTALLATION OF TEMPORARY FENCING BARRICADES, SAFETY LIGHTING, CONES, POLICE DETAIL AND/OR FLAGMEN AS DETERMINED NECESSARY BY THE TOWN OF READING. THE CONTRACTOR IS RESPONSIBLE FOR THE COST OF POLICE DETAIL AND FOR COORDINATING WITH THE LOCAL OR STATE POLICE DEPARTMENT FOR ALL REQUIRED POLICE DETAIL.
- MAKE ALL NECESSARY CONSTRUCTION NOTIFICATIONS AND APPLY FOR AND OBTAIN ALL NECESSARY CONSTRUCTION PERMITS. PAY ALL FEES INCLUDING POLICE DETAILS AND POST ALL BONDS, IF NECESSARY, ASSOCIATED WITH THE SAME, AND COORDINATE WITH THE OWNER AND THE ENGINEER
- ALL EXISTING CONDITIONS SHOWN ARE APPROXIMATE AND ARE BASED ON THE BEST INFORMATION AVAILABLE. PRIOR TO THE START OF CONSTRUCTION VERIFY THAT THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS DO NOT CONFLICT WITH ANY KNOWN EXISTING OR OTHER PROPOSED IMPROVEMENTS. IF ANY CONFLICTS ARE DISCOVERED. NOTIFY THE OWNER AND THE ENGINEER PRIOR TO INSTALLING ANY PORTION OF THE SITE WORK WHICH WOULD BE AFFECTED.
- THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AND STRUCTURES AS INDICATED ON THE DRAWINGS ARE BASED ON RECORDS OF VARIOUS UTILITY COMPANIES. AND WHEREVER POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THIS INFORMATION IS NOT TO BE RELIED UPON AS BEING EXACT OR COMPLETE. VERIFY THE LOCATION OF ALL UNDERGROUND UTILITIES AND STRUCTURES IN THE FIELD PRIOR TO THE START OF CONSTRUCTION. CONTACT THE APPROPRIATE UTILITY COMPANY, ANY GOVERNING PERMITTING AUTHORITY IN THE TOWN, AND "DIGSAFE" (1-888-344-7233) AT LEAST THREE BUSINESS DAYS PRIOR TO ANY EXCAVATION WORK TO REQUEST EXACT FIFLD LOCATION OF UTILITIES. THE CONTRACTOR MUST, RESOLVE CONFLICTS BETWEEN THE PROPOSED UTILITIES AND FIELD-LOCATED UTILITIES AND REPORT ANY DISCREPANCIES TO THE ENGINEER IMMEDIATELY. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR DAMAGES INCURRED AS A RESULT OF UTILITIES OMITTED, INCOMPLETELY OR INACCURATELY SHOWN. THE CONTRACTOR MUST MAINTAIN ACCURATE RECORDS OF THE LOCATION AND ELEVATION OF ALL WORK INSTALLED AND EXISTING UTILITIES FOUND DURING CONSTRUCTION FOR THE PREPARATION OF THE AS-BUILT PLAN.
- THE CONTRACTOR MUST MAINTAIN ALL EXISTING UTILITIES IN WORKING ORDER AND FREE FROM DAMAGE DURING THE ENTIRE DURATION OF THE PROJECT. REPAIR ANY DAMAGE TO EXISTING UTILITY LINES OR STRUCTURES INCURRED DURING CONSTRUCTION OPERATIONS AT NO COST TO THE OWNER. THE CONTRACTOR IS RESPONSIBLE FOR ALL COST RELATED TO THE REPAIR OF UTILITIES. EXCAVATION REQUIRED WITHIN THE PROXIMITY OF EXISTING UTILITY LINES MUST BE DONE BY HAND.
- COORDINATE ALL TRENCHING WORK WITHIN ROADWAYS WITH THE PROPER LOCAL & STATE AGENCY. THE CONTRACTOR IS RESPONSIBLE FOR ALL TRENCH SAFETY INCLUDING ANY LOCAL AND/OR STATE PERMITS REQUIRED FOR THE TRENCH WORK. IF THIS WORK IS REQUIRED TO OCCUR OUTSIDE THE AGREED UPON HOURS OF OPERATION FOR THE FACILITY, THE CONTRACTOR MUST PLAN ACCORDINGLY
- SAWCUT ALL TRENCH WORK WITHIN EXISTING PAVEMENT AS INDICATED ON THE DRAWINGS. BACKFILL AND COMPACT TRENCH WORK AS INDICATED ON THE DRAWING AND IN THE SPECIFICATIONS. IF SETTLEMENT OCCURS DUE TO INADEQUATE COMPACTION. AS DETERMINED BY THE ENGINEER, WITHIN THE WARRANTY PERIOD, CONTRACTOR IS REQUIRED TO REMOVE, PATCH AND REPAVE AFTER ONE COMPLETE 12-MONTH CYCLE.
- IMPORT ONLY CLEAN MATERIAL. MATERIAL FROM AN EXISTING OR FORMER 21E SITE AS DEFINED BY THE MASSACHUSETTS CONTINGENCY PLAN 310 CMR 40 0000 WILL NOT BE ACCEPTED
- IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ESTABLISH AND MAINTAIN ALL CONTROL POINTS AND BENCHMARKS DURING CONSTRUCTION INCLUDING BENCHMARK LOCATIONS AND ELEVATIONS AT CRITICAL AREAS. COORDINATE WITH THE ENGINEER THE LOCATION OF ALL CONTROL POINTS AND BENCHMARKS.
- SITE LAYOUT SURVEY REQUIRED FOR CONSTRUCTION MUST BE PROVIDED BY THE CONTRACTOR AND PERFORMED BY A MASSACHUSETTS' REGISTERED PROFESSIONAL LAND SURVEYOR. THE CONTRACTOR IS RESPONSIBLE FOR COORDINATING WITH THE SURVEYOR FOR ALL SITE SURVEY WORK.
- MAINTAIN ALL GRADE STAKES SET BY THE SURVEYOR. GRADE STAKES ARE TO REMAIN UNTIL A FINAL INSPECTION OF THE ITEM HAS BEEN COMPLETED BY THE ENGINEER. RE-STAKING OF PREVIOUSLY SURVEYED SITE FEATURES IS THE RESPONSIBILITY (INCLUDING
- COST) OF THE CONTRACTOR UNLESS OTHERWISE INDICATED ON THE DRAWINGS AND/OR IN THE SPECIFICATIONS, ALL SITE CONSTRUCTION MATERIALS AND
- STANDARD SPECIFICATIONS (THE COMMONWEALTH OF MASSACHUSETTS DEPARTMENT OF TRANSPORTATION SPECIFICATIONS FOR HIGHWAY AND BRIDGES 2021 EDITION). PROVIDE ALL CONSTRUCTION SERVICE IN ACCORDANCE WITH APPLICABLE LAWS AND REGULATIONS REGARDING NOISE, VIBRATION,

METHODOLOGIES ARE TO CONFORM TO THE MOST RECENT VERSION OF THE MASSACHUSETTS DEPARTMENT OF TRANSPORTATION

- DUST. SEDIMENTATION CONTAINMENT. AND TRENCH WORK
- COLLECT SOLID WASTES AND STORE IN A SECURED DUMPSTER. THE DUMPSTER MUST MEET ALL LOCAL AND STATE SOLID WASTE MANAGEMENT REGULATIONS
- RESTORE ALL SURFACES EQUAL TO THEIR ORIGINAL CONDITION AFTER CONSTRUCTION IS COMPLETE PER SPECIFICATIONS. LEAVE ALL AREAS NOT DISTURBED BY CONSTRUCTION IN THEIR NATURAL STATE. TAKE CARE TO PREVENT DAMAGE TO SHRUBS, TREES, OTHER LANDSCAPING AND/OR NATURAL FEATURES. WHEREAS THE PLANS DO NOT SHOW ALL LANDSCAPE FEATURES. EXISTING CONDITIONS MUST BE VERIFIED BY THE CONTRACTOR IN ADVANCE OF THE WORK.
- REGULARLY INSPECT THE PERIMETER OF THE PROPERTY TO CLEAN UP AND REMOVE LOOSE CONSTRUCTION DEBRIS BEFORE IT LEAVES THE SITE. PROMPTLY REMOVE ALL DEMOLITION DEBRIS FROM THE SITE TO AN APPROVED DUMP SITE.
- . ALL TRUCKS LEAVING THE SITE MUST BE COVERED.
- DO NOT WASH ANY CONCRETE TRUCKS ONSITE. REMOVE BY HAND ANY CEMENT OR CONCRETE DEBRIS LEFT IN THE DISTURBED
- BURIAL OF ANY STUMPS, SOLID DEBRIS, AND/OR STONES/BOULDERS ONSITE IS PROHIBITED. DO NOT USE ROAD SALT OR OTHER DE-ICING CHEMICALS ON THE ACCESS ROADWAY.
- AT THE END OF CONSTRUCTION, REMOVE ALL CONSTRUCTION DEBRIS AND SURPLUS MATERIALS FROM THE SITE. PERFORM A THOROUGH INSPECTION OF THE WORK PERIMETER. COLLECT AND REMOVE ALL MATERIALS AND BLOWN OR WATER CARRIED

SENERAL DEMOLITION NOTES

HIS PLAN SET DOES NOT INCLUDE DETAILS & SPECIFICATIONS FOR ALL DEMOLITION WORK REQUIRED WITHIN THE PROPOSED ONSTRUCTION LIMITS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE WITH THE OWNER PROJECT ENGINEERS INVOLVED WITH THE PROPOSED NEW CONSTRUCTION TO DEVELOP A SUITABLE DEMOLITION PLAN, WHICH WILL ALLOW THE FACILITIES TO REMAIN IN OPERATION DURING THE ENTIRETY OF CONSTRUCTION.

- UNLESS OTHERWISE NOTED, THE CONTRACTOR IS RESPONSIBLE FOR THE RELOCATION, DEMOLITION, REMOVAL AND DISPOSAL, IN A LOCATION APPROVED BY ALL GOVERNING AUTHORITIES, OF ALL EXISTING SITE ELEMENTS AND STRUCTURES INCLUDING, BUT NOT LIMITED TO ROADWAYS PARKING AREAS PARKING ISLANDS BITUMINOUS CONCRETE CEMENT CONCRETE GRAVEL CURBS WALKWAYS, SIDEWALKS, BERMS, FENCES, BOLLARDS, POSTS, PLANTING BEDS, TREES, SHRUBS, UTILITIES, DRAINAGE STRUCTURES AND ALL OTHER STRUCTURES SHOWN AND NOT SHOWN WITHIN CONSTRUCTION LIMITS. AND WHERE NEEDED. TO ALLOW FOR NEW CONSTRUCTION. ALL FACILITIES TO BE REMOVED ARE TO BE UNDERCUT TO SUITABLE MATERIAL AND BROUGHT TO GRADE WITH SUITABLE COMPACTED FILL MATERIAL PER SPECIFICATIONS.
- REMOVE ALL DEBRIS FROM THE SITE AND DISPOSE OF THE DEBRIS IN A PROPER AND LEGAL MANNER.
- OBTAIN ALL PERMITS REQUIRED FOR DEMOLITION AND DISPOSAL.
- COORDINATE WITH RESPECTIVE UTILITY COMPANIES PRIOR TO THE REMOVAL AND/OR RELOCATION OF UTILITIES. COORDINATE WITH THE UTILITY COMPANIES CONCERNING PORTIONS OF THE WORK WHICH MAY BE PERFORMED BY THE UTILITY COMPANY AND ANY FEES WHICH ARE TO BE PAID TO THE UTILITY COMPANY FOR THEIR SERVICES. THE CONTRACTOR IS RESPONSIBLE FOR PAYING ALL
- REFER TO UTILITY PLANS AND SPECIFICATIONS FOR ALL WORK WHICH REQUIRES UTILITIES TO BE REMOVED, RELOCATE OR
- MAINTAIN CONTINUOUS ACCESS AND OPERATION FOR SURROUNDING FACILITIES, AS DEEMED BY THE OWNER, AT ALL TIMES DURING DEMOLITION OF THE EXISTING FACILITIES.
- PRIOR TO DEMOLITION OCCURRING, ALL EROSION CONTROL DEVICES ARE TO BE INSTALLED.

BASIC CONSTRUCTION SEQUENCE:

THE FOLLOWING CONSTRUCTION SEQUENCE IS TO BE USED AS A GENERAL GUIDELINE. COORDINATE WITH THE OWNER, ENGINEERS, AND LANDSCAPE ARCHITECT AND SUBMIT A PROPOSED CONSTRUCTION SEQUENCE FOR REVIEW AND APPROVAL PRIOR TO CONSTRUCTION.

- 1. SURVEY AND STAKE THE PROPOSED LIMIT OF DISTURBANCE AND LIMIT OF SEDIMENTATION BARRIERS.
- 2. PLACE SEDIMENTATION BARRIERS AS INDICATED ON DRAWINGS AND STAKED OUT IN THE FIELD. UNDER NO CIRCUMSTANCES IS THE LIMIT OF WORK TO EXTEND BEYOND THE SEDIMENTATION BARRIERS/LIMIT OF DISTURBANCE AS INDICATED ON DRAWINGS AS APPROVED BY THE READING CONSERVATION COMMISSION AND DEPARTMENT OF ENVIRONMENTAL PROTECTION (DEP).
- INSTALL TEMPORARY CONSTRUCTION ENTRANCES IN LOCATIONS INDICATED ON DRAWINGS. NO OTHER ENTRANCES ARE TO BE USED TO GAIN ACCESS TO THE SITE BY ANY CONSTRUCTION OR DELIVERY VEHICLES.
- BEGIN CLEARING THE SITE AS REQUIRED.
- 5. SURVEY AND STAKE CENTERLINE OF THE PROPOSED ROADS, STORMWATER MANAGEMENT AREAS, AND DRAINAGE LINES.
- EXCAVATE AND ROUGH GRADE THE PROPOSED STORMWATER MANAGEMENT AREAS AND ANY ADDITIONAL TEMPORARY BASINS NECESSARY TO CONTROL SITE RUNOFF AND SEDIMENTS. TEMPORARILY STABILIZE/SEED PERMANENT STORMWATER MANAGEMENT AREAS AS NECESSARY TO REDUCE SIDE SLOPE EROSION AND SEDIMENT ACCUMULATION.
- BEGIN CLEARING AND GRUBBING THE AREAS OF ROADWAYS AND STORMWATER MANAGEMENT AREAS. TOPSOIL IS TO BE STRIPPED FROM THE AREA OF THE PROPOSED ROADWAYS AND STORMWATER MANAGEMENT AREAS AND STOCKPILED IN APPROVED LOCATIONS. TOPSOIL STOCKPILES MUST BE PROTECTED BY A SEDIMENT BARRIER.
- INSTALL TEMPORARY CONVEYANCE DEVICES (SWALES, CHECK DAMS, PIPES, ETC.) AS NECESSARY TO CONVEY RUNOFF TO TEMPORARY TREATMENT AREAS. DIVERT OVERFLOW FROM PERMANENT STORMWATER TREATMENT AREAS; THEY ARE NOT BE USED AS ONLINE SYSTEMS DURING CONSTRUCTION.
- BEGIN ROUGH GRADING FOR ROADWAYS & PARKING AREAS. BRING ROUGH GRADING TO PROPER ELEVATIONS AS SOON AS PRACTICABLE. COORDINATE WORK TO MINIMIZE TIME SOILS ARE UN-STABILIZED.
- 10 INSTALL DRAINAGE PIPES DRAINAGE MANHOLES AND CATCH BASINS BEGIN WORK AT THE STORMWATER MANAGEMENT AREAS AND PROGRESS UP-GRADIENT. PROTECT DISCHARGE OUTLETS WITH RIP-RAP APRONS. THE STORMWATER MANAGEMENT AREA(S) AND DRAINAGE NETWORK ARE TO BE PROTECTED FROM SEDIMENTATION UNTIL ALL UN-STABILIZED AREAS ARE STABILIZED WITH STONE SUB-BASE OR VEGETATION. INSTALL SEDIMENT BARRIERS AT ALL POINTS OF ENTRY INTO THE DRAINAGE NETWORK. TAKE PARTICULAR CARE TO PROTECT THE UNDERGROUND STRUCTURES FROM SEDIMENT.
- 11. PERMANENTLY SEED ALL DISTURBED AREAS OUTSIDE OF THE AREA TO BE PAVED.
- BEGIN ROAD AND PARKING CONSTRUCTION PER SITE PLANS AND IN ACCORDANCE WITH APPLICABLE STATE AND LOCAL REGULATIONS. ROADS AND PARKING AREAS ARE NOT TO BE PAVED UNTIL THE ENTIRE PERMANENT DRAINAGE SYSTEM HAS BEEN INSTALLED AND ALL PIPE CONNECTIONS COMPLETE.
- FINISH PERMANENT STABILIZATION. COMPLETE PERMANENT STORMWATER MANAGEMENT AREA SEEDING AND PLANTING AFTER THE CONTRIBUTING AREA TO THE BASIN HAS REACHED A MINIMUM OF 80% STABILIZATION AND IS NO LONGER REQUIRED AS A CONSTRUCTION SEDIMENTATION BASIN.
- 14. COMPLETE ALL REMAINING PLANTING AND SEEDING.
- SWEEP PAVEMENT TO REMOVE ALL SEDIMENTS. REPAIR DRAINAGE OUTLETS AND BASINS AS REQUIRED. CLEAN AND FLUSH THE DRAINAGE STRUCTURES AND PIPES AT THE END OF CONSTRUCTION AND REMOVE ALL ACCUMULATED SEDIMENTS IN THE STORMWATER MANAGEMENT AREAS. CONTRACTOR MUST INSPECT THE DRAINAGE NETWORK AND REPAIR ANY DAMAGE IMMEDIATELY
- 16. ENGINEER TO APPROVE THE REMOVAL OF ALL TEMPORARY SOIL EROSION AND SEDIMENTATION CONTROL MEASURES FOLLOWING VEGETATIVE ESTABLISHMENT OF ALL DISTURBED AREAS AND DETERMINE WHEN THE CONTRIBUTING AREA HAS REACHED A MINIMUM OF 80% STABILIZATION

GENERAL GRADING AND DRAINAGE NOTES:

- 1. ALL CUT AND FILL SLOPES SHALL BE 3:1 OR FLATTER UNLESS OTHERWISE NOTED.
- 2. EXISTING GRADE CONTOUR INTERVALS SHOWN AT 1 FOOT.
- PROPOSED GRADE CONTOUR INTERVALS SHOWN AT 1 FOOT.
- ADJUST AND/OR CUT EXISTING PAVEMENT AS NECESSARY TO ASSURE A SMOOTH FIT AND CONTINUOUS GRADE WITH NEW
- PROPOSED ELEVATIONS ARE SHOWN TO FINISH PAVEMENT OR GRADE UNLESS NOTED OTHERWISE.
- ALL EARTHWORK AND SITE PREPARATION MUST BE DONE IN STRICT ACCORDANCE WITH THE RECOMMENDATIONS OF ANY SUBSURFACE INVESTIGATION OR GEOTECHNICAL REPORTS PREPARED FOR THIS SITE.
- ALL DRAINAGE STRUCTURES AND PIPES MUST BE INSPECTED AFTER INSTALLATION PRIOR TO PATCHING OF ROADWAY AND ALLOWING OF FLOW TO THE STORMWATER TREATMENT AREAS.

- A HIGH WATER TABLE IS ANTICIPATED. IF DEWATERING IS REQUIRED DURING EXCAVATION, TEMPORARILY LOWER THE WATER TABLE [PER SPECIFICATIONS OR] BY PUMPING. INSTALL A DEWATERING BASIN AS INDICATED IN THE DEWATERING BASIN DETAIL AND PROVIDE A DEWATERING PLAN DEPICTING PROPOSED DEWATERING LOCATION FOR REVIEW AND APPROVAL. DIRECT THE PUMP CHARGE TO BASIN TO PREVENT SEDIMENTS FROM LEAVING THE CONSTRUCTION AREA. INISTA REQUIRED. INSTALL THE BASIN AS INDICATED ON DRAWINGS IF SO NOTED, OTHERWISE INSTALL THE BASIN(S) WITHIN THE LIMIT OF DISTURBANCE INDICATED BY THE SILT FENCE OR STRAWBALES.
- 2. PRIOR TO ANY DEWATERING, THE DEWATERING PLAN MUST BE APPROVED BY THE ENGINEER.
- IF DEWATERING IS NECESSARY DURING CONSTRUCTION, IMPLEMENT THE PROPER ESC MEASURES ON SITE TO PREVENT EROSION OR SEDIMENT RUNOFF. THESE MEASURES CAN INCLUDE DEWATERING BAGS, TEMPORARY STRAWBALES, SILT FENCES, SILT SOCKS AND/OR OTHER APPROVED DEVICES AS INDICATED IN THE DETAILS.

INVASIVE SPECIES MANAGEMENT:

- INVASIVE SPECIES MANAGEMENT SHOULD BE CUSTOMIZED TO THE INDIVIDUAL SPECIES FOLLOWING THE SPECIFIC MEASURES OUTLINED IN THE SPECIFICATIONS. MANAGERS SHOULD READ AND UNDERSTAND INVASIVE SPECIES CONTROL SPECIFICATIONS
- 2. ALL PESTICIDE APPLICATIONS MUST BE CONDUCTED BY A MASSACHUSETTS LICENSED PESTICIDE APPLICATOR.

FOR THE SITE PRIOR TO COMMENCING ANY INVASIVE SPECIES MANAGEMENT ACTIVES.

- 3. PRIOR TO ANY WORK ALL INVASIVE SPECIES ARE TO BE IDENTIFIED AND MARKED BY A QUALIFIED PROFESSIONAL. ANY SPECIES IDENTIFIED, OR ANY INVASIVE ON THE MASSACHUSETTS INVASIVE SPECIES LIST, LOCATED WITHIN THE LIMIT OF WORK SHOULD BE REMOVED FOLLOWING THE MEASURES OUTLINED IN THE SPECIFICATIONS.
- 4. MONITOR ALL INVASIVE SPECIES AT THE SITE THROUGHOUT THE DURATION OF THE CONSTRUCTION PERIOD, AND A MINIMUM OF THREE YEARS FOLLOWING SUBSTANTIAL COMPLETION. NEW GROWTH OF ANY INVASIVE SPECIES SHOULD BE REMOVED AS SOON AS IT IS DETECTED

ROOT PRUNING:

STABILIZATION.

- ALL ROOTS ABOVE 1" IN DIAMETER ENCOUNTERED DURING DEMOLITION OR CONSTRUCTION SHALL BE ROOT PRUNED.
- CUT ROOT CLEAN WITH A SAW ON THE SURFACE OF THE ROOT, WHICH IS STILL ATTACHED TO THE TREE. DO NOT PAINT THE
- ROOT PRUNING WORK WILL NOT BE DONE WHEN MORE THAN THE TOP 1 INCH OF SOIL IS FROZEN. ROOT PRUNING WILL NOT BE UNDERTAKEN WHEN THE SOIL IS WET AND CONDITIONS ARE MUDDY.
- 4. PRUNE TREE BRANCHES IF ANY DIE AS A RESULT OF ROOT PRUNING.

COVERED WITH SOIL. THOROUGHLY WATER.

5. IF MORE THAN 40% OF A TREES DRIP LINE IS DISTURBED, AND IT'S ROOTS DESTROYED OR REMOVED, NOTIFY PROJECT ENGINEER TO DETERMINE IF TREE SHOULD BE REMOVED.


3. ONCE CUT, BACK FILL SOIL OVER ROOT. DO NOT LEAVE ROOT EXPOSED OVER NIGHT. AFTER ROOT HAS BEEN CUT, AND

STORMWATER FACILITY OPERATION & MAINTENANCE

THE CONTRACTOR IS RESPONSIBLE FOR THE PROPER INSPECTION AND MAINTENANCE OF ALL STORMWATER MANAGEMENT FACILITIES AS OUTLINED BELOW DURING CONSTRUCTION AND UNTIL SUCH TIME THAT THE ROADWAYS AND ASSOCIATED UTILITIES ARE ACCEPTED BY THE OWNER AND THE ENGINEER


- INSPECT AND RESTORE/CLEAN ALL FACILITIES (INLETS, MANHOLES, STORMWATER MANAGEMENT AREAS AS DESCRIBED BELOW OF SEDIMENT AND DEBRIS PRIOR TO THE OWNER'S ACCEPTANCE.
- 2. REMOVE AND DISPOSE ALL SEDIMENT AND DEBRIS TO A PRE-APPROVED LOCATION.
- 3. REFER TO THE STORMWATER POLLUTION PREVENTION PLAN (SWPPP) FOR ADDITIONAL INFORMATION PERTAINING TO STORMWATER FACILITY OPERATION AND MAINTENANCE REQUIREMENTS. MAINTAIN A WORKING COPY OF THE SWPPP ON SITE AT ALL TIMES.
- 4. AT A MINIMUM INSPECT MONTHLY AND AFTER STORM EVENTS GREATER THAN OR EQUAL TO 1" OF RAINFALL AS NECESSARY FOR THE ENTIRE DURATION OF THE CONSTRUCTION PROJECT AND THE FIRST 3 MONTHS AFTER CONSTRUCTION TO ENSURE PROPER
- SPECIFIC MAINTENANCE REQUIRED DURING CONSTRUCTION:
 - $\underline{\mathsf{DRAINAGE}} \ \mathsf{STRUCTURES} \ (\mathsf{INLETS}, \ \mathsf{MANHOLES}, \ \mathsf{CATCHBASINS}, \ \mathsf{DIVERSION} \ \mathsf{STRUCTURE}) \! \! : \ \mathsf{MONITOR} \ \mathsf{AND} \ \mathsf{REGULARLY} \ \mathsf{INSPECT}$ ALL EXISTING AND PROPOSED DRAINAGE STRUCTURES FOR PROPER OPERATION, COLLECTION OF LITTER OR TRASH, AND STRUCTURAL DETERIORATION. CLEAN AND REMOVE SEDIMENT FRO THE STRUCTURES (INCLUDING SUMPS) AS NECESSARY, AND REPAIR WHEN REQUIRED.
 - B. RIP-RAP SLOPE PROTECTION: MONITOR, REGULARLY INSPECT AND REPAIR AS NECESSARY.
 - SEDIMENT FOREBAY: REGULARLY INSPECT TO ENSURE PROPER FUNCTION. REMOVE SEDIMENT BUILD-UP ON THE FLOOR OF HE FOREBAY AND PROPERLY DISPOSE , AS NECESSARY, TO LIMIT CLOGGING. CLEAN SEDIMENT FOREBAYS PRIOR TO COMPLETION OF CONSTRUCTION.
 - D. <u>CONSTRUCTED WETLAND SYSTEM</u>: MONITOR AND INSPECT STRUCTURAL COMPONENTS OF THE SYSTEM, INCLUDING ORIFICE STRUCTURES, WEIR WALLS, DRAINAGE INLETS, AND SPILLWAY STRUCTURES, FOR PROPER FUNCTION. CLEAN AND REPAIR ANY CLOGGED OPENINGS IDENTIFIED DURING INSPECTIONS. FOR PROPER OPERATION. REMOVE SEDIMENT OR ORGANIC BUILD-UP FROM THE CONSTRUCTED WETLAND AS NEEDED FOR PROPER OPERATION. REMOVE AND REPLACE ILL-ESTABLISHED, DEAD OR SEVERELY DISEASED PLANTS. PRUNE AND REMOVE FROM THE SITE ANY INVASIVE VEGETATION. ENCROACHING UPON THE PERIMETER OF THE FACILITY. CHECK EMBANKMENTS FOR STABILITY AND REMOVE ANY BURROWING ANIMALS. RE-VEGETATE PER THE PLANTING DESIGN ALL BARREN AREAS WITHIN THE EXTENTS OF THE
- ROUTINE MAINTENANCE: OTHER ROUTINE MAINTENANCE INCLUDES THE REMOVAL OF TRASH AND LITTER FROM PAVED AND ERIMETER AREAS, AND STREET AND PARKING LOT SWEEPING UPON COMPLETION OF CONSTRUCTION TO AVOID EXCESSIVE ACCUMULATION OF SEDIMENT IN THE DRAINAGE SYSTEM. INSPECT THE PIPES AND STRUCTURES FOR SEDIMENT ACCUMULATION AND PROPER FLOW


LEGEND:





SOIL BORING LOG DATA

PERFORMED BY J. HENDERSON OF HORSLEY WITTEN GROUP, INC. ON APRIL 19, 2021











PERMITTING SET ONLY NOT FOR CONSTRUCTION


୪ଟ୍ୟବ୍ୟବ୍ୟ


G


21008 2 of 15
















PERMITTING SET ONLY
NOT FOR CONSTRUCTION











THE ALLOWABLE MATERIALS TO BE USED IN THE CONSTRUCTED WETLAND AREA ARE DETAILED IN TABLE 1.

Table 1. Materials Specifications for Constructed Wetlands				
Parameter	Specification	Size	Notes	
Planting Soil Media	See Below	n/a	See below.	
Subgrade Soil	Well-compacted, fine- grained, stable soil.	n/a	Native materials may be used in appropriate. USDA soil groups C and/or D are best.	
Geomembrane Liner	Ultraviolet resistant, HDPE impermeable liner	30 MIL	Liner shall be installed per manufacturer recommendations with proper seam sealing and penetration sealing methods.	
Reverse Flow Outlet Pipe	Non-perforated HDPE pipe and all associated fittings	24 inch	See detail.	

PLANTING SOIL - THE PLANTING SOIL SHOULD BE AN APPROVED HIGH ORGANIC CONTENT MEDIUM EXTURED LOAM OR SANDY CLAY LOAM, FREE OF STONES, STUMPS, ROOTS OR OTHER SIMILAR OBJECTS LARGER THAN TWO INCHES. NO OTHER MATERIALS OR SUBSTANCES SHOULD BE MIXED OR DUMPED WITHIN THE CONSTRUCTED WETLAND AREA THAT MAY BE HARMFUL TO PLANT GROWTH, OR PROVE A HINDRANCE TO THE PLANTING OR MAINTENANCE OPERATIONS. THE PLANTING SOIL SHOULD BE FREE OF NOXIOUS WEEDS.

THE CONSTRUCTED WETLAND SHALL UTILIZE PLANTING SOIL HAVING A COMPOSITION AS FOLLOWS: SAND: 45-55% SILT: 15-25%

CLAY:5-15% ORGANIC MATTER: 15-20%

ELECTRICAL CONDUCTIVITY:

CATION EXCHANGE CAPACITY:

*NOTE: ORGANIC MATTER SHALL BE WELL AGED (6-12 MONTHS), WELL AERATED, LEAF COMPOST OR APPROVED EQUIVALENT.

NOT TO EXCEED 4 MMHO/CM

>15 MEQ/100 GRAMS OF SOIL

THE PLANTING SOIL SHALL BE TESTED AND MEET THE FOLLOWING CRITERIA: PH RANGE: ORGANIC MATTER

THE PLANTING SOIL SHALL ALSO CONTAIN MAGNESIUM, PHOSPHORUS (P205), & POTASSIUM (K2O) AT A STANDARD LEVEL TO FACILITATE PROPER PLANT GROWTH AS APPROVED BY THE ENGINEER OR LANDSCAPE ARCHITECT.

ALL CONSTRUCTED WETLAND AREA SHOULD HAVE A MINIMUM OF ONE TEST. EACH TEST SHOULD CONSIST OF BOTH THE STANDARD SOIL TEST FOR PH, PHOSPHORUS, AND POTASSIUM AND ADDITIONAL TESTS OF ORGANIC MATTER, ELECTRICAL CONDUCTIVITY, AND CATION EXCHANGE CAPACITY. A TEXTURAL ANALYSIS IS REQUIRED FROM THE SITE'S STOCKPILED TOPSOIL. IF TOPSOIL IS IMPORTED, THEN A TEXTURE ANALYSIS SHOULD BE PERFORMED FOR EACH LOCATION WHERE THE TOP SOIL WAS EXCAVATED.

SINCE DIFFERENT LABS CALIBRATE THEIR TESTING EQUIPMENT DIFFERENTLY, ALL TEST RESULTS SHOULD COME FROM THE SAME TESTING FACILITY. THE TESTING RESULTS SHALL BE SUBMITTED TO THE ENGINEER FOR REVIEW AND APPROVAL

SHOULD THE PH FALL OUT OF THE ACCEPTABLE RANGE, IT MAY BE MODIFIED (HIGHER) WITH LIME OR (LOWER) WITH IRON SULFATE PLUS SULFUR.

- FACILITY BACKFILLING WHEN BACKFILLING THE CONSTRUCTED WETLAND, PLACE SUBGRADE SOIL IN LIFTS 12" OR GREATER. PLACE A MINIMUM OF 4" OF PLANTING SOIL ABOVE SUBGRADE SOIL FOR PROMOTING PLANT GROWTH. HEAVY EQUIPMENT CAN BE USED AROUND THE PERIMETER OF THE BASIN TO SUPPLY SOIL. GRADE CONSTRUCTED WETLAND MATERIALS WITH LIGHT EQUIPMENT SUCH AS A COMPACT LOADER OR A DOZER/LOADER WITH MARSH TRACKS. SATURATE PLANTING SOIL AFTER PLACEMENT AND ALLOW TO SETTLE FOR AT LEAST ONE WEEK PRIOR TO INSTALLING PLANT MATERIAL.
- . **PLANT INSTALLATION** SEE LANDSCAPE PLANS.
- MISCELLANEOUS THE CONSTRUCTED WETLAND FACILITY MAY NOT BE CONSTRUCTED UNTIL ALL CONTRIBUTING DRAINAGE AREAS HAVE BEEN STABILIZED, AND SHALL REMAIN OFFLINE AND NOT OPERATIONAL UNTIL ALL VEGETATION IS STABILIZED.

CONSTRUCTED WETLAND FACILITY OPERATION & MAINTENANCE

- 1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROPER INSPECTION AND MAINTENANCE THE CONSTRUCTED WETLAND AND ALL ASSOCIATED APPURTENANCES UNTIL SUCH TIME THAT THE
- ALL SEDIMENT AND DEBRIS SHALL BE DISPOSED OF PROPERLY IN A PRE-APPROVED LOCATION AS
- THE CONTRACTOR SHOULD REFER TO THE STORMWATER POLLUTION PREVENTION PLAN (SWPPP) FOR ADDITIONAL INFORMATION PERTAINING TO STORMWATER FACILITY OPERATION AND MAINTENANCE REQUIREMENTS AND SHALL MAINTAIN A WORKING COPY ON SITE AT ALL TIMES.
- THE CONSTRUCTED WETLAND FACILITIES SHALL BE INSPECTED BY THE CONTRACTOR AFTER EVERY MAJOR RAINFALL EVENT FOR THE ENTIRE DURATION OF THE CONSTRUCTION PROJECT AND THE FIRST

PE THREADED ROD

1. PE THREADED ROD W/WING NUTS PROVIDED FOR END SECTIONS

12"-24". 30" & 36" END SECTIONS TO BE WELDED TO PIPE PER

3. DETAIL PROVIDED BY ADVANCED DRAINAGE SYSTEMS, INC.

MANUFACTURER'S RECOMMENDATIONS.

ALL DIMENSIONS ARE NOMINAL

W/WING NUTS (SEE NOTE)

RIGHT SIDE VIEW

15" HDPE FLARED END SECTION

3-MONTHS AFTER CONSTRUCTION TO ENSURE PROPER STABILIZATION AND CONSTRUCTION.

- SPECIFIC ANNUAL MAINTENANCE SHALL BE AS FOLLOWS:
 - A. DRAINAGE STRUCTURES (INLETS, OUTLETS, SPILLWAYS, MANHOLES, CATCHBASINS, ETC): ALL DRAINAGE STRUCTURES WILL BE INSPECTED ANNUALLY TO MONITOR FOR PROPER OPERATION, COLLECTION OF LITTER OR TRASH, AND STRUCTURAL DETERIORATION. THE BASINS WILL BE CLEANED OF SEDIMENT (INCLUDING SUMPS) AS NECESSARY, AND REPAIRED WHEN REQUIRED.
 - B. <u>STONE PROTECTION</u>: STONE TREATMENT AT THE OUTFALLS OR INFLOW POINTS WILL BE INSPECTED ANNUALLY AND REPAIRED AS NECESSARY.
 - C. SEDIMENT FOREBAY: THE SEDIMENT FOREBAY TO THE CONSTRUCTED WETLAND WILL BE INSPECTED ANNUALLY TO ENSURE PROPER FUNCTIONING. THE SEDIMENT BUILD-UP ON THE FLOOR OF THE FOREBAY WILL BE REMOVED AND PROPERLY DISPOSED OF APPROXIMATELY ONCE EVERY FIVE TO SEVEN YEARS, OR MORE OFTEN AS NECESSARY TO LIMIT SEDIMENT BUILDUP TO LESS THAN 50 PERCENT OF THE DESIGN VOLUME.
 - D. ROUTINE MAINTENANCE: OTHER ROUTINE MAINTENANCE WILL INCLUDE REMOVAL OF TRASH AND LITTER FROM PAVED AND PERIMETER AREAS AND ANNUAL STREET/PARKING LOT SWEEPING AFTER THE SPRING THAW TO AVOID EXCESSIVE ACCUMULATION OF SEDIMENT IN THE DRAINAGE SYSTEM. THE PIPES DRAINING THE PROJECT WILL BE INSPECTED ANNUALLY FOR PROPER FLOW.
 - E. <u>VEGETATION:</u> VEGETATION WILL BE INSPECTED ANNUALLY TO ENSURE ADEQUATE PLANT GROWTH AND TO REMOVE INVASIVE SPECIES. DEAD OR DYING PLANTS WILL BE REPLACED AS NECESSARY. HARVESTING OF DEAD PLANT MATERIAL IS NOT REQUIRED,

NOTE: OPERATION AND MAINTENANCE CHECKLIST AVAILABLE UPON REQUEST

CONSTRUCTED WETLAND CONSTRUCTION SEQUENCE AND REQUIRED INSPECTIONS

- PRECONSTRUCTION MEETING.
- 2. INSTALLATION OF EROSION AND SEDIMENT CONTROL PRACTICES.
- 3. CLEAR/GRUB PROPOSED DISTURBED AREA.
- 4. ROUGH GRADE CONSTRUCTED WETLAND AND SEDIMENT FOREBAY AREAS DURING GENERAL SITE
- 5. INSTALL INFLOW DRAINAGE SYSTEM AS SHOWN IN DETAILS (PIPE, CHANNEL, ETC). SEE NOTES ON SHEET C-2 AND DETAILS FOR INSTALLATION PROCEDURES.
- 6. GRADE AND STABILIZE ALL CONTRIBUTORY DRAINAGE AREAS TO THE CONSTRUCTED WETLAND
- FACILITY.
- OVER EXCAVATE CONSTRUCTED WETLAND AREAS TO 4 INCHES BELOW PROPOSED GRADES. 8. INSTALL OVERFLOW OUTLET STRUCTURE PER DETAILS.
- 9. INSTALL SILT SOCK ALONG THE CONSTRUCTED WETLAND PERIMETER TO PREVENT SEDIMENT FROM WASHING INTO THE BASINS FROM DISTURBED AREAS AROUND THE FACILITY.
- 10. CONSTRUCT ALL BERMS AND SPILLWAYS AS SHOWN IN THE DETAILS.
- INSTALL 4 INCHES OF ORGANIC PLANTING SOIL AS SHOWN IN THE DETAILS (UN-COMPACTED) SEE PLANTING SOIL SPECIFICATIONS. <u>THE CONTRACTOR MUST SUBMIT A SOIL SAMPLE (1 GALLON) TO THE ENGINEER PRIOR TO SOIL DELIVERY TO THE SITE.</u>
- 12. STABILIZE ALL REMAINING DISTURBED AREAS AROUND FACILITY BY SEEDING, HYDROSEEDING AND/OR OTHER EROSION CONTROL METHODS AS OUTLINED IN THE EROSION AND SEDIMENT CONTROL PLANS AND DETAILS. MANDATORY INSPECTION REQUIRED SEE NOTE (3) BELOW
- 13. INSTALL WETLAND PLANTS AS SHOWN IN PLANTING PLANS AND DETAILS. NO PLANTING SHOULD OCCUR BEFORE REMAINING DISTURBED AREAS AROUND THE FACILITY(IES) ARE STABILIZED. THE CONTRACTOR WILL BE REQUIRED TO REMOVE ANY SEDIMENT WHICH WASHES INTO THE CONSTRUCTED WETLAND AREA DURING THE CONSTRUCTION AND PLANTING PHASES. IF SUITABLE TO PLANTING, A SILT FENCE PERIMETER SHALL BE INSTALLED AT THE TOE OF THE CONSTRUCTED WETLAND SLOPESAND REMAIN IN PLACE UNTIL VEGETATIVE COVER IS ESTABLISHED. MANDATORY INSPECTION REQUIRED SEE NOTE (3) BELOW.
- 14. INSTALL REMAINING PLANTING SOIL AROUND PLANTS AS SHOWN IN DETAILS.
- 15. REMOVE REMAINING EROSION AND SEDIMENT CONTROLS ONLY AFTER SURROUNDING EXPOSED SOIL ARES HAVE BEEN PROPERLY STABILIZED. MANDATORY INSPECTION REQUIRED SEE NOTE (3) BELOW.
- (1.) SEE GENERAL CONSTRUCTION NOTES FOR OVERALL CONSTRUCTION SEQUENCE. (2.) SEE GENERAL NOTES/SPECIFICATIONS/CONSTRUCTION DETAILS FOR DETAILED CONSTRUCTION (3.) MANDATORY NOTIFICATION/APPROVAL OF THE PROJECT ENGINEER IS REQUIRED PRIOR TO PROCEEDING WITH NEXT STAGE. <u>CALL THE ENGINEER (HORSLEY WITTEN GROUP, INC.) AT 508-833-6600 PRIOR TO 12:00 NOON THE PROCEEDING DAY TO ARRANGE FOR INSPECTION.</u>

OVERFLOW SPILLWAY

EROSION CONTROL FABRIC

(SEE PLANS FOR LIMITS)

CONSTRUCTED WETLAND

EXISTING SURFACE

(SEE SITE PLAN)

INFLOW (SEE DETAIL)

INFLOW PIPE

SEE INFLOW DETAIL

TYP. (SEE DETAIL)

SEDIMENTATION

AREA (0-6")

(ONLY IN HIGH AND LOW MARSH)

4" WETLAND PLANTING SOIL -

SPILLWAY

FOREBAY

WATER QUALITY STORM (1")

VARIABLE EXTENDED

DETENTION STORAGE

(TYPICAL) (

CONSTRUCTED WETLAND TYPICAL DETAIL

NOT TO SCALE

LOW MARSH

AREA (6-18")

WETLAND PLANTINGS

<u>NOTES:</u> 1. STONE **I**N SPILLWAY

CHANNEL TO BE

SET LEVEL WITH


L: SEE PLANS TOP OF CURB.

VARIES SEE PLANS TRAIL DRIVABLE GRASS PAVER SEE DETAIL 3/8" WASHED **CRUSHED STONE** VARIES - FILTER FABRIC SEE PLAN MIRIFI 140N OR APPROVED EQUIVALENT

1. SUBGRADE SHALL BE UNIFORM AND SMOOTH. REMOVE ALL ROCKS, CLODS, VEGETATION OR OTHER

- OBJECTS. BOTTOM AND SIDE SLOPES WITHIN THE EMERGENCY OVERFLOW SHALL BE STABILIZED WITH DRIVABLE GRASS PAVERS OR ENGINEER APPROVED EQUAL.
- MERGENCY SPILLWAY TO EXCLUDE 3" PEA STONE FILTER LAYER AND 6" STONE RESERVOIR FROM TYPICAL DRIVABLE GRASS PAVER CONSTRUCTION DETAIL.

EMERGENCY SPILLWAY DETAIL




CONCRETE CUTOFF WALL

EROSION CONTROL BLANKET TO BE NORTH AMERICAN GREEN BIONET OR APPROVED EQUIVALENT VEGETATIVE COVER HAS NOT BEEN ESTABLISHED ALONG THE CONSTRUCTED WETLAND SLOPES PRIOR

2. VEGETATIVE COVER: GRASS TO BE NEW ENGLAND EROSION CONTROL/RESTORATION MIX OR APPROVED 3. LOAM MATERIAL: THE LOAM MATERIAL TO CONSIST OF 60-70% WASHED SCREENED SAND, 20-30% TOPSOIL, AND 10-20% ORGANIC MATTER. THE LOAM MATERIAL TO BE MIXED TO A UNIFORM CONSISTENCY. 4. TOPSOIL TO BE NATURAL, FERTILE, FRIABLE, LOAM OR SANDY LOAM TYPICAL OF CULTIVATED TOPSOIL TOPSOIL TO BE FREE OF SUB-SOIL, LARGE STONES, EARTH CLODS, STICKS, STUMPS, CLAY LUMPS, ROOTS,


OR OTHER OBJECTIONABLE MATTER. TOPSOIL TO ALSO BE FREE OF NOXIOUS WEEDS. TOPSOIL TO NOT

HAVE A pH FACTOR OF LESS THAN 6.0 OR GREATER THAN 7.0



CONSTRUCTED WETLAND EMBANKMENT DETAIL

SEASONAL HIGH GV



PRECAST CONCRETE CATCH BASIN (CB) WITH HOOD

NOT TO SCALE

1. ALL SECTIONS TO BE DESIGNED FOR H-20

MAX. CLEARANCE TO OUTSIDE OF PIPE.

MORTAR ALL PIPE CONNECTIONS

TO BE PREFORMED BUTYL RUBBER.

2. PROVIDE "V" KNOCKOUTS FOR PIPES WITH 2"

3. JOINT SEALANT BETWEEN PRECAST SECTIONS

4. CATCH BASIN FRAME AND GRATE TO BE SET IN

GRADE WITH PRECAST CONCRETE RISER OR

STRUCTURE UNTIL IT IS AT THE REQUIRED

MASSACHUSETTS STANDARDS HEAVY DUTY

. HDPE PIPE HOOD TO BE 90° BEND FASTENED

PURGE HOLE DRILLED INTO TOP OF ELBOW.

TO PIPE WITH SEALANT. BEND TO HAVE 1 INCH

(EAST JORDAN, NEENAH, OR APPROVED

FULL 12" WIDE MORTAR BED. ADJUST TO

. DO NOT PLACE MORTAR BED AROUND

FINISH ELEVATION AND ALIGNMENT.

6. FRAME AND COVER TO CONFORM TO

— 3/4" WASHED

6" MIN. COMPACTED

3/4" CRUSHED STONE

APPROVED COMPACTED SUBGRADE

STONE

LOADING.

EQUIVALENT)

6" MIN. <

SEE NOTE 3

ALTERNATE ECCENTRIC CONE SECTIO

48" DIA. (MIN.) ———

ALTERNATE TOP SLAB

COLLAR T

—— 48" DIA. (MIN.) −

4' (MIN.)


(SEE NOTE 7)

8" (MIN.)


(MIN.)

FRAME AND COVER SHALL CONFORM TO MASSACHUSETTS STANDARDS HEAVY DUTY (EAST JORDAN, NEENAH, OR APPROVED EQUIVALENT).

TYPICAL DRAINAGE STRUCTURE FRAME AND COVER/GRATE



DRAINAGE STRUCTURE FRAME AND GRATE NOT TO SCALE



EMBED BOULDERS INTO SIDES OF CHANNEL AS SHOWN ON THE DETAIL PEA GRAVEL TO BE DOUBLE WASHED AND FREE OF ALL FINES. SHOULDER TREATMENT VARIES, SEE PLANS

> STONE CONNECTION CHANNEL NOT TO SCALE

UNDISTURBED SURFACE VARIES EARTH 1. FOUNDATION: WHERE THE TRENCH SEE PLANS BOTTOM IS UNSTABLE, THE CONTRACTOR TO EXCAVATE TO A DEPTH REQUIRED BY THE ENGINEER AND REPLACE WITH A FOUNDATION OF CLASS I OR II MATERIAL AS DEFINED IN ASTM D2321, "STANDARD COVER TO PRACTICE FOR INSTALLATION OF RIGID THERMOPLASTIC PIPE FOR SEWERS PAVMENT (H) AND OTHER GRAVITY-FLOW APPLICATIONS," LATEST EDITION; AS AN ALTERNATIVE AND AT THE DISCRETION OF THE ENGINEER, THE TRENCH BOTTOM MAY BE STABILIZED USING A WOVEN INITIAL BACKFILL GEOTEXTILE FABRIC. 6"-12" ABOVE TOP OF PIPE. 2. BEDDING, HAUNCHING AND INITIAL BACKFILL: SUITABLE MATERIAL TO CONSIST OF CLEAN, HARD, PARTICLES OF GRAVEL MEETING THE FOLLOWING: SPRINGLINE OF PIPE 👃 SIEVE SIZE % PASSING 3/8" 85-95 NO. 4 5-15 NO. 8 - FOUNDATION MATERIAL TO BE INSTALLED AS – MIN. TRENCH WIDTH 🛶

REQUIRED IN ASTM D2321, LATEST EDITION. DETAIL PROVIDED BY ADVANCED DRAINAGE SYSTEMS, INC. MINIMUM BEDDING THICKNESS TO BE 4" (100mm) FOR 4"-24" (100-600mm)

AND 42"-48"(1050-1200mm) CORRUGATED POLYETHYLENE PIPE (CPEP); 6" (150mm) FOR 30"-36" (750-900mm) CPEP.

3. MINIMUM TRENCH WIDTHS TO BE AS FOLLOWS: NOMINAL MIN. RECOMMENDED

25 (630) 10 (250) 28 (710) 12 (300) 31 (790) 15 (375) 34 (860) 18 (450) MINIMUM COVER: MINIMUM

RECOMMENDED DEPTHS OF COVER FOR VARIOUS LIVE LOADING CONDITIONS ARE SUMMARIZED IN THE FOLLOWING TABLE. UNLESS OTHERWISE NOTED, ALL DIMENSIONS ARE TAKEN FROM THE TOP OF PIPE TO THE GROUND SURFACE.

BEDDING MATERIA

H25 (FLEXIBLE PAVEMENT)

RAILWAY HEAVY

CONSTRUCTION

H25 (RIGID PAVEMENT) E80

PRECAST DRAIN MANHOLE (DMH)

NOT TO SCALE

Ø in (mm) TRENCH WIDTH, in (mm)

TRAFFIC LOADS IF INSTALLED IN ACCORDANCE WITH AASHTO SECTION 30. THIS IS BASED ON EMPIRICAL CALCULATION OF LOAD RESPONSE, MANUFACTURER'S TESTING AND FIELD EXPERIENCE WITH THE PIPE. AASHTO SPECIFICATIONS SECTION 18.4.1.5 DEFINES THE MINIMUM COVER AS "ID/8 BUT NOT LESS THAN 12 INCHES". THIS COVER IS MEASURED FROM THE PIPE OD TO THE TOP OF A RIGID (CONCRETE) PAVEMENT OR THE BOTTOM OF A FLEXIBLE (BITUMINOUS) PAVEMENT. BOTH AASHTO AND ASTM. AS WELL AS MOST MANUFACTURERS, REQUIRE ADDITIONAL (TEMPORARY COVER, MOUNDED OVER THE PIPE AND REMOVED FOR FINAL GRADING AND PAVING, IS SUFFICIENT FOR LARGE CONSTRUCTION VEHICLE LOADS.

TOP OF PIPE TO BOTTOM OF BITUMINOUS PAVEMENT

THE MINIMUM COVER FOR A HDPE PIPE IS 1'-0" FOR H-20

1. ALL SECTIONS SHALL BE DESIGNED FOR H-20

INSTALLED AT 12" O.C. FOR THE FULL DEPTH OF

3. PROVIDE "V" KNOCKOUTS FOR PIPES WITH 2" MAX

CLEARANCE TO OUTSIDE OF PIPE. MORTAR ALL

SET IN FULL 12" MORTAR BED. ADJUST TO GRADI

STRUCTURE UNTIL IT IS AT THE REQUIRED FINISH

MASSACHUSETTS STANDARDS HEAVY DUTY (EAS

JORDAN, NEENAH, OR APPROVED EQUIVALENT).

6" MIN. COMPACTED

3/4" CRUSHED STONE

COVER, in (mm)

12 (300)

12 (300)

24 (610)

48 (1220)

୯ଟ୍ୟବ୍ୟବ୍ୟ

4. JOINT SEALANT BETWEEN PRECAST SECTIONS

WITH PRECAST CONCRETE RISER OR BRICK.

SHALL BE PREFORMED BUTYL RUBBER. 5. DRAIN MANHOLE FRAME AND COVER SHALL BE

6. DO NOT PLACE MORTAR BED AROUND

7. FRAME AND COVER SHALL CONFORM TO

ELEVATION AND ALIGNMENT.

2. COPOLYMER MANHOLE STEPS SHALL BE

LOADING.

ACCESS

ALTERNATE TOP SLAB

ACCESS

STEPS (SEE

NOTE 2)

- 48" DIA. (MIN.)

VARIES >

GRADE `

SEE NOTE 5,6.

(MIN.)

COMPACTED SUBGRADE


THE STRUCTURE

PIPE CONNECTIONS.

SFF NOTF 4

— COMPACTED CRUSHED STONE

HDPE DRAINAGE PIPE TRENCH



1. SEE GRADING PLANS FOR CHANNEL SLOPE AND EXTENTS OF GRADING WIDTH VARIES: MAXIMUM WIDTH = 12'

> RIVER OVERFLOW CHANNEL NOT TO SCALE

ROUNDED "LANDSCAPE RIVER STONE" (D50 = 6")A STONE INFLOW SHALL BE CONSTRUCTED AT THE END OF ALL DRAIN PIPES THAT DISCHARGE INTO THE WETLAND SEDIMENT FOREBAY AREA(S) ROCK SHALL SURROUND THE INFLOW PIPE IN THE PER THE DIMENSIONS SHOWN. BACKFILL SHALL COMPLETELY COVER GEOMEMBRANE LINER. GEOMEMBRANE LINER SHALL BE TOE-ED INTO THE SUBGRADE MATERIAL AND UPPER SLOPE (3" MIN.).

— SEDIMENT FOREBAY SURFACE

TOP VIEW

D + 24" BOTH SIDES

CONSTRUCTED WETLAND INFLOW DETAIL

EXTEND ROCK UP SLOPE 6" ABOVE TOP OF PIPE 6" OF 3/4" WASHED CRUSHED STONE **BOTH SIDES**

FRONT VIEW

KEY CURB A NOTE 2 MINIMUM OF 18" INTO COMPACTED COMPACTED BERM BERM TO PREVENT CONCRETE CURB FLOW DIVERSION. SET LEVEL LEVEL → SURFACE SEE PLANS TOP OF BERM SPILLWAY 1 EL: SEE PLANS EL: SEE PLANS__ 12" OF LANDSCAPE STONE-ROUNDED RIVER **UP-GRADIENT** WASHED (D₅₀ = 12") GRADIENT SURFACE NATIVE FILL CONCRETE FILTER FABRIC -COMPACTED -STRUCTURAL FILL 3" OF 3/4" WASHED -(SEE BERM DETAIL STONE OVER FABRIC WHERE APPLICABLE) ANCHOR FABRIC -

STONE SPILLWAY

7' HORIZONTAL CUT ALL BRUSH, -CLEARING LIMIT SAPLINGS & BRANCHES TRIM BRANCHES FLUSH WITH TRUNK. MULCH TRAIL LAY BARE BRANCHES ALONG -SIDE OF FOOT PATH TO IDENTIFY PATH LOCATION - PLACE 4" THICK LAYER OF MULCH ON 5' WIDE SECONDARY TRAIL

SUBGRADE

NO SIGNIFICANT EXCAVATION OR GRADING IS REQUIRED FOR TRAIL CONSTRUCTION. CONTRACTOR MAY RELOCATE TRAIL WITHIN THE LIMIT OF WORK AREA TO AVOID LARGE TREES OR OTHER 3. DO NOT REMOVE TREES GREATER THAN 10 INCHES IN DIAMETER WITHIN TRAIL LIMITS. 4. AVOID REMOVING TREES GREATER THAN 6 INCH IN DIAMETER IF TRAIL RELOCATION WITHIN THE LIMIT OF

TYPICAL CLEARING LIMITS & TRAIL DETAIL


NOT FOR CONSTRUCTION

21008

 $\mathbf{Z} \mathbf{Z} \mathbf{Z}$

13 of 15 C - 13

PERMITTING SET ONLY



GENERAL PLANTING NOTES:

- THE FOLLOWING NOTES ARE PROVIDED AS GENERAL PLANTING GUIDELINES ONLY. THOROUGHLY REVIEW THE PROJECT SPECIFICATIONS FOR ALL LANDSCAPE REQUIREMENTS PRIOR TO THE COMMENCEMENT OF ANY LANDSCAPE WORK. SUBMIT IN WRITING TO THE LANDSCAPE ARCHITECT ANY QUESTIONS OR CLARIFICATIONS REQUIRED AT A MINIMUM OF 30 DAYS PRIOR TO ORDERING ANY MATERIALS OR BEGINNING ANY LANDSCAPE CONSTRUCTION.
- SUBMIT TO THE LANDSCAPE ARCHITECT FOR REVIEW AND APPROVAL ALL REQUIRED LANDSCAPE SUBMITTALS AS DESCRIBED IN THE SPECIFICATIONS INCLUDING A PLANT LIST WITH PLANT SIZE AND QUANTITIES TO BE ORDERED PRIOR TO DELIVERY TO THE PROJECT SITE.
- FURNISH AND INSTALL ALL PLANTS AS SHOWN ON THE DRAWINGS AND IN THE SIZE AND QUANTITIES SPECIFIED ON THE PLANTING SCHEDULE. PLANT SUBSTITUTION SELECTION MUST BE APPROVED BY BIOLOGIST OR LANDSCAPE ARCHITECT PRIOR TO INSTALLATION.
- ALL PLANTS TO COMPLY WITH APPLICABLE REQUIREMENTS OF ANSI Z60.1 "AMERICAN STANDARD FOR NURSERY STOCK." LATEST EDITION, PUBLISHED BY THE AMERICAN NURSERY AND LANDSCAPE ASSOCIATION INC.
- PLANTS TO BE GROWN UNDER CLIMATIC CONDITIONS SIMILAR TO THOSE IN THE LOCALITY OF THE PROJECT FOR AT LEAST TWO (2) YEARS. USE HEALTHY NURSERY GROWN PLANTS THAT HAVE A WELL DEVELOPED ROOT SYSTEM. PLANTS MUST BE FREE OF DISEASE, INSECTS, EGGS OR LARVAE
- INSTALL PLANTS WITHIN ONE (1) WEEK OF PURCHASE. IF PLANTS ARE TO BE STORED AT THE SITE PRIOR TO PLANTING, IT IS THE CONTRACTOR'S RESPONSIBILITY TO ENSURE THEY ARE PROPERLY MAINTAINED, WATERED, AND REMAIN HEALTHY.
- PROCEED WITH PLANTING ONLY WHEN EXISTING AND FORECASTED WEATHER CONDITIONS PERMIT. SUBMIT TO THE LANDSCAPE ARCHITECT IN WRITING THE PROPOSED PLANTING SCHEDULE. OBTAIN APPROVAL OF PLANTING SCHEDULE FROM THE LANDSCAPE ARCHITECT PRIOR TO PERFORMING ANY WORK.
- 8. SEASONS FOR PLANTING: SPRING: DECIDUOUS: **EVERGREEN**:
 - APRIL 1 TO JUNE 15 APRIL 15 TO JUNE 1 PERENNIALS: **GROUNDCOVERS:** APRIL 15 TO JUNE 1
 - DECIDUOUS: SEPTEMBER 15 TO NOVEMBER 15 **EVERGREEN:** SEPTEMBER 15 TO NOVEMBER 15 PERENNIALS: SEPTEMBER 15 TO NOVEMBER 15 GROUNDCOVERS: SEPTEMBER 15 TO NOVEMBER 15

APRIL 1 TO JUNE 15

- PLANTING UNDER FROZEN CONDITIONS WILL NOT BE PERMITTED. PLANTING BEFORE OR AFTER THE ABOVE REFERENCED PLANTING DATES WILL INCREASE THE LIKELIHOOD OF PLANT ESTABLISHMENT FAILURE. ANY DEVIATION FROM THE ABOVE REFERENCED PLANTING DATES IS UNDERTAKEN AT SOLE RISK OF THE CONTRACTOR AND IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO PROVIDE ANY ADDITIONAL MAINTENANCE AND WATERING WHICH MAY BE REQUIRED TO ENSURE SATISFACTORY PLANT ESTABLISHMENT.
- 10. FURNISH ONE YEAR MANUFACTURER WARRANTY FOR TREES, PLANTS, AND GROUND COVER AGAINST DEFECTS INCLUDING DEATH AND UNSATISFACTORY GROWTH. EXCEPTIONS ARE DEFECTS RESULTING FROM LACK OF ADEQUATE MAINTENANCE, NEGLECT OR ABUSE BY OWNER, OR ABNORMAL WEATHER CONDITIONS UNUSUAL FOR WARRANTY PERIOD. THE DATE OF FINAL ACCEPTANCE OF ALL COMPLETED PLANTING WORK ESTABLISHES THE END OF INSTALLATION AND INITIAL MAINTENANCE PERIOD AND THE COMMENCEMENT OF THE GUARANTEE PERIOD.
- 1. ALL TREES WITHIN 5'-0" OF WALKWAYS AND SIDEWALKS TO HAVE A 6'-8" STANDARD BRANCHING HEIGHT.
- 2. INSPECT ALL AREAS TO BE PLANTED OR SEEDED PRIOR TO STARTING ANY LANDSCAPE WORK. REPORT ANY DEFECTS SUCH AS INCORRECT GRADING INCORRECT SUBGRADE ELEVATIONS OR DRAINAGE PROBLEMS, ETC. TO THE LANDSCAPE ARCHITECT AND ENGINEER PRIOR TO BEGINNING WORK COMMENCEMENT OF WORK INDICATES ACCEPTANCE OF SUBGRADE AREAS TO BE PLANTED, AND THE LANDSCAPE CONTRACTOR ASSUMES RESPONSIBILITY FOR
- 3. PROVIDE PROPER PREPARATION OF ALL PROPOSED PLANTED AND SEEDED AREAS PER THE NOTES AND SPECIFICATIONS.
- 14. ALL PLANT LAYOUT AND ACTUAL PLANTING LOCATIONS ARE TO BE FIELD VERIFIED BY LANDSCAPE ARCHITECT PRIOR TO PLANTING. NOTIFY THE LANDSCAPE ARCHITECT AT A MINIMUM OF 48 HOURS IN ADVANCE PRIOR TO SCHEDULING ANY
- 5. BALL AND BURLAP: REMOVE BURLAP AND WIRE BASKETS FROM TOPS OF BALLS AND FROM TOP HALF OF ROOTBALL AS INDICATED ON DRAWINGS. REMOVE PALLETS, IF ANY, BEFORE SETTING.
- 16. POTTED PLANTS: REMOVE THE PLANT FROM THE POT AND LOOSEN OR SCORE THE ROOTS BEFORE PLANTING TO PROMOTE OUTWARDS ROOT GROWTH INTO
- 17. PLUGS: PLANT UPRIGHT AND NOT AT AN ANGLE. DIG PLANTING HOLES LARGE ENOUGH AND DEEP ENOUGH TO ACCOMMODATE THE ENTIRE ROOT MASS. PLANT PLUGS WITH NO TWISTED OR BALLED ROOTS AND WITH NO ROOTS EXPOSED ABOVE THE GRADE LINE. HAND PACK THE SOIL AROUND THE ENTIRE PLUG ROOT
- 18. DIG THE THE PLANTING HOLE TO THE SAME DEPTH AS THE ROOT BALL AND TWO TO THREE TIMES WIDER. SCORE ALL SIDES OF THE HOLE, PLACE THE PLANT IN THE HOLE SO THE TOP OF ROOT BALL IS EVEN WITH SOIL SURFACE. FILL THE HOLE HALFWAY AND THEN ADD WATER ALLOWING IT TO SEEP INTO BACK FILLED MATERIAL. BE SURE TO REMOVE ALL AIR POCKETS FROM BACK FILLED SOIL. DO NOT SPREAD SOIL ON TOP OF THE ROOTBALL. IF SOIL IS EXTREMELY POOR, REPLACE BACK FILL WITH GOOD QUALITY TOP SOIL. AMEND THE SOIL, AS
- 19. CREATE A 2" TO 4" BERM AROUND THE EDGE OF PLANTING HOLE WITH REMAINING SOIL TO RETAIN WATER.
- 20. REMOVE ALL PLANT TAGS AND FLAGS FROM THE PLANTS.
- 21. MULCH ALL PLANTING BEDS AS INDICATED ON DRAWINGS. UNLESS NOTED OTHERWISE, ALL PLANTS TO RECEIVE 2-3 INCHES OF MULCH. DO NOT PILE OR MOUND MULCH AROUND THE PLANT STEMS OR TRUNK.
- 22. TRIM BROKEN AND DEAD BRANCHES FROM TREES AND SHRUBS AFTER PLANTING. NEVER CUT A LEADER.
- 23. TRIM ANY BROKEN AND DEAD BRANCHES FOR EXISTING TREES TO REMAIN WITHIN THE LIMIT OF WORK. ALL TRIMMING AND PRUNING TO BE PREFORMATTED BY A REGISTERED ARBORIST.

GENERAL SEEDING NOTES:

- 1. SEND A REPRESENTATIVE SAMPLE OF THE TOPSOIL TO A TESTING LABORATORY FOR STANDARD SOIL ANALYSIS AS DESCRIBED IN THE SPECIFICATIONS. SUBMIT TO THE LANDSCAPE ARCHITECT AND ENGINEER TEST RESULTS WITH RECOMMENDED SOIL TREATMENTS TO PROMOTE PLANT AND GRASS GROWTH. CORRECT DEFICIENCIES IN THE LOAM AND STOCKPILED TOPSOIL AS DIRECTED BY THE TESTING AGENCY.
- 2. ALL AREAS THAT ARE DISTURBED AND/OR GRADED DURING CONSTRUCTION ARE TO BE BROUGHT TO FINISHED GRADE WITH AT LEAST 4" MINIMUM DEPTH OF GOOD QUALITY LOAM AND SEEDED WITH A QUICK GERMINATING GRASS SEED SUCH AS NEW ENGLAND EROSION CONTROL RESTORATION MIX OR AS SPECIFIED ON THE PLANS.
- 3. PRIOR TO THE PLACEMENT OF TOP SOIL, LOOSEN THE SUBGRADE OF ALL PROPOSED SEEDED AREAS TO A DEPTH OF 6" AND RAKE TO REMOVE STONES LARGER THAN 1 INCH, STICKS, ROOTS, RUBBISH AND OTHER EXTRANEOUS MATTER AND LEGALLY DISPOSE TO AN OFF SITE LOCATION.
- 4. DO NOT SPREAD TOPSOIL IF THE SUBGRADE IS FROZEN, EXCESSIVELY WET, COMPACTED OR NOT PROPERLY PREPARED PER THE NOTES AND SPECIFICATIONS.
- 5. SEE SPECIFICATIONS FOR SEASONAL REQUIREMENTS FOR SEEDING.

WATERING NOTES

- 1. PROVIDE PROPER PLANT CARE, MAINTENANCE AND WATERING ON SITE UNTIL SUCH TIME AS THE LANDSCAPING IS ACCEPTED BY THE PROPERTY OWNER AS SATISFACTORY PER THE SPECIFICATIONS OR AS DETERMINED BY ANY WRITTEN AGREEMENTS BETWEEN THE CONTRACTOR AND PROPERTY OWNER.
- 2. ESTABLISH AN APPROPRIATE WATERING SCHEDULE FOR ALL PLANT MATERIAL BASED UPON PLANT SPECIES REQUIREMENTS AND SITE CONDITIONS. PROVIDE SCHEDULE IN WRITING TO THE LANDSCAPE ARCHITECT AND OWNER FOR REVIEW AND APPROVAL. ADHERE TO THE APPROVED SCHEDULE UNTIL PLANTS ARE FULLY ESTABLISHED.
- 3. AT A MINIMUM THE NEWLY SEEDED AND/OR HYDROSEEDED LAWNS SHOULD BE WATERED DAILY. SPECIAL CARE SHOULD BE TAKEN TO ENSURE THAT THE LAWN IS NOT SATURATED DURING WATERING. IF AN IRRIGATION SYSTEM IS NOT PROVIDED, A TEMPORARY IRRIGATION SYSTEM OR HANDHELD GARDEN HOSE SHALL BE USED FOR WATERING SEEDED AREAS. THE AREA MUST BE MAINTAINED CONSISTENTLY MOIST FOR THE BEST GERMINATION RESULTS. ADDITIONAL WATERING MAY BE REQUIRED IF PLANTING AND SEEDING OCCUR OUTSIDE OF THE RECOMMENDED PLANTING SEASONS.

PLANTING LAYOUT NOTES

1½" DADO JOINT

2" x 4" CAP -

6" MIN. GRAVEL —

COMPACT SUBGRADE -

REMOVE TOP THIRD OF

BURLAP AT ROOTBALL

SCARIFY BOTTOM OF

PLANTING HOLE 4"

DEEP

1. FOR AREAS WITH MIXED PERENNIALS AND/OR GRASSES (SHOWN AS HATCHED AREAS ON PLANS) DO NOT PLANT IN A PATTERN OR WITH LARGE AREAS OF THE SAME SPECIES. RANDOMLY PLANT AS INDICATED ON THE PLANTING PLANS INTO SMALL GROUPINGS OF THE SAME SPECIES TO CREATE A MORE NATURALISTIC APPEARANCE. PLANT THE SAME PLANT SPECIES IN GROUPS OF 8-12 AND NOT LARGER THAN 12, DEPENDING ON THE OVERALL NUMBER OF PLANTINGS.

INTERPRETIVE GRAPHIC PANEL FRONT ELEVATION

2 x DIAMETER OF

ROOTBALL

SHRUB PLANTING DETAIL

NOT TO SCALE

USE EQUIDISTANT TRIANGULAR SPACING FOR PLANTS - FOR ACTUAL SPACING

PLANTING SPACING DETAIL

SEE PLANS OR PLANTING SCHEDULE

SIGN ON ALUMINUM

3/4" THREADED BOLT

AND PLUG

COUNTERSUNK AND PLUGGED

2 CARRIAGE BOLTS AT

EACH JOINT - COUNTERSINK

PRUNE BROKEN OR DEAD

LANDSCAPE ARCHITECT

PLANT SHRUB PLUMB

TO MATCH FINISH **GRADE WITHIN 1"**

MULCH AS INDICATED

— 2"-4" SOIL BERM

PREPARED PLANTING

UNDISTURBED PERVIOUS

SOIL MIXTURE

3" SHREDDED

BRANCHES AS DIRECTED BY

2" x 8" BRACERS

FINISH GRADE

FINISH GRADE

PLACEMENT OF TOPSOIL

PACK BACKFILL BY HAND

PANEL BOX



KIOSK REFERENCE PHOTO NOT TO SCALE



ROCK CAIRN REFERENCE PHOTO NOT TO SCALE

SEE LANDSCAPE GRADING SPECIFICATIONS FOR TOPSOIL REQUIREMENTS.

CONFIRM SUBGRADES ARE CORRECT AND POSITIVE DRAINAGE IS MAINTAINED PRIOR TO

NOTIFY ENGINEER/LANDSCAPE ARCHITECT FOR REVIEW OF SUBGRADE PRIOR TO PLACEMENT OF

LOAM AND SEED DETAIL

- SEED AS SPECIFIED IN NOTES

TOPSOIL- NO STONES GREATER THAN 1" Ø,

SUBSOIL- COMPACTION NO > 90% DENSITY

COMPACT WITH A HANDROLLER IN TWO

DIRECTIONS AND FINE RAKE PRIOR TO


- SUBSOIL- SCARIFY AND LOOSEN

PLANT 12-18" ON CENTER


AS NOTED IN PLANT LIST

PLACEMENT


ROUGH GRADE PRIOR TO TOPSOIL




TREE PLANTING DETAIL



PERENNIAL PLANTING DETAIL






PLUG PLANTING DETAIL

NOT TO SCALE


1. PLANTING BACKFILL: 1/3 LOAM, 1/3 SAND, 1/3 PEAT, BY VOLUME 2. WHEN PLANTING ON SLOPE-MODIFY SLOPE AS SHOWN.

SHRUB PLANTING ON SLOPE DETAIL




NOT TO SCALE

NOT TO SCALE




CONTAINER PLANT ROOTBALL TREATMENT **NOT TO SCALE**



TOPSOIL AND SEEDED. SEE PLANTING PLAN & SCHEDULE **FLUSH STEPPING STONES**


NOT TO SCALE



TREE PLANTING ON SLOPE DETAIL

NOT TO SCALE

EVERGREEN TREE PLANTING DETAIL NOT TO SCALE



- FOLD FABRIC BACK AND PIN DOWN TO CREATE A HOLE IN THE MAT. DIG THE HOLE PER PLANTING DETAILS. AFTER PLANTING, FOLD FABRIC BACK INTO PLACE AND STAPLE DOWN AS REQUIRED TO SECURE FABRIC IN PLACE.

PLANTING IN COIR FABRIC DETAIL

PLANT TREE PLUMB -

PRUNE BROKEN OR DEAD

LANDSCAPE ARCHITECT

NYLON GUY WEBBING

STAPLE OR TIE TO STAKE

WOOD STAKES TO FIRST WHORL

INTERVALS AND PLACED PLUMB

OF BRANCHES @ 120 DEGREE

/ IN TREE PIT OR AS INDICATED

FIRMLY FORMED SAUCER (USE

TOPSOIL) ANGLE OF REPOSE

VARIES WITH STEEPNESS OF

PREPARED PLANTING

SOIL MIXTURE

PERVIOUS SOIL

- PLANT TREE PLUMB -

PRUNF BROKEN OR DEAD

SLOPE AND SOIL TYPE

3" SHREDDED MULCH

REMOVE TOP THIRD OF

BURLAP AT ROOTBALL

BRANCHES AS DIRECTED BY

21008 15 of 15

L - 15

PERMITTING SET ONLY NOT FOR CONSTRUCTION