JOHNSON BROOK RESTORATION

KLAUS ANDERSON RD OVER JOHNSON BROOK · SOUTHWICK · MASSACHUSETTS

PROPOSED CULVERT REPLACEMENT

FEBRUARY 16, 2022 BID DOCUMENTS

PREPARED FOR


TOWN OF SOUTHWICK

454 COLLEGE HIGHWAY SOUTHWICK, MA 01077



SHEET INDEX

SHEET No.	SHEET TITLE
GI-001	COVER SHEET
C1.00	OVERALL SHEET LAYOUT KEY
C1.01-1.02	EXISTING CONDITIONS PLAN
C1.11-1.12	SITE PREPARATION, EROSION & SEDIMENT CONTROL, AND DEWATERING PLAN
C1.21-1.22	SITE LAYOUT PLAN
C1.31-1.32	GRADING & DRAINAGE PLAN
C1.41	ROADWAY PLAN AND PROFILE
C1.42	STREAM PROFILE
L1.01-1.02	SITE LANDSCAPE PLAN
C5.00	EROSION & SEDIMENT CONTROL DETAILS
C5.01-5.04	CONSTRUCTION DETAILS
STR-1	BRIDGE LAYOUT PLAN
STR-2	BRIDGE SECTIONS AND ELEVATIONS
STR-3	FOOTING PLAN
STR-4	BORING LOGS
STR-5-6	BRIDGE DETAILS
STR-7	S3-TL4 BRIDGE RAILING DETAILS TOP OF PRECAST HIGHWAY
STR-8	TOP OF PRECAST HIGHWAY GUARDRAIL TRANSITION FOR S3-TL4 RAILING
STR-9	BOTTOM OF PRECAST HIGHWAY GUARDRAIL TRANSITION FOR S3-TL4 RAILING
STR-10-11	TRANSITION TO BRIDGE RAIL
STR-12	GUARDRAIL SECTIONS
STR-13	APPROACH GEOMETRY: SINGLE FACED
TMP-01	TEMPORARY TRAFFIC DETOUR PLANS




SCALE: 1" = 1000'



BID ALTERNATES:

ALTERNATE 1 - DEDUCT STEP POOLS AND ASSOCIATED WORK ON CURTIS ROAD
 ALTERNATE 2 - DEDUCT VEGETATED COIR LOG SYSTEM

PROJ. No.: 20180390.G14 DATE: FEBRUARY 2022





8. APPROVED PLANS SHALL BE ON SITE AT ALL TIMES.

PERMITS, PAY FEES, AND POST BONDS ASSOCIATED WITH THE WORK AS REQUIRED BY THE

4. LOCATION OF UTILITIES SHOWN HEREON ARE THE RESULT OF SURFACE EVIDENCE AS LOCATED BY FIELD SURVEY, PLANS OF RECORD, INFORMATION FURNISHED BY THE RESPECTIVE UTILITY

EXACT LOCATION OF ALL UTILITIES WHICH MAY EXIST AT THIS TIME WITHIN THE PREMISES SURVEYED. LOCATIONS SHOULD BE VERIFIED BY THE RESPECTIVE UTILITY COMPANY BEFORE

6. FUSS & O'NEILL MAKES NO GUARANTEES THAT THE UNDERGROUND UTILITIES SHOWN COMPRISE ALL SUCH UTILITIES IN THE AREA. FUSS & O'NEILL FURTHER DOES NOT WARRANT THAT THE UNDERGROUND UTILITIES SHOWN ARE IN THE EXACT LOCATION INDICATED. FUSS & O'NEILL HAS

NOT PHYSICALLY LOCATED THE UNDERGROUND UTILITIES. BEFORE CONSTRUCTION, THE CONTRACTOR SHALL CALL DIG SAFE SYSTEMS FOR CLEARANCE.

BEING RELIED UPON. ALL FIELD CHANGES MUST BE APPROVED BY THE ENGINEER.

TO CONSTRUCTION. ALL FIELD CHANGES MUST BE APPROVED BY THE ENGINEER.


7. REFER TO CONTRACT DOCUMENTS FOR GEOTECHNICAL REQUIREMENTS.

9. WITHIN LOCAL RIGHTS-OF-WAY, PERFORM THE WORK IN ACCORDANCE WITH LOCAL MUNICIPAL

10. THE CONTRACTOR IS RESPONSIBLE FOR SITE SECURITY AND JOB SAFETY. PERFORM COMPANIES, AND OTHER AVAILABLE SOURCES. THIS PLAN DOES NOT NECESSARILY DEPICT THE CONSTRUCTION ACTIVITIES IN ACCORDANCE WITH OSHA STANDARDS AND LOCAL REQUIREMENTS. 11. DISPOSE OF DEMOLITION DEBRIS IN ACCORDANCE WITH APPLICABLE FEDERAL, STATE AND LOCAL REGULATIONS, ORDINANCES AND STATUTES.

5. LOCATION AND INVERTS OF EXISTING UTILITIES SHALL BE VERIFIED WITH THE ENGINEER PRIOR 12. CALL DIG-SAFE 811 OR 1-888-DIG-SAFE A MINIMUM OF 72 HOURS PRIOR TO CONSTRUCTION.

PROJ. No.: 20170390.G14 DATE: 02/16/2022




FUSS 8
1550 MAIN STRE
SPRINGFIELD, N

EXISTING CONDITIONS PLAN JOHNSON BROOK RESTORATION

PROJ. No.: 20170390.G14

DATE: 02/16/2022

C1.01



PROJ. No.: 20170390.G14 DATE: 02/16/2022

C1.11

- 1. CALL DIG-SAFE 811 OR 1-888-DIG-SAFE A MINIMUM OF 72 HOURS PRIOR TO CONSTRUCTION.
- STOP WORK IN THE VICINITY OF SUSPECTED CONTAMINATED SOIL, GROUNDWATER OR OTHER MEDIA. IMMEDIATELY NOTIFY THE OWNER SO THAT APPROPRIATE TESTING AND SUBSEQUENT ACTION CAN BE TAKEN. RESUME WORK IN THE IMMEDIATE VICINITY ONLY UPON DIRECTION BY THE OWNER.
- 3. CONTRACTOR SHALL PROTECT ALL SLOPES, VEGETATION, PAVING, WALKS, AND IMPROVEMENTS OUTSIDE THE AREAS TO BE AFFECTED BY THE CONSTRUCTION OF
- 4. REFER TO EROSION AND SEDIMENTATION CONTROL DETAILS FOR EROSION AND SEDIMENTATION CONTROL NOTES.
- 5. WATER AND CALCIUM CHLORIDE MUST BE AVAILABLE AT ALL TIMES FOR DUST
- 6. WATER IS AVAILABLE MON-FRI, 8AM-4PM AT THE DPW AT NO COST TO THE CONTRACTOR. CONTRACTOR RESPONSIBLE FOR COORDINATING WITH DPW.

DEMOLITION

- 1. THE DEMOLITION PLAN IS PROVIDED FOR INFORMATION ONLY AND MAY NOT INDICATE ALL ITEMS REQUIRED TO BE DEMOLISHED. PERFORM A PRE-BID SITE INSPECTION. COORDINATE DEMOLITION OF UNIDENTIFIED UTILITIES OR STRUCTURES WITH OWNER. DEMOLISH STRUCTURES, SITE IMPROVEMENTS, UTILITIES, ETC. AS REQUIRED TO CONSTRUCT PROPOSED FACILITY AND UTILITY SERVICES.
- 2. TREES, BRUSH AND STUMPS REMOVED BY CLEARING & GRUBBING OPERATIONS AND/OR SELECTIVE CLEARING SHALL BE TRANSPORTED OFF THE PROJECT SITE TO AN APPROVED DISPOSAL LOCATION.
- 3. ITEMS TO BE STOCKPILED ON-SITE FOR REUSE OR TO BE RELOCATED SHALL BE PROTECTED FROM CONSTRUCTION OPERATIONS. IF DAMAGED DURING CONSTRUCTION THEY SHALL BE REPLACED IN-KIND AT NO ADDITIONAL COST TO THE OWNER.

SELECTIVE CLEARING

CONTRACTOR SHALL FLAG ALL TREES TO BE REMOVED OR TRIMMED TO INSTALL PROPOSED WORK. CONTRACTOR SHALL NOTIFY AND COORDINATE REVIEW AND APPROVAL WITH TOWN PRIOR TO ANY TREE TRIMMING OR REMOVAL.

WORK RESTRICTIONS

- 1. DO NOT CLOSE OR OBSTRUCT ROADWAYS, FIRE HYDRANTS, AND UTILITIES WITHOUT
- 2. WORK IS RESTRICTED TO THE HOURS OF 8AM TO 4PM, MONDAY THROUGH FRIDAY.
- 3. MAINTAIN AND PROTECT ALL EXISTING UTILITY POLES AND TRAFFIC SIGNS TO
- 4. CONTRACTOR MUST MAINTAIN VEHICULAR ACCESS FOR SCHOOL BUSES FOR THE REMAINDER OF THIS SCHOOL YEAR AND FOR THE START OF THE FALL 2022 SCHOOL YEAR. CONTRACTOR TO COORDINATE WITH TOWN.

LEGEND & STANDARD ABBREVIATIONS

FULL DEPTH ASPHALT RECONSTRUCTION

MILL ASPHALT DEPTH 1¹/₂"


REMOVE AND DISPOSE OVER HEAD WIRE

TYPICAL

REMOVE & DISPOSE CONCRETE

MINIMIZE DISTURBANCE AREA


-/-/-/-/-/-/-/-/-/-/-/-/-/-/-/-/- REMOVE & DISPOSE PIPE





2/16/2022

PROJ. No.: 20170390.G14


DATE: 02/16/2022








4. REFER TO SHEET C1.32 FOR ADDITIONAL NOTES.




3. RESTORE AREAS DISTURBED BY CONSTRUCTION OPERATIONS OUTSIDE OF THE WORK AREA TO THEIR ORIGINAL CONDITION OR BETTER, AT NO ADDITIONAL COST TO OWNER.

4. BIODEGRADABLE EROSION CONTROL MATTING TO BE PLACED ON ALL SLOPES 3:1 AND GREATER.




PROJ. No.: 20170390.G14 DATE: 02/16/2022




2/16/2022 NEILL

STREAM PROFILE

PROJ. No.: 20170390.G14 DATE: 02/16/2022






- EROSION AND SEDIMENT CONTROL MEASURES WILL BE INSTALLED PRIOR TO STUMP REMOVAL AND CONSTRUCTION, STABILIZATION OF ALL REGRADED AND SOIL STOCKPILE AREAS WILL BE INITIATED AND MAINTAINED DURING ALL PHASES OF CONSTRUCTION.
- SEDIMENT REMOVED FROM EROSION CONTROL STRUCTURES WILL BE DISPOSED OF IN A MANNER WHICH IS CONSISTENT WITH THE INTENT OF THIS PLAN. ALL STRAW BALES OR SILT FENCE RETAINING SEDIMENT OVER 6" HIGH SHALL HAVE THE SEDIMENT REMOVED AND ALL DAMAGED EROSION CONTROLS REMOVED AND REPLACED.
- THE CONTRACTOR WILL BE ASSIGNED THE RESPONSIBILITY FOR IMPLEMENTING THIS EROSION AND SEDIMENT CONTROL PLAN. THIS RESPONSIBILITY INCLUDES THE INSTALLATION AND MAINTENANCE OF CONTROL MEASURES, INFORMING ALL PARTIES ENGAGED ON THE CONSTRUCTION SITE OF THE REQUIREMENTS AND OBJECTIVES OF THE PLAN, AND NOTIFYING THE PROPER TOWN AGENCY OF ANY TRANSFER OF THIS RESPONSIBILITY. THE OWNER SHALL BE RESPONSIBLE FOR CONVEYING A COPY OF THE EROSION AND SEDIMENT CONTROL PLAN IF THE TITLE TO THE LAND IS
- . THE CONTRACTOR SHALL BE RESPONSIBLE TO CONTROL DUST AND WIND EROSION THROUGHOUT THE LIFE OF HIS CONTRACT. DUST CONTROL SHALL INCLUDE, BUT IS NOT LIMITED TO, SPRINKLING OF WATER ON EXPOSED SOILS AND HAUL ROADS. CONTRACTOR SHALL CONTROL DUST TO PREVENT A HAZARD TO TRAFFIC ON ADJACENT
- . IF FINAL GRADING IS TO BE DELAYED FOR MORE THAN THIRTY (30) DAYS AFTER LAND DISTURBANCES CEASE. TEMPORÀRÝ VEGETATION OR MULCH SHALL BE USED TO STABILIZE SOILS. OUTSIDE OF THE GROWING SEASON, ONLY WOOD MULCH SHALL BE USED.
- STRAW BALES SHALL BE USED ONLY AS A TEMPORARY MEASURE. WHERE CONTROL MEASURES WILL BE REQUIRED FOR LONGER THAN SIXTY (60) DAYS, FILTER FABRIC SHALL BE USED.
- CONTRACTOR SHALL SUBMIT A DETAILED DEWATERING PHASING PLAN AS OUTLINED IN THE ORDER OF CONDITIONS FOR REVIEW AND APPROVAL BY THE ENGINEER AND CONSERVATION COMMISSION PRIOR TO THE COMENCEMENT OF ANY LAND DISTURBING ACTIVITIES
- WHERE DEWATERING IS NECESSARY, THERE SHALL NOT BE A DISCHARGE DIRECTLY INTO WETLANDS OR WATERCOURSES. PROPER METHODS AND DEVICES SHALL BE UTILIZED TO THE EXTENT PERMITTED BY LAW, SUCH AS PUMPING WATER INTO A TEMPORARY SEDIMENTATION BASIN, PROVIDING SURGE PROTECTION AT THE INLET AND THE OUTLET OF PUMPS, FLOATING THE INTAKE OF THE PUMP, OR OTHER METHODS TO MINIMIZE AND RETAIN THE SUSPENDED SOLIDS. IF A PUMPING OPERATION IS CAUSING TURBIDITY PROBLEMS, SAID OPERATION SHALL CEASE UNTIL SUCH TIME AS FEASIBLE MEANS OF CONTROLLING TURBIDITY ARE DETERMINED AND IMPLEMENTED. THE CONTRACTOR MUST SUBMIT HIS DESIGN ALONG WITH THE LOCATIONS OF THE BASIN TO THE TOWN PRIOR TO CONSTRUCTION.
- INSPECTION A CERTIFIED PROFESSIONAL EROSION AND SEDIMENT CONTROL PERSONAL OR ENGINEER SHALL INSPECT ALL DISTURBED AREAS OF THE CONSTRUCTION ACTIVITY THAT HAVE NOT BEEN FINALLY STABILIZED. STRUCTURAL CONTROL MEASURES, AND LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE AT LEAST ONCE EVERY WEEK AND WITHIN 24 HOURS OF THE END OF A STORM THAT IS 0.25 INCH OR GREATER. INSPECTION REPORTS SHALL BE SUBMITTED TO THI OWNER WEEKLY. AND TO THE INLAND WETLANDS AGENT AND THE PLANNING & ZONING COMMISSION MONTHLY. WHERE SITES HAVE BEEN FINALLY STABILIZED, SUCH INSPECTION SHALL BE CONDUCTED AT LEAST ONCE EVERY MONTH FOR THREE MONTHS. CONTROLS SHALL E CLEANED, REPAIRED, AND OR REPLACED AS REQUIRED. ANY DAMAGED CONTROLS SHALL BE REPAIRED IMMEDIATELY.
- 10. PERFORM CONSTRUCTION SEQUENCING IN SUCH A MANNER TO CONTROL EROSION AND TO MINIMIZE THE TIME THAT EARTH MATERIALS ARE EXPOSED BEFORE THEY ARE COVERED, SEEDED, OR OTHERWISE STABILIZED.

OPERATION & MAINTENANCE PLAN DURING CONSTRUCTION AN OPERATION AND MAINTENANCE (O&M) PLAN DURING CONSTRUCTION FOR STORMWATER CONTROLS IS DESCRIBED

OWNER SHALL BE RESPONSIBLE FOR ALL OPERATION AND MAINTENANCE OF THE SITE.

AS FOLLOWS:


- NO EARTHWORK ACTIVITIES SHALL COMMENCE UNTIL SILT FENCE HAS BEEN INSTALLED. SILT FENCE SHALL BE INSTALLED AS SHOWN ON THE DRAWINGS.
- AREAS LEFT EXPOSED TO EROSION FOR MORE THAN SEVEN DAYS SHALL BE ROUGH GRADED AND TEMPORARILY STABILIZED. AREAS DISTURBED BUT INACTIVE FOR MORE THAN THIRTY DAYS SHALL BE TEMPORARILY SEEDED.
- BIODEGRADABLE EROSION CONTROL MATTING SHALL BE PLACED ON ALL SLOPES 3:1 OR GREATER.
- EROSION AND SEDIMENTATION CONTROLS SHALL BE MAINTAINED UNTIL SUCCESSFUL ESTABLISHMENT OF GROUND COVER.
- NO STAGING OF MATERIALS OR LAY DOWN AREAS SHALL BE LOCATED WITHIN ANY BORDERING VEGETATED WETLAND OR BANK AREAS.
- PAVED AREAS SHALL BE KEPT FREE OF SEDIMENT, AND SHALL BE CLEANED PERIODICALLY AS REQUIRED BY CONSTRUCTION ACTIVITIES.
- TEMPORARY SOIL STOCKPILES SHALL BE LOCATED WITHIN AREAS CONSISTING OF FORMERLY PAVED OR DEVELOPED SURFACES AND WILL BE MOVED AS NECESSARY TO ACCOMMODATE ONGOING WORK.
- SEDIMENT STOCKPILES SHALL HAVE A SIDE SLOPE OF NO GREATER THAN 2:1. ALL STOCKPILES SHALL BE ROUGH GRADED OR MAINTAIN A ROUGHENED SURFACE TO PREVENT EROSION. STOCKPILES THAT ARE NOT TO BE USED WITHIN 7 DAYS SHALL BE SEEDED AFTER FORMATION OF STOCKPILE AS TO PREVENT EROSION. A STRAW BALE AND SILT FENCE BARRIER SHALL BE INSTALLED AROUND STOCKPILE AREA APPROXIMATELY 10 FEET FROM TOE OF SLOPE.
- 10. THE CONTRACTOR IS RESPONSIBLE TO INSPECT AND REPAIR EROSION AND SEDIMENTATION CONTROL MEASURES AS REQUIRED TO PREVENT DAMAGE OR SEDIMENTATION.
- 1. UPON COMPLETION OF CONSTRUCTION AND ESTABLISHMENT OF PERMANENT GROUND COVER. REMOVE AND DISPOSE OF TEMPORARY EROSION CONTROL MEASURES. CLEAN SEDIMENT AND DEBRIS FROM TEMPORARY MEASURES AND FROM PERMANENT STORM DRAINAGE SYSTEMS.



TURBIDITY CURTAIN DETAIL SCALE: N.T.S.

DISCHARGE HOSE FROM


2"x2" (NOMINAL) HARDWOÒD STAKÉ (MIN. LENGTH: 54") SELF-SUPPORTING SILT FENCE FABRIC OR FILTER FABRIC ATTACHED TO STAKE FINISH GRADE <u>FLOW</u> RECOMPACTED BACKFILL EXTEND 8" OF FABRIC DRIVE STAKE A BELOW GROUND MIN. 16" INTO THE GROUND **SECTION** 8' MAX. 8' MAX.




SILT FENCE NOTES:

1.) INSTALL SILT FENCE & WOOD STAKES AS RECOMMENDED BY MANUFACTURER. 2.) SYNTHETIC FILTER FABRIC SHALL BE A PERVIOUS SHEET OF PROPYLENE, NYLON, POLYESTER OR ETHYLENE FILAMENTS AND SHALL BE CERTIFIED BY THE MANUFACTURER OR SUPPLIER AS CONFORMING TO THE SPECIFICATIONS.

SILT FENCE SCALE: N.T.S.



TEMPORARY SOIL STOCKPILE SCALE: N.T.S.



SILT FENCE BACKED W/ STRAW BALES SCALE: N.T.S.

POST-CONSTRUCTION OPERATION & MAINTENANCE

1)STEP POOLS

A) INSPECT FOR PLANT SURVIVAL AND PROVIDE TEMPORARY IRRIGATION AS NEEDED UNTIL PLANTS MATURE

B) INSPECT AFTER EVERY RAINFALL EVENT IN THE FIRST SIX MONTHS; INSPECT SEMI-ANNUALLY AND AFTER SIGNIFICANT RAIN EVENTS (E.G. >0.5 INCH) THEREAFTER. I) INSPECT FOR EVIDENCE OF EROSION; RESTORE AS NECESSARY.

ÚTILIZE ORIGINAL DESIGN MATERIAL AND VEGETATION II) INSPECT INFLOW FOR CLOGGING AND REMOVE ANY SEDIMENT AND/OR DEBRIS III) FOR STEP POOLS, CHECK THAT OUTFLOWS FROM EACH POOL ARE

IN GOOD CONDITION AND DEVOID OF EROSION OR BLOCKAGES; REPAIR AS NECESSARY IV) CHECK THAT POOLS DEWATER WITHIN 48 HOURS AFTER STORMS V) CHECK STRUCTURAL STABILITY OF WEIRS, RIFFLES, POOLS, COIR

VI) REMOVE ACCUMULATED SEDIMENT EACH SPRING

VII) ENSURE THAT SURROUNDING DRAINAGE AREA IS STABLE AND FREE OF SEDIMENT AND DEBRIS VIII)INSPECT FOR PLANT HEALTH/SURVIVAL AND REPLACE DEAD OR DYING VEGETATION TO MAINTAIN PERCENT COVER AS DESIGNED IN SITE PLANS. DEVELOP A REINFORCEMENT PLANTING PLAN IF THE VEGETATION GENERATES A VEGETATIVE COVER OF LESS THAN 50%

WITHIN THE FIRST TWO YEARS OF OPERATION. C) IN SPRING: CUT BACK AND REMOVE PREVIOUS YEAR'S PLANT MATERIAL AND ACCUMULATED LEAVES D) AS NEEDED AFTER FIRST YEAR OF MAINTENANCE:

I) PRUNE AND WEED TO MAINTAIN APPEARANCE I) REMOVE TRASH AND DEBRIS

III) REPAIR ANY STRUCTURAL DAMAGE TO WEIRS, RIFFLES, POOLS, OR TIE-IN TO DOWNSTREAM CHANNEL IV) DO NOT DUMP OR STORE SNOW IN THE STRUCTURE.

2)ROAD-STREAM CROSSING

>0.5 INCH) THEREAFTER.

A) INSPECT FOR PLANT SURVIVAL AND PROVIDE TEMPORARY IRRIGATION AS NEEDED UNTIL PLANTS MATURE B) INSPECT AFTER EVERY RAINFALL EVENT IN THE FIRST SIX MONTHS; INSPECT SEMI-ANNUALLY AND AFTER SIGNIFICANT RAIN EVENTS (E.G.

I) CHECK FOR SCOUR OR EXCESSIVE EROSION OF STREAMBANKS AND STREAM CROSSINGS. REPAIR TO MATCH DESIGN GRADES AS NECESSARY. UTILIZE ORIGINAL DESIGN MATERIAL. II) REMOVE DEBRIS THAT COULD CAUSE DAMAGE TO THE STRUCTURE OR ANY BLOCKAGES THAT ARE ALTERING THE FLOW IN A MANNER THAT


MAY DAMAGE THE STRUCTURE OR CAUSE BANK EROSION. III)REPAIR DAMAGE CAUSED BY VEHICLES, EROSION, WILDLIFE, ETC. THAT AFFECT THE INTEGRITY OF THE STRUCTURE OR ADJACENT STREAMBANKS. IV)INSPECT FOR PLANT HEALTH/SURVIVAL AND REPLACE DEAD OR

DYING NATIVE VEGETATION TO MAINTAIN PERCENT COVER AS DESIGNED SITE PLANS. DEVELOP A REINFORCEMENT PLANTING PLAN IF THE VEGETATION GENERATES A VEGETATIVE COVER OF LESS THAN 50% WITHIN THE FIRST TWO YEARS OF OPERATION. C) CONDUCT AN ANNUAL VISUAL INSPECTION OF THE STRUCTURE;


FOLLOW-UP ON ANY DEFICIENCIES NOTED BY THE TOWN OR BY MASSDOT D) REMOVE BURROWING ANIMALS IN ACCORDANCE WITH LOCAL, STATE, AND FEDERAL GUIDELINES AND REGULATIONS E) DO NOT APPLY FERTILIZER.


F) IMPLEMENT LOW-IMPACT PEST MANAGEMENT CONTROLS IF PEST-CONTROL IS NECESSARY. EXAMPLES INCLUDE REMOVAL BY HAND, VACUUM, OR SPRAYING WATER. G) DO NOT DUMP OR STORE SNOW WITHIN THE STRUCTURE

H) DO NOT DRIVE VEHICLES AND HEAVY CONSTRUCTION EQUIPMENT INTO THE STRUCTURE I) DO NOT OBSTRUCT ACCESS TO AND AROUND THE INFRASTRUCTURE. ACCESS IS REQUIRED FOR MAINTENANCE PURPOSES.



<u>SIZING FORMULA:</u> CUBIC FT. OF REQUIRED STORAGE = PUMP DISCHARGE RATE (GPM) x 16





NOTES:

1. STRAW BALES FOR EROSION CONTROL SHALL CONFORM TO SECTION

1. STRAW BALES FOR EROSION CONTROL SHALL CONFORM TO SECTION

1. STRAW BALES FOR EROSION CONTROL SHALL CONFORM TO SECTION

1. STRAW BALES FOR EROSION CONTROL SHALL CONFORM TO SECTION

1. STRAW BALES FOR EROSION CONTROL SHALL CONFORM TO SECTION

1. STRAW BALES FOR EROSION CONTROL SHALL CONFORM TO SECTION

1. STRAW BALES FOR EROSION CONTROL SHALL CONFORM TO SECTION

1. STRAW BALES FOR EROSION CONTROL SHALL CONFORM TO SECTION

1. STRAW BALES FOR EROSION CONTROL SHALL CONFORM TO SECTION

1. STRAW BALES FOR EROSION CONTROL SHALL CONFORM TO SECTION

1. STRAW BALES FOR EROSION CONTROL SHALL CONFORM TO SECTION

1. STRAW BALES FOR EROSION CONTROL SHALL CONFORM TO SECTION

1. STRAW BALES FOR EROSION CONTROL SHALL CONFORM TO SECTION

1. STRAW BALES FOR EROSION CONTROL SHALL CONFORM TO SECTION


1. STRAW BALES FOR EROSION CONTROL SHALL CONFORM TO SECTION


1. STRAW BALES FOR EROSION CONTROL SHALL CONFORM TO SECTION CONTROL 767 OF THE STANDARD SPECIFICATIONS INCLUDING MATERIALS AND CONSTRUCTION METHODS. 2. BALES OF STRAW SHALL BE FASTENED WITH WIRE AND HAVE A

MINIMUM SIZE OF 1'x1.5'x3'. 3. STONE SHALL CONSIST OF 1-1/2 INCH STONE CONFORMING TO SUBSECTION M2.01.1 OF THE STANDARD SPECIFICATIONS. 4. FILTER FABRIC SHALL CONFORM TO A TYPE I FABRIC AS INCLUDED

WITHIN SECTION M9.50.0 OF THE STANDARD SPECIFICATIONS.

CONSTRUCTION DEWATERING DISCHARGE SETTLING BASIN SCALE: N.T.S.






TEMPORARY COFFER DAM SCALE: N.T.S.

2/16/202 EIL


S S

> SEDIMEN DETAILS ROSION

PROJ. No.: 20170390.G14 DATE: 02/16/2022







GRANITE CURB-

1. LENGTH OF CURB VARIES TO FIT RADIUS. 2 FT. MIN.


2. ENDS SHALL BE SQUARE TO TOP AND RADIAL TO FACE.

3. BUTT ENDS TOGETHER AS CLOSE AS POSSIBLE. MAXIMUM SPACE

└-GRAVEL BORROW


CEMENT CONCRETE


CEMENT CONCRETE LIMITS 🗝



CONCRETE FLARED END W/RIP RAP APRON SCALE: N.T.S.


C5.01





- 2. BIODEGRADABLE EROSION CONTROL MAT SHALL BE ABLE TO WITHSTAND 8 FPS WATER VELOCITIES AND 2.10 PSF SHEAR STRESS.

SCALE: N.T.S.



BIODEGRADABLE EROSION CONTROL MAT WITH LIVE STAKES (FOR SLOPES STEEPER THAN 3:1) SCALE: N.T.S.

Microtopography - Maximum Depth is 8 inches Wetland Mound -- Existing Ground Surface Microtopography Final surface roughness desired, no finish grading is desired.

DEPRESSION.

- 1. CUSTOMIZE SHAPES TO FIT EXISTING LANDSCAPE CONDITIONS IN A RANDOM ORDER. EXCAVATION AND MOUND AREAS ARE TO BE IRREGULAR IN SHAPE AND VARY IN DEPTH (SEE TYPICAL CROSS SECTION FOR EXAMPLE). LENGTH AND WIDTH RATIO OF
- DEPRESSION AND MOUND SHAPES SHALL NOT EXCEED 2:1. 2. MINIMUM TOPSOIL DEPTH IN AREAS FOR MICROTOPOGRAPHY SHALL BE 8 INCHES. WHERE THERE IS INSUFFICIENT TOPSOIL, SALVAGING AND SPREADING WILL BE REQUIRED TO ENSURE A MINIMUM LAYER OF 2 INCHES TOPSOIL THROUGHOUT THE
- 3. PROPOSED GRADING WITHIN JOHNSON BROOK AND ROADSIDE STREAM TO BE DONE IN ACCORDANCE WITH THIS DETAIL.

TYPICAL MICROTOPOGRAPHY CROSS SECTION SCALE: N.T.S.


EILL &07

2/16/2022



CONSTRUCTION DETAILS

PROJ. No.: 20170390.G14 DATE: 02/16/2022





6"± FROM TOP

1. MATS SHALL BE STAPLED TO SLOPE. REFER TO MANUFACTURERS INSTALLATION INSTRUCTIONS FOR DETAILS OF STAPLING PATTERN.

3. REFER TO MANUFACTURERS INSTALLATION INSTRUCTIONS FOR DETAILS ON INSTALLATION INCLUDING STAPLING PATTERN, OVERLAPPING DETAILS, EDGE EMBEDMENT, AND ANCHOR DETAILS. TO BE INSTALLED ON SLOPES 3:1 OR

BIODEGRADABLE EROSION CONTROL MAT







2/16/2022 KEILL

C5.03

PROJ. No.: 20170390.G14 DATE: 02/16/2022





JOHNSON BROOK RESTORATION CONSTRUCTION DETAILS

PROJ. No.: 20170390.G14 DATE: 02/16/2022

C5.04

DATE:
TO BE PLACED ON THE NORTHEAST AND SOUTHWEST GUARDRAIL TRANSITIONS. A SHEET SHOWING SIZE AND CHARACTER OF NUMERALS WILL BE FURNISHED. THE DATE USED SHALL BE THE LATEST YEAR OF CONTRACT COMPLETION AS OF THE DATE THE FIRST GUARDRAIL TRANSITION IS CONSTRUCTED.

FOUNDATIONS MAY BE ALTERED, IF NECESSARY, TO SUIT CONDITIONS ENCOUNTERED DURING CONSTRUCTION, WITH THE APPROVAL OF THE DESIGN ENGINEER OF RECORD.

UNSUITABLE MATERIAL: ALL UNSUITABLE MATERIAL SHALL BE REMOVED WITHIN THE LIMITS OF THE FOUNDATIONS OF THE STRUCTURE, AS DIRECTED BY THE DESIGN ENGINEER OF RECORD.

GEOTECHNICAL REPORT: REFER TO GEOTECHNICAL REPORT DATED JANUARY 20, 2020 PREPARED BY FUSS & O'NEILL.

REINFORCING STEEL SHALL CONFORM TO THE REQUIREMENTS OF ASSHTO M31, GRADE 60. EPOXY COATED REINFORCING BARS SHALL CONFORM TO THE REQUIREMENTS OF ASSHTO M284. UNLESS OTHERWISE NOTED ON THE

MODIFICATION COL	<u>NDITION</u>	#4 BARS	#5 BARS
. NONE		21"	["] 26"
2. 12" OF CONC	RETE BELOW BAR	29"	36"
S. COATED BARS	S, COVER < 3db, OR	31 "	39"
CLEAR SPACI	NG < 6db		
. COATED BARS	S, ALL OTHER CASES	25 "	31 "
5. CONDITION 2.	AND 3.	35 "	44"
6. CONDITION 2.	AND 4.	34"	43"

IF THE ABOVE BARS ARE SPACED 6" OR MORE ON CENTER, THE LAP LENGTH SHALL BE 80% OF THE THE LENGTH GIVEN ABOVE. ALL OTHER BARS SHALL BE LAPPED AS SHOWN ON THE CONSTRUCTION DRAWINGS. ALL REINFORCING BARS ANDSUPPORTING DEVICES SHALL BE COATED, UNLESS OTHERWISE NOTED.

CONSTRUCTION REQUIREMENTS AND PROCEDURES:

THE EXISTING BRIDGE TO BE REPLACED IS TO REMAIN CLOSED DURING CONSTRUCTION OF THE NEW BRIDGE REPLACEMENT. ADDITIONALLY THE CONTRACTOR SHALL TAKE THE PROPER PRECAUTIONS TO ENSURE THE STABILITY AND SAFE PERFORMANCE OF ALL STRUCTURAL ELEMENTS DURING DEMOLITION AND CONSTRUCTION. REFER TO APPROVED DEMOLITION / ERECTION PLANS.

DIMENSIONS SHOWN ARE TAKEN FROM SURVEY, ORIGINAL DESIGN DRAWINGS AND VARIOUS FIELD MEASUREMENTS AND ARE NOT GUARANTEED. THE CONTRACTOR SHALL DETERMINE AND ESTABLISH ALL DIMENSIONS AND DETAILS NECESSARY FOR COMPLETION OF ALL WORK BY FIELD MEASUREMENT AND SURVEY. THE CONTRACTOR SHALL BE RESPONSIBLE AND NOT ORDER ANY MATERIAL OF COMMENCE ANY FABRICATION UNTIL HE HAS MADE THE REQUIRED MEASUREMENTS ON THE ACTUAL STRUCTURE AND THE EXTENT OF THE PROPOSED WORK HAS BEEN APPROVED BY THE ENGINEER.

POLES WTC. WHEN LOCATING, TEMPROARILY RELOCATING AND PERMANENTLY RECONSTRUCTING ALL EXISTING AND NEWLY CONSTRUCTED UTILITIES AS NOTED HEREIN THROUGHOUT CONSTRUCTION. THE CONTRACTOR SHALL COORDINATE WITH RESPECTIVE UTILITY OWNERS ALL UTILITIES THAT ARE TO BE TEMPORARILY OR PERMANENTLY RELOCATED DURING ALL PHASES OF BRIDGE REPLACEMENT

AREAS SURROUNDING THE CONSTRUCTION SITE AND UTILITIES OUTSIDE THE LIMITS OF PROPOSED WORK DISRUPTED BY THE CONTRACTORS OPERATIONS SHALL BE RESTORED TO THEIR ORIGINAL CONDITION AT THE CONTRACTORS EXPENSE.

SEISMIC DESIGN CRITERIA	
DESIGN RETURN PERIOD:	XX
DESIGN SPECTRA	
As	0.071
SDs	0.130
SD1	0.037
SITE CLASS	С
SEISMIC DESIGN CATEGORY (SDC)	Α

	QUANTITIES*		
ITEM #	DESCRIPTION	QTY	UNIT
120	EARTH EXCAVATION	261	C.Y.
151.20	GRAVEL BORROW FOR BACKFILLING STRUCTURES AND PIPES	142	C.Y.
460	HOT MIX ASPHALT	12	TON
628.24	TRANSITION TO BRIDGE RAIL	4	EA.
903	3000 PSI, 1.5 INCH, 470 CEMENT CONCRETE	92	C.Y.
904	4000 PSI, ¾ INCH, 610 HP CEMENT CONCRETE	64	C.Y.
910.10	STEEL REINFORCEMENT FOR STRUCTURES - EPOXY COATED	10037	LB
915.36	ARCH FRAME UNIT (OVER 6 FEET WIDE— 30 TO 34.99 FOOT SPAN)	7	EA.
970	BITUMINOUS DAMP-PROOFING	218	S.Y.
975.10	METAL BRIDGE RAILING (3 RAIL), STEEL (TYPE S3-TL4)	89	FT

GUARDRAIL SCHEDULE					
LOCATION	SEGMENT	START STA.	END STA.	OFFSET FROM ROADWAY BL	
NE	TERMINAL CONNECTOR	3+74.53	3+72.85	18.0' LEFT	
NE	THRIE BEAM	3+72.85	3+60.40	18.0' LEFT	
NE	THRIE BEAM TRANSITION	3+60.40	3+54.13	18.0' LEFT	
NE	W BEAM	3+54.13	3+37.03	18.0' LEFT	
NE	FLARED END	3+37.03	3+12.11	18.0' LEFT	
NW	TERMINAL CONNECTOR	4+21.86	4+23.51	18.0' LEFT	
NW	THRIE BEAM	4+23.56	4+35.98	18.0' LEFT	
NW	THRIE BEAM TRANSITION	4+35.98	4+42.22	18.0' LEFT	
NW	W BEAM	4+42.22	4+59.11	18.0' LEFT	
NW	FLARED END	4+59.11	4+84.00	18.0' LEFT	
SE	TERMINAL CONNECTOR	3+78.12	3+76.46	12.0' RIGHT	
SE	THRIE BEAM	3+76.46	3+63.96	12.0' RIGHT	
SE	THRIE BEAM TRANSITION	3+63.96	3+57.71	12.0' RIGHT	
SE	W BEAM	3+57.71	3+51.59	12.0' RIGHT	
SE	FLARED END	3+51.59	3+26.30	12.0' RIGHT	
SW	TERMINAL CONNECTOR	4+25.44	4+27.11	12.0' RIGHT	
SW	THRIE BEAM	4+27.11	4+39.61	12.0' RIGHT	
SW	THRIE BEAM TRANSITION	4+39.61	4+45.86	12.0' RIGHT	
SW	W BEAM	4+45.86	4+62.94	12.0' RIGHT	
SW	FLARED END	4+62.94	4+87.90	12.0' RIGHT	

* QUANTITIES ON THIS SHEET DO NOT INCLUDE THE FULL SCOPE OF

THE PROJECT AND SHALL BE IGNORED FOR BIDDING PURPOSES.

COMMONWEALTH OF MASSACHUSETTS MassDOT, Highway Division TO MASSDOT FOR CONTRACTING DISTRICT TWO BRIDGE ENGINEER DATE

CONCEPTUAL DESIGN IS ACCEPTABLE

PROPOSED BRIDGE REPLACEMENT SOUTHWICK KLAUS ANDERSON ROAD OVER

JOHNSON BROOK

CITY OF SOUTHWICK

SHEET 1 OF 13 SHEETS BRIDGE NO. S-22-026 (C8X)

DESIGN SCOUR FLOOD EVENT

RETURN FREQUENCY (YEARS)

CHECK SCOUR FLOOD EVENT

RETURN FREQUENCY (YEARS)

FREQUENCY (IF KNOWN, YEARS)

MAXIMUM ELEVATION (FEET, NAVD)

DISCHARGE (C.F.S.)

DATE (MM/YYYY)

AND EROSION

HISTORY OF ICE FLOES

JANUARY 2021

EVIDENCE OF SCOUR

DESIGN FLOOD ABUTMENT SCOUR DEPTH (FEET)

CHECK FLOOD ABUTMENT SCOUR DEPTH (FEET)

FLOOD OF RECORD

DESIGN FLOOD PIER SCOUR DEPTH (FEET)

CHECK FLOOD PIER SCOUR DEPTH (FEET)

11/28/202

S



12.9

N/A

200

13.5

N/A

LUNKNOWN

UNKNOWN

UNKNOWN

UNKNOWN

UNKNOWN


UNKNOWN

PROJ. No.: 20170390.G11 DATE: NOVEMBER 2021

STR-1 CHIEF ENGINEER

REINFORCEMENT:

CONSTRUCTION DRAWINGS, ALL BARS SHALL BE LAPPED AS FOLLOWS:



TOP OF CURB EL. 250.88

- TOP OF NEW CONCRETE CULVERT

FOOTING

--- MEMBRANE WATERPROOFING

---PROPOSED GRADE (3% APPROX. SLOPE)

— EXISTING BROOK


SOUTHWICK KLAUS ANDERSON RD


FED. AID PROJ. NO. 3 14 PROJECT FILE NO.

STREAMBED MATERIAL

1. STREAMBED MATERIAL SHALL CONSIST OF NATURAL FIELD ROCK OR NATURAL RIVER ROCK OR CRUSHED ROCK.

- 2. STREAMBED MATERIAL MAY BE SALVAGED DURING EXCAVATION OF THE EXISTING STREAMBED.
- 3. EXCAVATED MATERIALS SHALL BE SAMPLED TO DETERMINE THEIR GRADATION. 4. ALL OFF-SITE STREAMBED MATERIALS SHALL
- CONFORM TO THE SAME GRADATION AS THE NATIVE MATERIAL.
- 5. EXCAVATE STREAM CHANNEL AND CONTOUR STREAM BANKS AS SHOWN ON PLANS. 6. PLACE STREAMBED SIMULATION MATERIAL ON A
- PREPARED SURFACE TO FORM A WELL-GRADED. UNIFORMLY DENSE, COMPACT, LOW PERMEABILITY MASS. SIMILAR IN APPEARANCE AND TEXTURE TO THE NATURAL STREAMBED.
- 7. PLACE STREAM SIMULATION ROCK IN ONE OR MORE LAYERS WITH A LAYER DEPTH LESS THAN 1 1 TIMES THE MAXIMUM DIMENSION OF THE STREAM SIMULATION ROCK.
- 8. FILL VOIDS BY MACHINE OR HAND TAMPING BEFORE PLACING NEXT LIFT.
- 9. COMPACT BED MATERIALS BY MECHANICAL MEANS SUCH AS PLATE COMPACTORS, LOADERS, ETC.
- 10. STREAMBED MATERIAL SHALL BE INSTALLED TO A MINIMUM DEPTH OF 18 INCHES IN RESTORED AREAS.





33.25

-1-1/2" ASPHALT TOP COURSE

∠—2-1/2" ASPHALT BINDER COURSE

EXISTING CONCRETE HEAD

-CENTERLINE OF NEW ASPHALT

__EXISTING ASPHALT

CULVERT

WATER LEVEL

EL 250.51 STA. 4+1.08

— PROCESSED AGGREGATE BASE

- MEMBRANE WATERPROOFING

(M1.03.1)

249.43

WALL TO BE REMOVED -

-CONCRETE SIDEWALK

12.0'

- APPROX. WATER LEVEL

PROPOSED & CHANNEL


EL. 242.1—

AUGUST 2019

┌── VA CURB

FINAL SHOP DRAWINGS AND COMPUTATIONS DETAILING THE PROPOSED RIGID FRAME DESIGN SHALL BE SEALED AND SIGNED BY A PROFESSIONAL ENGINEER REGISTERED IN THE COMMONWEALTH OF MASSACHUSETTS FOR FINAL CHAPTER 85 SECTION 35 REVIEW AND APPROVAL. ALL FINAL SHOP DRAWINGS AND DESIGN CALCULATIONS SHALL BE SUBMITTED TO THE ENGINEER AND MASSDOT FOR FINAL APPROVAL, ONCE APPROVED THE SHOP DRAWINGS

- ALL OVERALL FRAME DIMENSIONS INCLUDING THE SIZE AND SPACING OF STEEL REINFORCEMENT PROVIDED ARE SHOWN TO ESTABLISH THE SIZE OF THE PROPOSED OPENING AND BRIDGE TYPE. THE WIDTH'S AND THICKNESS OF ALL PRECAST CONCRETE ELEMENTS SHALL NOT VARY AND ARE TO BE PARALLEL AND ALIGNED WITH THE CONSTRUCTION BASELINE AS SHOWN ON THESE CONSTRUCTION DRAWINGS.
- PRECAST ELEMENTS: THE FABRICATOR IS RESPONSIBLE FOR THE DESIGN AND INSTALLATION OF LIFT HOOKS FOR ALL PRECAST ELEMENTS, PLANS PROVIDING SPACING AND LOCATION OF LIFTING DEVICES AND HANDLING STRESS CALCULATIONS, DESIGNED AND STAMPED BY A PROFESSIONAL ENGINEER REGISTERED IN MASSACHUSETTS FOR REVIEW AND APPROVAL. REINFORCING STEEL SHOWN ON AND ALONG THE RIGID FRAME MEMBERS SHALL
- 5. PRECAST CONCRETE FRAME UNITS SHALL CONFORM TO THE APPLICABLE PARTS OF THE SECTION 930 OF THE SPECIFICATIONS. ALL FOOTINGS, AND BRIDGE RAILING HEADWALLS SHALL BE CAST IN PLACE AS SHOWN ON THE
- 6. THE DESIGN OF THE FOOTINGS DETAILED HEREIN WAS BASED UPON THE GEOMETRY OF THE FRAME SHOWN.
- 7. CONCRETE FOR ALL PRECAST RIGID FRAME UNITS SHALL BE 5,000 PSI, 3 IN., 685 CEMENT CONCRETE.
- 8. FOOTINGS: THE PRECAST CONCRETE RIGID FRAME UNITS SHALL BE INSTALLED ON CAST-IN-PLACE CONCRETE FOOTINGS.




PROJ. No.: 20170390.G11 DATE: NOVEMBER 2021 STR-2

SEC


11/28/2023


AEII



SOUTHWICK KLAUS ANDERSON RD


STATE	FED. AID PROJ. NO.	SHEET NO.	TOT/ SHEE
MA	-	5	14
	PROJECT FILE N	0.	





BORING NOTES:

- 1. LOCATION OF THE BORINGS ARE SHOWN THUS: •
- 2. BORINGS ARE TAKEN FOR PURPOSE OF DESIGN AND SHOW CONDITIONS AT BORING POINTS ONLY, BUT DO NOT NECESSARILY SHOW THE NATURE OF THE AMTERIALS TO BE ENCOUNTERED DURING CONSTRUCTION.
- 3. BORINGS SHALL EXTEND TO THE SPECIFIED HIGHEST BOTTOM ELEVATION OR TO REFUSAL BELOW THE H.B.E., WHICHEVER IS DEEPER.
- 4. SHOULD BEDROCK BE ENCOUNTERED AT OR ABOVE THE SPECIFIED HIGHEST BOTTOM ELECATION, THE BORING SHALL BE CONTINUED AS A ROCK CORE BORING FOR A DEPTH OF 10', THEN TERMINATED.
- 5. BORINGS ARE LOCATED FROM THE BASELINE OF THE ROAD.
- 6. ADDITIONAL BORINGS MAY BE REQUESTED BY THE ENGINEER, IF NECESSARY



ISSUED FOR CONSTRUCTION FEBRUARY 2021 DESCRIPTION USE ONLY PRINTS OF LATEST DATE

SHEET 4 OF 13 SHEETS BRIDGE NO. S-22-026 (C8X)

DISTRICT TWO BRIDGE ENGINEER DATE

DATE: NOVEMBER 2021 STR-4


11/28/202


WEILL O



PROJ. No.: 20170390.G11

PRECAST FRAME LEG







SOUTHWICK KLAUS ANDERSON RD

PROJECT FILE NO.

FED. AID PROJ. NO. SHEET TOTAL NO. SHEETS

6 | 14





(NON-EXCAVATABLE).

COURSE FOR BRIDGES, PLACES IN 2" LAYERS AND COMPACTED WITH A MECHANICAL HAND—GUIDED TAMPER WITHIN 12 HOURS AFTER PLACING MEMBRANE WATERPROOFING.

- DRAPE MEMBRANE WATERPROOFING OVER CLOSED CELL FORM BACKER ROD.
- 3. APPROACH SLAB AND SEAT TO BE C.I.P 4,000 PSI, ₹ IN., 610 CEMENT CONCRETE.
- 4. PLACE TRANSVERSE REINFORCEMENT PARALLEL TO VERTICAL FRAME LEG.

COMMONWEALTH OF MASSACHUSETTS MassDOT, Highway Division CONCEPTUAL DESIGN IS ACCEPTABLE TO MASSDOT FOR CONTRACTING 12/8/21 DISTRICT TWO BRIDGE ENGINEER DATE

ISSUED FOR CONSTRUCTION FEBRUARY 2021 DESCRIPTION USE ONLY PRINTS OF LATEST DATE

SHEET 5 OF 13 SHEETS BRIDGE NO. S-22-026 (C8X)

PRECAST APPROACH SLAB SHELF DETAIL

STR-5

PROJ. No.: 20170390.G11 DATE: NOVEMBER 2021

BRIDGE DETAILS


11/28/2021

MEILL


9

8

FUSS



vate\dfs\CadProj\DWG\P2017\0390\G11\Civil\Structures\20170390G11_STR01.dwg Layout: STR-6 Plotted: Wed, November 24, 2021 - 3:15



e\dfs\CadProj\DWG\P2017\0390\G11\Civil\Structures\20170390G11_STR01.dwg Layout: STR-7 Plotted: Wed, November 24, 2021 - 3:18 PM User: j

PUSS

150 MAIN STR
SPRINGFIELD
413.452.0445
www.fando.com

WEILL

O

11/28/2023

K RESTORATION


-TL4 BRIDGE RAILING D
JOHNSON BROOK RESTORA

PROJ. No.: 20170390.G11 DATE: NOVEMBER 2021

STR-7

USE ONLY PRINTS OF LATEST DATE

SHEET 7 OF 13 SHEETS BRIDGE NO. S-22-026 (C8X)



PROJ. No.: 20170390.G11 DATE: NOVEMBER 2021 STR-8 SHEET 8 OF 13 SHEETS BRIDGE NO. S-22-026 (C8X)

USE ONLY PRINTS OF LATEST DATE




STA	re	FED. AID PROJ. NO.	SHEET NO.	T Sł
MA	`	-	10	
		PROJECT FILE N	0.	

CONST. JOINT

(RAKE FINISH)

∕2" CHAMFER

SEE NOTE 1



PRECAST GUARDRAIL TRANSITION


ELEVATION AT U-WINGWALL

SCALE: $\frac{1}{2}$ " = 1'-0"

FOR S3-TL4 RAILING AND S3-TL4 RAILING AT SAFETY

<u>CURB</u>

7'-4"



WINGWALL REINFORCEMENT AND STRIATIONS NOT SHOWN FOR CLARITY.

 $\frac{\text{SECTION 2}}{\text{SCALE: } \frac{1}{2}" = 1'-0"}$

1. $1\frac{1}{2}$ " H x 1" D GROOVE. ALIGN WITH GROOVE AT TOP OF STRIATIONS. 2. REINFORCEMENT OF THE TRANSITION TOP IS NOT SHOWN FOR CLARITY.

SEE NOTE

∽#5 @ 6" (TYP.)

←2" CHAMFER

___1" D x 2" W

TOP OF

ROADWAY-

V-GROOVE

SECTION 1

SCALE: $\frac{1}{2}$ " = 1'-0" FOR S3-TL4 RAILING AT SIDEWALK SIDE

TOP OF SIDEWALK —

¹" PREFORMED JOINT FILLER—

2" CL. (TYP.)


NOTES:


SECTION 1 SCALE: $\frac{1}{2}$ " = 1'-0" FOR S3-TL4 RAILING AT SAFETY CURB

22"

2021 ISSUED FOR CONSTRUCTION
DESCRIPTION
USE ONLY PRINTS OF LATEST DATE FEBRUARY 2021

SHEET 9 OF 14 SHEETS BRIDGE NO. S-22-026 (C8X)







STR-9


PROJ. No.: 20170390.G11 DATE: NOVEMBER 2021

11/28/2021

NEILL

FUSS&O']

TOWN OF SOUTHWICK
BOTTOM OF PRECAST HIGHWAY
GUARDRAIL TRANSITION FOR S3-TL4



File Path: \\private\dfs\CadProj\DWG\P2017\0390\G11\Civi\\Structures\20170390G11_STR01.dwg Layout: STR-10 Plotted: Wed, November 24

[MS VIEW: | LAYER STATE: | LAYER STATE


DATE: NOVEMBER 2021

STR-10

SHEET 10 OF 14 SHEETS BRIDGE NO. S-22-026 (C8X)

ISSUED FOR CONSTRUCTION
DESCRIPTION
USE ONLY PRINTS OF LATEST DATE

FEBRUARY 2021



DATE: NOVEMBER 2021 STR-11

ISSUED FOR CONSTRUCTION
DESCRIPTION
USE ONLY PRINTS OF LATEST DATE SHEET 11 OF 14 SHEETS BRIDGE NO. S-22-026 (C8X)

FEBRUARY 2021


STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
MA	1	13	14
	PROJECT FILE N	0.	

SLOPE BREAK SINGLE FACED: EDGE OF TRAVEL LANE EDGE OF USEABLE SHOULDER

PAVEMENT MILLING MULCH -


TOP OF PANEL -

FLUSH WITH ROADWAY



(TYPE A BERM SIMILAR)

A (AT FACE) 0" TO 6" AA (OFFSET) 6'-0" (MIN) N/A (SEE NOTE 5)



TYPE VA CURB (HMA CURB SIMILAR)

<u>TL-3</u> 0" TO 6" BB (OFFSET) 6'-0" (MIN) N/A (SEE NOTE 5)

NOTES:

- 1. TYPE VA CURB PER E 106.3.0.
- 2. HMA CURB PER E 106.2.0. 3. SLOPED EDGING PER E 106.5.0.
- 4. TYPE A BERM PER 106.1.0.
- 5. TL-3 GUARDRAIL SHALL NOT BE OFFSET FROM VERTICAL CURB AND SINGLE FACED TL-3 GUARDRAIL SHALL NOT BE OFFSET FROM SLOPED EDGING UNLESS OTHERWISE SHOWN IN THE PLANS OR THESE STANDARDS.
- 6. IN ORDER TO FACILITATE DESIGN AND CONSTRUCTION, THE OFFSET FROM THE CURB TO FACE OF GUARDRAIL DOES NOT HAVE TO BE SYMMETRICAL BETWEEN SIDES. ONE SIDE MAY BE LOCATED AT THE FACE OF CURB AND THE OPPOSITE MAY BE OFFSET.

2021 ISSUED FOR CONSTRUCTION
DESCRIPTION
USE ONLY PRINTS OF LATEST DATE FEBRUARY 2021

11/28/2021 NEILL

PROJ. No.: 20170390.G11 DATE: NOVEMBER 2021 STR-12

SHEET 13 OF 14 SHEETS BRIDGE NO. C-22-026 (C8X)

ISSUED FOR CONSTRUCTION FEBRUARY 2021 DESCRIPTION USE ONLY PRINTS OF LATEST DATE SHEET 14 OF 14 SHEETS BRIDGE NO. S-22-026 (C8X)


PROJ. No.: 20170390.G11 DATE: NOVEMBER 2021 STR-13

ACH GEOMETRY:

11/28/2023

EIL

&0'I



PROJ. No.: 20170390.G14 DATE: 02/16/2022 **TMP-01**