

CAST-IN-PLACE CLOSURE POUR NOTES:

1. THE EDGE SURFACE OF THE PRECAST CONCRETE DECK PANELS SHALL BE BLAST CLEANED AND WETTED WITH CLEAN WATER, IMMEDIATELY PRIOR TO PLACING CLOSURE POUR CONCRETE.
2. CLOSURE POUR CONCRETE SHALL BE PLACED AFTER LONGITUDINAL POST-TENSIONING IS COMPLETED.
3. CLOSURE POUR CONCRETE SHALL BE 4000 PSI, $\frac{3}{4}$ IN., 585 HP CEMENT CONCRETE.

(If required by project constraints, high early strength may be specified)



LRFD BRIDGE
MANUAL, PART III

CAST-IN-PLACE
CLOSURE POUR NOTES
PRECAST CONCRETE DECK PANELS

DATE OF ISSUE
JUNE 2013

DRAWING NUMBER

5.1.22