CHAPTER 4 FIELD INSPECTION, DATA COLLECTING, REPORT WRITING AND REPORT REVIEW

4.1 INTRODUCTION

In this chapter, MassDOT policies and procedures for performing bridge inspections are presented. This chapter will also discuss conducting the field inspections, data collecting, report writing and report review. In addition, the policy for reporting and addressing "Critical" findings is outlined. As mentioned in Chapter 3, inspections performed in Massachusetts are "hands on", and all inspections are performed by NBIS qualified Team Leaders with the assistance of one or more team members.

Bridge inspections and inspection reports that are developed are essential for protecting lives and for protecting the public's investment in bridge structures. The Bridge Inspection Management System (4D) includes the reports that correctly and efficiently evaluate the condition of a structure. This information is also a valuable aid in establishing maintenance and replacement priorities. Finally, inspection reports are stored in 4D and are also used for determining a structure's load carrying capacity.

The information necessary to make these determinations must come largely from the bridge inspection reporting system. The importance of the reporting system cannot be over emphasized as the success of any bridge inspection program is dependent upon its reporting system. A new inspection report shall be created each time a bridge is inspected. To achieve maximum effectiveness, each report should be supplemented with sketches, photographs, or any other additional explanatory information. Reports and supplemental information must be accurate, and descriptions or explanations shall be clear and concise.

4.2 STANDARD INSPECTION REPORT FORMS

The standardization of the inspection forms is a necessary step for a uniform bridge inspection reporting system. Prior to performing inspections for MassDOT, one should be aware of the standard inspection report forms available in the 4D system. In Chapter 3, the types of inspections commonly performed were briefly explained. Standardized forms have been created to assist in the report preparation and review process. These forms also provide a uniform method for querying information pertaining to the elements and sub-elements of a structure for prioritization of maintenance repairs. The Standard Inspection Forms used are:

- Initial Inspection Report
- Routine Inspection Report
- Routine Arch Inspection Report
- Routine Culvert Inspection Report
- Routine Underwater Inspection Report
- Routine Segmental Box Girder Inspection Report*
- Other Inspection Report
- Routine Movable (Mechanical/Electrical) Inspection Report*
- Routine Closed Inspection Report
- Special Member Inspection Report
- Routine & Special Member Inspection Report



- Fracture Critical Inspection Report
- Damage Inspection Report
- Divers Activity Report
- Underwater Special Member Report
- Underwater Low Clearance Report
- Element Level Inspection Report (AASHTOWare Bridge Management)

* Not available in 4D.

4.3 SI&A SHEET

The Structure Inventory and Appraisal (SI&A) sheet is a tabulation of pertinent elements of information about an individual structure. It includes data that is required by the Federal Highway Administration (FHWA) to effectively monitor and manage the National Bridge Program. Such data is submitted annually to the FHWA and comprises the National Bridge Inventory database. The SI&A sheet also includes information specific to the needs of MassDOT.

There are three formats available on 4D for the SI&A sheet. The three formats are:

- 1. Inventory
- 2. For Inspection
- 3. MA Specific

The first two formats are very similar but have certain unique items. The "For Inspection" format includes accessibility information while the "Inventory" format includes projected future project costs. In most cases the "For Inspection" format should be used, which is the default format within 4D. The "MA Specific" format, as it suggests, is a collection of data utilized by MassDOT.

The SI&A sheet is not an inspection form but it is to be included with each inspection report submission. Bridge inspection personnel shall become familiar with all of the data items appearing on the SI&A sheet. Descriptions and explanations of the FHWA required data are provided in the FHWA's Recording and Coding Guide for the Structure Inventory and Appraisal of the Nation's Bridges. Massachusetts specific items are described in MassDOT's Supplemental Coding Guide included in Chapter 9.

Responsibility for the accuracy of the data appearing on the SI&A sheet is shared between the Boston Bridge Inspection Headquarters and the District Bridge Inspection Units. A clarification of which items are to be confirmed/revised and by who is provided in Chapter 9.

4.4 ELEMENT LEVEL INSPECTIONS

Element Level Bridge Inspection Data (ELBID) (formerly PONTIS Core Element Data) is to be collected and entered into the BIMS (4D) with every Routine Inspection. Also, when requested by the District Bridge Engineer to perform an inspection outside of the established frequency, for the documentation of repairs performed on the structure a revision to the ELBID shall be performed. A hard copy of the Element Level Data is to be attached to the inspection report. Please refer to the AASHTO Guide Manual for Bridge Element Inspection.



Bridge elements to be collected include National Bridge Elements, Bridge Management Elements and Agency Developed Elements as appropriate. Typically, quantities for each bridge element shall be calculated during the Initial Inspection. Ideally the quantities will be calculated from the as-built plans.

At each Routine Inspection, the Team Leader is to identify the quantity of each bridge element that can be categorized as being in each of the four condition states. Guidelines for the assessment of conditions for each condition state can be found in the AASHTO Guide Manual, see Attachment 4-1 for a quick reference guide for the Element Level Condition States.

For bridges that have an underwater inspection, the Team Leader is to also include Element Level Bridge Data collected by the Dive Team. At the time of publication of this Handbook, the underwater inspectors do not have the capability of inputting the Element Level Data into 4D.

It is of the utmost importance that Element Level Inspection Data mirrors the NBI condition ratings for each inspection report submission. The Element Level evaluation is to be reviewed by the DBIE and the ABIE with as much scrutiny that the NBI inspection report receives to assure consistency in the reporting.

The information contained in the Element Level Data is utilized by MassDOT in assessing the placement of structures on the Bridge Prioritization Model.

4.5 FIELD INSPECTIONS

All inspections performed shall be by Teams lead by Team Leaders, where at least two inspectors are on the site at all times, for safety reasons. It is understood that at times additional data or clarification may be required after the bulk of an inspection has been completed, and a team leader may visit the site for clarification as long it is safe do so. The Team Leader (TL) is the principle person in charge of the inspections. Work assigned by the TL during the inspection to the team members is ultimately the responsibility of the Team Leader.

4.5.1 Field Inspection for Initial Inspections

Initial Inspections are to be performed on the following: completed structures after they have undergone rehabilitation; newly constructed structures; or structures being added to the inventory for the first time.

It is understood, that during an Initial Inspection of a structure, the inspection team shall thoroughly examine all elements and state any irregularities observed in the Initial Inspection report. The secondary purpose of this inspection is to document the "as built" condition. Inspectors should also document any details in the main carrying members that differ from the construction drawings.

At a minimum the following shall be evaluated: beams should be evaluated for vertical alignment (plumb) and the presence of camber both positive and negative; if bearings exist they should be evaluated based on the type of bearing system present; guardrail and bridge railing alignment should be checked for both vertical and horizontal alignment; curb reveal measurements and locations where measurements were taken shall be obtained; substructure elements should be checked for vertical alignment. Photos of the elements above shall be stored as part of the history file for reference in the future to evaluate changed conditions when encountered.



For non-dive bridges it will be necessary to take stream bed profiles at both the upstream and downstream fascia to obtain an as built profile. This could be used in the future to determine if a scour is occurring and re-evaluation of Item 113 is required. Above water inspectors are to take the measurements. In some cases the measurements can be taken with drop lines from the bridge deck. If stream flow is too swift for drop lines other methods may be required. The data can be presented in chart form or in graph form or both. Points of measurement and elevation references must be clearly stated. Whatever method is chosen for use, it is important that it be repeatable from cycle to cycle. The value of the information is in the comparison from inspection to inspection to recognize major bed changes.

4.5.2 Field Inspection for Special Member Inspections

Team Leaders shall give Special Member Inspections their highest priority in their monthly scheduling. As such, every attempt shall be undertaken to perform Special Member inspections at the beginning of every month. If a Special Member Inspection is to be done in conjunction with a Routine Inspection, then both the Routine and Special Member Inspections shall be attempted to be completed at the beginning of the month.

The documentation of repairs performed on a structure shall be reported in the Special Member Inspection Report. As previously mentioned, Section 4.4, the ELBID shall also be updated and included in the submission of the inspection report.

Team Leaders shall be cognizant to inspect all structural components of a Special Member Element. For example, if the Special Member on a structure is for Item 59.4; Girders or Beams, and the inspection is to inspect the girder ends of 2 particular girders, then it shall be expected that the Team Leader will not only inspect the 2 particular girder ends, but shall inspect and document the deficiencies on all girders and beams for that particular detail and surrounding environment.

4.5.3 Field Inspection for Damage Inspections

Upon notification of an Incident, the DBIE shall dispatch an Inspection Team to the structure. The DBIE shall then concurrently notify the District Bridge Engineer and the Area Bridge Inspection Engineer. The Area Bridge Inspection Engineer will then notify the Bridge Inspection Engineer, who in turn will notify the State Bridge Engineer. The District Bridge Engineer, DBIE and inspection staff should be aware that a request for incident response may occur at any time of day or night.

Damage Inspection for verification of reported damage does not require extensive in-depth inspection of all members of the structure, but a cursory investigation to observe if the reported damage has affected other components or if damage is hiding or causing other damage or overstress. In addition, inspection should cover areas other than the immediate area of damage impact. This means Inspectors must assess the interconnectivity of the bridge elements to determine the paths that the initial impact force could have taken to inflict damage to other elements. Inspectors shall inspect and identify members or areas where items are disconnected or loose and could vibrate free, and are removed or directed to be removed by appropriate forces.

For example, diaphragms can transmit the initial impact force to other interior beams, causing localized damage around the diaphragm connections. Also, when reporting the information from a damage inspection, the inspector must obtain measurements to a known referenced fixed point on the structure.



When damage is verified and deemed to be a danger to pedestrians and/or vehicles, the site shall not be left unattended until the custodial owners have arrived and are preparing to respond with the necessary safety precautions. The Inspection Team shall document the safety precautions implemented in the Damage Inspection Report.

In situations where a repair cannot be performed immediately, after the appropriate maintenance forces have installed the hazard prevention devices, the District Bridge Inspection Engineer, with the concurrence of the District Bridge Engineer, shall establish a schedule for inspection to monitor and verify that the barricades and hazard prevention devices have not moved and are still effective until the danger has been resolved.

When a damage incident is reported by the District, and the Inspection Team has responded, inspected and written the Damage Inspection Report, the time associated with those activities shall be charged to the Reimbursable Cost Code generated by the District for that particular incident, if one has been generated.

4.5.4 Field Inspection for Scour Critical Structures

For bridges that have been determined to be Scour Critical it will be necessary to take stream bed profiles at both the upstream and downstream fascia to comply with the FHWA mandated Scour Plan of Action (POA). Scour Critical bridges have a numerical coding for Item 113 of 3 or less. For bridges that have underwater inspections, the stream bed profiles will be obtained by the Underwater Inspection Unit as part of their inspection. For non-dive bridges, the above water inspectors are to take the measurements. In some cases the measurements can be taken with drop lines from the bridge deck. If stream flow is too swift for drop lines other methods may be required. The data can be presented in chart form or in graph form or both. Points of measurement and elevation references must be clearly stated. Whatever method is chosen for use, it is important that it be repeatable from cycle to cycle. The value of the information is in the comparison from inspection to inspection to recognize major bed changes.

4.5.5 Plan of Inspection

In order to make the inspection as orderly and systematic as possible, the inspector should plan the inspection in advance. The plan shall include the review of previous inspections; load rating report; fracture critical procedures (if applicable); and SI&A. In addition, a plan includes determining the appropriate inspection sequence, establishing a time schedule, preparing for special inspection requirements (e.g. non-destructive testing and underwater inspection), organizing the field notes, anticipating the effects of traffic control procedures, and facilitating a thorough and complete inspection.

Prior to the actual inspection of a structure, the inspection team leader shall coordinate any and all parties (i.e.; RR flaggers, Police details, traffic set up, etc.) that may be required to accomplish the inspection. It is advisable that the team leader scope the bridge prior to the inspection to evaluate entry points, means of inspection, and any other aspects that may be required to inspect the structure.

The Team Leader shall be aware of the data needed for the particular inspection being performed. At times special requests are made and it is essential that all data is collected during the inspection. Once the Team Leader has reviewed the Load Rating Report, he/she may feel that a new rating may be warranted. In such cases the inspection will require in depth documentation and additional time to complete for the

preparation of a new load rating. Discussions with the District Bridge Inspection Engineer should occur so that other scheduled inspections get reassigned if needed.

4.5.6 Orientation

The orientation and numbering of bridge elements should be as shown on the plans whenever available. When plans are not available the rating report should be used. If no rating report exists, then the numbering of piers, beams, etc. shall be orientated from west to east, or from south to north.

It is important that the orientation of each element be clearly established. Orientation for rivers and streams is looking downstream. That is the left bank is on your left as you face downstream and the right bank is on your right as you face downstream. For tidal rivers, downstream is in the direction of the ebb (outgoing) tide.

Some examples:

- Identify substructure units (abutments) and sides of floorbeams, such as north/south or east/west designations; alternately, number the substructure units (piers) such Pier #3
- Sides of members can be identified by direction (e.g. "south side of floorbeam #2" or "north side of Pier #4")
- Span numbers and bay numbers should be used to identify general areas on the bridge, as shown on plans or as established otherwise
- Upstream or downstream designations can be assigned to structures over waterways (e.g., "upstream truss", "downstream girder", or "upstream arch")
- For truss elements, identify the member with joint designations

If the orientation used during the inspection differs in any way with that used in existing documents, these differences shall be clearly stated in the inspection report under the general remarks section of the inspection report.

4.5.7 Condition Information

To ensure a comprehensive condition inspection and as a part of the requirements of record keeping and documentation, an inspector shall record the type, size, quantity, severity and location of deterioration and deficiencies for each applicable element in a given component. The Bridge Inspectors Reference Manual (BIRM) and the Manual for Bridge Evaluation (MBE) are the inspectors' guide for identifying the members and the deficiencies on a variety of structure types.

The condition rating guidelines contained in the 1995 Recording and Coding Guide for the Structure Inventory and Appraisal of the Nation's Bridges (or most recent) are to be used in the evaluation of the deck, superstructure, and substructure. During the inspection, the inspector shall be aware of items in the SI&A that must be verified and updated, should it be required.

The outcome of the inspection shall always be to provide a clearly presented narrative description of the conditions. Inspectors shall note the following: all signs of distress, failure, or defects with sufficient accuracy so that another inspector at a future date can make a comparison of condition or rate of deterioration; load, speed, or traffic restrictions on the bridge; information about high water marks and unusual loadings, the presence of any negative camber on any elements, and section losses to beam ends.

All work or repairs to the bridge since the last inspection should be documented. If work is undertaken on a structure that improves the physical condition of a structure and results in the Team Leader increasing the numerical value of an element, the Team Leader must explain what work was undertaken to improve the condition. Verify or obtain new dimensions when maintenance or improvement work has altered the dimensions of the structure.

The end result of the inspection performed is to ensure the public that a safe structure is in place to carry traffic. The data collected on defects found helps with the determination of the safe load carrying capacity of the structure. The documentation will assist the custodian of the structure with important information for the proper maintenance and rehabilitation information. Consistency in coding, data collection and documentation is discussed in subsequent sections.

4.5.8 Critical Inspection Findings

Deficiencies are occasionally discovered during bridge inspections that require immediate action. They can be structural in nature such as a severely undermined girder bearing or they may present a hazardous situation to the travelling public. When such deficiencies are discovered a special procedure of notification is warranted as explained below.

4.5.8.1 Critical Structural (CS/I) Definition and Notification

If a deficiency is discovered that may affect the structural integrity of the bridge, it is considered a Critical Structural Deficiency. A Critical Structural Deficiency is defined as a deficiency in a structural element of a bridge that poses an extreme unsafe condition due to the failure or imminent failure of the element which will affect the structural integrity of the bridge. Because of the critical nature of the deficiency must be Immediate. To assure an immediate response the details of the deficiency must be transmitted quickly. During an inspection, if an inspector discovers a Critical Structural deficiency, the inspector shall immediately notify the DBIE, or in his absence, the DBE. For more information, refer to Section 4.7 of this Handbook regarding CS/I documentation.

4.5.8.2 Critical Hazard (CH/I) Definition and Notification

If a deficiency is discovered that poses an extreme hazard or unsafe condition to the public, it is considered a Critical Hazard. A Critical Hazard condition is defined as a deficiency in a component or element of a bridge that poses an extreme hazard or unsafe condition to the public, but does not impair the structural integrity of the bridge. Because of the critical nature of the deficiency the urgency code must be Immediate. To assure an immediate response the details of the deficiency must be transmitted quickly. During an inspection, if an inspector discovers a Critical Hazard deficiency, the inspector shall immediately notify the DBIE, or in his absence, the DBE. For more information, refer to Section 4.7 of this Handbook regarding CH/I documentation.

4.5.9 Request for Re-Evaluation of Item 113 - Scour Critical Bridges

The Team Leader must be aware, able to recognize and document changes that are occurring in the stream bed in the vicinity of the structures. These changes, documented by inspections, are to be used to assist the DBIE in determining if the request for a re-evaluation of Item 113 - Scour Critical Bridges is necessary. A re-evaluation does not just apply to structures with Item 113 less than or equal to a

Massachusetts Department of Transportation Highway Division

numerical rating of 3. A re-evaluation may be necessary for structures with Item 113 greater than a 3. If a re-evaluation is required, then the Bridge Scour – Item 113 Re-evaluation Form will be filed out and submitted to the Area Bridge Inspection Engineer, see Attachment 4-2.

Some concerns the Team Leader shall be aware of and document are as follows:

- Channel changing course
- Evidence of erosion or scour around footings and embankments
- Large amounts of debris around the substructure
- Evidence of rip rap, bank protection removed or altered
- Stream work performed by others that might change the hydraulic characteristics at the bridge

All of the concerns mentioned above could result in a request for a re-evaluation.

In Summary, a request for an Item 113 re-evaluation shall be submitted for the following cases

- When a structure over water has been replaced
- Substructure scour repairs performed and/or streambed scour countermeasures have been installed on a structure that is scour critical
- Significant changes mentioned above have occurred that alter the stream bed or flow characteristics of the waterway

4.5.9.1 Structure over Water That Has Been Replaced

When a structure over water has been replaced, the DBIE will be required to forward the Initial Inspection to the ABIE who will then submit the report to the Bridge Engineer for an initial coding of Item 113.

4.5.9.2 Substructure Scour Repairs Performed and/or Stream Bed Scour Countermeasures Installed

When a structure is scour critical and has had scour repairs performed on the substructure and/or stream bed scour countermeasures have been installed, the DBIE will be required to forward the Inspection that documents the improvements to the ABIE, who will then submit the report to the Bridge Engineer for re-evaluation of Item 113 coding.

4.5.9.3 Stream Bed or Waterway Changes

The Team Leader shall compare the stream bed profiles being collected and waterway changes to what was documented in past inspections. The loss of the stream bed material, or change in flow characteristics may warrant the re-evaluation of the Item 113 to ensure proper coding and structural stability. The DBIE will submit these Inspection Reports with the documented findings on the streambed changes to the ABIE who will submit the report to the Bridge Engineer for re-evaluation of Item 113 coding.

4.5.10 Reporting of Structurally Deficient Bridges

When a Team Leader inspects a structure and observes a condition that warrants a lowering of the numerical condition coding of a structure to a 4, or from a 4 to a 3, for Item 58, Item 59, Item 60, or Item

62, they shall notify the District Bridge Inspection Engineer. Preferably, this notification shall be done while the Team Leader is still at the structure, so as to allow the DBIE the opportunity to come to the structure to observe and concur with the Team Leader's decision. The intent of notifying the DBIE would be to ensure Items 90 thru Item 92 are coded in a timely manner so that the next inspection is undertaken.

4.5.11 Other Information Gathered at Routine Inspections

4.5.11.1 Request for Rating or Re-rating

The Team Leader shall be responsible for recommending a rating request or a re-rating request for a structure. This recommendation shall be stated in the request for rating or re-rating block located on the 2^{nd} page of the Routine Inspection Report or 1^{st} page of a Special Member Inspection Report. The Team Leader shall evaluate the deficiencies observed on the structure and any alterations made to the structure, in relation to the previous rating report, which would warrant a recommendation to rate or re-rate a structure.

4.5.11.2 Curb Reveal Measurements

The average curb reveal measurement should be used in documenting the curb reveal on the inspection report. The curb reveal measurement is taken primarily to identify if additional pavement material has been added to the structure since the last inspection. The measurement should be made to the nearest 10 mm. If there is no curb, then a measurement should be taken from the parapet, either the top or lowest break line and the point of reference should be clearly defined so that future measurements can be repeated. The reference point shall be stated in the curb comments of the inspection report.

4.5.11.3 Vertical Clearance Measurements & Vertical Clearance Signage Verification

Inspection Teams are required to check the low point vertical height clearances under a bridge, or through a bridge in the case of thru truss bridges, or both. The low point clearance is taken within the traveled way. The travel way is defined as the roadway lane that is allowing travel on a regular basis. Team Leaders should use their judgment when accessing a roadway traveled way. For example, if a roadway has a breakdown lane that travel is permitted on a regular basis, then the clearance will need to be verified at the outer limits of the breakdown lane. Team leaders should not adjust clearance measurements because the travel way is being altered for the convenience of a construction project.

Vertical clearances shall be taken during every routine or damage inspection performed. However, it is understood that it should not be different unless a change condition has occurred to the wearing surface below the structure or on the structure as in the case of a thru truss bridge. This verification frequency will ensure accuracy of the data being recorded at the time of the inspection. The location of the low point(s) should be clearly identified on a framing plan incorporated into the inspection report, see Attachment 4-3. Team Leaders shall place a note in the general remarks when they do not verify the vertical clearance and the reason why.

When the inspection team field verifies the vertical clearance height is less than 14'-6", then the team shall verify the placement of any clearance posting signs in the field during the inspection. Note if any of the "advanced" clearance posting signs or "at bridge" clearance posting signs are missing, then the Team Leader shall notify the DBIE of the missing signs and the location of the missing signs.

In relation to the discussion in this article, it is appropriate to define the "At Bridge" and "Advanced" clearance posting sign terms:

At Bridge Clearance Posting Signs: Signs erected immediately in advance of, or on the bridge being posted.

Advance Clearance Posting Signs: Signs placed at approach road intersections or other points where a vehicle which exceeds the posted limits must detour or turn around.

There are no Massachusetts General Law requirements for installing clearance posting signs, however in order for a bridge to be considered properly clearance posted, an At Bridge Sign must be either within visible distance of the structure or attached to the structure and be erected facing each direction of traffic. If there is an intersecting street between the sign and the bridge, an additional sign must be erected immediately adjacent to the bridge. These additional signs must be in place in order for the bridge to be considered properly posted.

When the inspection team field verifies that the vertical clearance is equal to or exceeds 14'-6", then the team leader shall record the measurement and check off the "not applicable" box in the area of the report dedicated for "Clearance Posting" on the inspection report. Further discussion of clearance posting sign procedure is contained in Section 4.8 of this Handbook.

4.5.11.4 Weight Posting Verification & Weight Posting Signage Verification

The Team Leader shall review the latest rating report of the structure to be inspected, if one exists, so as to obtain any recommended posting for the structure. The Team Leader shall verify the actual weight posting for the structure in the field and compare it to the recommended weight posting contained in the rating report. The actual and recommended weight posting values shall be stated in the "weight posting" area of the inspection report. If a discrepancy exists between the actual and recommended weight posting recommended weight posting the DBIE of his findings.

The Team Leader shall verify the "at bridge" and "advanced" weight posting signs are in place and are accurate for all structure that require posting.

Further discussion of the actions to be taken by the DBIE when discrepancies are encountered shall be contained in Section 6.11 of this Handbook.

4.5.11.5 Average Daily Traffic

At every Routine Inspection the inspector shall refer to the MassDOT website location to obtain traffic data counts for the structure being inspected. The website is at the MassDOT TransNet site. Click on Highway, then Quick Links, then Departments, under Design and Engineering, click Traffic Data Collection. In the first paragraph there is a link to the interactive map. Zoom in to your area of interest. The map shows where the latest traffic counts have been taken and the year.

If there are no traffic counts available on the website, then a manual vehicular and truck traffic count on the structure shall be undertaken. The counts shall be performed and the SI&A shall be marked with the time the counts where taken and number of vehicles observed. The counts can then be calculated using

ImassDOI Market Department of Transportation Hyphyway Division Field Inspection, Data Collecting, Report Writing and Report Review

the formulas and example attached in Attachment 4-4. Other instructions on what will be recorded in Items 29, 30 and 109 of the SI&A are in subsequent sections.

The Team Leader should use his/her judgment as to whether or not the traffic counts at the MassDOT website are still relevant. This could depend on how old the count is, whether traffic patterns have changed for the area, etc. If the TL suspects that the counts may not represent current traffic conditions then the team should obtain a manual count as described above.

4.5.11.6 Inventory Photos

During the Initial Inventory Inspection, a series of photographs shall be taken to document the structure for inventory purposes. At a minimum, the following views shall be taken:

- Two photographs of the roadway on the bridge, one from the approach roadway at each end of the bridge, taken such that the near guardrail-bridge rail transition is clearly visible
- Two elevation photographs, one of each elevation of the bridge
- One photograph of the general underside of the bridge
- If the bridge is over water, two photographs, one looking upstream and the other downstream from the bridge

If the bridge has any unusual features or characteristics, a photograph should be taken of them for inventory purposes as well. If the bridge has a commemorative plaque, or multiple commemorative plaques attached to the structure, a photograph of each plaque shall be taken and included in the inventory photos. The photo shall be taken directly perpendicular to the plaque with a measured scale, such as a tape measure or folding ruler, placed adjacent to the plaque within the photograph so that its true size can be obtained in case it needs to be duplicated in the future.

During the life of the bridge, this series of inventory photographs shall be repeated every ten years unless conditions at the bridge have changed dramatically before the ten year time period is out, rendering the previous set obsolete. These photos shall be saved in the 4D database.

4.5.11.7 Stream Bed Profiles

For all bridges over water that are non-dive bridges, the Team Leader will take stream bed profiles measurements at both the upstream and downstream fascia and record this in the inspection reports. In some cases, the measurements can be taken with drop lines from the bridge deck. If stream flow is too swift for drop lines other methods may be required. The data can be presented in a chart form or in graph form, or both. Points of measurement and elevation references must be clearly stated. Whatever method is chosen for use, it is important that it be repeatable from cycle to cycle. The value of the information is in the comparison from inspection to inspection to recognize major bed changes.

For bridges that have underwater inspections, the stream bed profiles will be obtained by the Underwater Inspection Unit as part of their inspection.

4.6 INSPECTION DOCUMENTATION and REPORT WRITING

4.6.1 Creation of Inspection Report

Team Leaders are responsible for the creation of the inspection report record in the Bridge Inspection Management System (4D). The report record shall be created in the system while the field inspection is occurring. If it is not created while inspection is ongoing it shall be in the system no later than 3 days after the inspection has been completed. It is understood that the creation of this record as a duplicate of the previous inspection is acceptable. In no way will this inspection report be construed as the actual inspection report until the Team Leader has committed the report for review.

4.6.2 Date of Inspection

When inspections are performed over multiple days, the start date of the inspection should always be used for the report and SI&A coding. The start date is the date that elements are actually inspected (a recon of a structure shall not be considered as a start date). This is especially important when inspections are started in one month but completed in the next month.

When inspections are delayed for access issues such as construction operations or right-of-entry permit acquisition, the inspection team should complete as much of the inspection that is physically possible and complete an inspection report depicting the areas and elements inspected. The report should clearly state the limits of the inspection and explain which areas were not inspected and why. When access for the other areas is granted and/or possible, the TL should then return to the bridge to complete an "Other" inspection with its own date of inspection.

4.6.3 Inspection Defects

In the inspection of a structure, a Team Leader may discover faults, flaws and imperfections to the structural elements. These defects should be identified and described by their type, size and location. The Team Leader shall document the defect and describe the seriousness of the defect in the body of the inspection report. If, in the opinion of the Team Leader, an observed defect could receive CORRECTIVE ACTION, then it is to be considered a DEFICIENCY.

4.6.4 Inspection Deficiencies

The Team Leader shall assign a deficiency code to any observed defects that require corrective action. A deficiency code consists of a Deficiency Category and an Urgency Code. The complete Deficiency Code is entered in the column adjacent to the sub-elements condition rating on the Routine Inspection Report. The code is similarly entered on Special Member and Fracture Critical Inspection Reports as needed.

Deficiencies are classified into four categories. The categories are as follows:

M = Minor Deficiency:Deficiencies which are minor in nature, generally do not impact
the structural integrity of the bridge and could easily be repaired.
Examples may include but are not limited to: Spalled concrete,
Minor pot holes, Minor corrosion to steel, Minor scouring,
Clogged drainage, Minor damage to guard rail, etc.

Massachusetts Department of Transportation

S = Severe/Major Deficiency:	Deficiencies which are more extensive in nature and need more planning and effort to repair. Examples may include but are not limited to: Moderate to major deterioration in concrete, Exposed and corroding rebars, Considerable settlement, Considerable scouring or undermining, Moderate to extensive corrosion to structural steel with measurable loss of section, etc.
C-S = Critical-Structural Deficiency:	A deficiency in a structural element of a bridge that poses an extreme unsafe condition due to the failure or imminent failure of the element which will affect the structural integrity of the bridge. All Critical-Structural Deficiencies need Immediate corrective action.
C-H = Critical-Hazard Deficiency:	A deficiency in a component or element of a bridge that poses an extreme hazard or unsafe condition to the public, but does not impair the structural integrity of the bridge. Examples may include but are not limited to: Loose concrete hanging down over traffic or pedestrians, A hole in a sidewalk that may cause injuries to pedestrians, Missing section of bridge railing, etc. All Critical-Hazard Deficiencies need immediate corrective action.
Urgency codes are classified into three	categories. The categories are as follows:
P= Prioritize:	Shall be prioritized by District Bridge Engineer or the Responsible Party (if not a State bridge) and repairs should be made when funds and/or manpower available.
A= As soon as possible:	Action/Repair should be initiated by District Bridge Engineer or the Responsible Party (if not a State bridge) upon receipt of the Inspection Report.
I= Immediate Corrective Action:	Immediate means that Inspector(s) immediately contact District Bridge Inspection Engineer (DBIE) to report the Deficiency and receive further instruction from him/her. This level of urgency

4.6.5 Inspection Dimensioning

Sufficient dimensions shall be provided of any deficiencies observed. The dimensioning shall provide actual size measurements and depth measurements to capture the scale of the defect. These measurements shall then be referenced to a fixed and definable reference point on the structure. It is desirable that all reference points refer from the centerline of bearings for the structure. All units of measurement shall be stated in English Units.

shall only apply to C-S and C-H deficiencies.

Inspectors shall measure and record crack sizes found during inspections. They shall record the lengths and widths and depths were possible and reference to the locations of the cracks to a fixed point on the structure.



When inspectors discover section loss on structural steel elements (i.e.; girders, stringers, truss elements, or reinforcing bars) they shall measure and state the **remaining** structural steel available. The inspector shall **not** assume a section loss percentage, but shall provide measurements of remaining thickness.

4.6.6 Inspection Sketches

When inspecting bridges, it may be necessary to use sketches to clarify locations and/or details of defects. When the sketch format is selected for recording bridge inspection results, the information should be recorded systematically.

In most cases it will be possible to use reproductions of portions of the plans for the sketches. However, in some instances, such as when the "as built" detail is different from what is shown on the construction drawings, an accurate sketch showing the existing detail will have to be drawn.

For examples of typical sketches, see Attachment 4-5: Typical Underside of Deck Condition Sketch, Attachment 4-6: Typical Beam End Elevation Sketch, Attachment 4-7: Typical Beam Elevation Sketch, and Attachment 4-8: Typical Cross Section View of Deteriorated Prestressed Concrete Beam.

4.6.7 Inspection Photos

All photographs shall be taken in color with a digital camera. The camera used shall be capable of taking all required photographs in proper focus and sufficient level of detail, whether overall inventory photographs or close-up detail photographs of deficiencies. The camera must also be capable of operating with an adjustable flash unit in order to properly light up dark areas and fine details. It is preferable that the camera will record a date stamp on every image.

A photograph should be taken to assist either the written description or sketch of a deficiency. If there are several deficiencies of the same type, a photograph would be taken to show a typical deficiency while sketches would be used to show and dimension each deficiency at each location.

When photographing a deficiency, it is usually best to take two photographs, one being a general view of the deficiency which should locate it in relation to the rest of the bridge structure, while a second should be a close up of the deficiency itself, showing its extent and any distinguishing features. This close up view must be in focus, properly lit and should include a ruler to help establish the scale of the deficiency. A pencil, pick or screw driver tip may be used to point to important details that might otherwise be overlooked in the photograph.

If a deficiency is being monitored as part of Special Member Inspection, in lieu of repair, every effort should be made to take a new detail photographs from the same location and at approximately same scale as the ones before so that the progress of the deficiency can be readily established.

4.6.8 Videos of Deficiencies

In some cases, a deficiency is only apparent when under traffic. For example, the longitudinal joint between butted precast beams may have failed so that the beams are deflecting independently of each other. This situation could only be documented during a live action video of a vehicle going over the bridge. In such cases, the video segment should be shot showing the deficiency in action. The video



should be properly focused, well lit and the view should be framed such that the entire action is kept within the view of the camera without having to move the camera to follow the action. If at all possible, a ruler should be used to establish the scale of the view and deficiency. The video will then be forwarded, via email, to the District Bridge Inspection Engineer, District Bridge Engineer, Bridge Inspection Engineer.

4.6.9 Condition Coding

The numerical condition ratings should characterize the general condition of the entire component being rated. They should not attempt to describe localized or nominally occurring instances of deterioration or disrepair. Correct assignment of a condition rating must, therefore, consider both the severity of the deterioration or disrepair and the extent to which it is widespread throughout the component being rated.

It shall be noted that a bridge's load-carrying capacity is <u>not</u> to be used in the condition coding process. The fact that a bridge was designed for less than current legal loads, and may even be posted, should have no influence upon the condition rating.

Narrative descriptions of the conditions should be clearly presented. Note all signs of distress, failure, or defects with sufficient accuracy so that another inspector at a future date can make a comparison of condition or rate of deterioration. When a sub-item is assigned a numerical condition of 6 or less, the inspector will be required to write a narrative description of the defect. Also, if any sub-element is assigned a deficiency coding of S-A, then it will be required that a photo of the sub-element be contained in the inspection report.

In relation to Item 60, 61 and 62, the inspection report will have two columns (Dive & Cur) for each sub-element. If a bridge is a Dive (Underwater Inspection) bridge then the inspectors shall import the condition rating of each sub-element from the latest Underwater Inspection Report and place them in the "Dive" column. The Inspector's own evaluations of these sub-elements are coded in the "Cur" column. Generally, the overall condition of each of the above items is the lower number between Underwater Inspection Report and the Inspector's Report and that would be the number which is entered in the SI&A. The above water inspector needs to review what is contained in the Underwater Inspection Report and make the determination if the item controlling the Underwater Inspection is valid for controlling the overall condition. Two examples and attachments are provided for clarification as follows:

- Example #1: The "Abutment" from an Underwater Inspection Report is an "N" and from a Routine Inspection is a "6". The "Pier or Bents" from an Underwater Inspection Report is a "7" and from a Routine Inspection is a "5". The "Pile Bents" from both reports is an "N", then the overall "Abutment" rating is a "6", "Pier or Bents" is a "5" and "Pile Bents" is "N". Overall condition rating of the Item 60 (Superstructure) would be a "5" and this is the number which will be coded in the SI&A. The Routine Inspection condition rating is less than the Underwater Inspection Condition Rating. Refer to Attachment 4-9, Example 1: Condition Coding of Item 60.
- Example #2: The "Abutment" from an Underwater Inspection Report is a "6" and from a Routine Inspection is a "7". The "Pier or Bents" from an Underwater Inspection Report is a "5" and from a Routine Inspection is a "7". The "Pile Bents" from both reports is an "N", then the overall "Abutment" rating is a "7", "Pier or Bents" is a "7" and "Pile Bents" is

"N". Overall condition rating of the Item 60 (Superstructure) would be a "7" and this is the number which will be coded in the SI&A. Although, in this example the Underwater Inspection overall condition rating is a "5" the scour that has occurred does not impact the main load carrying member of this rehabilitated structure. The existing arch structure is remaining but the new structure above the arch is supported on piles. Loads are not being transferred to the arch. Refer to Attachment 4-10, Example 2: Condition Coding of Item 60.

4.6.10 Narrative Presentation

The narrative presentation shall be the writing remarks segment of the inspection report summarizing the field inspection findings of the inspection team.

The narrative shall begin with the inspector describing the method of orientation selected to orient the reader. The inspector will then write in the "General Remarks" section any load, speed, or traffic restrictions on the bridge, as well as any special means of access utilized to inspect the structure. Include information about high water marks and unusual loadings. Also, all work or repairs to the bridge since the last inspection should be listed. If work is undertaken on a structure that improves the physical condition of a structure, the Team Leader must explain what work was undertaken to improve the condition. Verify or obtain new dimensions when some maintenance or improvement work has altered the dimensions of the structure.

When numerous defects are to be documented under a sub-element it is encouraged to do so in "bullet" form. The condition narrative should begin with a summary statement which identifies the general condition and/or highlights the controlling deficiencies that are presented in the bullets which are listed below. Refer to Attachment 4-11 for an example of presenting information in an inspection report. The application of this method of presentation will allow the ease of comparison between successive inspection cycles and allow for the visual progression of the deterioration of the sub element.

4.6.11 SI&A Edits

During every inspection cycle, the inspector shall submit a marked up SI&A sheet with every inspection report submission. Team Leaders shall submit a copy of the SI&A sheet with all suggested revisions for the latest inspection marked up in red. At a minimum the latest inspection date should be revised. Other common revisions may include condition ratings for Items 58, 59 and/or 60 as well as ADT dates and values. After the corrections are made to the SI&A sheet electronically (within 4D) by the District Bridge Inspection Engineer or his/her designee a copy of the revised sheet should be printed out and attached to the inspection report. Refer to Attachment 4-12 for an example of a marked up SI&A sheet. It shall be noted on the marked up copy of the SI&A sheet that the ADT was calculated and shown, the changes that were recommended for Item 58, 59, and 60 are shown and any changes recommended on the appraisal section are shown.

4.6.12 Element Level Inspection Report

The Element Level inspection report is produced within the bridge inspection module of 4D under the "Pontis" tab. A separate report is produced and is printed out as an attachment to the inspection report. As mentioned previously, the Element Level report is required with each Routine Inspection and when inspections are performed to document improvements from rehabilitation efforts.

When completing an Element Level inspection report on a bridge that is a dive bridge, the Team Leader must ensure that the Underwater (U/W) Element Level inspection information is incorporated into the above water Element Level report. The U/W Element Level inspection data is a paper report only. The above water Element Level report is where the information is entered into the 4D database. The Team leader should obtain a copy of the latest U/W inspection report and Element Level inspection report prior to the above water inspection and incorporate the U/W information on his/her Element Level inspection report.

4.7 CS/I & CH/I PROCEDURE AND DOCUMENTATION

In the case of Critical-Structural and Critical-Hazard Deficiencies which require **Immediate** corrective action, the Inspection Team Leader (TL) shall immediately verbally notify the District Bridge Inspection Engineer (DBIE), who after verification shall immediately verbally notify the District Bridge Engineer and the Area Engineer (who in return will immediately notify the Bridge Inspection Engineer, who in return will notify the State Bridge Engineer and FHWA officials).

Upon observation of a deficiency, the Inspection Team Leader (TL) shall code all the deficiencies and complete the inspection report and include all sketches and photographs necessary to clearly identify the deficiencies. All reports shall then be given to the DBIE who after review of the report shall forward it to the District Bridge Engineer (DBE) for corrective action. The Team Leader shall indicate in the inspection report the notification of the DBIE.

When the deficiency is verified and deemed to be a danger to pedestrians and/or vehicles, the site shall not be left unattended until the custodial owners have arrived and are preparing to respond with the necessary safety precautions. The Inspection Team shall document the safety precautions implemented in the Inspection Report.

4.7.1 CS/I & CH/I Field Observations at MassDOT Owned Bridges

In the case of a Critical Deficiency, in addition to the prior paragraphs requirement, the DBIE shall prepare a Critical Deficiency Activity Log/Critical Deficiency Verification Form (See Attachment 4-13: Critical Deficiency Activity Log/Critical Deficiency Verification Form) and forward a scanned copy via email to the District Bridge Engineer. The log documents the reporting of the Critical Deficiency and requests that it be returned with documentation of the action taken. Copies shall be forwarded to the Bridge Inspection Engineer who in turn will forward a copy to the FHWA and shall catalog the CS Deficiency in a database.

4.7.2 CS/I & CH/I Field Observations at Municipally Owned Bridges

In the case of Critical-Structural and Critical-Hazard Deficiencies which require Immediate corrective action, the District Bridge Inspection Engineer shall immediately notify the Municipal Officials in Charge.

The DBIE shall prepare the Critical Deficiency Activity Log/Critical Deficiency Verification Form (see Attachment 4-13) with supporting documentation and send a copy to the Municipality with a cover letter signed by the District Highway Director (see Attachment 4-14). Copies shall be forwarded to the District

Bridge Engineer and Bridge Inspection Engineer who in turn will forward a copy to the FHWA and shall log the CS Deficiency in a log book.

4.7.3 Follow-Up Procedures on Critical Deficiency Findings

The Follow-Up Critical Deficiency Inspection process is intended to meet the NBIS requirements for recording the corrective action taken by the Department or Municipality as a result of the Bridge Inspection Unit filing a Critical Deficiency in the Inspection Report found during an inspection. This procedure shall be used for all MassDOT and Municipally-owned bridges as follows. The process should be completed as soon as possible after repair, but no later than one month after the report of Critical Deficiency.

4.7.3.1 Procedures - Follow-Up Procedures for MassDOT Bridges

The District Bridge Inspection Engineer shall verify and document the status of the Critical Deficiency. If the deficiency has been addressed then the DBIE shall ensure that the Verification Form has been signed and forwarded to the appropriate parties. Copies shall be forwarded to the Bridge Inspection Engineer who in turn will forward a copy to the FHWA and shall log the CS Deficiency in a log book.

If the deficiency has not yet been addressed, the DBIE shall notify the ABIE that the status of the CS/I has not changed. The ABIE shall then forward the notification of the un-changed CS/I to the BIE who shall initiate a conversation with the District Bridge Engineer regarding the schedule for such repair. A hard copy of the email string should be retained as documentation of the situation. If the schedule for repairs has not been determined, then a follow up Critical Deficiency memo (Attachments 4-15 or 4-16) shall be sent.

The completed Follow-Up Critical Deficiency Notification Form (See Attachment 4-15 and 4-16) and re-inspection report shall be filed in a separate file in both the District Bridge Inspection Engineer's Office and the Boston Bridge Inspection Engineer's Office. A copy of all correspondence will also be kept in both the District's and Boston's Bridge History File.

4.7.3.2 Procedures – Follow-Up Procedures for Municipally Owned Bridges

The District Bridge Inspection Engineer shall verify and document the status of the Critical Deficiency. The DBIE shall then prepare the Follow-Up Critical Deficiency Notification Form (see Attachment 4-17 and 4-18) and send a copy to the Municipality with supporting documentation with cover letter signed by District Highway Director. Copies shall be forwarded to the Bridge Inspection Engineer who in turn will forward a copy to the FHWA and shall log the CS Deficiency in a log book.

The completed Follow-Up Critical Deficiency Notification Form and re-inspection report shall be filed in a separate file in both the District Bridge Inspection Engineer's Office and the Boston Bridge Inspection Engineer's Office. A copy of all correspondence will also be kept in both the District's and Boston's Bridge History File.

4.7.3.3 Repeat Procedures – Follow-Up Procedures for MassDOT & Municipally Owned Bridges

The procedures outlined in Section 4.7.3.1 and 4.7.3.2 shall be repeated when re-inspection verifies that the Critical Deficiency has not been corrected.

4.8 VERTICAL CLEARANCE SIGNAGE PROCEDURE

MassDOT clearance sign procedure is derived from the latest FHWA Manual for Uniform Traffic Control Devices (MUTCD), in which it states that Low Clearance signage shall be used to warn road users of clearances less than 12 inches above statutory maximum vehicle height. Massachusetts General Laws (M.G.L.) Chapter 90 Section 19 states no vehicle shall exceed a height of 13'-6". Clearance posting of the roadway is the responsibility of the roadway owner, <u>not</u> the owner of the obstruction (bridge, railroad structure, pedestrian structure).

When vertical measurements taken in the travel way are less than 14'-6", then vertical clearance signs will be required. MassDOT's recommended posting values as they relate to the measured field clearance are shown in Chart 4.8-1 below. These recommended posting values are to be used to provide consistency throughout the Commonwealth. Recommended posted clearance values have been derived to be within what is allowable as mentioned in the MUTCD. MUTCD states a reduction not to exceed 3 inches should be used. The reduction reflected in the chart is established to account for the dynamic envelope of the vehicle.

Field Measured Clearance	Recommended Posted Clearance
≥14' - 6"	NO POSTING REQUIRED
$< 14' - 6"$ but $\ge 14' - 5"$	14' - 3"
$< 14' - 5"$ but $\ge 14' - 4"$	14' - 2"
$< 14' - 4''$ but $\ge 14' - 3''$	14' - 1"
$< 14' - 3''$ but $\ge 14' - 2''$	14' - 0"
$< 14' - 2"$ but $\ge 14' - 1"$	13' - 11"
$< 14' - 1"$ but $\ge 14' - 0"$	13' - 10"
$< 14' - 0"$ but $\ge 13' - 11"$	13' – 9"
$< 13' - 11"$ but $\ge 13' - 10"$	13' - 8"
$< 13' - 10"$ but $\ge 13' - 9"$	13' – 7"
$< 13' - 9"$ but $\ge 13' - 8"$	13'-6"

Chart 4.8-1

Special consideration shall be given for signing in situations when the clearance varies along the travel way. This situation occurs at times with Arch structures. Attachment 4-19 is an example showing how to post for an arch structure. Truss portals are another situation that may require clarification by signing the low point location to alert the driver of where the clearance is the lowest along the roadway. Attachment 4-20 is an example showing how to post for the low point along the truss portal.

4.8.1 Notification to Post under Clearance - State Owned Roadway

For roadways under the jurisdiction of MassDOT, the DBIE will be responsible for sending out the notification to the responsible party in the District office that will erect the requested clearance posting signs. Attachment 4-21 is an example of what is sent to the District representative that is responsible for the placement of the signs. Exhibits should be attached to the requests for clarification with regards to where the signs are to be located.

4.8.2 Notification to Post under Clearance – Municipally Owned Roadway

For roadways under the jurisdiction of a Municipality, the DBIE will be responsible for sending out the notification to the Municipality requesting that posted clearance signs are required. Attachment 4-22 is an example of what is to be sent to the Municipality. Exhibits should be attached to the requests for clarification with regards to where the signs are to be located.

4.9 COMPLETION and SUBMISSION of INSPECTION REPORTS by TEAM LEADERS

All MassDOT Inspectors and Consultant Inspectors shall follow the procedures established for completing and submitting inspection reports as outlined in Sections 4.9.1 and 4.9.2, respectively. This procedure shall be used for all MassDOT and Municipally-owned bridges under the NBIS program.

A complete inspection report includes a hard copy of the inspection report, Element Level inspection, and a marked up SI&A. Dive reports are not required to be submitted with the inspection report. They are sent to the bridge owner by the Underwater Operations Unit.

4.9.1 MassDOT Inspections

Inspection reports completed by MassDOT teams shall be completed within the MassDOT Bridge Inspection Management System (4D) no later than the 15th day of the month following the inspection.

4.9.2 Consultant Inspections

Inspection reports completed by Consultant teams shall be completed within 4D no later than 21 days following completion of the inspection, or in accordance with specific deadlines contained in their inspection contract.

Upon initial completion of the inspection report and a QC/QA review by the Consultants PM, the Consultant TL should indicate within 4D that the report is ready for review. The Consultant TL should then send an email to the DBIE alerting him/her that the inspection report is ready for review.

4.10 DBIE INSPECTION REPORT REVIEW

The DBIE and the ADBIE shall collectively review 100% of all inspection reports. The DBIE or ADBIE will sign all inspection reports reviewed by him/her. If the ADBIE signs the inspection report that they have reviewed, the ADBIE shall sign his/her name and place the word "for" after their name.

The DBIE will be personally responsible for the review of all inspection reports that have an assigned numerical ratings of 5 or below for Item 58, Item 59, Item 60, or Item 62. The Assistant District Bridge Inspection Engineer may be responsible for the review of all inspection reports that have assigned numerical ratings of 6 or greater for Item 58, Item 59, Item 60, or Item 62 if the DBIE chooses to delegate that task to the ADBIE.

When required based on operational needs, the DBIE may perform an inspection as the Team Leader. In such cases, the DBIE should sign the inspection report as the team leader. The ABIE will then perform the function of the DBIE and shall review and sign the inspection report. This occurrence shall only be done on an intermittent basis when extenuating circumstances arise.

Note: The signatory's signature on the inspection report only signifies that the signatory has reviewed the inspection report in accordance with FHWA and MassDOT standards. The signature does not under any circumstances signify, nor has it ever signified even prior to the formal issuance of this Handbook, the corroboration of the accuracy and thoroughness of either the field inspection itself, the assessment of the structure's condition by the Team Leader, or the description of the structure's condition by the Team Leader.

4.10.1 DBIE Review of MassDOT Inspections

The DBIE shall complete a review of all internally completed inspection reports in a timely manner and in conformance with metrics determined by the District. Approved reports shall be signed and one copy shall be submitted to the Bridge Inspection Engineer.

4.10.2 DBIE Review of Consultant Inspections

The DBIE will complete an expeditious review of the inspection report within 4D in a timely manner and in conformance with metrics determined by the District.

If revisions are requested, the DBIE should either email the Consultant's PM and TL with the requested changes, or indicate within 4D the requested changes. When changes are made, the Consultant PM and TL should again inform the DBIE. When the report is deemed acceptable the DBIE shall check the report approved within 4D.

The consultant shall print out a hard copy, sign the original and submit it with two copies to the Bridge Inspection Engineer. The BIE will then update 4D with the report submission information.

The report will be forwarded to the DBIE through the ABIE with a Bridge Inspection Consultant Performance Evaluation Report form, see Attachment 4-23. The DBIE is to provide an evaluation score, sign the inspection report and copies and return one report to the ABIE along with the evaluation form.

4.10.3 DBIE Review of Inspection Report Content

A review by the DBIE will include the review of all inspection reports for bridges in their district prepared by MassDOT staff and/or Consultants for compliance with FHWA, NBIS and MassDOT requirements before the data is entered in the bridge inventory files.

The DBIE is not responsible for reviewing inspection reports for bridges of other state agencies.

The DBIE's review will consist of the following:

- 1. Overall review of the Inspection Report to ensure that the correct form has been used, that the correct bridge is identified and that all required information has been entered.
- 2. Review that all information has been correctly entered in accordance with the FHWA Coding Guide and the MassDOT Bridge Inspection Handbook criteria. This review will include but not be limited to a check that proper coding conventions, format, significant digits and correct units have been used.

- 3. Check that the Condition Ratings for Items 58 through 62 are consistent with the condition ratings of the individual sub-items.
- 4. Check that there is adequate documentation for inspection sub-items with condition ratings of 6 or lower.
- 5. Check that all Photographs and/or Sketches have been properly cross referenced to the Inspection Report.
- 6. Check that there is consistency of information between the current Inspection Report and previous Inspection Reports, as well as the Dive Report and/or Rating Report, if applicable.
- 7. Check that proper documentation was incorporated into the inspection report for any changes that may have occurred from the previous SI&A and previous Inspection Report.
- 8. Review of all Items in the SI&A after data entry to check that they have been properly and correctly entered.
- 9. For Initial Inventory Inspections, a check of the inventory data on the SI&A against the construction plans to ensure that the data is consistent.
- 10. For every initial inspection, a set of Inventory Photos has been taken and included in the report.
- 11. For every routine inspection, an Element Level inspection created with the routine inspection shall be reviewed for accuracy, including elements, quantities and condition states.

4.11 DISTRIBUTION OF COMPLETED INSPECTION REPORTS

Upon approval of the inspection report, the DBIE shall review the marked up SI&A and ensure all changes are made. The DBIE shall print out a new SI&A and attach it to the inspection report.

Completed Inspection reports shall be distributed by the DBIE to the bridge owners as follows:

Boston HQ copy:	Report; SIA; Marked-up SIA; Element Level Inspection Report
District copy:	Report, Element Level Inspection Report
Municipal copy:	Report only. The cover letter* is from the district with a copy to the Bridge Inspection Engineer. See attachment 4-24.

* Cover letter attachments shown being signed by the DHD are intended to have the minimum language required, the District have the right to add additional language as they see fit.

4.12 ABIE REVIEW OF COMPLETED INSPECTION REPORTS

Upon receiving the reviewed inspection reports from the DBIE, the ABIE shall review 100% of the inspection reports with numerical condition ratings of 4 or less on Items 58, 59, 60, or 62. Also the ABIE shall review a minimum of 10% of all reports for completeness. Upon completion of the review by the ABIE, he/she will check off in 4D whether the review was a regular review or an in depth review. Upon completion of the ABIE's review, the ABIE shall place the accepted inspection report into the Boston Bridge history file.

If an inspection report is rejected by the ABIE, the ABIE shall return the inspection report to the DBIE with comments, so that they may forward the rejected inspection report to the Team Leader for revision. When the rejection comments have been addressed, the Team Leader will then resubmit the inspection report to the DBIE for review, who will concur and accept the inspection report in 4D and then resubmit the report to the ABIE.

4.13 CHAPTER 4 ATTACHMENTS

	Reinf	Reinforced Concrete - Condition State Definitions	tion State Definitions			Prestress	Prestressed Concrete - Condition State Definitions	on State Definitions	
Defect Delamination / Spall / Pp++hed Area	CS 1 - 0 None.	CS 2 - Fair CS 2 - Fair Delaminated. Spall 1 in. or less deep or 6 in. or less in diarreter. Patched area that is sound.	CS 3 - Poor Spall greater than 1 in. deep or greater than 6 in. diameter. Patched area that is unsound or showing distress. Deen not warrant structural	Cs 4 - Severe	Defect Delamination / Spall / Patched Area (1080)	CS 1 - Good None	CS 2 - Fair Delaminated. Spall 1 in. cr less deep or 6 in. or less in diameter. Patched area that is sound.	CS 3 - Poor Spall greater than 1 in. deep or greater than 6 in. diameter. Patched area that is unsound or showing distress. Does not warrant structural review.	C5 1 + Severe
Exposed Rebar (1090)	None.	Present without measurable section loss.	Present with measurable section loss, but does not warrant structural review.		Exposed Rebar (1090)	None	Present without measurable section loss.	Present with measurable section loss, but does not warrant structural review.	
Efflorescence / Rust Staining (1120)	None.	Surface white without build- up or leaching without rust staining.	Heavy build-up with rust staining.	The condition warrants a structural review to	Exposed Prestressing (1100)	None	Present without section loss	Present with section loss, but does not warrant structural review.	The condition warrants a
Cracking (1130)	Width less than 0.012 in. or spacing greater	Width 0.012-0.05 in. or spacing of 1.0-3.0 ft.	Width greater than 0.05 in. or spacing of less than 1 ft.	determine the effect on strength or serviceability of the element or bridge; OR a		Width less than 0.004 in. or spacing greater than 3 ft.	Width 0.004–0.009 in. or spacing 1.0–3.0 ft.	Width greater than 0.009 in. or spacing less than 1 ft.	structural review to determine the effect on strength or serviceability of the element or bridge O8 a
Abrasion / Wear (1190)	than 3.0 ft. No abrasion or wearing.	Abrasion or wearing has exposed coarse aggregate but h the aggregate remains secure o in the concrete.	Coarse aggregate is loose or has popped out of the concrete matrix due to abrasion or wear.	structural review nas been completed and the defects impact strength or serviceability of the element	g B B Dn / Wear	None No abrasion or wearing		rreavy build-up with rust staining. Coarse aggregate is loose or has popped out of the	completed and the defects impact strength or completed and the defects
Distortion (1900)	None.	Distortion not requiring mitigation or mitigated distortion.	Distortion that requires mitigation that has not been addressed but does not warrant structural review.		Distortion	None	but the aggregate remains secure in the concrete. Distortion not requiring mitigation or mitigated	concrete matrix due to abrasion or wear. Distortion that requires mitigation that has not been	or bridge.
(4000)	None.	Exists within tolerable limits or arrested with no observed structural distress.	Exceeds tolerable limits but does not warrant structural review.		Settlement	None	distortion. Exists within tolerable limits	addressed but does not warrant structural review. Exceeds tolerable limits but	
Scour (6000)	None.	Exists within tolerable limits or has been arrested with effective countermeasures.	Exceeds tolerable limits, but is less than the critical limits determined by scour evaluation and does not warrant structural review.		Scour (6000)	None	or arrested with no observed structural distress. Exists within tolerable limits or has been arrested with effective countermeasures.		
Damage (7000)	Not applicable.	The element has impact damage. The specific damage caused by the impact has been captured in condition state 2 under the appropriate material defect entry.	The element has impact damage. The specific damage caused by the impact has been captured in condition state 3 under the appropriate material defect entry.	damage. The specific damage damage. The specific damage caused by the impact has been captured in condition state 4 under the appropriate material defect entry.	Damage (7000)	Not applicable	The element has impact damage. The specific damage caused by the impact has been captured in condition state 2 under the appropriate material defect	evaluation and does not warrant structural review. The element has impact damage caused by the impact has been captured in impact has been captured in condition state 3 under the appropriate material defect	The element has impact damage. The specific damage custed by the impact has been captured in condition state 4 under the appropriate material defect
Defect	Pand 1 2	Concrete Keintorcing Steel	ITOTCING Steel Protective Systems	ES 4 - Severe			entry.	entry.	enuy.
Effectiveness (3600)	1	ai	Limited effectiveness.	The protective system has failed or is no longer effective.					
Damage (7000)	Not applicable.	The element has impact damage. The specific damage caused by the impact has been captured in condition state 2 under the appropriate material u	The element has impact damage. The specific damage caused by the impact has been captured in condition state 3 under the appropriate material	The element has impact damage. The specific damage caused by the impact has been captured in condition stare 4 under the appropriate material					

Attachment 4-1: Quick Reference Guide for the Element Level Condition States, Page 1 of 5

-			2				Lointe - Condition Ces	te Dofinitions	
	Wearing Surface	Surface - Condition State Definitions	ate Definitions				Joints - Condition State Derinitions		
Defect Delamination / Spall / Patched Area /	CS 1 – Good None.	CS 2 - Fair Delaminated. Spall less than 1 in. deep or less than 6 in.	CS 3 - Poor Spall 1 in. deep or greater or 6 in. diameter or greater.	CS 4 - Severe	Defect Leakage N (2310)	CS 1 - Good None.	CS 2 - Fair Minimal. Minor dripping through the joint.	Moderate. More than a drip and less than free flow of	drip Free flow of water through the joint.
		diameter. Patched area that is sound. Partial depth pothole.			Seal Adhesion F	Fully Adhered.	Adhered for more than 50% of the joint height.	-	oint Complete loss of adhesion.
	Width less than 0.012 in. or spacing greater than	Width 0.012–0.05 in. or spacing of 1.0–3.0 ft.	Width of more than 0.05 in. or spacing of less than 1.0 ft.	no longer effective.	Seal Cracking N	None.	Surface crack.	acression. Crack that partially penetrates the seal.	Crack that fully penetrates the seal.
	Fully effective. No evidence of leakage or further deterioration of	Substantially effective. Deterioration of the protected elément has slowed.	Limited effectiveness. Deterioration of the protected element has	1	amage	None.	Seal abrasion without punctures.	Punctured or ripped or partially pulled out.	Punctured completely through, pulled out, or missing.
		The element has impact damage. The specific damage caused by the impact has	-		Debris N Impaction 0 (2350) e	No debris to a shallow cover of loose debris may be evident but does not affect the performance of the ioint.	er Partially filled with hard- packed material, but still t allowing free movement. int.	Completely filled and impacts joint movement.	Completely filled and prevents joint movement.
		been captured in condition state 2 under the appropriate material defect entry.	impact has been captured in condition state 3 under the appropriate material defect entry.	caused by the impact has been captured in condition state 4 under the appropriate material defect entry.	Adjacent Deck S or Header d (2360) p	Sound. No spall, delamination or unsound patch.	Edge delamination or spall 1 in. or less deep or 6 in. or less in diameter. No exposed rebar. Patched Area that is sound.	1 in. Spall greater than 1 in. deep in or greater than 6 in. ar. diameter. Exposed rebar. Delamination or unsound patched Area that inart Area	eep Spall, delamination, unsound patched Area or loose joint anchor that prevents the joint from functioning as intended.
		Bearings - Condition State Definitions	Definitions	an a 21 111	Metal	None.	Freckled rust, metal has no		Metal cracking, section
	CS 1 - Good None.	Freckled Rust. Corrosion of 5 the steel has initiated.	Section loss is evident or pack rust is present but does not warrant structural review.	015000- + 00	or Damage (2370)		Connection may be loose but functioning as intended.	2002	
	Connection is in place and functioning as intended. Free to move.	Loose fasteners or pack rust without distortion is present but the connection is in place and functioning as intended. Minor restriction.	Missing botts, rivers, broken welds, fasteners or pack rust with distortion but dees not warrant a structural review. Restricted but not warranting structural review.	The condition warrants a structural review to determine the effect on strength or or serviceability	Damage (7000)	Not applicable.	The element has impact damage. The specific damage caused by the impact has been captured in condition state 2 under the oppropriate material defect entry.	The element has impact age damage. The specific been damage cussed by the e 2 impact has been captured in terial condition state 3 under the appropriate material defect entry.	
	Lateral and vertical	or vertical	Approaching the limits of	bridge; OR a structural		Concrete F	Protective Coating - Co	Concrete Protective Coating - Condition State Definitions	SUI
	alignment is as expected for the temperature	inconsistent with the	for the bearing but does not	completed and the	Defect	CS 1 - Good	CS 2 - Fair	CS 3 - Poor	CS 4 - Severe
Bulging, Splitting or Tearing	_	of	warrant a structural review. Bulging 15% or more of the thickness. Splitting or tearing. Bearing's surfaces are not		Wear (3510)	None. Un ext	Underlying concrete not exposed, coating showing wear from UV exposure, friction course missing.	Underlying concrete is not exposed, thickness of the coating is reduced.	Underlying concrete exposed, treated cracks are exposed.
			parallel. Does not warrant structural review.		Chalking (3520)	None. Sur		Loss of Pigment.	Not Applicable.
Loss of Bearing Area (2240) Damage	None. Not applicable.	act	10% or more but does not warrant structural review. The element has impact		Peeling / Bubbling / Cracking (3530)	None.	Finish coats only.	Finish and primer coats.	Exposure of bare concrete.
		damage. The specific damage caused by the immart has been contured	damage. The specific damage caused by the impact has been captured in condition	damage. The specific damage caused by the impact has been	Effectiveness (3540)			Limited effectiveness.	The protective system has failed or is no longer effective.
		ition state 2 under ropriate material entry.	state 3 under the appropriate material defect entry.		Damage (7000)	Not applicable. The date of th	The element has impact damage. The specific damage caused by the impact has been captured in condition state 2 under the appropriate	The element has impact damage. The specific damage caused by the impact has been captured in condition state 3 under the appropriate	The element has impact damage. The specific damage caused by the impact has been captured in condition state 4 under the appropriate

Attachment 4-1: Quick Reference Guide for the Element Level Condition States, Page 2 of 5

		Steel - Condit	Steel - Condition State Definitions	itions				Timber - Condition State Definitions	te Definitions	
Defect	CS1-Good	CS 2 - Fair	S	CS 3 - Poor	CS 4 - Severe	Defect	CS 1 - Good	CS 2 - Fair	CS 3 - Poor	CS 4 - Severe
uo a		ion .		Section loss is evident or pack rust is present but does not warrant structural review. Identified crack exists that is		-	Connection is in place and functioning as intended.	Loose fasteners or pack rust without distortion is present but the connection is in place and functioning as intended.	Missing bolts, rivets, broken welds, fasteners or pack rust with distortion but does not warrant a structural review.	20 A
(1010) Connection	Connection is	has oeen arrested with effective arrest holes, doubli plates, or similar. Loose fasteners or pack rust		S	The condition warrants a	Decay / Decay / Section Loss (1140)	None.	Affects less than 10% of the member section.	Affects 10% or more of the member but does not warrant structural review.	
		without distortion is present but the connection is in place and functioning as intended. Distortion not requiring	1.		structural review to determine the effect on strength or serviceability of the element or bridge; OR a structural review	/ Shake	oenetration less of the member s regardless of	Penetrates 5% - 50% of the thickness of the member and not in a tension zone.	Penetrates more than 50% of the thickness of the member or more than 5% of the member thickness in a tention space	
(0061)	8	mitigation or mitigated distortion.	mitigation that h addressed but do	varrant	has been completed and the defects impact strength or	Canal	location.	Court that has haan arracted		The condition warrants a
Settlement 1 (4000)	None.	ble	sor	e limits but structural	bridge.	1				determine the effect on strength or serviceability
Scour (6000)	None.	structural distress. Exists within tolerable limits or has been arrested with effective countermeasures.		review. Exceeds tolerable limits, but is less than the critical limits determined by scour evaluation and does not warrant structural		Split / Delamination (1170)	None.	Length less than the member depth or arrested with effective actions taken to mitigate.		of the element or bridge; OR a structural review has been completed and the defects impact strength
Damage (7000)	Not applicable.	The element has impact damage. The specific damage	1	_	The element has impact damage. The specific damage	Abrasion / Wear	None or no measurable section loss.	Section loss less than 10% of the member thickness	Section loss 10% or more of the member thickness but does not warrant structural review.	or serviceability of the element or bridge.
		caused by the impact has been captured in condition state 2 under the appropriate material defect entry.	12	caused by the impact has been ca captured in condition state 3 ca under the appropriate material ur defect entry.	caused by the impact has been captured in condition state 4 under the appropriate material defect entry.	ion	None.	Distortion not requiring mitigation or mitigated distortion.	Distortion that requires mitigation that has not been addressed but does not warrant structural review.	
	Stee	Steel Protective Coating - Condition State Definitions	ng - Condition S	tate Definitions	di Canada	Settlement (4000)	None.	Exists within tolerable limits or arrested with no observed	Exceeds tolerable limits but does not warrant structural review.	
Chalking (3410)	None.	CS 1 - GOOD Surfa	Surface Dulling.	Loss of Pigment.	Not Applicable.	Scour	None.	Exists within tolerable limits	Exceeds tolerable limits, but is	
Peeling / Bubbling / Cracking (3420)			Finish coats only.	Finish and primer coats.	22	(2000)		or has been arrested with effective countermeasures.	less than the critical limits determined by scour evaluation - and does not warrant structural	-
uctoe Film Degradation Color / Texture Adherence (weathering steel patina) (3430)		or iight / chocolate- le-brown for 1. Tightly ble of ammering or orushing, or		1/2 in diameter.		Damage (7000)	Not applicable.	The element has impact damage. The specific damage caused by the impact has been captured in condition state 2 under the appropriate material defact entry.	review. The element has impact damage. The specific damage caused by the impact has been captured in condition state 3 under the appropriate material defect entry.	The element has impact damage. The specific damage caused by the impact has been captured in condition state 4 under the appropriate material
Effectiveness (3440)	Fully effective.		ostantially effective.	Limited effectiveness.	 Failed, no protection of the underlying metal 					מכוכרו כוונוא.
(7000)	Not applicable.		The element has impact damage. The specific damage caused by the impact has been captured in condition state 2 under the appropriate material	The element has impact damage. The specific damage caused by the impact has been ceptured in condition state 3 under the appropriate material	е					


Attachment 4-1: Quick Reference Guide for the Element Level Condition States, Page 3 of 5



							Macanua - Candition State Definitions	tata Dafinitions	
	0		Condition State Definitions						FC.4 - Cottono
Defect Corrosion (۲۰۰۰۵)	CS 1 - Good None.	sion of the	CS 3 - Poor Section loss is evident or pack rust is present but does not warrant structural review.	CS 4 - Severe	Defect Delamination / Spall / Patched Area (1080)	B009	Délaminated. Spall 1 in. or léss deep or 5 in. or less in diameter. Patched area that is	Spall greater than 1 in. deep or greater than 6 in. diameter. Patched area that is unsound	00000
Cracking (1010)	None.	Crack that has self arrested or has been arrested with effective arrest holes, doubling plates, or similar.	Identified crack exists that is not arrested but does not warrant structural review.		ence / Rust	None.	sound. Surface white without build-	or showing distress. Does not warrant structural review. Heavy build-up with rust	×
Connection (1020)	Connection is in place and functioning as intended.	Loose fasteners or pack rust withiout distortion is present but the connection is in place and functioning as intended.	Missing bolts, rivets, broken welds, fasteners or pack rust with distortion but does not warrant a structural review.	- - -	Staining (1120) Mortar Breakdown (1610)	None.	up or reacting without rust staining. Cracking or voids in less than 10% of joints.	staining. Cracking or voids in 10% or more of the of joints	
Delamination / Spall / Patched Area	None.	Delaminated. Spall 1 in. or less deep or 6 in. or less in diameter. Patched area that is sound	Spall greater than 1 in. deep or greater than 6 in. diameter. Patched area that is unsound or showing distress. Does not	The condition warrants a	pall	None.	Block or stone has split or spalled with no shifting.	Block or stone has split or spalled with shifting but does not warrant a structural review.	The condition warrants a structural review to determine the effect on strength or serviceability of the element
. foor			warrant structural review.	structural review to determine the affect on strength or	Patched Area	None.	Sound patch.	Unsound patch.	or bridge; OR a structural review has been completed
Efflorescence / Rust Staining (1120)		our leaching without rust staining.	staining.	serviceability of the element or bridge; OR a structural review has been completed and the	Masonry Displacement (1640)	None.	Block or stone has shifted slightly out of alignment.	Block or stone has shifted significantly out of alignment or is missing but does not	and the defects impact strength or serviceability of the element or bridge.
CI duNIIK (1130)	0.012 in. or spacing greater than 3.0 ft.	spacing of 1.0–3.0 ft.		defects impact strength or serviceability of the element or	Distortion (1900)	None.	Distortion not requiring mitigation or mitigated	Warrant structural review. Distortion that requires mitigation that has not been	
Deterioration (1720)	None.	Initiated breakdown or deterioration.	-	bridge.	Settlement	None.	distortion. Exists within tolerable limits or	addressed but does not warrant structural review. Exceeds tolerable limits but	
Distortion (1900)	None.	Distortion not requiring mitigation or mitigated	Warrant structural review. Distortion that requires mitigation that has not been		(4000) Scour	2	arrested with no observed structural distress. Exists within tolerable limits or		
Settlement (4000)	None.	distortion. Exists within tolerable limits or arrested with no observed			(6000)		has been arrested with effective countermeasures.		
Scour (6000)	None.	Exists within noterable limits or has been arrested with effective countermeasures.	Exceeds tolerable limits, but is less than the critical limits determined by scour evaluation and does not warrant structural review.		Damage (7000)	Not applicable	The element has impact damage. The specific damage caused by the impact has been captured in condition state 2 under the appropriate	The element has impact damage. The specific damage caused by the impact has been captured in condition state 3 under the appropriate	The element has impact damage. The specific damage caused by the impact has been captured in condition starte 4 under the appropriate
Damagé (7000)	Not applicable.	The element has impact damage. The specific damage caused by the impact has been captured in condition state 2 under the appropriate material defect entry.	The element has impact damage. The specific damage caused by the impact has been captured in condition state 3 under the appropriate material defect entry.	The element has impact damage. The specific damage caused by the impact has been captured in condition state 4 under the appropriate material defect entry.			marenal defect entry.	material derect entry.	ווופרבו מ חבוברי בו ה.
а 191			2			ж.». 			
7/08/2013							an a an ti		

Attachment 4-1: Quick Reference Guide for the Element Level Condition States, Page 4 of 5

Massachusetts Department of Transportation




Attachment 4-1: Quick Reference Guide for the Element Level Condition States, Page 5 of 5



REQUIRED INFORMATION Town:	REQUIRED INFORMATION BRIDGE N BRIDGE:	e Number:
Town: BRIDGE NUMBER: FACILITY ON BRIDGE: STRUCTURE NO.: FEATURES INTERSECTED: BIN: THE DISTRICT BRIDGE INSPECTION ENGINEER HAS REVIEWED THE INSPECTION REPORT ATTACHED AND IS RECOMMENDING EVALUATION OF ITEM 113- SCOUR CRITICAL BRIDGES FOR THE FOLLOWING REASONS: DISTRICT BRIDGE INSPECTION ENGINEER DATE DISTRICT BRIDGE INSPECTION ENGINEER DATE New Structure over Water Substructure over Water Substructure fact is scour critical Significant changes have occurred that have altered the stream bed or flow characteristics of the water PLEASE INDICATE WHAT HAS OCCORED AT THE SITE: CHANNEL CHANGING COURSE EVIDENCE OF EROSION OR SCOUR AROUND FOOTINGS AND EMBANKMENTS LARGE AMOUNT OF DEBRIS AROUND SUBSTRUCTURE	N BRIDGE: STRUCT	e Number:
FACILITY ON BRIDGE: STRUCTURE NO.: FEATURES INTERSECTED: BIN: THE DISTRICT BRIDGE INSPECTION ENGINEER HAS REVIEWED THE INSPECTION REPORT ATTACHED AND IS RECOMMENDING DISTRICT BRIDGE INSPECTION ENGINEER HAS REVIEWED THE FOLLOWING REASONS: DISTRICT BRIDGE INSPECTION ENGINEER Date New Structure over Water Substructure over Water Substructure Scour repairs Performed and/or Streambed Scour Countermeasures have been installed structure that is scour critical Significant changes have occurred that have altered the stream bed or flow characteristics of the wate PLEASE INDICATE WHAT HAS OCCORED AT THE SITE: CHANNEL CHANGING COURSE EVIDENCE OF EROSION OF SCOUR AROUND FOOTINGS AND EMBANKMENTS LARGE AMOUNT OF DEBRIS AROUND SUBSTRUCTURE	N BRIDGE: STRUCT	
THE DISTRICT BRIDGE INSPECTION ENGINEER HAS REVIEWED THE INSPECTION REPORT ATTACHED AND IS RECOMMENDING EVALUATION OF ITEM 113- SCOUR CRITICAL BRIDGES FOR THE FOLLOWING REASONS: DISTRICT BRIDGE INSPECTION ENGINEER DATE New Structure over Water Substructure Scour repairs Performed and/or Streambed Scour Countermeasures have been installed structure that is scour critical Significant changes have occurred that have altered the stream bed or flow characteristics of the wate PLEASE INDICATE WHAT HAS OCCORED AT THE SITE: CHANNEL CHANGING COURSE EVIDENCE OF EROSION OR SCOUR AROUND FOOTINGS AND EMBANKMENTS LARGE AMOUNT OF DEBRIS AROUND SUBSTRUCTURE	INTERSECTED: BIN:	FURE INO.
EVALUATION OF ITEM 113-SCOUR CRITICAL BRIDGES FOR THE FOLLOWING REASONS: DISTRICT BRIDGE INSPECTION ENGINEER Date New Structure over Water Substructure Scour repairs Performed and/or Streambed Scour Countermeasures have been installed structure that is scour critical Significant changes have occurred that have altered the stream bed or flow characteristics of the wate PLEASE INDICATE WHAT HAS OCCORED AT THE SITE: CHANNEL CHANGING COURSE EVIDENCE OF EROSION OR SCOUR AROUND FOOTINGS AND EMBANKMENTS LARGE AMOUNT OF DEBRIS AROUND SUBSTRUCTURE		
New Structure over Water Substructure Scour repairs Performed and/or Streambed Scour Countermeasures have been installed structure that is scour critical Significant changes have occurred that have altered the stream bed or flow characteristics of the wate PLEASE INDICATE WHAT HAS OCCORED AT THE SITE: CHANNEL CHANGING COURSE EVIDENCE OF EROSION OR SCOUR AROUND FOOTINGS AND EMBANKMENTS LARGE AMOUNT OF DEBRIS AROUND SUBSTRUCTURE		
Substructure Scour repairs Performed and/or Streambed Scour Countermeasures have been installed structure that is scour critical Significant changes have occurred that have altered the stream bed or flow characteristics of the wate PLEASE INDICATE WHAT HAS OCCORED AT THE SITE: CHANNEL CHANGING COURSE EVIDENCE OF EROSION OR SCOUR AROUND FOOTINGS AND EMBANKMENTS LARGE AMOUNT OF DEBRIS AROUND SUBSTRUCTURE	RIDGE INSPECTION ENGINEER DATE	
EVIDENCE OF RIP RAP, BANK PROTECTION REMOVED OR ALTERED STREAM WORK PERFOMED BY OTHERS THAT MIGHT CHANGE THE HYDRAULIC CHARACTERISTIC AT THE BRIDGI OTHER:	ructure Scour repairs Performed and/or Streambed Scour Co ure that is scour critical icant changes have occurred that have altered the stream be ASE INDICATE WHAT HAS OCCORED AT THE SIT CHANNEL CHANGING COURSE EVIDENCE OF EROSION OR SCOUR AROUND FOOTINGS AND EMBANH LARGE AMOUNT OF DEBRIS AROUND SUBSTRUCTURE EVIDENCE OF RIP RAP, BANK PROTECTION REMOVED OR ALTERED STREAM WORK PERFOMED BY OTHERS THAT MIGHT CHANGE THE HYD	ed or flow characteristics of the waterway ГЕ: кментs
The area bridge inspection engineer has reviewed the request and concurs witht the recommendation for evaluation of item 113-scour critical bridges.		CURS WITHT THE RECOMMENDATION FOR A RE-
AREA BRIDGE INSPECTION ENGINEER DATE		
STATE SCOUR COORDINATOR USE	E INSPECTION ENGINEER DATE	
	COUR COORDINATOR USE	

Attachment 4-2: Bridge Scour – Item 113 Re-evaluation Form






Attachment 4-3: Vertical Clearance Location Placed on a Framing Plan

Massachusetts Department of Transportation

	Traffic Count Formula for use when MassDOT Traffic Volumes are not provided.
	Definitions:
	Rush Hour = 3hrs A.M. + 3hrs. P.M. = 6 hrs $(7 \text{ AM} - 10 \text{ AM & 3 PM} - 6 \text{ PM})$ Off-Peak= Early AM= 3 hrsRemaining == 3 hrs $(4 \text{ AM} - 7 \text{ AM})$ = 15 hrs $(10 \text{ AM} - 3 \text{ PM & 6 PM} - 4 \text{ AM})$ = 24 hrs
	Off - Peak carries no traffic
	Rush hour (6)hrs = 42% ADT Remaining (15)hrs = 58% ADT
	Instructions :
	Take twelve minute counts and extrapolate according to the above. Document and note actual time count was made. If 12 minute counts are used then a factor of 5 will be used to make the counts per hour i.e. $5X12 = 60 \text{ min} = 1 \text{ hour}$
	Example #1
(Counts where taken at 11:00 AM for 12 minutes the total vehicles counted was 50. Find the ADT.
	50 cars X 5(factor to convert to per hour) X 15(counts taken at outside rush hour) = 3750 cars/hr
	Therefore, $3750/.58 = 6466$ ADT Round up to 6500 ADT
	Example #2
	Counts where taken at 9:00 AM for 12 minutes the total vehicles counted was 75. Find the ADT.
	75 X 5 = 375 cars/ hr 375 X 6 = 2250 cars
	Therefore, $2250/.42 = 5357$ ADT Round up to 5400 ADT
	х. х
Ţ.	


Attachment 4-4: Average Daily Traffic Count Formulas & Example Calculations






Attachment 4-5: Typical Underside of Deck Condition Sketch





Attachment 4-6: Typical Beam End Elevation Sketch






Bridge Inspection Handbook Field Inspection, Data Collecting, Report Writing and Report Review

Attachment 4-7 Typical Beam Elevation Sketch





Attachment 4-8: Typical Cross Section View of Deteriorated Prestressed Concrete Beam



2-DIST B.I.N. 01 4GT				S INSPE								EPT. N = R-1	
CITY/TOWN			8S	TRUCTURE NO.					41-STATUS			NE INS	
MONTGOMERY=	RUSSE	ELL		M30008-40	GT-DOT-	NBI	0	58.257	A:OPEN	N	IAY	14,	20
07-FACILITY CARRIED				MEMORIAL NAM	IE/LOCAL NA	ME	27	-YR BUILT	106-YR REBUILT 1990	YR		B'D (NO 2010	
06-FEATURES INTERSECTED				26-FUNCTIONAL	CLASS		DIST BRID	GE INSPECTIO				2010	,
COMB US20&WE		D R&CS	x	Urban Inters			DIST. DIGD	02110120110	IT LITOITTELK				
43-STRUCTURE TYPE 409 : Steel contin				22-OWNER State Highway			TEAM LEA	DER G. Gabrie	elli PROJ	MGR	AEC	COM (I	DMJ
107-DECK TYPE 1 : Concrete Cast			JUUN	Agency WEATHER Varied	Agency TEMP. (air) 22°C		TEAM MEN	MBERS					_
ITEM 58			ITT	EM 59				ITEM 6	50			1	
DECK	5			PERSTRUCTU		5			RUCTURE	L	5		
1.Wearing Surface	6	DEF M-A		ringers		5	M-P	1. Abut		Dive	Cur	6	D
2.Deck Condition	5	S-P		oorbeams		5	S-P	a. Pedesta	als	N	6		М
3.Stay-in-Place Forms	7	M-P	3.Flo	oor System Brac	ing	5	M-P	b. Bridge c. Backwa		N	6		M
4.Curbs	N	-	4.Gi	rders or Beams		5	M-P	d. Breastv		N	6		M
5.Median	6	M-P	5.Tr	usses - General		5	M-P	e. Wingwa	alls Paving/Rip-Rap	N	7 N		
6.Sidewalks	N	-	a.	Upper Chords	6		M-P	g. Pointing		N	N		2
7.Parapets	6	M-P		Lower Chords	5	6	M-P	h. Footing	15	N	H		
8.Railing	6	M-P		Web Members	6		M-P	i. Piles j. Scour		N	N		
9.Anti Missile Fence	N	-		Lateral Bracing	5		M-A	k. Settlem		N	8		
10.Drainage System	5	M-P		Sway Bracing Portals	N		M-A	I. Erosior m.	1	N	5 N		M
11.Lighting Standards	6	M-P		End Posts	N		-	2. Piers	or Bents			5	
12.Utilities	6	M-P		n & Hangers	1.1	N	1 -	a. Pedesta b. Caps	als	N	7	-	M
13.Deck Joints	6	M-P	7.Cc	onn Plt's, Gusset	s & Angles	5	S-A	c. Column	าร	N	5		M
14.	N	-	8.Cc	over Plates		5	M-P	d. Stems/ e. Pointin	Webs/Pierwalls a	7 N	5 N		M
15.	N	-	9.Be	aring Devices		5	M-P	f. Footing		Н	н		
16.	N)iaphragms/Cros	s Frames	7	-	g. Piles h. Scour		H 7	H 7		
L	N	S		livets & Bolts		6	M-P	i, Settlem		8	8		
CURB REVEAL (In millimeters)	96	114		Velds		4	M-A	j. Erosior	1	N	5 N		M
				lember Alignmer	m	6 6	M-P	3. Pile E	Bents			N	
APPROACHES		DEF	-	atwalk		4	M-P M-A	a. Pile Ca	ps	N	N		
a. Appr. Pavement Condition	6	M-P]	b. Piles	al Bracing	N	N		
b. Appr. Roadway Settlemen		-	Yea	r Painted	2010]	d. Horizor	ntal Bracing	N	N		
c. Appr. Sidewalk Settlement		-		LISION DAMAGE:				e. Fastene	ers	N	N		-
d.	N	-			Moderate (vere ()	UNDERMI	NING (Y/N) If Y	′ES pl	ease e	explain	
OVERHEAD SIGNS (Attached to bridge)	(Y/N)	Ν	Non		Moderate (X) Se	vere ()	COLLISIO None (X	N DAMAGE:) Minor () M	lodera	te () Sev	ere (
a Condition of Mulda	N	DEF	10000		Moderate (vere ()	SCOUR:	Please explain				
a. Condition of Welds b. Condition of Bolts	N N	-	A	Franture Outline	Momber	VIND		None (X) Minor () N	lodera	te () Sev	ere (
c. Condition of Signs	N	-		Fracture Critical		T/N)	Y	I-60 (Dive	Report): 7	1-0	60 (Thi:	s Repo	rt):
		L .	Any	Cracks: (Y/N)	Y			03B-11/M	(DIVE) Insp		11/	19/2	009

Attachment 4-9: Example 1: Condition Coding of Item 60



2-DIST B.I.N.	STR	UCIU	JRES INSPE ROUTINE		1.) REP(EPT. N 5-00	
			8-STRUCTURE NO.	INSPE	511		Cilo. POINT	41-STATUS	-	-	NE INS	
DEDHAM			005005-A	PW-MUN	-NB		00.000	A:OPEN			20,	
07-FACILITY CARRIED			MEMORIAL NA	en onder Hundberg ander	11-0201020		7-YR BUILT	106-YR REBUILT			B'D (N	
HWY AMES ST							2012	0000		(0000)
06-FEATURES INTERSECTED			26-FUNCTIONAL			DIST. BRID	GE INSPECTIO	ON ENGINEER	J. O'O	Connor	r	
WATER CHARLES	S RIVE	R	Urban Colle									
43-STRUCTURE TYPE 101 : Concrete Sla	h		22-OWNER Town	21-MAINTA Town	NER	TEAM LEA	DER E. J. Ray					
107-DECK TYPE	aD		Agency WEATHER	Agency Agency		TEAM MEMBERS						
1 : Concrete Cast	-in-Pla	ice	Sunny	7°C				SAMMATA	ARO), M	. HA	RT
ITEM 58			ITEM 59	- <u>'</u> Г		7	ITEM	60	F	_	1	
DECK	8	DEF	SUPERSTRUCTU		8	DEF		RUCTURE		7]	DE
1.Wearing surface	8	-	1.Slab		8		1. Abut		Dive	Cur	7	DL
2.Deck Condition	8	-	2.Floorbeams		N	-	a. Pedest		N	N		
3.Stay in place forms	N	-	3.Floor System Bra	cing	N	-	b. Bridge		N	N N		-
4.Curbs	8	-	4.Girders or Beams	3	Ν	-	d. Breast	walls	7	н		
5.Median	N	-	5.Trusses - General		Ν	<u> </u>	e. Wingw	alls Paving/Rip-Rap	7 N	7 N		
6.Sidewalks	8	-	a. Upper Chords	N		-	g. Pointin	g	8	8		
7.Parapets	N	-	b. Lower Chords	N		-	h. Footing	gs/Cribbing	7 N	H		-
8.Railing	7	M-P	c. Web Members d. Lateral Bracing	N			j. Scour		6	н		
9.Anti Missile Fence	Ν	-	e. Sway Bracings	N		-	k. Settlen		7	8 H		
10.Drainage System	Ν	-	f. Portals	N		-	<i>m</i> .		N	N		
11.Lighting Standards	N	-	g. End Posts	N		-	The second second second	or Bents			7	
12.Utilities	8		6.Pin & Hangers		Ν	-	a. Pedest b. Caps	als	N N	N N		
13.Deck Joints	8	-	7.Conn Plt's, Gusse	ets & Angles	0342-02	-	c. Colum		8	8		
14.	Ń	-	8.Cover Plates		Ν	- '	e. Pointin	Webs/Pierwalls g	6 N	7 N		M.
15.	N		9.Bearing Devices		N			g/Cribbing	5 N	H H		
16.	N	-	10. Diaphragms/Cro	oss Frames	N N		g. Piles h. Scour		5	н		
	E	w	12. Welds		N		i. Settlen j. Curtair		7	8 H	-	-
(In millimeters)	187	187	13. Member Alignm	ent	8	-	<i>k</i> .		N	N		
ADDDO ACHES			14. Spandrel Wall		7	M-P	3. Pile I	okine na sina co- Ilano sh		19369	N	
APPROACHES	8	DEF	15. Arch		5	M-P	a. Pile Ca	ps	N N	N N		-
a. Appr. pavement condition b. Appr. Roadway Settlement			Year Painted	N		1	c. Diagon	al Bracing	N	N		
c. Appr. Sidewalk Settlement		<u> </u>		Blass		1	d. Horizo e. Fasten	ntal Bracing ers	N N	N N		
d.	N	-	COLLISION DAMAGE: None (X) Minor () Moderate () Se	evere ()		INING (Y/N) If Y				
OVERHEAD SIGNS (Attached to bridge)	(Y/N)	N	LOAD DEFLECTION: None (X) Minor () Moderate () Se	evere ()		N DAMAGE:		10) Sev	
		DEF	LOAD VIBRATION: None (X) Minor (Please expl) Moderate (evere ()		Please explain			,	- 1
a. Condition of Welds	N						None (X		oderat	te () Sev	ere (
b. Condition of Bolts c. Condition of Signs	N		Any Fracture Critica	al Member: (Y/N)	Ν	I-60 (Dive	Report): 5	1-6	50 (Thi:	s Repo	rt):
		-	Any Cracks: (Y/N)	N			028 11/1	V (DIVE) Insp		02	/10/2	012

Attachment 4-10: Example 2: Condition Coding of Item 60



Example 1:	
Written Narrative submitted:	
Item 59.9 - Bearing Devices Sole and masonry plates typically exhibit minor to moderate surface rust with mo	dorato to hony
surface rust at the exterior girders (see Photos 14, 16, 17 and 18). Many of the be	
anchor bolts are not fully fastened. At the west abutment, the south bolt on girder	
and the north bolt on girder 3 are not fully fastened. At the pierwall, the south bo	olt on girder 2 is
not fully fastened. At the east abutment, the north bolt on girders 2 and 5 are not	fully fastened.
Preferred List or Table format :	
Item 59.9 - Bearing Devices	donata ta baarre
Sole and masonry plates typically exhibit minor to moderate surface rust with mo surface rust at the exterior girders (see Photos 14, 16, 17 and 18).	derate to neavy
Bearing plate anchor bolts not fully fastened: West abutment,	
Girders 2, 5 & 6, the south bolt.	
Girder 3, the north bolt.	
Pierwall,	
Girder 2, the south bolt	
East abutment,	
Girders 2 and 5, the north bolt.	
Example 2:	
Written Narrative submitted:	
Item 60.1.c - Backwalls There is a 3.5' long x 1.5' high x 3" deep spall in the west abutment backwall behi	ind heam 1 (see
Photo 21). There is a 1' long x 4" high x 4" deep spall in the west abutment backwan ben	wall behind
beam 4. There is hairline cracking with efflorescence and a 10" high x 4" wide x	
spall in the west abutment behind beam 8 (see Photo 22). There is a 2.5' high x 1	0" wide x 2"
deep spall at the east backwall behind beam 1 (see Photo 23). Both backwalls have	e corrosion
staining from the expansion joints (see Photos 19,	
Preferred List or Table format :	
Item 60.1.c - Backwalls Both backwalls have accreasing steining from the expansion joints (see Photos 10	21 22 and 22)
Both backwalls have corrosion staining from the expansion joints (see Photos 19,	, 21, 22 and 23).
West Abutment,	
Beam 1 - 3.5' long x 1.5' high x 3" deep spall (see Photo 21).	
Beam 4 - 1' long x 4" high x 4" deep spall. Beam 8 hairline cracking with efflorescence and a 10" high x 4" wide x up to 2"	deen snall (see
Photo 22).	deep span (see
East Abutment,	
Beam 1 - 2.5' high x 10" wide x 2" deep spall (see Photo 23).	

Attachment 4-11: Example of presenting information in an Inspection Report



= 1023 H.I. 84.3 % Identification FHWA Select List= ructure Number P030252VQDOTN 1110009 1110009 ventory Route 1110009 110009 245 ate Highway Department District 00 5245 unty Code 009 (4) Place code 195 RAMP C cillty Carried I 95 RAMP C 195 RAMP C cation .1 MI E US1 1001	0 (102) Direction of Traffic - 1-way traffic 1 4 (103) Temporary Structure N 0 (105) Federal Lands Highways 0 (110) Designated National Network Y (20) Toll - On free road 3 (21) Maintain - State Highway Agency 01 6 (22) Owner - State Highway Agency 01
= 2VQ AASHTO= 065 = 1023 H.I.= 84.3 % FHWA Select List= ructure Number P030252VQDDTN ventory Route 11100095 atter Bildway Department District 065 unty Code 009 (4) Place code 5245 atures Intersected I 95 RAMP C 6011.66 cation .1 MIE US1 0101.66 ase Highway Network 85 Inventory Route & Subroute 00000000000 astlude 42DEG 31MIN 17.86SE	8 (26) Functional Class - Freeway/Expressway 12 Y (100) Defense Highway 1 1 (101) Parallel Structure N 0 (102) Direction of Traffic - 1-way traffic 1 4 (103) Temporary Structure N 0 (105) Federal Lands Highways 0 (110) Designated National Network Y (20) Toll - On free road 3 (21) Maintain - State Highway Agency 01 6 (22) Owner - State Highway Agency 01
Image: system Image: s	Y (100) Defense Highway 1 B1 (101) Parallel Structure N O (102) Direction of Traffic - 1-way traffic 4 (103) Temporary Structure N 0 (105) Federal Lands Highways 0 0 (100) Designated National Network Y (20) Toll - On free road 3 (21) Maintain - State Highway Agency 01 6 (22) Owner - State Highway Agency 01
Identification P030252VQDOTN ventory Route 1110009 ate Highway Department District 0 unty Code 009 (4) Place code 5245 atures Intersected I 95 RAMP C 6 cation .1 M E US1 0101.66 ase Highway Network 00000000000 6 RS Inventory Route & Subroute 00000000000 6 atude 42DEG 31MIN 17.865E	N N 0 (102) Direction of Traffic - 1-way traffic 1 4 (103) Temporary Structure N 0 (105) Federal Lands Highways 0 0105) Federal Lands Highways 0 0105) Federal Lands Highways 0 0(110) Designated National Network Y (20) Toll - On free road 3 (21) Maintain - State Highway Agency 01 6 (22) Owner - State Highway Agency 01
Journer 11100095 ate Highway Department District 0 unty Code 009 (4) Place code 5245 atures Intersected 1.95 RAMP C 0 cation .1 MI E US1 0 Jometerpoint 0.101.66 0 ase Highway Network 000000000000 0 RS Inventory Route & Subroute 000000000000 0 attude 42DEG 31MIN 17.86SE	0 (102) Direction of Traffic - 1-way traffic 1 4 (103) Temporary Structure N 0 (105) Federal Lands Highways 0 (110) Designated National Network Y (20) Toll - On free road 3 (21) Maintain - State Highway Agency 01 6 (22) Owner - State Highway Agency 01
Anton Fronce Control Anton Fronce Control Anton Scheduler	N N 0 (103) Temporary Structure N 0 (105) Federal Lands Highways 0 (110) Designated National Network Y (20) Toll - On free road 3 (21) Maintain - State Highway Agency 01 6 (22) Owner - State Highway Agency 01
unity Code 009 (4) Place code 5245 atures Intersected I 95 RAMP C I 95 RAMP C cation I 95 RAMP C I 95 RAMP C illometerpoint 0101.66 326 Highway Network RS Inventory Route & Subroute 000000000000000000000000000000000000	(110) Designated National Network Y (20) Toll - On free road 3 (21) Maintain - State Highway Agency 01 6 (22) Owner - State Highway Agency 01
cation 1 95 RAMP IC cation .1 MI E US1 illometerpoint 0101.66 ase Highway Network 000000000000 RS Inventory Route & Subroute 000000000000 atitude 42DEG 31MIN 17.86SE	(20) Toll - On free road 3 (21) Maintain - State Highway Agency 01 6 (22) Owner - State Highway Agency 01
cation .1 MI E US1 Ilometerpoint Q101.66 ase Highway Network RS Inventory Route & Subroute 00000000000 atitude 42DEG 31 MIN 17.86 SE	(21) Maintain - State Highway Agency .01 6 (22) Owner - State Highway Agency 01
Illometerpoint Q101.64 ase Highway Network RS Inventory Route & Subroute RS Inventory Route & Subroute 000000000000 atitude 42DEG 31MIN 17.86SE	6 (22) Owner - State Highway Agency 01
ase Highway Network	
RS Inventory Route & Subroute 00000000000 atitude 42DEG 31MIN 17.86SE	
atitude 42DEG 31MIN 17.86SE	Y (37) Historical Significance built after 1949 presumed to be not eligi Z Condition
	(FO) Consistent and (I
order Bridge State Code Share %	(60) Substructure 7 🗸
order Bridge Structure No. #	(61) Channel & Channel Protection N
Structure Type and Material	(62) Culverts N Load Rating and Posting
tructure Type Main: Steel Code 30	
er/Girder Jointless bridge type: Not applicable	(63) Operating Rating Method - Allowable Stress (AS) 2
tructure Type Appr:	(64) Operating Rating 50.4
Other Code 00	()()
umber of spans in main unit 00	()
umber of approach spans 000 Deck Structure Type - Concrete Cast-In-Place Code	
	AppraisalCode
Wearing Surface / Protective System: Type of wearing surface - Bituminous Code	(67) Structural Evaluation 7
	(68) Deck Geometry 2
	(69) Underclearances, vert. and horiz. 4
Age and Service	(71) Waterway adequacy
ear Built 195	(72) Approach Roadway Alignment 6 9 (36) Traffic Safety Features 0 1 1
Year Reconstructed 000	0 (113) Scour Critical-Bridges
/pe of Service: On - Highway	Inspections
ler - Highway Code 11	(90) Inspection Date -09/01/11 9/14/13 (91) Frequency 24 MO
anes: On Structure 02 Under structure 0	
verage Daily Traffic 13,600 01235	(A) Fracture Critical Detail N 00 MO A) 00/00/00 (B) Underwater Inspection N 00 MO B) 00/00/00
ear of ADT 2013 -2011 (109) Truck ADT 10 -11 %	(C) Other Special Inspection N 00 MO C) 00/00/00
ypass, detour length 008 KM	(*) Other Inspection (FT) N 00 MO *) 05/01/08
ength of maximum span 0012.5N	
cructure Length 00013.4N	(*) UW Special Inspection N 00 MO *) 00/00/00
urb or sidewalk: Left 00.8 M Right 00.8M	
ridge Roadway Width Curb to Curb 006.7N	Report Date 12/01/92 H20 Type 3 Type 352 Type H5
eck Width Out to Out 009.2N	Operating 31.0 55.0 84.0 56.0
pproach Roadway Width (w/shoulders) 006.7N	Inventory 21.0 33.0 30.0 30.0
lage riedich ho hiedich o	Field Posting Status LEGAL Posting Date 11/09/94
kew 26 DEG (35) Structure Flared Inventory Route MIN Vert Clear 99.99N	
Iventory Route Total Horiz Clear 06.7N	
in Vert Clear Over Bridge Rdwy 99.99N	
in Vert Underclear ref H 04.44N	Missing Signs N
in Lat Underclear RT ref H 01.7M	Misc
in Lat Underclear LT 01.9N	N Anti-missile fence N Acrow Panel N Jointless Bridge
Navigation Data	Freeze/Thaw 3: No Deteriorated concrete; No known problematic history
vigation Control - Not applicable, no waterway Code N ier Protection Code	Accessibility (Needed/Used)
vigation Vertical Clearance 000.0M	N/N Rigging N/N Other
ert-lift Bridge Nav Min Vert Clear M	N/N Boat Y/Y Traffic Control
vigation Horizontal Clearance 0000.0M	N / N Boat Y / Y Traffic Control Inspection N / N Wader N / N RR Flagperson Hours: 012

Attachment 4-12: Marked up copy of SI&A sheet



MASSACHUSETT	'S DEPARTMENT OF TRANSPORTATION
CRI	TICAL DEFICIENCY ACTIVITY LOG
DEFICIENCY TYPE: ()	STRUCTURAL () HAZARD
City/Town:	Bridge No.: BIN No:
Location:	
Team Leader:	Date Reported: Time Reported:
Critical – Deficiency:	
Name Date & Time of and report to:	Special Follow Its Inspection:
Name, Date & Time of oral report to: District Representative:	Special Follow-Up Inspection: Needed? Y/N ()
Municipality or Custodian:	Estimate Date:
Boston Bridge Section:	
Action Taken/Comments:	
District Bridge Inspection Engineer:	Date:
CRI	Date:
<u>CRE</u> Return to: (The DBIE's name) (Address) PLEASE SIGN AND RETURN THIS	FICAL DEFICIENCY VERIFICATION FORM, NOTING ANY CORRECTION ACTION AND ATTA
CRE Return to: (The DBIE's name) (Address) PLEASE SIGN AND RETURN THIS DOCUMENTATION REGARDING T () Immediate Corrective	FICAL DEFICIENCY VERIFICATION FORM, NOTING ANY CORRECTION ACTION AND ATTA THE FOLLOWING": action taken on:
<u>CRE</u> Return to: (The DBIE's name) (Address) PLEASE SIGN AND RETURN THIS DOCUMENTATION REGARDING T () Immediate Corrective () Future additional corr	FICAL DEFICIENCY VERIFICATION FORM, NOTING ANY CORRECTION ACTION AND ATTA THE FOLLOWING":
Return to: (The DBIE's name) (Address) PLEASE SIGN AND RETURN THIS DOCUMENTATION REGARDING T () Immediate Corrective	FICAL DEFICIENCY VERIFICATION FORM, NOTING ANY CORRECTION ACTION AND ATTA THE FOLLOWING": action taken on:
<u>CRE</u> Return to: (The DBIE's name) (Address) PLEASE SIGN AND RETURN THIS DOCUMENTATION REGARDING T () Immediate Corrective () Future additional corr Action Taken/Comments:	FICAL DEFICIENCY VERIFICATION FORM, NOTING ANY CORRECTION ACTION AND ATTA THE FOLLOWING": 2 action taken on: rective action to be taken by:
<u>CRE</u> Return to: (The DBIE's name) (Address) PLEASE SIGN AND RETURN THIS DOCUMENTATION REGARDING T () Immediate Corrective () Future additional corr	FICAL DEFICIENCY VERIFICATION FORM, NOTING ANY CORRECTION ACTION AND ATTA THE FOLLOWING": action taken on:

Attachment 4-13: Critical Deficiency Activity Log/Critical Deficiency Verification Form

Massachusette Department of Transportation

	April 30, 2012
City/Town Address	
Attn: Highw	vay Superintendent
SUBJECT:	NATIONAL BRIDGE INSPECTION STANDARDS (NBIS) BRIDGE CLOSURE New Marlborough: NORFOLK RD / UMPACHENE BROOK Bridge No: N-08-001 BIN No: 067 Structure No: N08001-067-MUN-NBI
Dear Mr./Mr	s :
taken on the <i>City/Town of</i>	the MassDOT Critical Deficiency Log, please indicate the action deficiency noted, and return the form to the Department. On <i>DATE ficial</i> was notified of the deficiency and the Department expects in taken by the <i>City/Town</i> would be immediate.
Massachuset	e Massachusetts Bridge Inspection Program Policy we notify the ts Division of Federal Highway Administration of all Critical Hazar ructural deficiencies found Statewide.
deficiencies r	bilitation or reconstruction of any bridges to address these reported are the owner /custodian's responsibility. Chapter 90 funds for these purposes.
Questions re Engineer,	garding this issue may be directed to the District Bridge Inspection at
The Departm	nent is pleased to assist you in this matter of bridge safety.
	Sincerely,
	District Highway Director.
cc: DHD, A	A. Bardow, File

Attachment 4-14: Critical Deficiency Log/Verification Letter to Municipalities



TO:	District Highway Director
ATTN:	District Bridge Engineer
FROM:	Alexander K. Bardow, P.E., State Bridge Engineer
DATE:	
RE:	CRITICAL –STRUCTURAL DEFICIENCY
	Town Name: Facility Carried / Facility Intersected Bridge No: BIN No: Structure No:
Critical-Structu poses an extre element which	iciency for the subject structure. Please be advised that a ural Deficiency is a deficiency to a structural element of a bridge that eme unsafe condition, due to the failure or imminent failure of the n will affect the structural integrity of the bridge. Critical- Structural equire immediate corrective action.
Critical-Structu poses an extre element which deficiencies re Please inform soon as possil Log/Verificatio	ural Deficiency is a deficiency to a structural element of a bridge that eme unsafe condition, due to the failure or imminent failure of the n will affect the structural integrity of the bridge. Critical- Structural equire immediate corrective action. this Office with regards to the corrective action that has taken place as ble. Also, please return the Critical –Structural Deficiency Activity on Form attached with action taken. ny question with regards to this issue please contact the Brian Clang, tion Engineer at 857-368-9425.
Critical-Structu poses an extre element which deficiencies re Please inform soon as possil Log/Verification If you have an Bridge Inspect cc: DBIE D#	ural Deficiency is a deficiency to a structural element of a bridge that eme unsafe condition, due to the failure or imminent failure of the n will affect the structural integrity of the bridge. Critical- Structural equire immediate corrective action. this Office with regards to the corrective action that has taken place as ble. Also, please return the Critical –Structural Deficiency Activity on Form attached with action taken. ny question with regards to this issue please contact the Brian Clang, tion Engineer at 857-368-9425.
Critical-Structu poses an extre element which deficiencies re Please inform soon as possil Log/Verification If you have an Bridge Inspect cc: DBIE D#	ural Deficiency is a deficiency to a structural element of a bridge that eme unsafe condition, due to the failure or imminent failure of the n will affect the structural integrity of the bridge. Critical- Structural equire immediate corrective action. this Office with regards to the corrective action that has taken place as ble. Also, please return the Critical –Structural Deficiency Activity on Form attached with action taken. hy question with regards to this issue please contact the Brian Clang, tion Engineer at 857-368-9425.

Attachment 4-15: Follow Up Critical Structural Deficiency Memo for State Owned Bridges



TO:	District Highway Director
ATTN:	District Bridge Engineer
FROM:	Alexander K. Bardow, P.E., State Bridge Engineer
DATE:	
RE:	CRITICAL -HAZARD DEFICIENCY
	Town Name: Facility Carried / Facility Intersected Bridge No: BIN No: Structure No:
or unsafe conc bridge. Critical Please inform soon as possik Log/Verificatio If you have an Bridge Inspect cc: DBIE D#,	deficiency in a component or element that poses an extreme hazard dition to the public, but does not impair the structural integrity of the - Hazard deficiencies require immediate corrective action. this Office with regards to the corrective action that has taken place as ole. Also, please return the Critical –Hazard Deficiency Activity n Form attached with action taken. y question with regards to this issue please contact the Brian Clang, ion Engineer at 857-368-9425. BBC tical –Hazard Deficiency Activity Log/Verification Form

Attachment 4-16: Follow Up Critical Hazard Deficiency Notification Memo for State Owned Bridges



\$				
	L. Datrick Concerner			DOT
	I L. Patrick, Governor rd A. Davey, Secretary & CEO			IASSDUI
Frank	DePaola, Administrator		Massac	husetts Department of Transportation
Souther the second				
Town of Abingt	con	May 12, 2014		
Board of Select				
500 Gliniewcz V Abington, MA 0	12351			
Attn: John J. (Caine, Superintendent of S	Streets		
SUBJECT:	FOLLOW-UP CRITICAL S	TRUCTURAL DEFICIENCY		
	Abington: ADAMS ST / : Bridge No: A-01-004			
	BIN No: 41D			
	Structure No: A01004-4	1D-MUN-NBI		
Dear Mr. Caine	:			
				1
A Follow-Up Cri	itical Structural deficiency	inspection was performed o	n (date) for the	above subject bridge.
We are informing	ng you that no action has	been taken since we reporte	ed this Critical St	ructural deficiency. Please
		iency is a deficiency to a str		
		ure or imminent failure of th		
		deficiencies require immedi	iate corrective a	ction
5,		deficiencies require immedi		
Please inform t please return t	his Office with regards to he Critical –Structural Defi	the corrective action that ha ciency Activity Log/Verificati	is taken place as on Form attache	soon as possible. Also, d with action taken.
Please inform t please return t	his Office with regards to he Critical –Structural Defi	the corrective action that ha	is taken place as on Form attache	soon as possible. Also, d with action taken.
Please inform t please return t	his Office with regards to he Critical –Structural Defi	the corrective action that ha ciency Activity Log/Verificati	is taken place as on Form attache	soon as possible. Also, d with action taken.
Please inform t please return t	his Office with regards to he Critical –Structural Defi	the corrective action that ha ciency Activity Log/Verificati	is taken place as on Form attache	soon as possible. Also, d with action taken.
Please inform t please return t	his Office with regards to he Critical –Structural Defi	the corrective action that ha ciency Activity Log/Verificati this issue please contact the	is taken place as on Form attache	soon as possible. Also, d with action taken.
Please inform t please return t	his Office with regards to he Critical –Structural Defi	the corrective action that ha ciency Activity Log/Verificati this issue please contact the	is taken place as on Form attache	soon as possible. Also, d with action taken.
Please inform t please return t	his Office with regards to he Critical –Structural Defi	the corrective action that ha ciency Activity Log/Verificati this issue please contact the Sincerely, Mary-Joe Perry	is taken place as on Form attache e <i>District Bridge</i>	soon as possible. Also, d with action taken.
Please inform t please return t	his Office with regards to he Critical –Structural Defi	the corrective action that ha ciency Activity Log/Verificati this issue please contact the Sincerely,	is taken place as on Form attache e <i>District Bridge</i>	soon as possible. Also, d with action taken.
Please inform t please return t	his Office with regards to he Critical –Structural Defi	the corrective action that ha ciency Activity Log/Verificati this issue please contact the Sincerely, Mary-Joe Perry	is taken place as on Form attache e <i>District Bridge</i>	soon as possible. Also, d with action taken.
Please inform t please return tl If you have any	his Office with regards to he Critical –Structural Defi	the corrective action that ha ciency Activity Log/Verificati this issue please contact the Sincerely, Mary-Joe Perry	is taken place as on Form attache e <i>District Bridge</i>	soon as possible. Also, d with action taken.
Please inform t please return th If you have any cc: DHD, DBIE	his Office with regards to he Critical –Structural Defi y question with regards to	the corrective action that ha ciency Activity Log/Verificati this issue please contact the Sincerely, Mary-Joe Perry	is taken place as on Form attache e <i>District Bridge</i>	soon as possible. Also, d with action taken.
Please inform ti please return ti If you have any cc: DHD, DBIE Attachments: 1) Critical	his Office with regards to he Critical –Structural Defi y question with regards to E, Alexander Bardow –Structural Deficiency Acti	the corrective action that ha clency Activity Log/Verificati this issue please contact the Sincerely, Mary-Joe Perry District 5 Highway D	is taken place as on Form attache e <i>District Bridge</i>	soon as possible. Also, d with action taken.
Please inform ti please return ti If you have any cc: DHD, DBIE Attachments: 1) Critical	his Office with regards to he Critical –Structural Defi y question with regards to E, Alexander Bardow	the corrective action that ha clency Activity Log/Verificati this issue please contact the Sincerely, Mary-Joe Perry District 5 Highway D	is taken place as on Form attache e <i>District Bridge</i>	soon as possible. Also, d with action taken.
Please inform ti please return ti If you have any cc: DHD, DBIE Attachments: 1) Critical	his Office with regards to he Critical –Structural Defi y question with regards to E, Alexander Bardow –Structural Deficiency Acti	the corrective action that ha clency Activity Log/Verificati this issue please contact the Sincerely, Mary-Joe Perry District 5 Highway D	is taken place as on Form attache e <i>District Bridge</i>	soon as possible. Also, d with action taken.
Please inform ti please return ti If you have any cc: DHD, DBIE Attachments: 1) Critical	his Office with regards to he Critical –Structural Defi y question with regards to E, Alexander Bardow –Structural Deficiency Acti	the corrective action that ha clency Activity Log/Verificati this issue please contact the Sincerely, Mary-Joe Perry District 5 Highway D	is taken place as on Form attache e <i>District Bridge</i>	soon as possible. Also, d with action taken.
Please inform ti please return ti If you have any cc: DHD, DBIE Attachments: 1) Critical	his Office with regards to he Critical –Structural Defi y question with regards to E, Alexander Bardow –Structural Deficiency Acti	the corrective action that ha clency Activity Log/Verificati this issue please contact the Sincerely, Mary-Joe Perry District 5 Highway D	is taken place as on Form attache e <i>District Bridge</i>	soon as possible. Also, d with action taken.
Please inform ti please return ti If you have any cc: DHD, DBIE Attachments: 1) Critical	his Office with regards to he Critical –Structural Defi y question with regards to E, Alexander Bardow –Structural Deficiency Acti	the corrective action that ha clency Activity Log/Verificati this issue please contact the Sincerely, Mary-Joe Perry District 5 Highway D	is taken place as on Form attache e <i>District Bridge</i>	soon as possible. Also, d with action taken.
Please inform ti please return ti If you have any cc: DHD, DBIE Attachments: 1) Critical	his Office with regards to he Critical –Structural Defi y question with regards to E, Alexander Bardow –Structural Deficiency Acti	the corrective action that ha clency Activity Log/Verificati this issue please contact the Sincerely, Mary-Joe Perry District 5 Highway D	is taken place as on Form attache e <i>District Bridge</i>	soon as possible. Also, d with action taken.
Please inform ti please return ti If you have any cc: DHD, DBIE Attachments: 1) Critical	his Office with regards to he Critical –Structural Defi y question with regards to E, Alexander Bardow –Structural Deficiency Acti	the corrective action that ha clency Activity Log/Verificati this issue please contact the Sincerely, Mary-Joe Perry District 5 Highway D	is taken place as on Form attache e <i>District Bridge</i>	soon as possible. Also, ed with action taken. <i>Engineer</i> at <i>tel no.</i> .
Please inform t please return th If you have any cc: DHD, DBIE Attachments: 1) Critical - 2) Initial R	his Office with regards to he Critical –Structural Defi y question with regards to E, Alexander Bardow –Structural Deficiency Acti	the corrective action that ha clency Activity Log/Verificati this issue please contact the Sincerely, Mary-Joe Perry District 5 Highway D	is taken place as on Form attache e <i>District Bridge</i>	1000 County Street, Taunton, MA 0278 Tel: (508) 824-6633, Fax: (508) 880-610
Please inform t please return th If you have any cc: DHD, DBIE Attachments: 1) Critical - 2) Initial R	his Office with regards to the Critical –Structural Defice y question with regards to E, Alexander Bardow –Structural Deficiency Active ecommendation Notice	the corrective action that ha clency Activity Log/Verificati this issue please contact the Sincerely, Mary-Joe Perry District 5 Highway D	is taken place as on Form attache e <i>District Bridge</i>	soon as possible. Also, ed with action taken. <i>Engineer</i> at <i>tel no.</i> . 1000 County Street, Taunton, MA 0278
Please inform to please return to If you have any cc: DHD, DBIE Attachments: 1) Critical 2) Initial R	his Office with regards to the Critical –Structural Defice y question with regards to E, Alexander Bardow –Structural Deficiency Active ecommendation Notice	the corrective action that ha clency Activity Log/Verificati this issue please contact the Sincerely, Mary-Joe Perry District 5 Highway D	is taken place as on Form attache e <i>District Bridge</i>	1000 County Street, Taunton, MA 0278 Tel: (508) 824-6633, Fax: (508) 880-610

Attachment 4-17: Follow Up Critical Structural Deficiency Notification Letter to City/Town



2					
	al L. Patrick, Governor ard A. Davey, Secretary & CEO		Ama	SSDOT	
	ik DePaola, Administrator		Massachusetts Highway D		
Town of Abing	ton	May 12, 2014			
Board of Selec	tmen	May 12, 2014			
500 Gliniewcz Abington, MA					
Attn: John J.	Caine, Superintendent of	Streets			
SUBJECT:	FOLLOW-UP CRITICAL	HAZARD DEFICIENCY			
	Abington: ADAMS ST	/ SHUMATUSCACANT RIV			
	Bridge No: A-01-004 BIN No: 41D				
	Structure No: A01004-	-41D-MUN-NBI			
Dear Mr. Caine	2:				
A Follow-Up C	ritical Hazard deficiency ir	nspection was performed on	(<i>date)</i> for the above s	ubject bridge.	
be advised that	at a Critical-Hazard is a de	s been taken since we repor ficiency in a component or e	element that poses an	extreme hazard or	
	on to the public, but it do quire immediate correctiv	es not impair the structural i e action.	ntegrity of the bridge.	Critical- Hazardi	
deficiencies re Please inform	quire immediate correctiv		as taken place as soor	as possible. Also,	
deficiencies re Please inform please return	quire immediate correctiv this Office with regards to the Critical –Hazard Defici	e action. the corrective action that h	as taken place as soor n Form attached with a	as possible. Also, action taken.	
deficiencies re Please inform please return	quire immediate correctiv this Office with regards to the Critical –Hazard Defici	e action. o the corrective action that h iency Activity Log/Verification o this issue please contact th	as taken place as soor n Form attached with a	as possible. Also, action taken.	
deficiencies re Please inform please return	quire immediate correctiv this Office with regards to the Critical –Hazard Defici	e action. o the corrective action that h iency Activity Log/Verification	as taken place as soor n Form attached with a	as possible. Also, action taken.	
deficiencies re Please inform please return	quire immediate correctiv this Office with regards to the Critical –Hazard Defici	e action. o the corrective action that h iency Activity Log/Verification o this issue please contact th	as taken place as soor n Form attached with a	as possible. Also, action taken.	
deficiencies re Please inform please return	quire immediate correctiv this Office with regards to the Critical –Hazard Defici	e action. o the corrective action that h iency Activity Log/Verification o this issue please contact th	as taken place as soor n Form attached with a ne <i>District Bridge Engli</i>	as possible. Also, action taken.	
deficiencies re Please inform please return	quire immediate correctiv this Office with regards to the Critical –Hazard Defici	e action. to the corrective action that h iency Activity Log/Verification to this issue please contact th Sincerely, Mary-Joe Perry	as taken place as soor n Form attached with a ne <i>District Bridge Engli</i>	as possible. Also, action taken.	
deficiencies re Please inform please return If you have ar	quire immediate correctiv this Office with regards to the Critical –Hazard Defici	e action. to the corrective action that h iency Activity Log/Verification to this issue please contact th Sincerely, Mary-Joe Perry	as taken place as soor n Form attached with a ne <i>District Bridge Engli</i>	as possible. Also, action taken.	
deficiencies re Please inform please return If you have ar cc: DHD, DBI cc: DHD, DBI Attachments: 1) Critical	quire immediate correctiv this Office with regards to the Critical –Hazard Defici ny question with regards t	e action. to the corrective action that h iency Activity Log/Verification to this issue please contact th Sincerely, Mary-Joe Perry District 5 Highway	as taken place as soor n Form attached with a ne <i>District Bridge Engli</i>	as possible. Also, action taken.	
deficiencies re Please inform please return If you have ar cc: DHD, DBI cc: DHD, DBI Attachments: 1) Critical	quire immediate correctiv this Office with regards to the Critical –Hazard Defici ny question with regards to E, Alexander Bardow –Structural Hazard Activi	e action. to the corrective action that h iency Activity Log/Verification to this issue please contact th Sincerely, Mary-Joe Perry District 5 Highway	as taken place as soor n Form attached with a ne <i>District Bridge Engli</i>	as possible. Also, action taken.	
deficiencies re Please inform please return If you have ar cc: DHD, DBI cc: DHD, DBI Attachments: 1) Critical	quire immediate correctiv this Office with regards to the Critical –Hazard Defici ny question with regards to E, Alexander Bardow –Structural Hazard Activi	e action. to the corrective action that h iency Activity Log/Verification to this issue please contact th Sincerely, Mary-Joe Perry District 5 Highway	as taken place as soor n Form attached with a ne <i>District Bridge Engli</i>	as possible. Also, action taken.	
deficiencies re Please inform please return If you have ar cc: DHD, DBI cc: DHD, DBI Attachments: 1) Critical	quire immediate correctiv this Office with regards to the Critical –Hazard Defici ny question with regards to E, Alexander Bardow –Structural Hazard Activi	e action. to the corrective action that h iency Activity Log/Verification to this issue please contact th Sincerely, Mary-Joe Perry District 5 Highway	as taken place as soor n Form attached with a ne <i>District Bridge Engli</i>	as possible. Also, action taken.	
deficiencies re Please inform please return If you have ar cc: DHD, DBI cc: DHD, DBI Attachments: 1) Critical	quire immediate correctiv this Office with regards to the Critical –Hazard Defici ny question with regards to E, Alexander Bardow –Structural Hazard Activi	e action. to the corrective action that h iency Activity Log/Verification to this issue please contact th Sincerely, Mary-Joe Perry District 5 Highway	as taken place as soor n Form attached with a ne <i>District Bridge Engli</i>	as possible. Also, action taken.	
deficiencies re Please inform please return If you have ar cc: DHD, DBI cc: DHD, DBI Attachments: 1) Critical	quire immediate correctiv this Office with regards to the Critical –Hazard Defici ny question with regards to E, Alexander Bardow –Structural Hazard Activi	e action. to the corrective action that h iency Activity Log/Verification to this issue please contact th Sincerely, Mary-Joe Perry District 5 Highway	as taken place as soor n Form attached with a ne <i>District Bridge Engli</i> Director	n as possible. Also, action taken. <i>neer</i> at <i>tel no</i>	
deficiencies re Please inform please return If you have ar cc: DHD, DBI Attachments: 1) Critical 2) Initial I	quire immediate correctiv this Office with regards to the Critical –Hazard Defici ny question with regards to E, Alexander Bardow –Structural Hazard Activi	e action. to the corrective action that h iency Activity Log/Verification to this issue please contact th Sincerely, Mary-Joe Perry District 5 Highway	as taken place as soor n Form attached with a ne <i>District Bridge Engli</i> Director	n as possible. Also, action taken. <i>neer</i> at <i>tel no.</i> .	6102

Attachment 4-18: Follow Up Critical Hazard Deficiency Notification Letter to City/Town






Attachment 4-19: Example of Vertical Clearance Posting for Rigid Frame Structure



Bridge Inspection Handbook Field Inspection, Data Collecting, Report Writing and Report Review




Attachment 4-20: Example of Vertical Clearance Posting for Truss Portal Structure



	usetts Department of Transportation ay Division
TO:	District Maintenance Engineer
ATTENTION:	Patrick McKenna, District Traffic Maintenance Engineer
THRU:	Mary-Joe Perry, District Highway Director
FROM:	Daniel S. Crovo, P.E., District Bridge Engineer
DATE:	Resubmit 5/12/14 (Original request - June 20, 2012)
SUBJECT:	Bridge Posted Under Clearance - State Owned
Bridge No: City/Town:	e following bridge. B-01-018 BIN No: 46M Structure No: B01018-46M-DOT-NBI Barnstable US 6 EB/MD CP HWY Street over: MARY DUNN RD Barrier:
	Total number of signs 4
	Total number of posts 0
At Bridge: At Advance:	
Other (please posting of 14'	explain) Replace current clearance posting of 14'4" with a clearance 2". North advance sign should be moved (see attached).
	he bottom of this form and return a copy of it to the District Bridge Inspection signs have been placed.
Contrast reading and the second reading of the line of the	Date: 5/20/2014 s Name: McKenna a, File Date: 5/20/2014 Signature Pott Mu

Attachment 4-21: Letter for Missing Vertical Clearance Posting, State Owned Structure, Page 1 of 2

Massachusetts Department of Transportation Highway Division



Bridge Inspection Handbook Field Inspection, Data Collecting, Report Writing and Report Review

Attachment 4-21: Letter for Missing Vertical Clearance Posting, State Owned Structure, Page 2 of 2



Deval L. Patrick, Governor Richard A. Davey, Secretary & CEO Frank DePaola, Administrator
City of Springfield November 11, 2014 70 Tapley Street Springfield, MA 01104
Attn: Christopher M Cignoli, P.E., Director of Public Works
Subject: MISSING CLEARANCE POSTING SIGNS
Dear Members of the Board:
Based upon the Bridge Inspection done on 05/07/2013, (copy filed with the District Bridge Inspection Unit) the following bridge was found to have missing posting signs. Please post the following bridge.
Bridge No: S-24-032 Structure No: S24032-0N7-MUN-NBI BIN No: 0N7 City/Town: Springfield Location: STATE ST Street Over: ROOSEVELT AVE Barrier:
FOR THE FOLLOWING HEIGHT RESTRICTIONS
Total number of signs 2
Total number of posts 0
At Bridge: Both X North South East West
At Advance: Both North South East West Other (Please explain) This is field measured clearance.
Be advised that the missing Posting signs should be installed within 30 days of this notice. Please fill out the bottom of this form and return a copy of it to the District Bridge Inspection Office where the signs have been placed. Sincerely,
Albert Stegemann, P.E. District Highway Director cc: BIE (3), DHD, D-2 & DBIE, D-2
Signs Installed by: Date: Municipality Official's Name: Signature
Leading the Nation in Transportation 811 North King Street, Northampton, MA 01060 Excellence Tel: (413) 582-0596 Excellence www.mass.gov/massdot

Attachment 4-22: Letter for Missing Vertical Clearance Posting, Municipally Owned Structure



	MassDOT Highway Division- Bridge	Section	
Consultant's Name	Contract No.	Assignment No.	
//ASSDOT Evaluator's Name	MASSDOT Evaluator's Signature	Consultant Overall S	Score (1-10)
Bridge & BIN No(s).	Location(s)		
	l Directive E-98-001 <u>Consultant Performance Ev</u> District Bridge Inspection Engineer provide a sc		
CONSULTAN	T PERFORMANCE EVALUATION INSPE	CTION SUB ELEMENTS	0
10 200 00 200 100 000 000	Sub Element Grading Items		Score (1-10)
Inspection Frequency – Did the C in accordance with NBIS and were	onsultant complete the field inspection in the mo all required elements inspected?	onth that the inspection was due	
	t complete a Roadway Work Notification Form if n the DBIE of the field inspection in advance?	f required with the appropriate	
Critical Deficiency Notification – immediately inform the DBIE of the	f a Critical Deficiency was identified during the in situation?	nspection, did the Consultant	
Electronic Submission – Was the acceptable time frame?	first electronic submission of the inspection repo	ort completed within an	
Inspection Report Quality – Were produce an acceptable Inspection F	an excessive number of review comments and Report?	corrections required in order to	
	as the final approved inspection report submittee perative throughout the assignment?	in a timely manner and was	
CONS	JLTANT PERFORMANCE EVALUATION RATI	NG SCALE GUIDE	
	 <u>Consultant consistently exceeded expectation</u> of the work. This level should be reserved for on 		
	8) – <u>Consultant frequently exceeded expectatic</u> oring. Agency coordination and public involvement oring. Agency coordination and public involvement or a statement of the statement of the statement of the statement of the statement of the st		
	Consultant consistently met expectations. Meets some areas that need minor improvements but actices/management.		
	 Consultant frequently failed to meet expect e acceptable. Consultant's work is done solely b lected for additional projects. 		
) - <u>Consultant consistently failed to meet expect</u> requires a high degree of monitoring to complet ture work		

Attachment 4-23: Bridge Inspection Consultant Performance Evaluation Report



Richard A D	rick, Governor Javey, Secretary & CEO Sla, Administrator	Massachusetts Highway E	Department of Transportation
		February 19, 2014	
Town of Acto Board of Sele 472 Main St. Acton, MA 0	ectmen		
Attn: Corey	York, Director Publi	ic Works	
SUBJECT:	<u>NATIONAL BRII</u> BRIDGE INSPEC	DGE INSPECTION STANDARDS (NBIS) TION REPORTS	
A-02-008 A-02-009 A-02-020	(255) (23Y) (258)	RIVER ST / FORT POND BROOK BROOK ST / NASHOBA BROOK RIVER ST / FORT POND BROOK	Dated: 12/02/13 Dated: 12/02/13 Dated: 01/07/14
the inspectio	e Massachusetts Brid n of municipally own	lge Inspection Program, MassDOT - Highwa ned bridges that have a clear span of 20 feet cted every two years or less.	y Division performs or greater. These
reports for th any bridges t	ne referenced munici	cent Routine Arch and Routine Culvert bridg pally owned bridges. Repair, rehabilitation of encies reported is the owner/custodian's respo- oses.	or reconstruction of
funds may be		of the reports may be directed to the District	Bridge Inspection
Questions re	garding the content of ahmood Azizi, at 50	8-929-3822.	2
Questions re	garding the content of ahmood Azizi, at 50	8-929-3822. Sincerely, Jonathan D, Gulliver District 3 Highway Director	
Questions re Engineer, M	garding the content of ahmood Azizi, at 50 , DHD D-3, DBIE D	Sincerely, Jonathan D, Gulliver District 3 Highway Director	

Attachment 4-24: Cover Letter from DHD to Municipality transmitting Inspection Report