massDOT

Massachusetts Department of Transportation

Leading the Nation in Transportation Excellence

Bridge Inspection Handbook

2015 Edition

The Commonwealth of Massachusetts

Charles D. Baker
Governor

Karyn E. Polito
Lt. Governor

Stephanie Pollack
Secretary & CEO

Thomas J. Tinlin
Acting Administrator

MassDOT
Massachusetts Department of Transportation
Highway Division

Prepared by
The Massachusetts Department of Transportation
Highway Division
Bridge Section

April 2015

ACKNOWLEDGEMENTS

MassDOT would like to acknowledge the contributions made by the following individuals in the preparation of the MassDOT Bridge Inspection Handbook 2015 Edition. Their dedicated efforts have made this edition of the Bridge Inspection Handbook possible.

Bridge Inspection Handbook Committee

Alexander K. Bardow, P.E., State Bridge Engineer, MassDOT
Brian B. Clang, P.E., Bridge Inspection Engineer, MassDOT
Jean B. Marauszwski, P.E., Area Bridge Inspection Engineer Districts 1 & 2, MassDOT
Gregory Krikoris, P.E., Area Bridge Inspection Engineer Districts 3 & 4, MassDOT
Bruce J. Sylvia, Area Bridge Inspection Engineer Districts 5 & 6, MassDOT

Contributions Provided By

Randi Bonica, Underwater Operations Engineer, MassDOT
Laurie Briggs, DBIE District 1, MassDOT
William Drosehn, DBIE District 2, MassDOT
Mahmood Azizi, P.E., DBIE District 3, MassDOT
Thomas Weil, P.E., DBIE District 4, MassDOT
Daniel Palmer, P.E., DBIE District 5, MassDOT
Gerald O'Connor, DBIE District 6, MassDOT
Mark Griffin, P.E., Bridge/Tunnel Inspection Engineer District 6, MassDOT

The lower third photo from the left on the Bridge Inspection Handbook cover is courtesy of Michael Baker Jr, Inc

BRIDGE INSPECTION HANDBOOK
TABLE OF CONTENTS

INTRODUCTION AND PURPOSE OF THIS HANDBOOK

i. **PURPOSE** ..... i - 1
ii **USE OD THIS HANDBOOK** ..... i - 1

CHAPTER 1: INTRODUCTION

1.1 **INTRODUCTION** ..... 1 - 1
1.2 **PURPOSES OF BRIDGE INSPECTION** ..... 1 - 1
1.3 **FUNCTIONS** ..... 1 - 1
1.4 **NATIONAL BRIDGE INSPECTION STANDARDS (NBIS)** ..... 1 - 2
1.4.1 **MassDOT Qualification's and Training Requirements** ..... 1 - 2
1.4.1.1 Team Leader Qualifications ..... 1 - 2
1.4.1.2 Team Member Qualifications ..... 1 - 2
1.4.2 **Applicable Reference Materials for Bridge Inspectors** ..... 1 - 3
1.5 **BRIDGE INVENTORY DATABASE** ..... 1 - 3
1.6 **ABOUT THE HANDBOOK** ..... 1 - 4
1.6.1 **Summarization of Abbreviations and Acronyms Used Throughout the Handbook** ..... 1 - 5
1.6.2 **Revisions to the Handbook** ..... 1 - 5
1.6.3 **Supplemental Information** ..... 1 - 5
1.7 **PERMANENT HOLDING LOCATION** ..... 1 - 5
1.8 **CHAPTER 1 ATTACHMENTS** ..... 1 - 6

CHAPTER 2: GENERAL SAFETY REQUIREMENTS

2.1 **INTRODUCTION** ..... 2 - 1
2.2 **PERSONNEL** ..... 2 - 1
2.3 **CLOTHING** ..... 2 - 1
2.4 **EQUIPMENT** ..... 2 - 1
2.4.1 **Advance Work Signs & Safety Cones** ..... 2 - 2
2.4.2 **Ladders** ..... 2 - 2
2.4.3 **Scaffolding** ..... 2 - 2
2.4.4 **Safety Harness and Lanyards** ..... 2 - 3
2.4.5 **Tools – Hand and Power** ..... 2 - 3
2.4.6 **Life Jackets or Buoyant Work Vests** ..... 2 - 3
2.5 **ACCESS MEANS** ..... 2 - 3
2.5.1 **Confined Space Entry** ..... 2 - 3
2.5.2 **Aerial Lifts, Lift Buckets and Snooper Trucks** ..... 2 - 4
2.5.3 **Catwalks** ..... 2 - 4
2.5.4 **Rigging and Staging** ..... 2 - 4
2.6 **FIRST AID, EMERGENCY CONTACTS AND ACCIDENTS** ..... 2 - 4
2.6.1 **First Aid** ..... 2 - 4
2.6.2 **Immediate Life Threating Injuries** ..... 2 - 4
2.6.3 **Emergency Contact Numbers** ..... 2 - 4
2.6.4 **Accidents** ..... 2 - 4

2.7 CHAPTER 2 ATTACHMENTS ..... 2 - 6

CHAPTER 3: INSPECTION FREQUENCY, SCHEDULING AND COORDINATION

3.1 INTRODUCTION ..... 3 - 1
3.2 INSPECTION TYPES AND FREQUENCIES ..... 3 - 1
3.2.1 Routine Inspection ..... 3 - 1
3.2.2 Fracture Critical Inspection ..... 3 - 2
3.2.3 Underwater Inspection ..... 3 - 2
3.2.4 Special Member Inspection ..... 3 - 2
3.2.5 Underwater Special Member Inspection ..... 3 - 3
3.2.6 Closed Bridge Inspection ..... 3 - 3
3.2.7 Freeze/Thaw Inspection ..... 3 - 3
3.3 BRIDGE INSPECTION WAIVERS ..... 3 - 3
3.4 BRIDGE INSPECTION SCHEDULING ..... 3 - 4
3.5 OUT OF FREQUENCY ..... 3 - 4
3.5.1 Out of Frequency Checks ..... 3 - 5
3.6 INSPECTION COORDINATION ..... 3 - 5
3.6.1 Police Details for Bridge Inspection ..... 3 - 5
3.6.1.1 Procedures on Obtaining Police Details ..... 3 - 5
3.6.1.2 Scheduling Police Details ..... 3 - 5
3.6.1.3 Payment of Police Details ..... 3 - 6
3.6.1.4 Records of Police Details ..... 3 - 6
3.6.2 Railroad Flagging Services for Bridge Inspection ..... 3 - 6
3.6.2.1 Procedures on Obtaining Railroad Flaggers ..... 3 - 7
3.6.2.2 Scheduling Railroad Flaggers ..... 3 - 7
3.6.2.3 Payment of Railroad Flaggers ..... 3 - 7
3.6.2.4 Records of Railroad Flaggers ..... 3 - 8
3.6.3 Traffic Management Services for Bridge Inspection ..... 3 - 8
3.6.3.1 Procedures on Obtaining Traffic Management Services ..... 3 - 8
3.6.4 Navigable Waterway Inspection Coordination ..... 3 - 8
3.7 FIELD INSPECTION NOTIFICATION PROCEDURES ..... 3 - 8
3.7.1 Daily Field Inspection Notification ..... 3 - 9
3.7.2 Consultant Field Inspection Notification ..... 3 - 9
3.7.3 Dive Inspection Notification ..... 3 - 9
3.8 CHAPTER 3 ATTACHMENTS ..... 3 - 10

CHAPTER 4: FIELD INSPECTION, DATA COLLECTING, REPORT WRITING AND REPORT REVIEW

4.1 INTRODUCTION ..... 4 - 1
4.2 STANDARD INSPECTION REPORT FORMS ..... 4 - 1
4.3 SI&A SHEET ..... 4 - 2
4.4 ELEMENT LEVEL INSPECTIONS ..... 4 - 2
4.5 FIELD INSPECTIONS ..... 4 - 3
4.5.1 Field Inspection for Initial Inspections ..... 4 - 3
4.5.2 Field Inspection for Special Member Inspections ..... 4 - 4
4.5.3 Field Inspection for Damage Inspections ..... 4 - 4
4.5.4 Field Inspection for Scour Critical Structures ..... 4 - 5

4.5.5 Plan of Inspection ..... 4 - 5
4.5.6 Orientation ..... 4 - 6
4.5.7 Condition Information ..... 4 - 6
4.5.8 Critical Inspection Findings ..... 4 - 7
4.5.8.1 Critical Structural (CS/I) Definition and Notification ..... 4 - 7
4.5.8.2 Critical Hazard (CH/I) Definition and Notification ..... 4 - 7
4.5.9 Request for Re-Evaluation of Item 113 – Scour Critical Bridges ..... 4 - 7
4.5.9.1 Structure over Water That Has Been Replaced ..... 4 - 8
4.5.9.2 Substructure Scour Repairs Performed and/or Stream Bed Scour Countermeasures Installed ..... 4 - 8
4.5.9.3 Stream Bed or Waterway Changes ..... 4 - 8
4.5.10 Reporting of Structurally Deficient Bridges ..... 4 - 8
4.5.11 Other Information Gathered at Routine Inspections ..... 4 - 9
4.5.11.1 Request for Rating or Re-rating ..... 4 - 9
4.5.11.2 Curb Reveal Measurements ..... 4 - 9
4.5.11.3 Vertical Clearance Measurements & Vertical Clearance Signage Verification ..... 4 - 9
4.5.11.4 Weight Posting Verification & Weight Posting Signage Verification ..... 4 - 10
4.5.11.5 Average Daily Traffic ..... 4 - 10
4.5.11.6 Inventory Photos ..... 4 - 11
4.5.11.7 Stream Bed Profiles ..... 4 - 11
4.6 INSPECTION DOCUMENTATION AND REPORT WRITING ..... 4 - 12
4.6.1 Creation of Inspection Report ..... 4 - 12
4.6.2 Date of Inspection ..... 4 - 12
4.6.3 Inspection Defects ..... 4 - 12
4.6.4 Inspection Deficiencies ..... 4 - 12
4.6.5 Inspection Dimensioning ..... 4 - 13
4.6.6 Inspection Sketches ..... 4 - 14
4.6.7 Inspection Photos ..... 4 - 14
4.6.8 Videos of Deficiencies ..... 4 - 14
4.6.9 Condition Coding ..... 4 - 15
4.6.10 Narrative Presentation ..... 4 - 16
4.6.11 SI&A Edits ..... 4 - 16
4.6.12 Element Level Inspection Report ..... 4 - 16
4.7 CS/I & CH/I PROCEDURE AND DOCUMENTATION ..... 4 - 17
4.7.1 CS/I & CH/I Field Observations at MassDOT Owned Bridges ..... 4 - 17
4.7.2 CS/I & CH/I Field Observations at Municipally Owned Bridges ..... 4 - 17
4.7.3 Follow-Up Procedures on Critical Deficiency Findings ..... 4 - 18
4.7.3.1 Procedures – Follow-Up for MassDOT Bridges ..... 4 - 18
4.7.3.2 Procedures – Follow-Up for Municipally Owned Bridges ..... 4 - 18
4.7.3.3 Repeat Procedures – Follow-Up Procedures for MassDOT & Municipally Owned Bridges ..... 4 - 18
4.8 VERTICAL CLEARANCE SIGNAGE PROCEDURE ..... 4 - 19
4.8.1 Notification to Post under Clearance – State Owned Roadway ..... 4 - 19
4.8.2 Notification to Post under Clearance – Municipally Owned Roadway ..... 4 - 20
4.9 COMPLETION and SUBMISSION of INSPECTION REPORTS by TEAM LEADERS ..... 4 - 20
4.9.1 MassDOT Inspections ..... 4 - 20
4.9.2 Consultant Inspections ..... 4 - 20
4.10 DBIE INSPECTION REPORT REVIEW ..... 4 - 20

4.10.1 DBIE Review of MassDOT Inspections ..... 4 - 21
4.10.2 DBIE Review of Consultant Inspections ..... 4 - 21
4.10.3 DBIE Review of Inspection Report Content ..... 4 - 21
4.11 DISTRIBUTION OF COMPLETED INSPECTION REPORTS ..... 4 - 22
4.12 ABIE REVIEW OF COMPLETED INSPECTION REPORTS ..... 4 - 23
4.13 CHAPTER 4 ATTACHMENTS ..... 4 - 24

CHAPTER 5: QUALITY CONTROL AND QUALITY ASSURANCE

5.1 QUALITY CONTROL and QUALITY ASSURANCE ..... 5 - 1
5.2 QUALITY CONTROL ENGINEER ..... 5 - 1
5.2.1 Inspection Report Evaluations ..... 5 - 1
5.2.2 Inspection Team Field Evaluation Procedures ..... 5 - 3
5.2.3 Evaluation of Structure's Assigned a SD Classification ..... 5 - 3
5.3 QUALITY ASSURANCE ENGINEER ..... 5 - 3
5.4 QUALITY ASSURANCE SUPERVISOR ..... 5 - 4
5.5 INSPECTION TEAM FIELD EVALUATION ..... 5 - 4
5.5.1 Inspection Team Field Evaluation Procedures ..... 5 - 4
5.6 INSPECTION TEAM REPORT EVALUATION ..... 5 - 5
5.6.1 Inspection Team Report Evaluation Procedures ..... 5 - 5
5.7 CHAPTER 5 ATTACHMENTS ..... 5 - 6

CHAPTER 6: RATING, POSTING AND CLOSING OF BRIDGES

6.1 INTRODUCTION ..... 6 - 1
6.2 FACTORS THAT WARRANT A RATING/RE-RATING REQUEST ..... 6 - 2
6.3 PROCEDURES FOR REQUESTING A RATING/RE-RATING OF A STRUCTURE ..... 6 - 2
6.4 PROCEDURES FOR LOGGING, AND ROUTING OF RATINGS ..... 6 - 3
6.5 PROCEDURES FOR PROCESSING RATING REPORTS BY RATINGS & OVERLOAD UNIT ..... 6 - 4
6.6 PROCEDURES FOR PROCESSING RATING REPORTS WITH RED COVERS ..... 6 - 5
6.7 DOCUMENTATION AND DISTRIBUTION OF APPROVED RATINGS ..... 6 - 6
6.7.1 Procedures on Posting and Rating Items on SI&A ..... 6 - 7
6.8 BRIDGE POSTING REDUCTION BASED ON AN INSPECTION ..... 6 - 8
6.9 PROCEDURES FOR CLOSING A BRIDGE DUE TO AN INSPECTION OR A PREPARED BRIDGE RATING REPORT ..... 6 - 9
6.9.1 Closure of a Bridge Due To an Inspection ..... 6 - 9
6.9.2 Closure of a Bridge Due to a Rating Report ..... 6 - 10
6.10 DUAL RECOMMENDATIONS ..... 6 - 11
6.10.1 Dual Recommendations on Bridges Owned by MassDOT ..... 6 - 11
6.10.2 Dual Recommendations on Brides Owned by Municipalities ..... 6 - 12
6.11 PROCEDURES FOR POSTING OF BRIDGES ..... 6 - 13
6.11.1 Procedures for Posting of Bridges Owned by MassDOT ..... 6 - 13
6.11.2 Procedures for Posting of Bridges Owned by Municipalities ..... 6 - 14
6.12 FOLLOW UP SITE VISIT PROCEDURES REGARDING INSTALLATION OF POSTING SIGNS ..... 6 - 14
6.12.1 MassDOT Owned Structures ..... 6 - 14

6.12.2 Municipally Owned Structures ..... 6 - 15
6.13 CHAPTER 6 ATTACHMENTS ..... 6 - 16

CHAPTER 7: UNDERWATER OPERATIONS TEAM

7.1 INTRODUCTION ..... 7 - 1
7.2 ORGANIZATIONAL STRUCTURE ..... 7 - 1
7.3 DIVER CLASSIFICATIONS ..... 7 - 1
7.4 UNDERWATER INSPECTION DIVER QUALIFICATIONS ..... 7 - 2
7.4.1 Initial Eligibility Requirements for Divers ..... 7 - 2
7.4.2 Annual Requirements for Divers ..... 7 - 2
7.4.3 Additional NBIS Requirements for Divers ..... 7 - 3
7.5 DIVER SAFETY PRACTICES ..... 7 - 3
7.5.1 Compressed Air Injuries ..... 7 - 4
7.6 UNDERWATER BRIDGE INSPECTION ..... 7 - 5
7.6.1 Waterway Characteristics That Warrant Dive Inspections ..... 7 - 5
7.6.2 Inspection Frequency ..... 7 - 6
7.7 CLASSIFICATION OF UNDERWATER BRIDGE INSPECTIONS ..... 7 - 7
7.8 UNDERWATER INSPECTION PROCEDURES ..... 7 - 7
7.8.1 Bridge Data Review and Dive Planning ..... 7 - 7
7.8.2 Dive Equipment ..... 7 - 8
7.8.3 Dive Inspection Process ..... 7 - 9
7.8.3.1 Dive Master ..... 7 - 9
7.8.3.2 References ..... 7 - 9
7.8.3.3 Established Water Elevation ..... 7 - 9
7.8.3.4 Stationing ..... 7 - 10
7.8.3.5 Sounding Location Determination ..... 7 - 10
7.8.3.6 Defect Documentation ..... 7 - 10
7.9 REPORT PREPARATION ..... 7 - 10
7.10 CRITICAL DEFECT NOTIFICATION ..... 7 - 11
7.11 FLOOD INSPECTIONS ..... 7 - 11
7.12 INSPECTION REPORT REVIEW AND DISTRIBUTION ..... 7 - 11
7.13 UNDERWATER ELEMENTS ..... 7 - 12
7.13.1 Footing or Foundations ..... 7 - 12
7.13.2 Scour ..... 7 - 12
7.13.3 Undermining ..... 7 - 13
7.13.4 Sheeting ..... 7 - 13
7.13.5 Piles ..... 7 - 13
7.13.6 Pile Bents ..... 7 - 14
7.13.7 Fender System ..... 7 - 14
7.13.8 Scour Countermeasures ..... 7 - 14
7.13.9 Previous Underwater Repairs ..... 7 - 14
7.13.10 Soil – Bottom Material ..... 7 - 15
7.13.11 Marine Growth ..... 7 - 15
7.13.12 Debris ..... 7 - 15
7.13.13 Photographs ..... 7 - 15
7.13.14 Sketches ..... 7 - 15
7.14 CHAPTER 7 ATTACHMENTS ..... 7 - 16

CHAPTER 8: NON-NBI INSPECTIONS

8.1 INTRODUCTION ..... 8 - 1
8.2 BRI & CUL STRUCTURES ..... 8 - 1
8.2.1 Inspection of BRI & CUL Structures ..... 8 - 2
8.2.2 Documentation of BRI & CUL Structures ..... 8 - 2
8.2.3 Distribution of BRI Inspection Reports ..... 8 - 2
8.3 RAILROAD BRIDGES OVER HIGHWAYS (RRO STRUCTURES) ..... 8 - 2
8.3.1 Inspection of RRO Structures ..... 8 - 3
8.4 PRIVATELY OWNED BRIDGE (PRI STRUCTURES) ..... 8 - 3
8.5 PEDESTRIAN BRIDGES (PED), BIKEWAY (BKY) AND UTILITY (UTL) STRUCTURES ..... 8 - 3
8.6 EMERGENCY INSPECTIONS DUE TO ACTS OF NATURE ..... 8 - 3
8.6.1 Flood/Tidal Surge ..... 8 - 4
8.6.1.1 Available Information ..... 8 - 4
8.6.1.2 Structures Requiring Condition Assessment ..... 8 - 4
8.6.1.3 Condition Assessment Procedure ..... 8 - 4
8.6.1.4 Documentation and Reporting of During Flood Assessments ..... 8 - 5
8.6.1.5 Documentation and Reporting of Post Flood Assessments ..... 8 - 6
8.6.1.6 Flood Assessment Time Frame ..... 8 - 6
8.6.2 Earthquake ..... 8 - 7
8.6.2.1 Structures Requiring Condition Assessment ..... 8 - 7
8.6.2.2 Condition Assessment Procedure ..... 8 - 7
8.6.2.3 Documentation and Reporting ..... 8 - 7
8.6.2.4 Earthquake Assessment Time Frame ..... 8 - 7
8.7 FREEZE/THAW INSPECTIONS ..... 8 - 7
8.8 BRIDGE SECURITY ..... 8 - 8
8.8.1 Major and Critical Infrastructure Designation ..... 8 - 8
8.8.2 Alert Levels ..... 8 - 9
8.8.3 Bridge Security Inspection Objective ..... 8 - 9
8.8.4 Inspection Process for Alert Levels ..... 8 - 9
8.8.4.1 Low Alert Situations (Condition Green) ..... 8 - 9
8.8.4.2 Guarded Alert Situations (Condition Blue) ..... 8 - 9
8.8.4.3 Elevated Alert Situations (Condition Yellow) ..... 8 - 10
8.8.4.4 High Alert Situations (Condition Orange) ..... 8 - 10
8.8.4.5 Severe Alert Situations (Condition Red) ..... 8 - 11
8.9 DISSEMINATION OF SECURITY SENSITIVE INFORMATION ..... 8 - 11
8.9.1 Redaction of Inspection Reports ..... 8 - 11
8.10 CHAPTER 8 ATTACHMENTS ..... 8 - 12

CHAPTER 9: MassDOT SUPPLEMENTAL CODING GUIDE

9.1 INTRODUCTION ..... 9 - 1
9.2 DEFENITIONS TO BE USED WITH THE SUPPLEMENTAL CODING GUIDE ..... 9 - 1
9.2.1 Bridge Number (BDEPT#) ..... 9 - 1
9.2.2 Bridge Key # (BRKEY) ..... 9 - 1
9.2.3 BIN (Bridge Identification Number) ..... 9 - 2
9.2.4 Federal Information Processing Standards (FIPS) Code ..... 9 - 2

9.2.5 Strategic Highway Corridor Network (STRAHNET) ..... 9 - 2
9.2.6 Survey Convention ..... 9 - 2
9.2.7 Orientation ..... 9 - 2
9.2.8 Primary Record ..... 9 - 2
9.2.9 Secondary Record ..... 9 - 2
9.2.10 Town Line Bridge ..... 9 - 3
9.3 PROCEDURE FOR ASSIGNING BDEPT NUMBER AND/OR BIN NUMBER ..... 9 - 3
9.3.1 Definitions to be Used When Submitting BDEPT# and/or BIN Requests ..... 9 - 3
9.3.2 General Guidelines for Assigning a Bridge Number and/or Bridge Identification Number ..... 9 - 3
9.3.3 Existing Structure Not Previously on an Inventory ..... 9 - 4
9.3.4 A Bridge Structure Under Design ..... 9 - 5
9.4 CITY/TOWN DATA TO BE USED WITH THE SUPPLEMENTAL CODING GUIDE ..... 9 - 6
9.5 SUPPLEMENTAL CODING GUIDE ..... 9 - 6
ITEM 2 - DISTRICT ..... 9 - 6
ITEM 3 - COUNTY ..... 9 - 7
ITEM 4 - PLACE ..... 9 - 7
ITEM 5 - INVENTORY ROUTE ..... 9 - 7
ITEM 6 - FEATURES INTERSECTED ..... 9 - 7
ITEM 7 - FEATURES CARRIED BY STRUCTURE ..... 9 - 8
ITEM 8 - STRUCTURE NUMBER ..... 9 - 8
ITEM 16 - LATITUDE ..... 9 - 11
ITEM 17 - LONGITUDE ..... 9 - 11
ITEM 19 - BYPASS, DETOUR LENGTH ..... 9 - 11
ITEM 26 - FUNCTIONAL CLASSIFICATION OF INVENTORY ROUTE ..... 9 - 11
ITEM 27 - YEAR BUILT ..... 9 - 12
ITEM 29 - AVERAGE DAILY TRAFFIC (ADT) ..... 9 - 13
ITEM 36 - TRAFFIC SAFETY FEATURES ..... 9 - 13
ITEM 37 - HISTORICAL ..... 9 - 16
ITEM 41 - STRUCTURE OPEN, POSTED OR CLOSED TO TRAFFIC ..... 9 - 17
ITEM 48 - LENGTH OF MAXIMUM SPAN ..... 9 - 17
ITEM 60 - SUBSTRUCTURE ..... 9 - 18
ITEM 61 - CHANNEL AND CHANNEL PROTECTION ..... 9 - 18
ITEM 62 - CULVERTS ..... 9 - 18
ITEM 63 - METHOD USED TO DETERMINE OPERATING RATING ..... 9 - 19
ITEM 64 - OPERATING RATING ..... 9 - 19
ITEM 65 - METHOD USED TO DETERMINE INVENTORY RATING ..... 9 - 19
ITEM 66 - INVENTORY RATING ..... 9 - 20
ITEM 67 - STRUCTURAL EVALUATION ..... 9 - 20
ITEM 68 - DECK GEOMETRY ..... 9 - 20
ITEM 69 - UNDERCLEARANCES, VERTICAL AND HORIZONTAL ..... 9 - 20
ITEM 70 - BRIDGE POSTING ..... 9 - 20
ITEM 75 - TYPE OF WORK ..... 9 - 20
ITEM 76 - LENGTH OF STRUCTURE IMPROVEMENT ..... 9 - 20
ITEM 90 - INSPECTION DATE ..... 9 - 21
ITEM 91 - DESIGNATED INSPECTION FREQUENCY ..... 9 - 21
ITEM 92 - CRITICAL FEATURE INSPECITON ..... 9 - 21

ITEM 93 - CRITICAL FEATURE INSPECTION DATE....9 - 22
ITEM 94 - BRIDGE IMPROVEMENT COST....9 - 22
ITEM 95 - ROADWAY IMPROVEMENT COST....9 - 22
ITEM 96 - TOTAL PROJECT COST....9 - 22
ITEM 97 - YEAR OF IMPROVEMENT COST ESTIMATE....9 - 22
ITEM 100 - STRAHNET HIGHWAY DESIGNATION....9 - 22
ITEM 103 - TEMPORARY STRUCTURE DESIGNATION....9 - 23
ITEM 104 - HIGHWAY SYSTEM OF THE INVENTORY ROUTE....9 - 23
ITEM 106 - YEAR RECONSTRUCTED....9 - 23
ITEM 108 - WEARING SURFACE PROTECTIVE COATING....9 - 24
ITEM 109 - AVERAGE DAILY TRUCK TRAFFIC....9 - 24
ITEM 110 - DESIGNATED NATIONAL NETWORK....9 - 24
ITEM 113 - SCOUR CRITICAL BRIDGES....9 - 24
ITEM 114 - FUTURE AVERAGE DAILY TRAFFIC....9 - 25
9.5.1 MassDOT Convention for Coding Item 6 and Item 7....9 - 25
9.5.2 Coding Item 6 and Item 7 for a Single Feature/Facility....9 - 26
9.5.3 Coding Item 6 and Item 7 for a Multiple Features/Facility....9 - 30
9.5.3.1 Hierarchy of Precedence for Multi Features/Facility....9 - 30
9.5.3.2 Multiple Features/Facilities of the Same Type....9 - 31
9.5.3.3 Multiple Features/Facilities of Different Types....9 - 31
9.5.4 Coding Items 63, 64, 65, and 66....9 - 32
9.5.4.1 Design Ratings....9 - 32
9.5.4.2 Closed Structures....9 - 33
9.6 SECONDARY RECORDS....9 - 33
9.7 MASSACHUSETTS SPECIFIC ITEMS....9 - 34
9.7.1 Access Items....9 - 35
Access Other....9 - 35
Barge....9 - 35
Boat....9 - 35
Class A Emp....9 - 35
Confined Space....9 - 35
Ladder....9 - 35
Lift Bucket....9 - 35
Night/Off Hours Work....9 - 36
Police....9 - 36
Railroad Flagging....9 - 36
Rigging....9 - 36
Snooper....9 - 36
Traffic Control....9 - 36
Wader....9 - 36
9.7.2 Bridge Features....9 - 36
Foundation Type....9 - 36
Jointless Bridge....9 - 37
Overhead Signs....9 - 37
Pier Type....9 - 38
Pin & Hanger....9 - 38
Protective Screen....9 - 38
Snow Fence....9 - 39
Steel Coating....9 - 39

Temporary Bridge ..... 9 - 39
Utilities ..... 9 - 39
9.7.3 Clearance Information ..... 9 - 40
Posted for Vertical Clearance ..... 9 - 40
N/E Vertical Clearance Measured ..... 9 - 40
N/E Vertical Clearance Posting ..... 9 - 40
S/W Vertical Clearance Measured ..... 9 - 40
S/W Vertical Clearance Posting ..... 9 - 41
Truss Portal Measured ..... 9 - 41
9.7.4 Culvert Items ..... 9 - 41
Barrel Height ..... 9 - 41
Barrel Number ..... 9 - 41
Barrel Width ..... 9 - 41
Culvert Coating ..... 9 - 41
Culvert Material ..... 9 - 42
Culvert Shape ..... 9 - 42
Depth of Cover ..... 9 - 42
9.7.5 Inventory Items ..... 9 - 42
Agency Bridge # ..... 9 - 42
BDEPT # ..... 9 - 42
BIN ..... 9 - 43
Bridge Category Code ..... 9 - 43
Bridge Name ..... 9 - 43
Bridge Key ..... 9 - 43
Facility Carried by Structure ..... 9 - 46
Features Intersected ..... 9 - 47
FC Under ..... 9 - 47
FHWA Record ..... 9 - 47
Legacy Owner ..... 9 - 47
Mile Marker ..... 9 - 47
Owner Code ..... 9 - 48
Parallel BIN ..... 9 - 48
Railroad Branch ..... 9 - 48
Railroad Bridge # ..... 9 - 48
Town Line BDEPT # ..... 9 - 48
Town Name ..... 9 - 48
9.7.6 Inspection Items ..... 9 - 49
Closed Bridge Inspection Date ..... 9 - 49
Closed Bridge Inspection Frequency ..... 9 - 49
Complex Bridge ..... 9 - 49
Damage Inspection ..... 9 - 49
Inspection Hours ..... 9 - 49
Inspection Responsibility ..... 9 - 49
Inspection Waiver ..... 9 - 50
Inspection Waiver Remarks ..... 9 - 50
Other Inspection ..... 9 - 50
Underwater Inspection ..... 9 - 50
9.7.7 Load Rating Information ..... 9 - 50
INV H20 ..... 9 - 50

INV TYPE 3 ..... 9 - 51
INV TYPE 3S2 ..... 9 - 51
INV HS ..... 9 - 51
OPR H20 ..... 9 - 51
OPR TYPE 3 ..... 9 - 51
OPR TYPE 3S2 ..... 9 - 51
OPER HS ..... 9 - 51
9.7.7.1 Load Rating Values for "Design" Status ..... 9 - 52
9.7.7.2 Load Rating Values for Inventoried Structures with Unknown Design Load Criteria (no plans) ..... 9 - 52
9.7.8 Maintenance Information ..... 9 - 52
Year Painted ..... 9 - 52
Year Rehabbed ..... 9 - 52
9.7.9 Posting Information ..... 9 - 52
Actual 2 Axles ..... 9 - 53
Actual 3 Axles ..... 9 - 53
Actual 5 Axles ..... 9 - 53
Posting Date ..... 9 - 53
Posting Remarks ..... 9 - 53
Posting Status ..... 9 - 54
Recommended 2 Axles ..... 9 - 54
Recommended 3 Axles ..... 9 - 54
Recommended 5 Axles ..... 9 - 54
9.8 CHAPTER 9 ATTACHMENTS ..... 9 - 55

CHAPTER 10: SUPPLEMENTAL INFORMATION

10.1 INTRODUCTION ..... 10 - 1
10.2 CODING FOR MULTI BEAM BRIDGES ISSUED 5/1/09 ..... 10 - 2
10.3 TEAM MEMBER INITIALS ON INSPECTION REPORTS ISSUED 11/1/09 ..... 10 - 3
10.4 SUPERSTRUCTURE CODING FOR NE BULB TEE PRE-STRESSED GIRDER BRIDGES ISSUED 1/15/10 ..... 10 - 4
10.5 SHIELDING REPORTING AND CODING ISSUED 2/16/11 ..... 10 - 5
10.6 CODING CLARIFICATION FOR PARAPETS AND BRIDGE RAILING ISSUED 11/12/13 ..... 10 - 6
10.7 INSPECT WHAT YOU CAN… WHEN IT IS DUE DATED 11/17/14 ..... 10 - 11
10.8 BRI: DEFINITIONS AND METHOD OF MEASURING LENGTH OF SPAN DATED 4/4/16 ..... 10 - 12
10.9 NBIS DATA UPLOADING PROCESS CHANGE DATED 9/25/17 ..... 10 - 17